

# 2014 WIND POWER PROGRAM PEER REVIEW

U.S. DEPARTMENT OF  
**ENERGY**

Energy Efficiency &  
Renewable Energy



## Accelerate Technology Transfer

March 24-27, 2014

## Wind Energy Technologies

# Contents

## **Accelerate Technology Transfer**

*Development of On-Site Conical Spiral Welders for Large Turbine Towers*—Eric Smith, Keystone Tower Systems, Inc.

*High Performance Hollow Fiber Membranes for Lubricating Fluid Dehydration and Stabilization Systems*—Stuart Nemster, Compact Membrane Systems

*Advanced Manufacturing Initiative*—Daniel Laird, Sandia National Laboratories

*Manufacturing and Supply Chain R&D, Wind Turbine Logistics and Planning Issues Analysis*—Jason Cotrell, National Renewable Energy Laboratory


*Wind Turbine Repowering and Recycling Assessments*—Jason Cotrell, National Renewable Energy Laboratory

*U.S. Wind Energy Manufacturing and Supply Chain Development*—Bruce Hamilton, Navigant Consulting, Inc.

*U.S. Wind Energy Manufacturing and Supply Chain: A Competitiveness Analysis*—Patrick Fullenkamp, GLWN, Global Wind Network [WIRE-Net]

*Assessment of Vessel Requirements for the U.S. Offshore Wind Sector*—Jim Ahlgrimm, U. S. Department of Energy





## Development of On-Site Conical Spiral Welders for Large Wind Turbine Towers

**Eric Smith**

Keystone Tower Systems, Inc.

[Eric@KeystoneTowerSystems.com](mailto:Eric@KeystoneTowerSystems.com)

(857)225-0552

March, 2014

# Budget, Purpose, & Objectives

Total DOE Budget <sup>1,2</sup>: \$0.000M

Total Cost-Share<sup>1</sup>: \$0.000M

## Problem Statement:


- Transport constraints limits tower diameter to 4.3m
- Constraint makes 100m+ towers uneconomical
- Limits wind development primarily to plains regions



## Impact of Project:

- 1,800GW of wind unlocked in US (DOE)
- 50% cost reduction for 140m towers
- 150tons+ of steel saved per tower
- 10%+ reduction in LCOE at low wind sites
- Naturally favors domestic manufacturing

## Unlocked wind resources at 140m:



## This project aligns with the following DOE objectives and priorities

- **Optimize Wind Plant Performance:** Reduce Wind Plant Levelized Cost of Energy
- **Accelerate Technology Transfer:** Lead the way for new high-tech U.S. industries
- **Mitigate Barriers:** Reduce barriers to expand access to quality wind resources

<sup>1</sup>Budget/Cost-Share for Period of Performance FY2012 – FY2013


<sup>2</sup>Project remained active using DOE funds received prior to FY2012

Spiral welding is a proven in-field fabrication technique used in the pipe and piling industry




Keystone has developed a variant of spiral welding for the wind industry:


- Variable wall thickness
- Tapered towers




3. Tower dimensions can exceed shipping limits



2. Towers are fabricated at the wind farm





1. Steel is shipped as flat sheets






- 3<sup>rd</sup> party validated design & economics
- Working prototype of manufacturing equipment (partial scale)
- Fundamental patent issued, more pending
- Initial design-in with top turbine manufacturers
- Beginning design-in work with developers.

*Keystone accomplishments will meet or exceed all goals for our DOE funded work*



# Project Plan & Schedule



## Comments


- Project began August 2012, and will complete August 2014
- Most milestones completed on or near schedule, with two significant variances:
  - Costing and logistics study completed significantly early as part of an OEM evaluation
  - Structural testing delayed due to lab construction delays at NEU, will skip testing of partially manual fabricated tower sections and move directly to testing of fully automated fabricated tower sections

## Partners, Subcontractors, and Collaborators:

### Structural testing:


(Myers, NEU)

Specimen flange bolted to end plates and loaded in pure bending.




### Buckling characterization:

(Schafer, JHU)



### Demonstration turbine:

(MIT / MassCEC)



Massachusetts  
Institute of  
Technology



## Communications and Technology Transfer:

Working with turbine manufacturers and wind developers and construction companies to integrate spiral welded tower technology into commercial wind plants

Keystone presented at invited talks at:

- NAWEA future of wind energy panel
- NREL Industry Growth Forum
- MIT Energy Club & MIT Energy Showcase
- UMass Amherst Wind Energy IGERT




## FY14/Current research:

- Structural testing & characterization
- Demonstration install (18m tower, 1m diameter, 10kW turbine)
- Characterization / optimization of manufacturing tolerances

## Proposed future research:



**Commercial scale  
machine design and build**



**Detailed design and integration  
of mobile operation into wind plant**



**Full scale  
demonstration**



Mini



C-1



C-4



**High Performance  
Hollow Fiber Membranes  
for Lubricating Fluid Dehydration  
and Stabilization Systems**

**Stuart Nemser**

Compact Membrane Systems  
snemser@compactmembrane.com

302-999-7996

March 24, 2014



Total DOE Budget<sup>1</sup>: \$1.900M

Total Cost-Share<sup>1</sup>: \$0.000M

## Problem Statement


- Wind turbine gearbox reliability can be improved significantly by removing free, emulsified and dissolved water from the lubricating oil
- Effects of water on lubricating systems
  - Bearing wear
  - Surface corrosion
  - Micropitting of the gear
  - Reduced lubricity
  - Loss of viscosity
  - Additives dropout
- This project addresses the problem of dewatering lubricating oil in real time and thereby enhance the gearbox reliability

<sup>1</sup>Budget/Cost-Share for Period of Performance FY2012 – FY2013




## Impact of Project

- Bearing life can be extended over 500%, if the dissolved water in oil is reduced from 400 to 25 ppm.
- The same impact is expected for wind turbine and other industrial gearboxes.
- The final product is a compact, lightweight, long life and portable membrane dehydrator for gear oil that works in real time.




## Project Alignment with DOE Program Objectives and Priorities

**Optimize Wind Plant Performance:** Reduce Wind Plant Levelized Cost of Energy (LCOE)



- ✓ Amorphous perfluorinated membranes
- ✓ Superb chemical and thermal resistance
- ✓ Molecular sieving mechanism
- ✓ High water vapor flux, retains organics
- ✓ Nonporous, non-wetting membrane

- Gear oil is circulated outside of the membrane
- Ambient sweep air is drawn through the lumen side using a vacuum pump
- Easy 'kidney loop' installation in an existing lubrication circuit
- Removes free, dispersed and dissolved water



## Key Issues Currently being Addressed

- Wind turbine field testing and Castrol oil issues
- 20+ prototype installations in various industries
- Scale-up of membrane module for 7X water removal
- Cartridge design improvement for higher efficiency (50-60%)
- New winder; higher productivity and quality; cost reduction

## Unique Aspects

- ✓ Removes free, dispersed and dissolved water
- ✓ Compact, lightweight, long life and portable
- ✓ Simple design, minimal moving parts, 110 V
- ✓ Total automatic operation, suitable for remote applications
- ✓ Less energy intensive, no heater, lower cost of operation
- ✓ No flooding, loading, foaming or oil carryover
- ✓ Unlike vacuum purifiers, no complicated floats or drive




## Major Technical Accomplishments in 2012-2013

- ✓ **Wind Turbine Installation** – Installed 2 mini units on 2 different GE 1.5 MW wind turbine gearboxes at AES Wind farm, Belington, WV. Both units running 24/7 with minimal attention. No mechanical issues with membrane or system.
- ✓ **Castrol Wind Turbine Oil Testing** – Resolved measurement issues with Castrol wind turbine gear oils
- ✓ **Salt Water Demo** – Worked well with sea water (offshore application) in lab demo studies; only water permeates; salt precipitates out and is removed by a filter
- ✓ **Nuclear Power Plant Installation** – Installed 2 units on EHC fluid (phosphate ester) at Salem Nuclear Power Plant, NJ. First unit is operating for about 2 years without any issues.


## Major Technical Accomplishments in 2012-2013 (Contd.)

- ✓ **20+ Prototype Installations** – Refined design of Phoenix system through 20+ prototype installations and field testing in paper mill, cooling towers, gold mine etc.
- ✓ **7X Scale-up** – Designed and tested a scaled-up 4” membrane system with 7X water removal capability when compared to a 2” membrane system
- ✓ **Higher Productivity Device** – Demonstrated 50 to 60% enhancement in productivity per device through laboratory testing of improved cartridge design
- ✓ **New Winder** – Specified and purchased a new winder; provides greater flexibility; reduces winding time and scrap; enhances quality; leads to lower cost membrane cartridge


## Biodegradable PAG Drying



## Hydraulic Fluid Drying







## Awards / Recognition

- ✓ A broad patent (US 8,506,815) on removal of water from fluids has been awarded to CMS in 2013
- ✓ Our novel membrane dehydration technology has been recognized in an editorial article featured in the 'TLT' journal of STLE

# Project Plan & Schedule

Summary					Legend							
WBS Number or Agreement Number	DE-EE0004546				Work completed							
Project Number					Active Task							
Agreement Number	DE-EE0004546				Milestones & Deliverables (Original Plan)							
					Milestones & Deliverables (Actual)							
Task / Event	FY2012				FY2013				FY2014			
	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
<b>Project Name: High Performance Hollow Fiber Membranes for Lubricating Fluid Dehydration and Stabilization Systems</b>												
Milestone M2.1: Winder Specifications	◆											
Milestone M2.2: Respooler Specifications												◆
Milestone M2.5: Demonstrate Optimized Prototype Hollow Fiber Cartridge												◆
Milestone M3.1: Finalized Specifications for Production Cartridge												◆
Milestone M4.1: Finalized Specifications for First Generation Product												◆
Milestone M5.1: Quality Control Document												◆
Milestone M8: Deploy First Generation Product												◆
<b>Current work and future research</b>												

## Comments

- 1OCT2010 to 30SEP2014
- A nearly 12 month funding lag in 2012 caused serious delays in completing the effort, this resulted in delays in purchasing the winder and concurrently completing associated milestones. Budget Period #2 was effectively FY12 & 13.

## Partners, Subcontractors, and Collaborators

- **MSC Filtration Technologies** (System Integration)
- **Pall Trincor** (Marketing and Distribution)
- **AES Corporation** (Wind Turbine Trials)
- **HYDAC** (System Integration and Marketing in Europe)
- **United States Coast Guard** (Sea Trial on Ice-breaker)
- **Dow** (Environmentally Acceptable Lubricants Drying)
- **Major Bearing Company** (Third Party Technology Validation)

## Communications and Technology Transfer

- **NREL** - National Renewable Energy Laboratory, presented at the 2011 Wind Turbine Condition Monitoring Workshop, Broomfield, CO
- **ICOM** - International Congress on Membranes and Membrane Processes, presented at the 2011 Meeting, Amsterdam, Netherland
- **STLE** - Society of Tribologists and Lubrication Engineers, presented at the 2012 Annual Meeting, St. Louis, MO
- **AIChE** - American Institute of Chemical Engineers, presented at the 2013 Annual Meeting, San Francisco, CA
- **Noria** - Reliable Plant Conference 2012 and 2014 (Accepted)






## FY14/Current Research

- **Better cartridge design for higher productivity**
- **Field testing and refinement of larger (C-4) prototype**
- **Implement new winder – reduce manufacturing cost; improve quality**
- **Polyalkylene glycol (PAG) drying for sea/marine trial**
- **Trial on a wind turbine with non Castrol lubrication oil (DOE help needed)**
- **No new milestones to date – all existing milestones will be completed by the end of the project**

## Proposed Future Research

- ✓ **Cross-cutting technology; can be applied to other renewable energy areas, e.g., drying of ionic liquids with specific focus on enhancing biomass conversion to glucose (collaborating with JBEI)**
- ✓ **Explosion proof dehydrator system for chemical process industries; increase market and volume; reduce cost for wind turbine application**
- ✓ **Accelerated statistical bearing life tests (similar to Timken, 1977 study)**



AMI – Advanced Manufacturing Initiative

**Daniel Laird**  
Sandia National Laboratories  
Daniel.Laird@sandia.gov; 505-844-6188  
March 27, 2014

# Budget, Purpose, & Objectives

Total DOE Budget <sup>1,2</sup>: \$0.000M

Total Cost-Share<sup>1</sup>: \$0.000M

## Problem Statement:

- High relative cost of U.S. labor makes it difficult to competitively manufacture blades in the U.S.



## Impact of Project:

- Significantly improve labor productivity (and leverage transportation advantage) to make U.S. wind turbine blade manufacture for the U.S. market economically viable

## Aligns with these DOE Program objectives:

- Accelerate Technology Transfer
- Mitigate Market Barriers

<sup>1</sup>Budget/Cost-Share for Period of Performance FY2012 – FY2013

<sup>2</sup>Project remained active using DOE funds received prior to FY2012.



- **Improve Labor Productivity by 35%**
- Reduce Cycle Time by 35%
- Improve/Maintain Reliability and Cost



## Three-way Manufacturing Research Collaboration

- Multi-year effort
  - Aug 2009 start
- Equal funding
  - DOE (\$2100k)
  - Iowa OEI (\$2100k)
  - TPI (\$2100k)



PI – Steve Nolet



PI – Daniel Laird



PI – Frank Peters



## Challenges:

- Collaborating at “industry speed”
- Intellectual Property
- Disseminating Results

First DOE Wind AMI project  
First year Iowa OEI Project

## Technical Steering Committee (TSC)

- Laird, Nolet, Peters
- Generate and Solicit Proposals for AMI
  - Cost, Timeline, etc.
  - Very significant interaction with industrial suppliers
- Monthly Telecons/Meetings to Consider Proposals
  - Cost/Time versus Impact on Objectives
- Approved Proposals Presented to Oversight Committee

## Oversight Committee

- Project Status/Spending
- Consider Proposals from TSC

Exact research directions unknown (or falsely known) at beginning

# Technical Approach

Leveraging Broader Sandia Capabilities for AMI

## Core Competencies *Enabling Technology*

- Design Tools
- Sensors
- Aerodynamics & Acoustics
- Testing
- Reliability Analysis
- Materials
- Manufacturing
- Grid Operations Support

*Tools,  
Processes,  
Test Results,  
Analyses*

## Projects *Industry-oriented Applications*

- Advanced Manufacturing Initiative (AMI)
- SMART Rotor
- Wind / Radar
- Blade Reliability Collaborative
- Sensor Blade 2
- Reliability Database
- Advanced Rotor
- Blade Manufacturer Demonstration Platform
- Integration Studies & KAFB/SNL Wind Farm
- Certification & Standards

*Tech  
Transfer*


Wind  
Industry



# Technical Approach


Leveraging Broader Sandia Capabilities for AMI

## Broader SNL Capabilities



*Facilities,  
Processes,  
NDI equip,  
Simulation  
Capability,  
Analyses,  
Robots*

## Projects *Industry-oriented Applications*





*Tech Transfer*



# Accomplishments and Progress

## Sub-project List


- 49 proposals considered by the TSC
  - 27 rejected
  - 22 accepted
- Sub-projects (partial list)
  - **Automation**
    - **Fabric Laying**
    - **Finishing**
  - Factory Logic/Process Flow Simulation
  - True 3D Laser Projection
  - Edge Operations Study
  - Non-Destructive Inspection Capabilities Evaluation (2)
  - Engineering Data Software Platform
  - Spar Cap Assembly Fiber Placement
  - Ply Nesting Optimization
  - Novel Materials Assessments
  - Fabrication and Testing of Utility-scale Demonstration Blade



AMI Project actually a collection of smaller targeted projects

# Accomplishments and Progress Automation

- Initially, automation was a primary thrust of AMI
- Significant time/effort spent in this area
- Fabric Laying
  - Significant effort spent with commercial suppliers
    - KMT, MAG, Ingersoll, Globe
  - Several proposals evaluated
  - No proposals passed ROI
- Finishing
  - Feasibility Analysis - Cliff Loucks
  - Most processes not viable candidates for automation
  - Viable processes did not yield enough ROI in terms of saved labor
  - Most viable was robotic trim/grind/sand work cell due to human safety issues




Automation could not meet AMI ROI requirements

# Accomplishments and Progress

## Sandia-led sub-projects

- **Factory Logic / Process Flow Simulation**
  - Immediately identified and quantified overhead crane bottleneck
  - Spawned other AMI efforts
  - Assisted with cost/benefit evaluations
- **Engineering Data Software Platform**
  - Coupled to 3D laser for fabric positioning
- **Finishing Automation Feasibility Analysis**
- **Robotic Edge Trim and Grind**
- **Epoxy Compatible Reusable Bags**
- **Spar cap cure modelling**
- **Non-destructive Inspection**



Root Cart




“Tip” Cart





# Accomplishments and Progress


## Sandia Non-destructive Inspection (NDI)



- Comparison of NDI technologies for wind turbine blade application
- Wind-specific hardware
- Development of Reference Standards for Wind Turbine Blade NDI








Automated Scanning



# Accomplishments and Progress

## ISU-led sub-projects





# Accomplishments and Progress

## Utility-scale Blade Build and Test

- Significant support from GE
- Most AMI improvements brought together in one blade at utility-scale
- Static and flap fatigue completed
- Edge fatigue nearly complete
- Results will be published as comparisons to GE baseline product



# Accomplishments and Progress

## Labor Reduction

AMII Supported Project	Labor Reduction	Notes
Rotating Carts/Material Handling Systems	2.1%	Reduced surface preparation and peripheral trim
Use of B-Side Heating for Blade Skin Cure Time Reduction	1.1%	Cure Time of each Skin reduced
Trailing Edge Preform Fabrication	1.1%	Layup to preform is MUCH quicker than direct to Skin Mold
Component Handling Systems	2.0%	Improved material movement eliminates wasted time waiting for overhead bridge crane movements.
Development of Bond Cap Preform Section	1.1%	Much less complex layup of bond cap. 8 D/L save an hour.
3D Projected Laser Guidelines for Layup and Fixture Location	3.6%	Labor Savings in Lay-up and Assembly Op's with 8 Person Crew
<b>Advanced Technology Blade Demonstration Efforts</b>		
Fiberglass RodPack	8.2%	Significant savings in Layup, infusion preparation and Infusion time and cure time
TYCOR Sandwich Core	1.6%	Reduction in labor content for core installation
Latent Cure Epoxy Resin	1.3%	Reduction in labor content for part cure
Use of MMA/PU Bond Paste	1.7%	Reduction in Labor for bond assembly
	<b>23.7%</b>	




# Accomplishments and Progress

## Cycle Time Reduction

AMII Supported Project	Cycle Time Reduction	Notes
Rotating Carts/Material Handling Systems	6.6%	Reduced surface preparation and peripheral trim
Use of B-Side Heating for Blade Skin Cure Time Reduction	5.3%	Cure Time of each Skin (LP 7 HP) reduced by one hour
Trailing Edge Preform Fabrication	2.6%	Reduction in infusion time and layup time
Component Handling Systems	6.6%	Improved material movement eliminates wasted time waiting for overhead bridge crane movements
Development of Bond Cap Preform Section	2.6%	Reduction gained by parallel fabrication of complex bond cap layup
3D Projected Laser Guidelines for Layup and Fixture Location	4.6%	Gained efficiencies in both dry layup of kitted glass as well as location of critical bonded components
Advanced Technology Blade Demonstration Efforts		
Fiberglass RodPack	0.0%	Spar Cap Manf does not impact Mold Shell Cycle (Parallel Operation)
TYCOR Sandwich Core	3.2%	Shortened core installation
Latent Cure Epoxy Resin	5.4%	reduced curing time in mold
Use of MMA/PU Bond Paste	4.3%	Shortened bond cycle time
	<b>41.3%</b>	

**Exceeded cycle time goal (35%)!**

# Project Plan & Schedule



## Comments

- Several sub-projects within independent timelines

## Partners, Subcontractors, and Collaborators:

### Partners: TPI Composites, Iowa State University

- True 3-partner collaboration
- Only unanimous sub-projects pursued

### Industry Interaction:

- KMT, Ingersoll, MAG, Globe
- Neptco, BASF, Carter, Henkel, Milliken
- GE

### Universities: Iowa State University

## Communications and Technology Transfer (partial list):

- Sandia Blade Workshops, 2010, 2012 (Albuquerque)
- AWEA WindPower, 2011, 2012
- 2011 Wind & Ocean Energy Conference (Portland Maine)
- 2011 University of Massachusetts Wind Energy Research Workshop
- Wind Turbine Blade Manufacture Conference, 2012 (Dusseldorf)
- 2012 JEC America's Conference & Exhibition
- 2013 Thermosetting Resin Formulators Association Technical Conference
- International Conference on Future Technologies for Wind Energy, 2013
- Industrial Engineering Research Conference, 2013
- IAWind Conference, 2010
- Iowa Wind Energy Association Annual Meeting, 2011-2014
- QNDE, 2011-2013

**Final Report currently in-progress**

### Iowa State University Student Contributors:

- Fanqi Meng Ph.D. Industrial Engineering
- Sunil Chakrapani MS, Ph.D. Aerospace Engineering
- Siqi Zhu MS, Ph.D. Industrial Engineering
- Huiyi Zhang MS, Ph.D. Industrial Engineering
- Ben Wollner MS Industrial Engineering
- Corey Magnussen MS Industrial Engineering
- **Wade Johanns MS Industrial Engineering**
- Luke Schlanglan MS Industrial Engineering
- Luke Mitchell NSF Funded Summer REU student from Penn State
- David Deisenrogh NSF Funded Summer REU student from Michigan Tech

#### BS Industrial Engineering

- Travis Kieffer
- Brittany Becker
- Dan Chrusciel
- AJ Fitzsimmons
- Tom McGee
- Kyle Laska
- Camila Dantas
- Laura McMullen
- Sam Berg

#### BS Aerospace Engineering

- Andrew Gross
- Aaron Edal
- Ryan Krafka
- Alex Wilhelm
- Shivansh Upreti
- Steven Green



## FY14/Current research:

- Complete Comprehensive AMI Project Report
- Make publicly available
- No follow-up work currently planned



Reprinted with permission. Fischer, Martin. "World's Largest Blade Begins Journey to Scotland." SSP Technology A/S. July 17, 2013

Manufacturing and Supply Chain R&D, Wind  
Turbine Logistics and Planning Issues  
Analysis


Manufacturing and Supply Chain R&D

**Jason Cotrell**

NREL

Jason.Cotrell@NREL.gov, 303-384-7056

March 24, 2014



## Problem Statement:

1. Transportation and logistics challenges limit the size and tower height of land-based turbines that can be deployed in the United States.
2. There is relatively little literature that characterizes transportation and logistics challenges and the associated effects on U.S. wind markets.

# Budget, Purpose, and Objectives: Problem Statement

## Summary of Transportation and Logistics Barriers

**Exceeding FAA  
blade-tip height**

**Trucking large-  
diameter towers**



**Hoisting larger nacelles onto  
taller towers**

**Trucking larger blades with  
wider chords**

**Trucking longer blades**

**Trucking larger blades with  
bigger root diameters**

**Trucking heavier nacelles**

### Legend

- Impacts U.S. turbine installations today
- Potentially impacts U.S. turbine installations today
- Potentially impacts future U.S. turbine installations



# Budget, Purpose, and Objectives: Impact of Project

Addressing transportation and logistics barriers provides enduring economic benefits by:


- Enabling larger, taller turbines



- Providing LCOE reduction pathways
- Unlocking new U.S. land for deployment (~ 3000 GW)



- Improving stakeholder support and market stability
- Manufacturing competitiveness and domestic content



Total DOE Budget<sup>1</sup>: \$0.200M

Total Cost-Share<sup>1</sup>: \$0.000M

This project aligns with the following DOE Program objectives and priorities:

- **Optimize Wind Plant Performance:** Reduce Wind Plant Levelized Cost of Energy (LCOE)
- **Accelerate Technology Transfer:** Lead the way for new high-tech U.S. industries
- **Mitigate Market Barriers:** Reduce market barriers to preserve or expand access to quality wind resources
- **Advanced Grid Integration:** Provide access to high wind resource areas, and provide cost effective dispatch of wind energy onto the grid
- **Modeling & Analysis:** Conduct wind techno-economic and life-cycle assessments to help program focus its technology development priorities and identify key drivers and hurdles for wind energy technology commercialization

<sup>1</sup>*Budget/Cost-Share for Period of Performance FY2012 – FY2013*

- Identified mass, cost, and size breakpoints for wind turbine blades, tower, and nacelle
  - Performed interviews with wind industry project developers, OEMs, and transportation and logistics companies
  - Reviewed published literature on trends and developments in increasing wind turbine size, logistics, and transportation issues
- Performed analyses to:
  - Identify which transportation and logistics challenges affect wind plant installations today
  - Determine the increase in turbine size that could be achieved if transportation and logistics challenges are solved

# Accomplishments and Progress: Nacelle Hoisting Barrier

## Barrier

- Current single-crane picks require rare, extremely large cranes to hoist nacelles of larger turbines causing
  - Risk of crane shortages
  - Larger wind plant access roads
  - Limited access to complex terrain
  - Smaller wind turbines and shorter towers



## Benefits of Addressing the Barrier

- Nearly doubles the new deployable land to 614,000 sq km (~3000 GW)

## Recommended Actions

- Reduce uncertainty of multi-crane lifts via stakeholder engagement and demonstration projects

Hub height that crawler cranes can hoist conventional turbine nacelles (with the gearbox and generator hoisted separately) and the number of cranes estimated to be available





# Accomplishments and Progress: *Blade and Tower Transportation Barriers*

Blade designs are limited to lengths of 62 m to accommodate turns



Modern wind turbine blades, tower bases, mid-sections, and nacelles are designed to fit under traffic features and within road weight limits



## Barrier

- Dimensional and weight-transportation constraints increase blade and tower costs and limit deployment opportunities

## Barrier Impacts


- Smaller, structurally sub-optimal (expensive) tower and blade designs
- Economic upper limit on turbine size

## Recommended Actions


- Continued DOE technology development and demonstration of segmented blades and alternative tower manufacturing and assembly methods

## Benefits

- New LCOE reduction pathways
- New deployable land area (will be estimated in FY 14)



# Accomplishments and Progress: Potential Impacts of Mitigating Barriers



### Footnotes

1. The variability in rotor diameter reflects the variability in U.S. wind turbine design parameters (specific power rating, tower heights, blade precurve, etc.); the variability does not reflect the uncertainty or error in the data
2. Assumes hub height range of 80 m to 120 m
3. Assumes specific power rating range of 204 to 350 W/m<sup>2</sup>
4. Assumes rotor diameter to tower height ratio of 1.1

### Legend

- Impacts U.S. turbine installations today
- Potential impact on U.S. turbine installations
- Potential impact on U.S. turbine installations
- ▲ Average value

# Project Plan & Schedule

Summary					Legend											
WBS Number or Agreement Number	6.1.4				Work completed			Active Task			Milestones & Deliverables (Original Plan)			Milestones & Deliverables (Actual)		
Project Number																
Agreement Number																
Task / Event	FY2012				FY2013				FY2014							
	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)				
<b>Project Name: Wind Turbine Logistics and Planning Issues Analysis</b>																
Q1 Milestone: Submission of draft work plan (December 31, 2012)																
Q2 Milestone: Presentation on initial findings - Qualitative prioritization and breakpoints (March 31, 2013)																
Q3 Milestone: Submission of draft executive summary paper (June 30, 2013)																
Q4 Milestone: Submission of final executive summary paper (September 30, 2013)																
<b>Current work and future research</b>																

## Comments

- All work has been completed on time.

## Partners, Subcontractors, and Collaborators

- Coordinating with GLWN blade and tower manufacturing analyses

## Communications and Technology Transfer

- NREL Technical Report: Analysis of Transportation and Logistics Challenges Affecting the Deployment of Larger Wind Turbines  
Summary of Results: <http://www.nrel.gov/docs/fy14osti/61063.pdf>
- AWEA WINDPOWER 2014 Podium Presentation



## FY14/Current research

Support in the development and execution of DOE FOA 982 *U.S. Wind Manufacturing Taller Hub Heights to Access Higher Wind Resources and Lower Cost of Energy.*


## Proposed Future Research

Bigger turbines have potential to

- Provide LCOE reduction pathways
- Unlock new land for deployment
- Increase U.S. manufacturing competitiveness and domestic content

To estimate the deployment rate, we need to quantify

- System cost of energy
  - Costs for big advanced turbines
  - Installation costs
- Permitting and regulatory requirements





## Wind Turbine Repowering and Recycling Assessments

**Jason Cotrell**

NREL

Jason.Cotrell@nrel.gov; (303) 384-7056

March 24, 2014

Total DOE Budget<sup>1</sup>: \$0.300M

Total Cost-Share<sup>1</sup>: \$0.000M

## Problem Statement:

- As wind power facilities age, project owners are faced with plant end-of-life decisions on repowering and recycling
- Little literature exists to help with these decisions or policies

## Impact of Project:

Informs policymakers and the business community regarding the history, opportunities, and challenges associated with plant end-of-life actions related to repowering and recycling

## This project aligns with the following DOE Program objectives and priorities:

- **Optimize Wind Plant Performance:** Reduce Wind Plant Levelized Cost of Energy (LCOE)
- **Accelerate Technology Transfer:** Lead the way for new high-tech U.S. industries
- **Mitigate Market Barriers:** Reduce market barriers to preserve or expand access to quality wind resources
- **Advanced Grid Integration:** Provide access to high wind resource areas, and provide cost effective dispatch of wind energy onto the grid
- **Modeling & Analysis:** Conduct wind techno-economic and life-cycle assessments to help program focus its technology development priorities and identify key drivers and hurdles for wind energy technology commercialization

<sup>1</sup>Budget/Cost-Share for Period of Performance FY2012 – FY2013

### Scoped size of the recycling problem

- Projected recycling quantities and expectations

### Identified capabilities of recycling technologies and industry using a literature review and interviews for

- Blades (composites)
- Rare earth elements
- Generator (copper and steel)
- Gearbox (steel alloys)
- Towers and hubs (coated steel)

### Identified gaps in recycling infrastructure

- Recycling supply chain constraints, technology barriers, standards and regulations





















### Created metrics for assessing the gaps

### Provided recommendations to DoE





# Accomplishments and Progress Recycling

	Potential Economic Burden	Recycling Technology Maturity	Recycling Infrastructure	Recycling R&D Activity	
First Priority	Blades				
	REE				
Second Priority	Generator				
	Gearbox				
	Tower and Hub				

## Legend



*Severe Problem*



*Mild Problem*



*Neutral Impact*



*Positive Impact*



*Technology Infancy*

*Minimal Gaps*

*Some Development*

*Mature Technology*

*No Infrastructure*

*Minimal Infrastructure*

*Some Infrastructure*

*Well Established*

*Ignored Externally*

*Minimal Attention*

*Moderate Attention*

*Lots of Attention*

# Project Plan & Schedule


Summary					Legend							
WBS Number or Agreement Number 6					Work completed							
Project Number 6.3					Active Task							
Agreement Number 6					Milestones & Deliverables (Original Plan)							
					Milestones & Deliverables (Actual)							
Task / Event	FY2012				FY2013				FY2014			
	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
<b>Project Name: Recycling</b>												
Q3 Milestone: Deliver initial literature review and initial work plan			◆									
Q4 Milestone: Deliver Presentation and Executive Summary Report to DOE				◆								
Q1 Milestone: Publish NREL Technical Report					◆							
<b>Project Name: Repowering</b>												
Q3 Milestone: Deliver initial literature review and initial work plan			◆									
Q4 Milestone: Deliver Presentation and Executive Summary Report to DOE				◆								
Q2 Milestone: Draft NREL Comprehensive Technical Report						◆						
Q3 Milestone: Publish NREL Comprehensive Technical Report							◆					

## Comments

- The recycling final report was delayed by DOE to allocate resources to higher priority projects

- Two distinct analyses were conducted to understand the plant age when repowering becomes viable
  1. “Proto-typical” with commissioning years of 1999, 2003, 2008, and 2012
  2. Case studies of three actual wind plants operating in the United States selected for varying vintages and geographical diversity
- These analyses utilized NREL’s System Advisor Model (SAM)
  1. Predicts estimated cash flows from a variety of electric power generation technologies
  2. Net present value calculations were utilized to enable comparisons across time
- Provided recommendations to DOE

# Accomplishments and Progress *Repowering*



## Conclusions

1. Repowering tends to become financially attractive after 20–25 years of service (relative to investing in a nearby greenfield site)
2. Demand for repowering is expected to be low over the next decade
  - Less than 1 GW per year in the early 2020s
  - 1–3 gigawatts per year by the late 2020s.
3. The total estimated value of the repowering market segment is estimated at \$25 billion through 2030



## Partners, Subcontractors, and Collaborators:

Wind and recycling industry members were consulted for information and review.

## Communications and Technology Transfer:


- Repowering: NREL technical report *Wind Power Project Repowering: Financial Feasibility, Decision Drivers, and Supply Chain Effects*  
<http://www.nrel.gov/docs/fy14osti/60535.pdf>
- Recycling: An NREL technical report will be published in FY 14

### FY14/Current Research:

NREL technical report will be completed in May.

### Proposed Future Research:

- Leverage domestic and international recycling technology development efforts.
- Establish a long-term strategy and plan for addressing wind turbine end-of-life disposal and recycling issues and opportunities.



## U.S. Offshore Wind Manufacturing and Supply Chain Development

**Bruce Hamilton**

Navigant Consulting, Inc.

bruce.hamilton@navigant.com - 503.476.2711

March 24, 2014

Total DOE Budget<sup>1</sup>: \$0.15M

Total Cost-Share<sup>1</sup>: \$0.00M

**Problem Statement:** There are anticipated gaps in the infrastructure and supply chain that will serve the U.S. offshore wind (OSW) industry.

**Impact of Project:** Identifies strategies for addressing the infrastructure and supply chain gaps based on a comprehensive analysis of the U.S. OSW supply chain.

**This project aligns with the following DOE Program objectives and priorities:**

Mitigate Market Barriers: Reduce market barriers to preserve or expand access to quality wind resources.

<sup>1</sup>Budget/Cost-Share for Period of Performance FY2012 – FY2013



Chapter	Data Sources	Methodology
<b>1. OSW Plant Costs and Technology Advancements</b>	<ul style="list-style-type: none"><li>• Annual OSW survey</li><li>• Navigant’s OSW project data base</li><li>• Previous research by NREL, OCC</li></ul>	<ul style="list-style-type: none"><li>• Determine the cost breakdown of OSW plants</li><li>• Identify suppliers of OSW turbines and components with US manufacturing facilities</li></ul>
<b>2. Supply Chain Needs to Support U.S. Offshore Industry</b>	<ul style="list-style-type: none"><li>• Analyses conducted with NREL’s ReEDs model</li><li>• Navigant’s and NREL’s databases of wind turbine component suppliers</li></ul>	<ul style="list-style-type: none"><li>• Identify technical trends in OSW manufacturing and construction</li><li>• Determine the mix of plant locations, sizes, turbine types, and foundation types required</li><li>• Determine the specific demand on the supply chain needed</li><li>• Determine the investment and labor required by year for each component type</li></ul>

Chapter	Data Sources	Methodology
<b>3. Strategy for Future Development</b>	<ul style="list-style-type: none"><li>• DSIRE database and its international equivalents</li><li>• Key industry reports</li></ul>	<ul style="list-style-type: none"><li>• Evaluate the benefits of adding manufacturing capacity in the US vs. overseas</li><li>• Research federal and state policies for promoting OSW</li><li>• Identify US policy changes to close any competitive gaps.</li></ul>
<b>4. Analysis of Market Entry Pathways</b>	<ul style="list-style-type: none"><li>• Development experience by consortium partners</li><li>• Interviews with industry stakeholders</li></ul>	<ul style="list-style-type: none"><li>• Identify market barriers</li><li>• Assess likely future market entry pathways</li><li>• Recommendations for removing the identified barriers</li></ul>

Chapter	Accomplishments
<b>1. OSW Plant Costs and Technology Advancements</b>	Data repository for the US OSW industry supply chain, including costs and supplier information for all turbine and BOP components
<b>2. Supply Chain Needs to Support U.S. Offshore Industry</b>	Long-term market forecast for each component for three scenarios
<b>3. Strategy for Future Development</b>	Strategy for the US to close any competitive gaps and maximize domestic market share
<b>4. Analysis of Market Entry Pathways</b>	Road map for domestic suppliers to participate in the OSW market

## Summary of Near-term Domestic Supply Chain Opportunities under a Moderate-Growth Scenario

Component	Market Value (M\$/year)	Timing of Opportunity	Global Supply Risk	Transferability	Opportunity
<b>Wind Turbine Assembly</b>	\$1,817-\$2,200	2021-2025	Medium	Low	Moderate
<b>Blades</b>	\$320-\$391	2021-2025	Low	Low	Moderate
<b>Gearboxes and Generators</b>	\$415-\$507	2021-2025	Medium	Medium	Moderate
<b>Bearings</b>	\$76-\$94	2015-2020	Medium	Low	Moderate
<b>Power Converters</b>	\$81-\$99	2015-2020	Low	High	Favorable
<b>Power Transformers</b>	\$58-\$71	2015-2020	Low	High	Favorable
<b>Towers</b>	\$371-\$454	2021-2025	Medium	High	Favorable
<b>Castings</b>	\$100-\$122	2015-2020	Medium	Medium	Moderate
<b>Forgings</b>	\$39-\$47	2015-2020	Medium	Medium	Moderate
<b>Pitch and Yaw Systems</b>	\$83-\$101	2015-2020	Low	Medium	Moderate
<b>Resins</b>	\$24-\$29	2015-2020	Medium	High	Favorable
<b>Reinforcement Fibers</b>	\$36-\$44	2015-2020	Medium	High	Favorable
<b>Foundations and Substructures</b>	\$1,300-\$1,600	2015-2020	Medium	Medium	Favorable
<b>Substations</b>	\$174-\$213	2021-2025	Low	Medium	Moderate
<b>Array Cables</b>	\$282-\$345	2021-2025	Low	Medium	Moderate
<b>Export Cable</b>	Incl. w/array	Beyond 2025	Medium	Low	High-Risk




# Project Plan & Schedule

Summary					Legend											
Project Number					Work completed Active Task Milestones & Deliverables (Original Plan) Milestones & Deliverables (Actual)											
EE0005364																
Task / Event	FY2012				FY2013				FY2014							
	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)				
<b>Project Name: Offshore Wind Market and Economic Analysis</b>																
Q1 and Q2 Milestones: Issue offshore wind survey		◆														
Q2 and Q3 Milestones: Offshore wind workshops			◆	◆												
Q4 and Q1 Activity: Internal and peer review of Technical Report																
Q2 Milestone: Technical Report delivered to DOE						◆										

## Comments

- Project original initiation date: 10/1/11
- Project completion date: 2/22/13

## Partners, Subcontractors, and Collaborators:



## Communications and Technology Transfer:



- 2 workshops (market and technical trends, supply chain, economic impacts, and policy), plus guest speakers from other teams
- Portions of the reports presented at multiple webinars, podium and poster presentations
- Reports available at [www.navigant.com](http://www.navigant.com).

## FY14/Current research:

- none

## Proposed future research:

- Ongoing maintenance of offshore wind project and supply chain databases



## U.S. Wind Energy Manufacturing and Supply Chain: A Competitiveness Analysis

**Patrick Fullenkamp**

GLWN, Global Wind Network [WIRE-Net]

pfullenkamp@glwn.org 216-920-1956

March 24, 2014

Total DOE Budget<sup>1</sup>: \$0.300M

Total Cost-Share<sup>1</sup>: \$0.000M

**Problem Statement:** There is a need for greater understanding of the key factors determining wind energy component manufacturing costs and pricing on a global basis in order to enhance the competitiveness of U.S. manufacturers, and to reduce installed system costs.

**Impact of Project:** This project is carrying out detailed manufacturing comparisons of four large turbine components manufactured in the U.S., Europe and Asia in order to determine the global cost leaders, best current manufacturing processes, key factors determining competitiveness, and potential means of cost reduction. GLWN has also developed a wind industry scorecard assessing U.S. manufacturers' readiness to supply the next generation of turbines and key balance-of-plant components.

**This project aligns with the following DOE Program objectives and priorities**

- **Optimize Wind Plant Performance:** Reduce Wind Plant Levelized Cost of Energy (LCOE).
- **Mitigate Market Barriers:** Reduce market barriers to preserve or expand access to quality wind resources.

<sup>1</sup>*Budget/Cost-Share for Period of Performance FY2012 – FY2013*




- Develop **standardized component specifications and drawings** with industry and labs (NREL and SNL) for apples-to-apples comparisons between global manufacturers.
- **Visit and collect first-of-a-kind manufacturing cost and process data from 22 suppliers** across the U.S., Europe, and Asia for towers, blades, foundations, and PM generators, for next-generation wind turbines (3MW and 5MW) for both land-based and offshore applications. *[Note: Contract called for 12 site visits, but 22 were completed to improve data reliability]*
- Utilize **Cost Breakdown Analysis** and **Value Stream Mapping**
- Develop an **Industry Scorecard** for 13 key wind turbine and balance of plant components.

				<u>Balance of Plant</u>
• Towers	• Gearbox	• Cast Hubs	• Composite Housing	• Monopile Fdn.
• Blades	• Forge Ring	• Cast Support Base		• Jacket Fdn.
• Generator	• Forge Shaft	• Fab Support Base		• Subsea Cable
- Publicly disseminate information via **public access, web-enabled Wind Supply Chain Map** to include offshore wind industry search features.

- **Manufacturer Selection and Data Gathering Process**
  - **Identified and contacted** current active land based **suppliers in the U.S.A.**, and active land based and offshore suppliers in **Germany and China**,
  - Sent **letter of introduction (DOE & GLWN)** to suppliers explaining scope of project and asked for interest
  - Sent out an official **Request for Quote** with detailed manufacturing drawings, Cost Breakdown Form and set a targeted plant visit date
  - **Plant Visits** included meeting Management Teams, Project Presentation, Hosting Plant Presentation, Review of Process Flow, **Walking the Manufacturing Process** from beginning to end enabling the development of the **Value Stream Map**, Review of the cost data or plan to obtain it.
- **Cost Breakdown Analysis**
  - A Specific cost Breakdown Form was developed which included a complete **Bill of Materials** with weights, general process steps for **Labor** and **Burden**, categories of **SGA, Engineering, Logistics Cost to U.S. Port**, and **Profit**
  - **Quoted Data** was consolidated into spreadsheets for analysis
- **Value Stream Map (VSM)**
  - **VSMs** were generated using data gathered during plant visits.

# Technical Approach Value Stream Map – Towers



## USA 1 Tower – 17 Process Steps



- Identifies areas of waste and improvement opportunities for domestic suppliers
- Better characterize flow of materials, labor, tasks, and information


# Accomplishments and Progress

## TOWERS – Cost Breakdown





### Towers are on avg. 27% of Wind Turbine Cost R&D Projects from findings (partial list):

- **Material** is over 50% of the cost of the Tower of which Steel Plate accounts for 62% in the U.S. Mfg's to work with steel mills to **optimize material and size of plate** to reduce mill cost and mfg process weld time. **Welding in flat state** is more efficient. Circular weld highest labor hours
- **Weld wire size and delivery system** – 1 to 5 wires – magnetic field and weld pattern impact




# Accomplishments and Progress

## BLADES – Cost Breakdown



Blades are on avg. 20% of the Wind Turbine Cost R&D Projects from findings (partial list):



- **Material is ~45%** of the cost of the Blade of which **Resin, Carbon, Glass, & Foam** account for 90% of the U.S. material cost. Material Improvements that provide material cost and process time reductions would be of most benefit
- **Blade design and analysis** looking at: power output, least material usage, shape with 1 or 2 piece for cost and transportability
- **Smart Automation**





# Accomplishments and Progress


## FOUNDATIONS – Cost Breakdown



**Jacket Foundations are on avg.~15% of Offshore Capital Cost**



**R&D Projects** from findings (partial list):

- **Labor and Burden account for 50%** with material ave. 30%. The foundation main lattice is a prime candidate for a design for assembly and design for manufacturing exercise
- A higher volume **series production manufacturing process** needs to be developed and optimized to achieve LCOE



# Accomplishments and Progress

## GENERATORS – Cost Breakdown



### Generators are on avg. 7% of Wind Turbine Cost.

This study is of a **1MW PM Generator** that would need to be scaled for 5MW evaluation

### R&D Projects from findings (partial list):

- **Material is over 60%** of the cost of the PM Generator of which Stator Assembly, Bearing Assembly, and magnet assemblies account for 75%. Alternate material types, shapes, properties and total pieces should be investigated. **Design for Manufacturing** to be applied.

**Detailed Drawings with Bill of Materials** were required to get comparative global apples-to-apples quotes

## Objective Results:

- 1. Determine Global Cost Leaders: China** is the low cost manufacturer in 3 of the 4 product categories (Towers, Foundations, Generators), The **USA** had the lowest cost on Blades. **Germany** was the high cost manufacturer in all categories, although they have ~80% of the content in the North Sea Projects
- 2. Determine Best Current Mfg Process: US had the best process** (Towers, Blades, Generators). **Germany best Foundations. China** has the **highest rework and non-value added process** times
- 3. Key Factors that Determine Competitiveness: China's advantage** is the lowest material, labor, and burden cost. China's focus is on **volume production**.
- 4. Potential Means for U.S. Cost Reduction: U.S manufacturers are within reach of Best Overall: Focus** on Material, **Focus** on Product & Process Design for Lean series production, **Invest** to produce large parts near the coasts .

This **Competitiveness Analysis** was a productive & efficient process to capture detailed global quoted cost data and identify R&D to reduce component cost.

**Proposed Next Project – Forgings & Castings** with 14% & 8% of the Wind Turbine Cost. OEMs indicate there is **minimum competitive U.S. capacity** today

# Accomplishments and Progress

## Industry Scorecard – 280 Mfgs

Component		LAND-BASED		OFFSHORE	
		Investment Req.	Major Hurdles	Investment Req.	Major Hurdles
Towers	3MW	LOW	Capability Exists	LOW - MODERATE	Logistics: Rail/road challenges to ports. Mfgs located in midwest.
	5MW	MODERATE - HIGH	Logistics: Rail/road challenges Fac/Equip: Upgrades likely	HIGH	Logistics: Rail/road challenges to ports. Only one tower mfg port side.
Blades	3MW	LOW	Capability Exists	MODERATE - HIGH	Logistics: Rail/road challenges to ports. Mfgs located in midwest.
	5MW	MODERATE - HIGH	Logistics: Rail/road challenges. Fac/Equip: Upgrades likely	HIGH	Logistics: Rail/road challenges to ports. No blade mfg port side.
Jacket Fdn.	3MW	n/a		MODERATE - HIGH	Jackets are new product for U.S. mfgs. Learning curve can be expected. Investment likely for serial production.
	5MW	n/a		MODERATE - HIGH	Limited offshore experience on AT & GL coast.
Gen.	3MW	LOW	Capability Exists	LOW	Capability Exists
	5MW	LOW - MODERATE	Fac/Equip: Possible upgrades for crane capacity & finish tanks	LOW - MODERATE	Fac/Equip: Possible upgrades for crane capacity & finish tanks



# Accomplishments and Progress


## Industry Scorecard – Key Areas of Concern

Component		LAND-BASED		OFFSHORE	
		Investment Req.	Major Hurdles	Investment Req.	Major Hurdles
Cast Hubs	3MW	HIGH	Capability does not exist for larger than 2.5MW.	HIGH	Capability does not exist for larger than 2.5MW. Facilities concentrated in Midwest. Coastal region casting plant needed.
	5MW	HIGH	Capability does not exist for larger than 2.5MW.	HIGH	
Cast Support Bases	3MW	HIGH	Capability does not exist for larger than 2.5MW.	HIGH	Capability does not exist for larger than 2.5MW. Facilities concentrated in Midwest. Coastal region casting plant needed.
	5MW	HIGH	Capability does not exist for larger than 2.5MW.	HIGH	
Forged Rings	3MW	MODERATE - HIGH	Capability exists. Concern: U.S. mfgs are NOT supplying the wind market. They are not competitive.	MODERATE - HIGH	Capability exists. Concern: U.S. mfgs are NOT supplying the wind market. They are not competitive.
	5MW	MODERATE - HIGH		MODERATE - HIGH	
Forged Shafts	3MW	MODERATE - HIGH	Capability exists. Concern: U.S. mfgs are NOT supplying the wind market. They are not competitive.	MODERATE - HIGH	Capability exists. Concern: U.S. mfgs are NOT supplying the wind market. They are not competitive.
	5MW	MODERATE - HIGH		MODERATE - HIGH	



# Accomplishments and Progress

## GIS Wind Supply Chain Map



### Map Search Features

- ✓ Industry Sector
- ✓ Turbine Component
- ✓ Materials
- ✓ Process Equipment
- ✓ Offshore Construction
- ✓ Onshore Construction
- ✓ Area search

### Manufacturers Data

- ✓ Industry specialty
- ✓ Component capability
- ✓ Contact info

### Wind Farm Data

- ✓ Permitted
- ✓ Proposed
- ✓ Developer
- ✓ Resource links

# Project Plan & Schedule

Summary					Legend							
WBS Number : 5.0 Offshore Wind RD&T					Work completed							
Project Number: DE-EE0006102					Active Task							
Agreement Number					Milestones & Deliverables (Original Plan)							
					Milestones & Deliverables (Actual)							
Task / Event	FY2012				FY2013				FY2014			
	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
<b>Project Name: U.S. Wind Energy Manufacturing. And Supply Chain: A Competitiveness Analysis</b>												
Q1 Milestone 1: Data Gathering-Interview industry experts, establish SC capability criteria						◆	◆					
Q1 Milestone 1: Establish SC criteria, Identify potential suppliers, develop & deploy survey						◆	◆					
Q2/3 Milestone 2: Conduct site visits / Develop VSMs for selected mfgs from Europe, Asia & U.S.							◆	◆				
Q2/3 Milestone 2: Develop CBAs for selected manufacturers Europe, Asia & U.S.							◆	◆				
Q2/3 Milestone 2: Update GIS Map with new SC mfgs, and offshore wind search features							◆	◆				
Q4 Milestone 3: Validate and finalize CBA and VSM data / Validate manufacturers data									◆	◆		
Q4 Milestone 3: Develop Scorecard structure and complete rating									◆	◆		
<b>Current work and future research [no cost extension to contract]</b>												
Q1/2 NC Extension: Extend Scorecard kto include forged shafts, forged rings, submarine cable										◆	◆	
Q1/2 NC Extension: Complete Scorecard										◆	◆	
Q1/2 NC Extension: Complete VSM and CBA for 22 mfg site visits										◆	◆	
Q1/2 NC Extension: Complete Final Report										◆	◆	

## Comments

- Project start date: 01/01/13 Project planned completion date: 12/31/13
- No cost extension was requested to allow time to further validate VSM & CBA data for the 22 mfgs (Original Scope of 12 mfgs), and scorecard was extended to include forged rings, forged shafts, and submarine cable.
- Data reliability was improved with the added manufacturing visits and analysis

## Partners, Subcontractors, and Collaborators:

**GLWN collaborated** with the NREL, SNL, MassCEC Blade Technology Center, manufacturing industry associations, economic development agencies, and several DOC MEP (Manufacturing Extension Partnership) agencies. **Subcontracts** were issued to Ohio University's Voinovich School of Leadership and Public Affairs for expansion of the GLWN Wind Supply Chain Map, and with Mr. Bowen Liu, a Chinese national, for Chinese manufacturing connections, plant visit arrangements, and correspondence.

## Communications and Technology Transfer:

**CBA, VSM, and Scorecard Results:** Manufacturer's cost and process data is considered confidential and is only available to DOE, NREL, SNL, and GLWN. Sensitive data will be aggregated and compiled into the Final Report, appropriate for public dissemination. Weekly Team meetings were held, and 4 internal DOE webinars to review component findings, have been completed to date.

**GLWN Wind Supply Chain Map:** The offshore wind supply chain is communicated through the open-access web-based GIS map, located at [www.glwn.org](http://www.glwn.org). Now available for viewing.

**FY14/Current research:** Expansion of Scorecard, further review and validation of CBA data, and completion of final report.

## Proposed future research:

- Participate in the Evaluation and Implementation of all proposed R&D Projects for Towers, Foundations, Blades, & PM Generators. Continue dialogue with the manufacturers who participated in this study → **This will enable U.S. Manufacturers to be globally competitive, achieve LCOE, capture this new business, and add U.S. jobs.**
- Phase 2 – Apply this same CBA and VSM process to **Forging and Casting** wind turbine content (**14% & 8% of wind turbine cost respectively**).





## Assessment of Vessel Requirements for the U.S. Offshore Wind Sector

Offshore Wind: Optimized Vessel Assessment (Subtopic 5.2)

**Jim Ahlgrimm**

March 24, 2014

(Note – work performed by Douglas-Westwood)



Total DOE Budget <sup>1,2</sup>: \$0.000M

Total Cost-Share<sup>1</sup>: \$0.000M

**Problem Statement:** The installation of offshore wind farms requires a highly specialized fleet of vessels, but such a fleet does not currently exist in the US. The project investigated the vessel-related aspects of offshore wind development, and identified challenges and opportunities related to the installation and maintenance of offshore wind turbines in the US under a number of scenarios.

**Impact of Project:** The final report provides an aggregate view of the vessel-related aspects of offshore wind, and it is intended to serve as a handbook for all stakeholders in the US offshore wind industry. A number of outreach events (including conference presentations and webinars) served to disseminate the findings of the study to a wider audience. A follow-up project with the New Jersey Department of Transportation (completed in 2013) utilized the skillset and findings gained from the completion of the present project.

**This project aligns with the following DOE Program objectives and priorities:**

- **Mitigate Market Barriers:** Reduce market barriers to preserve or expand access to quality wind resources


<sup>1</sup>Budget/Cost-Share for Period of Performance FY2012 – FY2013

<sup>2</sup> Project remained active using DOE funds received prior to FY2012

A model was developed and used to calculate the demand for specialized offshore wind vessels under three scenarios in the US

Deployment Scenarios		54GW by 2030 (HH) High Growth- High Tech Scenario		28GW by 2030 Moderate Growth with High Technology Adoption (MH)		10GW by 2030 - Low Growth - Low Tech Scenario (LL)	
		2020	2030	2020	2030	2020	2030
<b>Total Capacity Deployed by Milestone Date (in GW)</b>		7	54	4	28	1	10
Regional Distribution	Atlantic Coast	4	28	2	12	1	8
	Great Lakes	1	6	0.5	4	0	1
	Gulf Coast	1	5	0.5	4	0	1
	Pacific Coast	1	15	0.5	8	0	0

Summary of Rollout Scenarios




Annual Installation Rate in Each Scenario – US Total

Some practical and economic constraints of vessel deployment (e.g. the Jones Act) were analyzed in detail



**Feeder Barge Transporting Turbine Components**

Suitable shipyards for US-flagged vessel construction were identified and a comprehensive list of current and planned installation vessels was provided in the report



Annual Construction Vessel Requirements in the US

Completed gap analysis by vessel type and various installation strategies. Together, rollout scenarios and vessel strategies determine vessel needs.

US Offshore Wind Development Scorecard														
Vessel-Related Aspects														
		Pre-Construction Phase			Construction Phase							Post-Construction Phase		
		Survey Vessel Availability			Construction Vessel Availability				Support Vessel Availability			O&M Vessel Availability		
		Environmental Survey Vessels	Geophysical Survey Vessels	Geotechnical Survey Vessels	Installation Vessels	Heavy Lift Vessels	Cable Lay Barges (near-shore)	Cable Lay Vessels (open ocean)	Tugs	Feeder Barges / Jackup Barges	Generic Barges / Offshore Supply Vessels	Personnel Transfer Vessels	Heavy Maintenance Vessels	Personnel Transfer Vessels
2013	Atlantic Coast	●	●	●	●	●	●	●	●	●	●	●	●	●
	Great Lakes	●	●	●	●	●	●	●	●	●	●	●	●	●
	Gulf Coast	●	●	●	●	●	●	●	●	●	●	●	●	●
	Pacific Coast	●	●	●	●	●	●	●	●	●	●	●	●	●

Legend	●	No vessels available meeting Jones Act requirements
	●	Vessels in short supply, but available on global market
	●	Work around with existing vessels feasible
	●	Vessels readily available



Total DOE Budget: \$300,000

Total Cost-Share: \$0

- Completed and published final report
- Conducted series of outreach events
- Conducted follow-on project with New Jersey Department of Transportation

Funding was sufficient to ensure the successful completion of the project



# Project Plan & Schedule

Summary					Legend																	
WBS Number or Agreement Number					Work completed																	
Project Number					Active Task																	
Agreement Number					Milestones & Deliverables (Original Plan)																	
					Milestones & Deliverables (Actual)																	
Task / Event	FY2012				FY2013				FY2014													
	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)										
<b>Project Name: Wind Energy Forecasting Methods and Validation for Tall Turbine Resource Assessment</b>																						
Finalizing Modeling Effort																						
Completion of Final Draft																						
Incorporating Modifications and Submission of Final Report																						
<b>Current work and future research</b>																						

## Comments

Project start date: Jan 31, 2012

Planned completion date: Dec 31, 2012 / Actual completion date: Sept 30, 2013

Explanation for slip in schedule: multiple rounds of feedback and peer review, modification requests related to the content of the report and other project work at Douglas Westwood occasionally hindered the completion of the final report

## Partners, Subcontractors:

Clean Energy Group (Warren Leon, Mark Sinclair)

Knud E. Hansen (Douglas Frongillo)

US Offshore Wind Collaborative (Fara Courtney)

Great Lakes Commission, (John Hummer)

## Collaborators:

NREL (Ben Maples, Aaron Smith)

## Communications and Technology Transfer:

- Presented early findings at two conferences in Chicago and Atlanta
- Hosted and presented preliminary findings on three webinars
- Presented findings at two outreach events in Maine and Delaware
- Presented findings at an AWEA offshore wind conference in Virginia Beach in October 2012
- Published final report on DOE Website ([link](#))
- Published article in DOE's Wind Program Newsletter ([link](#))

**FY14/Current research:** None

**Proposed future research:** More detailed state and regional level infrastructure and policy analysis.