

# Commercial Absorption Heat Pump Water Heater

2016 Building Technologies Office Peer Review



U.S. DEPARTMENT OF  
**ENERGY**

Energy Efficiency &  
Renewable Energy

Patrick Geoghegan  
geogheganpj@ornl.gov  
Oak Ridge National Laboratory

# Project Summary

## Timeline:

Start date: 10/1/13

Planned end date: 9/30/17

## Key Milestones

1. Completed breadboard analysis; 9/4/2015
2. Completed alpha prototype; 11/18/15
3. Complete beta prototype fabrication and evaluation; 9/30/16

## Budget:

### **Total Project \$ to Date:**

- DOE: \$1,392K
- Cost Share: \*

### **Total Project \$:**

- DOE: \$2,200K
- Cost Share: \*

## Key Partners:

**A.O. Smith**

**Stone Mountain  
Technologies, Inc.**

## Project Outcome:

An 140,000 BTU/hr GAHP achieving a cycle COP of 1.63 at the rated condition of 47 °F ambient.

The target market is the hospital, hotel and full service restaurant gas hot water heating market.

Field test unit will be ready in FY17.

\* In-kind contribution from CRADA partner – exceeds DOE funding level; exact total is confidential information

# Purpose and Objectives

## Problem Statement:

As stated in the BTO's MYPP


- **2020** Energy use intensity for WH **25%** lower than **2010** energy-efficient baseline – part of **1.8 quads** energy savings
- In **2014**, natural gas provided **3 quads** of the estimated **18** quads of commercial buildings energy use
- AHPWH achieving **45%** energy savings compared to ENERGY STAR-certified gas storage water heater
- **2020** Target Primary Energy Factor **1.2**
- **2020** Target Installed Cost **\$7.14** (\$/First Hour Rating)

# Purpose and Objectives



## Target Market and Audience:

The natural gas commercial water heating market.

A special emphasis on retrofits with minimal total installed cost




# Purpose and Objectives



# Purpose and Objectives



## Impact of Project:

An 140,000 BTU/h HPWH unit achieving a cycle COP of 1.63 at 47 °F rated ambient conditions



# Introduction

- Mechanical compressor replaced by Thermal Compressor
- Ammonia-water absorption system
- Heat Pump Unit sits outside building



# Approach

---

## Approach:

- Thorough single-effect cycle modeling to predict target performance
- System and Component analysis of the prototypes to identify areas of improvement
- Dedicated fabrication team at SMTI

**Key Issues:** High pressure drop on hydronic side and underperforming rectifier component

**Distinctive Characteristics:** Strong and dynamic relationship between partners and subcontractor





# Progress and Accomplishments

## Accomplishments:

- ✓ Optimized single-effect cycle model to predict target performance
  
- ✓ Breadboard testing complete
  - ✓ 87% of performance target at design condition
  - ✓ 3:1 modulation achieved
  
- ✓ Alpha packaged prototype fabricated and tested
  - ✓ 92% of performance target at design condition
  - ✓ 3:1 modulation achieved

# Progress and Accomplishments

- ❖ Cycle COP of 1.45 at design ambient/return of 47/100°F



- ❖ Operation over significant ambient (0 to 55°F) and hydronic return (90 to 125°F) temperature ranges

# Progress and Accomplishments

## Alpha Prototype



Nominal Output : 140,000 btu/hr (41.0 kW)

Gas Input: 97,000 btu/hr (28.4 kW)

Max Supply: 160°F (71°C)

Size: 49" × 66" × 65" ( 1.24 m × 1.68 m × 1.65 m)

Weight: ~1000 pounds

As of now:

Ambient: 0 to 78°F (-17.8 to 25.6°C)



Hydronic Return: 80 to 125°F (26.7 to 51.7°C)

Hydronic Supply: 92 to 142°F (33.3 to 61.1°C)

Modulation: 3:1

# Progress and Accomplishments



- ❖ Cycle COP of 1.51 at design ambient/return of 47/100°F
- ❖ Alpha Unit COP improvement of 0.06 compared to breadboard System



- ❖ 3:1 modulation achieved
- ❖ Environmental Chamber Characterization underway at ORNL

# Progress and Accomplishments

## Market Impact:



EnergyPlus simulations reveal average daily gas consumption drops from **1638** ft<sup>3</sup> to **1104** ft<sup>3</sup> based on real water draw data from a **full service restaurant** located in San Ramon, CA.

# Progress and Accomplishments

---

Lessons, Issues & Opportunities:

- ❖ Rectifier performance below design for Breadboard and Alpha unit
  - ❖ Component design change to limit heat exchange with surroundings
- ❖ Pressure loss management across components with 14 gpm hydronic flow

# Project Integration and Collaboration

## Partners, Subcontractors, and Collaborators:

- **ORNL:** Expertise in building equipment performance evaluation and modeling
- **AO Smith (OEM):** Provides component design, fabrication, testing support, market research, and cost share to the project
- **SMTI:** Provides component and system design, fabrication, testing, testing support, and market research



## Project Integration:

- Both are in constant communication with ORNL via conference calls, emails, and task reports



## Communications:

Commercial Water Heating Using Gas Absorption Heat Pumps ,  
ACEEE Hot Water Forum, Portland OR, February 2016  
ASHRAE 2016 in St. Louis and Purdue Conference 2016

# Next Steps and Future Plans

## Next Steps and Future Plans:

- ❖ Continued Testing & Verification of Alpha unit by ORNL (March to April 2016)
  - ❖ Steady-state testing
- ❖ Fabrication & Testing of Beta prototype at SMTI (May 2016)
  - ❖ Target incremental performance improvements
  - ❖ Controls optimization
  - ❖ Test under commercial water heating conditions
- ❖ Testing of Beta unit by ORNL (June 2016)
  - ❖ Steady-state testing



---

# REFERENCE SLIDES

# Project Budget

**Project Budget:** DOE Total \$2200k

**Cost to Date:** \$1392k

**Additional Funding:** None expected

## Budget History

10/1/13 – FY 2015 (past)		FY 2016 (current)		FY 2017 – 9/30/17 (planned)	
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share
\$1260k	*	\$540k	*	\$400k	*

\* In-kind contribution from CRADA partner – exceeds DOE funding level; exact total is confidential information

# Project Plan and Schedule

Project Schedule												
Project Start: 10/1/13	Completed Work											
Projected End: 9/30/17	Active Task (in progress work)											
	◆ Milestone/Deliverable (Originally Planned) use for missed											
	◆ Milestone/Deliverable (Actual) use when met on time											
	FY2014				FY2015				FY2016			
Task	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
<b>Past Work</b>												
Q4 Go/No-Go: Complete BB prototype design				◆								
Q4 Milestone: Complete BB analysis								◆				
Q4 Milestone: complete alpha								◆	◆			
<b>Current/Future Work</b>												
Q3 Milestone: submit alpha testing report											◆	
Q4 Milestone: submit beta performance report												◆