

Self-Consolidating Concrete for SC Modular Structures

Russell Gentry (PI)

Kimberly Kurtis (Co-PI)

Larry Kahn (Co-PI)

School of Civil and Environmental Engineering (CEE) – Georgia Institute of Technology

Giovanni Loreto (Researcher/Presenter)

College of Architecture and Construction Management – Kennesaw State University (Atlanta, GA)

Bojan Petrovic (Co-PI)

Nuclear and Radiological Engineering) – Georgia Institute of Technology

Jurie van Wyk (Industry partner)

Bernd Laskewitz (Industry partner)

Westinghouse Electric

1. Intro
2. Task 1 – Development of Self-Roughening Concrete (SRC) Mix Design
3. Task 2 – Assessment of Cold Joint Shear Friction Capacity
4. Task 3 – Assessment of Shear and Flexural Performances
5. Task 4 – Validation through Full-scale Test and Modeling
6. Conclusions and Outlooks

1. Intro

Objectives and outcomes

- Development of a self-consolidating concrete mixtures so that concrete placement can be made into steel plate composite (SC) modular structures without the need for continuous concrete placement.

Task 1: Development of SCC with Shear-Friction Capacity for Mass Placement

- SCC mixtures to ensure sufficient shear capacity across cold- joints (self-roughening), while minimizing shrinkage and temperature increase during curing to enhance concrete bonding with the steel plates.

Task 1: Development of SCC with Shear-Friction Capacity for Mass Placement

Task 2: Assessment of Cold Joint Shear-Friction Capacity

- SCC mixtures featuring a self-roughening capability to produce adequate shear friction between cold joints and to produce draft provisions addressing shear-friction, for consideration in the AISC N690-12 Appendix N9 code used for the design of SC modular structures.

Task 3: Assessment of Shear and Flexural Performance

Task 4: Validation through Full-Scale Testing and Modeling

Task 5: Draft Code Requirement for Shear Friction Design of Cold Joints

1. Intro

Problem statement

Some consideration

- Next 10 years 40% of NPP will approach their 40ys of service
 - Average time for construction for existing NPPs: 9.3 years
 - Longest time for construction: 23 years

1. Intro


Looking at Containment Buildings



1. Intro


Looking at Confinement Buildings

- In third generation modular (steel composite) construction of containment structures, concrete is placed between two steel plates, tied together




1. Intro

Facts



- In third generation modular (steel composite) construction of containment structures, concrete is placed between two steel plates, tied together



- To avoid cold joints, requires *continuous concrete placement* → 1200 trucks!

1. Intro

Problem statement

Some consideration

- Next 10 years 40% of NPP will approach their 40ys of service
 - Average time for construction for existing NPPs: 9.3 years
 - Longest time for construction: 23 years

Research need (DOE-NEET)

(1) Assembly and material innovation to enhance modular building techniques such as advances in high strength concrete and rebar, inspection equipment, and pre-assembled rebar systems; and

(2) Advances in modular construction to include improved design codes, improved methods for transport and delivery and advancements in integrated prefabrication.

1. Intro

Objectives

- Development of a self-consolidating concrete mixtures so that concrete placement can be made into steel plate composite (SC) modular structures without the need for continuous concrete placement (cold joint) .

1. Intro

Objectives

- Development of a self-consolidating concrete mixtures so that concrete placement can be made into steel plate composite (SC) modular structures without the need for continuous concrete placement (cold joint) .
- SCC mixtures to ensure sufficient shear capacity across cold- joints (self-roughening), while minimizing shrinkage and temperature increase during curing to enhance concrete bonding with the steel plates.

1. Intro

Objectives

Task 1


- Development of a self-consolidating concrete mixtures so that concrete placement can be made into steel plate composite (SC) modular structures without the need for continuous concrete placement (cold joint) .

Task 2, Task 3, Task 4

- SCC mixtures to ensure sufficient shear capacity across cold- joints (self-roughening), while minimizing shrinkage and temperature increase during curing to enhance concrete bonding with the steel plates.

2. Task 1 – Development of a Self-Roughening Concrete

Proposed idea



2. Task 1 – Development of a Self-Roughening Concrete Strategies

2. Task 1 – Development of a Self-Roughening Concrete Outcomes

Let's take a look!



2. Task 1 – Development of a Self-Roughening Concrete

Proprieties and tests



Self-Consolidating Concrete



Self-Roughening Concrete

Fresh SCC proprieties

- Flowability: flows easily at suitable speed into formwork (T20 = 4-5sec; Flow Slump = 24-26")
- S Groove test (good self-healing ability)
- Hardened Visual Stability Index (VSI = 0)

Hardened SRC proprieties



- Compressive strength: 6-7ksi
- Shrinkage: <math><250 \mu\epsilon</math>

2. Task 1 – Development of a Self-Roughening Concrete


Quantifying surface roughness

Measurement of Roughness

2. Task 1 – Development of a Self-Roughening Concrete Measurements of Roughness - Qualitative



2. Task 1 – Development of a Self-Roughening Concrete Measurements of Roughness - Quantitative




3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Mechanical tests for shear friction characterization



3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Mechanical tests for shear friction characterization



3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Mechanical tests for shear friction characterization



Wall Section

Cold Joint


When wet concrete is cast up to dry concrete.

3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Test Matrix



3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Test Matrix



Cold joint	No	Yes	Yes	Yes	Yes	Yes
Reinforcement ratio - ρ (%)	0.75	0.75	0.25	0.50	0.75	0.75
#3 shear reinforcement	Yes	Yes	No	No	No	No
Steel plate (thickness)	No	No	0.03125 in. (22 gauge)	0.0625 in. (16 gauge)	0.09375 in. (13 gauge)	0.375 in. (16 gauge) h= 2.90 in.
Repetition with 5% LWA	n/a	2	2	2	2	2
Repetition with 15% LWA	n/a	3	3	3	3	3
Tot. N. of repetitions	2	5	5	5	5	5

3. Task 2 - Assessment of Cold Joint Shear Friction Capacity Test Matrix



3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Specimens preparation

Step 1



Step 2



Step 3



Step 4




Step 5



3. Task 2 - Assessment of Cold Joint Shear Friction Capacity



Test set up






3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Behavior at cold joint with internal reinforcement





3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Behavior at cold joint with external steel plates



3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Behavior at cold joint comparing internal and external reinforcement.



3. Task 2 - Assessment of Cold Joint Shear Friction Capacity

Mechanical tests for shear friction characterization



Internal
Reinforcement
 $\rho=0.75\%$



External Steel
Plate
 $\rho=0.25\%$
 $t=0.031$ in.
(22 gage)



External Steel
Plate
 $\rho=0.50\%$
 $t=0.063$ in.
(16 gage)



External Steel
Plate
 $\rho=0.75\%$
 $t=0.094$ in.
(13 gage)






External Steel
Strips
 $\rho=0.75\%$
 $t=0.375$ in.

3. Task 2 - Assessment of Cold Joint Shear Friction Capacity


Behavior at cold joint comparing internal and external reinforcement.

- Self-roughening concrete carries higher load.
- Higher load with greater fraction of LWA.







(a) Non-linear finite element model in LS-DYNA explicit. This initial model approximate the geometry of specimen SP 15 50-1 but with fewer Nelson studs.



(b) Initial loading. Constant shear in the panel zone. In-plane shear stresses shown (all stresses in Pa).



(d) Onset of buckling. Panel zone shear dramatically reduced. Principle tensile stresses align with buckling of plate steel. Buckling is elastic, that is, steel plate does not yield before the buckling initiates. Model also predicts the lifting of the edge of the steel plate.



(e) Buckling progresses. Steel plate begins to yield in the vicinity of two studs (see red on stress contour). Buckling distortion as the plate pulls away from the concrete visible.

LS-DYNA keyword deck by LS-PrePost


Time = 0


Contours of Effective Stress (v-m)

max IP. value

min=0, at elem# 1

max=0, at elem# 1








4. Task 3 – Assessment of Shear and Flexure Performances

Specimen Design




4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design




4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design






4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design





4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design



4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design




4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design



4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design



4. Task 3 – Assessment of Shear and Flexure Performances Specimen Design



4. Task 3 – Assessment of Shear and Flexure Performances

Specimen Design

4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – welding



4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – welding



Monday, OCTOBER 17, 2016 – AMM Workshop – Germantown, MD

Self-Consolidating Concrete for SC Modular Structures

4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – formwork



4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – formwork



Monday, OCTOBER 17, 2016 – AMM Workshop – Germantown, MD
Self-Consolidating Concrete for SC Modular Structures

4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – formwork



Monday, OCTOBER 17, 2016 – AMM Workshop – Germantown, MD

Self-Consolidating Concrete for SC Modular Structures

4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction



4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – ready to be picked up



4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – cast



Monday, OCTOBER 17, 2016 – AMM Workshop – Germantown, MD

Self-Consolidating Concrete for SC Modular Structures

4. Task 3 – Assessment of Shear and Flexure Performances

Casting day

4. Task 3 – Assessment of Shear and Flexure Performances

Casting day

Facing construction challenges

First Trial



Second Trial



Third Trial



In the lab



GLISON COMPANY INC
800-444-1508
www.glison.com
MH-51

4. Task 3 – Assessment of Shear and Flexure Performances

Specimen construction – cast



Monday, OCTOBER 17, 2016 – AMM Workshop – Germantown, MD


Self-Consolidating Concrete for SC Modular Structures


In the lab – After Casting



4. Task 3 – Assessment of Shear and Flexure Performances



Measurements of Temperature





4. Task 3 – Assessment of Shear and Flexure Performances

Measurements of Temperature



4. Task 3 – Assessment of Shear and Flexure Performances

Getting ready to test

After 28dd

4. Task 3 – Assessment of Shear and Flexure Performances Behavior at cold joint




Monday, OCTOBER 17, 2016 – AMM Workshop – Germantown, MD

Self-Consolidating Concrete for SC Modular Structures

4. Task 3 – Assessment of Shear and Flexure Performances


In-Plane and Out-of-Plane set up





4. Task 3 – Assessment of Shear and Flexure Performances

Out-of-Plane behavior



4. Task 3 – Assessment of Shear and Flexure Performances

Monolithic Out-of-Plane failure mode



4. Task 3 – Assessment of Shear and Flexure Performances

Out-of-Plane failure mode



4. Task 3 – Assessment of Shear and Flexure Performances In-Plane and Out-of-Plane failure mode





4. Task 3 – Assessment of Shear and Flexure Performances In-Plane and Out-of-Plane failure mode




4. Task 3 – Assessment of Shear and Flexure Performances

Test Results and Analytical Model



5. Task 4 – Validation through Full-Scale Testing Specimen

5. Task 4 – Validation through Full-Scale Testing Specimen



5. Task 4 – Validation through Full-Scale Testing

External steel plates




5. Task 4 – Validation through Full-Scale Testing Vertical



3. Scaling things up

Three concrete lifts



Concrete Placement 3

Cold Joint 2


Concrete Placement 2

Cold Joint 1

Concrete Placement 1

3. Scaling things up

Cold joint



Concrete Placement 3

Cold Joint 2

Concrete Placement 2

Cold Joint 1

Concrete Placement 1



5. Task 4 – Validation through Full-Scale Testing




5. Task 4 – Validation through Full-Scale Testing

Moving the test specimen



5. Task 4 – Validation through Full-Scale Testing

Test setup




5. Task 4 – Validation through Full-Scale Testing

Test setup




5. Task 4 – Validation through Full-Scale Testing

Expected behavior




5. Task 4 – Validation through Full-Scale Testing

Cold joint detail




5. Task 4 – Validation through Full-Scale Testing

Cold joint detail





5. Task 4 – Validation through Full-Scale Testing

Cold joint detail
Cold joint detail







5. Task 4 – Validation through Full-Scale Testing

Load displacement curve




5. Task 4 – Validation through Full-Scale Testing


Load strain




5. Task 4 – Validation through Full-Scale Testing Model





(a) faces only



(b) faces plus continuous angles



(c) faces plus continuous angles, compression concrete transformed



6. Conclusions

And outlooks

Concluding

6. Conclusions

And outlooks

- SCC which self-roughens has been developed by replacing small fraction of coarse with lightweight aggregate (LWA) → avoids need for continuous placement
- Achieve improved shear friction capacity, which scales with LWA fraction.
- Full scale convalidation
- Meet strength and shrinkage targets.



6. Acknowledgments

The research described in this report was conducted at the Structural Engineering and Materials Laboratory at the Georgia Institute of Technology (Georgia Tech) and funded by the **Department of Energy (DOE)**. The financial support of DOE, the assistance of the laboratory staff at Georgia Tech, and the input of the DOE project advisory panel, including technical oversight from **Alison Hahn** and **Jack Lance**, are gratefully acknowledged.

The following companies contributed material and expertise to the research project:

1. Mr. **Ray Nixon and Ian Houston** of the **Nelson Stud Welding Company** provided significant support to our understanding of headed stud welding and quality control. Mr. Nixon spent countless hours teaching Georgia Tech faculty, students and staff to weld studs and arranged for a gift of a stud welder to Georgia Tech.
2. The **Carolina Stalite Company** provided expanded lightweight slate aggregate for the project. Mr. **Ken Harmon**, PE of the Stalite Company provided technical support during the design of concrete mixes using the lightweight aggregate.
3. **Thomas Concrete** provided ready-mix concrete for casting of the Task 3 and 4 specimens. Mr. **John Cook** and **Justin Lazenby** provided technical assistance in scaling the laboratory mixes used in Tasks 1 and 2 into self-roughening SCC mixes capable of being batched in a ready-mix plant.
4. The **Vulcan Materials Company** provided alluvial sand, crushed man-made sand, and crushed granite aggregate for the laboratory mixes used in Task 1 and Task 2 of the project.

6. Disclaimer

“This material is based upon work supported by the Department of Energy [DE-NE0000667 NEET]”

Disclaimer: “This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.”

Thank you. Questions?



Questions?

