

# Commercial Absorption Heat Pump Water Heater

2017 Building Technologies Office Peer Review



U.S. DEPARTMENT OF  
**ENERGY**

Energy Efficiency &  
Renewable Energy

Patrick Geoghegan  
geogheganpj@ornl.gov  
Oak Ridge National Laboratory

# Project Summary

## Timeline:

Start date: 10/1/13

Planned end date: 6/30/18

## Key Milestones

1. Field site selection: 3/31/17
2. Report evaluation of field study to date: 9/30/17

## Budget:

### **Total Project \$ to Date:**

- DOE: \$1792.9K
- Cost Share: \*

### **Total Project \$:**

- DOE: \$1,920K
- Cost Share: \*

\* In-kind contribution from CRADA partner – exceeds DOE funding level; exact total is confidential information

## Key Partners:

**A.O. Smith**



**Stone Mountain  
Technologies, Inc.**



## Project Outcome:

An 140,000 BTU/hr GAHP achieving a cycle COP of 1.63 at the rated condition of 47°F ambient.

The target market is the hospital, hotel and full service restaurant gas hot water heating market.

Field test unit in FY17.

# Purpose and Objectives

## Problem Statement:


As stated in the BTO's MYPP

- **2020** Energy use intensity for WH **25%** lower than **2010** energy-efficient baseline – part of **1.8 quads** energy savings
- In **2014**, natural gas provided **3 quads** of the estimated **18** quads of commercial buildings energy use
- AHPWH achieving **45%** energy savings compared to ENERGY STAR-certified gas storage water heater

# Purpose and Objectives



## Target Market and Audience:

The natural gas commercial water heating market with a special emphasis on retrofits with minimal total installed cost.



*Buildings Energy Data Book: 3.1 Commercial Sector Energy Consumption, <http://buildingsdatabook.eren.doe.gov>*

# Purpose and Objectives




*Buildings Energy Data Book: 3.1 Commercial Sector Energy Consumption, <http://buildingsdatabook.eren.doe.gov>*


# Purpose and Objectives

## Impact of Project:


An 140,000 BTU/h HPWH unit achieving a cycle COP of 1.63 at 47°F rated ambient conditions



# Introduction - Layout



- Mechanical compressor replaced by Thermal Compressor
- Ammonia-water absorption system
- Heat Pump Unit sits outside building



# Approach

---

- Thorough single-effect cycle modeling to predict target performance
- System and Component analysis of the prototypes to identify areas of improvement
- Dedicated fabrication team at SMTI

**Key Issues:** Field site location




**Distinctive Characteristics:** Harnessing energy from the outside ambient to push well beyond COP values of 1



# Progress and Accomplishments

- Optimized single-effect cycle model to predict target performance
- Breadboard testing complete
  - 87% of performance target at design condition
  - 3:1 modulation achieved
- Alpha packaged prototype fabricated and tested
  - 92% of performance target at design condition
  - 3:1 modulation achieved
- Beta packaged prototype fabricated and tested
  - 97% of performance target at design condition
  - 3:1 modulation achieved

# Progress and Accomplishments



# Progress and Accomplishments

Alpha Prototype



Beta Prototype



30% reduction in size from Alpha to Beta Prototype

## Beta Prototype

Nominal Output :  
**140,000 btu/hr (41.0 kW)**

Gas Input:  
**97,000 btu/hr (28.4 kW)**

Max Supply:  
**160°F (71°C)**

Size:  
**56.25" × 40.75" × 61.25" ( 1.43 m ×  
1.04 m × 1.56 m)**

Weight:  
**~850 pounds**


Modulation:  
**3:1**



# Progress and Accomplishments

Beta unit testing at ORNL:


- Testing performed at full and reduced firing rates
- COP of 1.31 at 47/100°F design ambient/return (90% of 1.45 target)
- Performance limited by underperforming Rectifier



# Progress and Accomplishments


Beta unit testing at SMTI:

- Alternative Rectifier design investigated and installed in unit
- Performance improved to highest level to date
- COP of 1.41 at 47/100°F design ambient/return (97% of 1.45 target)




# Progress and Accomplishments



GAHP Configuration



Conventional High Efficiency Configuration




On average, the GAHP configuration offered an annual gas savings of 35%



\*Geoghegan, P., Shen, B., Keinath, C., Garrabrant, M., "Regional Climate Zone Modeling of a Commercial Absorption Heat Pump Water Heater – Part 1: Southern and South Central Climate Zones," 16<sup>th</sup> International Refrigeration and Air Conditioning Conference at Purdue, July 11-14, 2016

# Progress and Accomplishments

- Payback analysis for 7 cities studied by Geoghegan *et al.* (2016)
- Capital cost of conventional high efficiency system assumed to be \$11,500
- Capital cost of GAHP system assumed to be \$18,800
- At national average of \$1.20/therm, payback is 3.7 years



# Next Steps and Future Plans

- Ongoing reliability testing with Beta 1 at SMTI
- Flyer distributed to identify potential field sites
- Fabrication & Testing of Beta 2 prototype at SMTI (June 2017)
  - Target incremental performance improvements
  - Controls optimization
  - Test under commercial water heating conditions
- Beta 2 Field Test (July 2017)
  - Installed in commercial application in Northeast Tennessee
- Pursue Commercial Buildings Integration funding



*Johnson City, TN*



# Project Integration and Collaboration

## Partners, Subcontractors, and Collaborators:

- **ORNL:** Expertise in building equipment performance evaluation and modeling
- **AO Smith (OEM):** Provides component design, fabrication, testing support, market research, and cost share to the project
- **SMTI:** Provides component and system design, fabrication, testing, testing support, and market research



## Project Integration:

- In constant communication with ORNL via conference calls, emails, and task reports

## Communications:

ACEEE Hot Water Forum, Portland OR, 2016 and 2017

ASHRAE, St. Louis, 2016

Purdue Conference, 2016

IEA Heat Pump Conference, 2017



---

# REFERENCE SLIDES

# Project Budget

**Project Budget:** DOE Total \$1920k

**Cost to Date:** \$1792.9k

**Additional Funding:** None expected

## Budget History

10/1/13 – FY 2017 (past)		FY 2017 (current)		FY 2017 – 9/30/17 (planned)	
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share
\$1760k	*	\$160k	*	\$0k	*

\* In-kind contribution from CRADA partner – exceeds DOE funding level; exact total is confidential information

# Project Plan and Schedule

	◆	Milestone/Deliverable (Originally Planned) <b>use for missed</b>											
	◆	Milestone/Deliverable (Actual) <b>use when met on time</b>											
		FY2016				FY2017				FY2018			
Task		Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Oct-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
<b>Past Work</b>													
Q4 Milestone: submit beta performance report					◆								
<b>Current/Future Work</b>													
Q1 Go/No Go: Field Site selection						◆							
Q4 Milestone: Report Field Study evaluation to date													