

# DOE Bioenergy Technologies Office (BETO) 2019 Project Peer Review

## WBS 2.4.1.103 Biochemical Pilot- Scale Integration (BPSI) Project

---

Advanced Development and Optimization

March 6, 2019

Dan Schell

National Renewable Energy Laboratory

# Goal

## Goal:

Support BETO's and industry's mission to develop cost-effective biofuels and bioproducts by providing a **well-maintained and process-relevant, engineering-scale pilot plant** for process development and technology verification (2022 and 2030).

## Outcomes:

- Integrated, engineering-scale performance data
- Performance data and testing of single unit operations
- Samples and bioproducts

## Relevance:


- Supports process development, technology selection, and verification testing
- Decreases risk and identifies and solves scale-up problems

## Biochemical Pilot Plant



[See additional slides for more information.](#)

# Key Milestones



\*Outlines current plant capabilities without additional funds to support verification run planning and equipment acquisition.

**DMR:** Deacetylation and Mechanical Refining - This pretreatment process option will be discussed later in the presentation.

# Project Budget Table

Budget Periods	Original Project Cost (k\$, Estimated)			Project Spending (k\$) and Balance		Final Project Costs
	DOE Funding	Project Team Cost Shared Funding	Contingency	Spending to Date (Jan 19)	Remaining Balance	What is Needed to Complete
FY19						
- Plant Operations	900	0	0	236	664	
- New Capabilities	200	0	0	50	150	
- Material Production	200	0	0	150	50	
- DMR System Design	200	0	0	5	195	

Outyear budgets determined annually.

# Quad Chart Overview

## Timeline

- Start: FY19
- Merit review cycle: FY19-20
- 15% complete for this review cycle

## Barriers

- ADO-A. Process Integration
- ADO-D. Technology Uncertainty of Integration and Scaling
- ADO-F. First-of-a-Kind Technology Development

## Budget (M\$) – All DOE Funded

Total Cost Pre FY17 (FY16)	FY17 Costs	FY18 Costs	Total Planned Funding (FY19-End of Project)
1.89	2.06	1.33	4.7


- Managed under conversion portfolio until FY19
- Current funding for maintaining readiness, materials generation, and DMR system
- Integration research eliminated in FY18
- Funding doesn't include verification work or money for new equipment

## Partners

Interactions with many facility users:


- NREL BETO
- Consortia
- Office of Science
- Industry
- Academia

# NREL BETO Platform Areas



# Project Interactions

- 2.5.3.105 Agile Biomanufacturing R&D



- 1.3.4.210 CAP Process Research
- 1.3.5.270 ABY2-RACER

- 2.3.4.100 Lignin Utilization
- 2.3.2.100 Biological Lignin Valorization

2.3.1.10X Catalytic Upgrading of Biochemical Intermediates

- 2.2.1.502 Process Integration
- 3.3.1.102 Process Control & Optimization

- 2.5.5.502 Separations Consortium

- 2.4.1.100 Bench Scale R&D
- 2.4.1.101 Continuous Enzymatic Hydrolysis Development
- 2.2.3.100 Low Temperature Advanced Deconstruction
- 2.3.2.105 Biological Upgrading of Sugars....

# Project Overview

## Biochemical Pilot Plant (30+ year-old facility)

- Feed handing through fermentation and downstream processing
- Continuous (1 t/d) or batch processing
- Stand-alone or integrated unit operations
- Highly instrumented and automated

## What this project does (Monetary support from BETO and NREL):

- Maintains and improves facility
- Evolves facility with changes in process technology

## What this project doesn't do:

- Perform research
- Solicit industry for projects

## Specific Objectives:

1. Maintain functional plant meeting all data quality/safety needs
2. Provide process-relevant materials for bench-scale R&D
3. Provide bioproducts for end-user and market acceptance testing
4. Acquire new capabilities to support BETO and industry

1985: First pilot plant, cellulose hydrolysis



1994: First integrated pretreatment/SSF fermentation process and labs




2011: Multiple integrated process trains, high-solids enzymatic hydrolysis






# Historical Pilot Plant Use (2013-2018)



“Contact Day” – On a given day, a BETO or industry (including FOAs) project used at least one piece of equipment or unit operation in the pilot plant. (Does not include routine repair and maintenance activities performed by this project. The scale and cost of the work is not represented.)

# Management Approach

## Current Project Structure (FY19- FY21):



### Management:

- Milestones and Go/No-Go decisions
- Plan updated/revised yearly if needed
- Consider revising plan to 2022

# Technical Approach-Pilot Plant Operations (Task 1)

## Pilot Plant Operations

**Objective:** Manage processes and resources to keep pilot plant safe and operational

**Challenges:**

- Unique, one-of-a-kind equipment
- High cost of parts and repairs
- Material handling difficulties
- Highly instrumented pilot plant

**Critical Success Factor:**

- Equipment/systems available when needed for BETO and industry work

### Equipment/Utilities

Routine maintenance  
Unexpected repairs  
Upgrades

### Documentation

P&IDs  
Operating procedures  
Lockout/Tagout procedures  
Plant operations tracking

### Process Control

SCADA/network upkeep  
Hard/software upgrades  
Instrument calibrations

### Safety

Process hazard analysis  
Management of change  
Readiness reviews  
Safe work and other permits  
Maintaining key safety devices  
Adherence to safety programs

# Technical Approach-New Capabilities (Task 2)

**Objective:** Acquire new capabilities to support BETO's and industry needs

## Technical Approach:

- Identify new needs:
  - Annual consultation with BETO and bioenergy research community
  - Interaction with industry partners
- Define/implement milestones/key decision points

## Challenges:

- Enough resources to acquire new equipment
- Long implementation time

## Critical Success Factors:

- Capabilities available to perform verification runs
- Support industrial projects and collaborations

## Recent focus areas:

- Separations
- Alternative pretreatment option (DMR)




Disc stack centrifuge



Disk refiner


# Process Operations Block Diagram



# Project Background and Previous Work

---


- Plant operations/Ongoing work
- New separation capabilities
- Material production



# Pilot Plant Operations

## Pilot Plant Scope:

- Two high bays – 27,000 ft<sup>2</sup>
- Seven utility systems (steam, air, etc.)
- 96 Process and Instrumentation Diagrams
- ~ 400 electronic instruments
- ~ 1,100 digital control points
- 35 operator screens



## Managing Processes:


- In/Out of service
- Change management
- Calibration: Paperless calibration management program
- Parts inventory/tracking
- Key safety devices
- Repair/maintenance

## Ongoing Work:

- Process hazard analysis
- Control system conversion
- Data management system

Example P&ID: Horizontal pretreatment reactor front end



# New Capabilities (FY17/18)—Separation/Concentration



**Rotary Drum Filter** (New equipment)—separation of solids (microfiltration) from biomass (pretreated or enzymatic hydrolysate) slurries where shear sensitivity is a problem



**Disc Stack Centrifuge** (New equipment)—cells recovery for cell recycle and bioproduct production technologies



**Forced Circulation Evaporator** (Added vacuum to existing unit)—production of concentrated sugar solutions for aerobic fed-batch fermentations





# Material Production

## Types of process samples include:

- Dilute-acid-pretreated corn stover
- Deacetylated and disk-refined (DDR\*) stover
- Deacetylation black liquor
- Enzymatic hydrolysate from DDR stover
- Concentrated enzymatic hydrolysate from DDR stover
- Solid lignin (from enzymatic hydrolysis)

## In FY18: Seven (7) BETO projects received materials from:

- 750 kg (dry) of deacetylated, dilute-acid pretreated slurry
- 600 L of raw DDR enzymatic hydrolysate
- 150 L of clarified/concentrated (> 400 g/L monomeric sugars) DDR enzymatic hydrolysate
- 80 L black liquor
- 20 kg solid lignin



During clarification of an enzymatic hydrolysate, twine used to bale stover pugged the membrane separation modules.

\*Deacetylated stover disk-refined at Andritz's Springfield, OH facility

# Relevance


**We maintain/improve the DOE/NREL biochemical pilot plant directly supporting ADO's and industry's mission to commercialize biofuel production technology.**

- Producing integrated, engineering-scale data
- Testing technical feasibility of single or multiple unit operations
- Generating process relevant materials and bioproducts

**Addresses ADO strategic goals (MYP) to:**

- Decrease commercialization risk
- Identity and solve scale-up issue
- Create added-value co-products
- Demonstrate innovative deconstruction approaches
- Enable high performance separations technology
- Develop technologies for utilizing waste streams
- Evaluate technology options

**The pilot plant has a long history of working with industrial clients testing, solving, and advancing their technical objectives since 1987.**



**BETO Consortia:**

BPS-BioProcess Separations

FCI-Feedstock Conversion Interface

ABF-Agile BioFoundry

CCB-Chemical Catalysis for Bioenergy


# Future Work

---

- Task 1
- Task 2
- 2022 Verification



# Task 1 Future Work Plans




More details on items in the green shaded area are provided in following slides.

# Process Control System Upgrade


## Original System (25-years old)

- Custom-coded software for data transfer
  - Not industry standard
  - Increasingly difficult to maintain
- Long-term viability of the vendor in doubt
- Expensive license fees (~\$25,000/y).



## New System

- Industry standard OPC communications
- License fees are about \$4,000/y
- Easier to learn, program, and maintain
- Modernized user interfaces
- Complete upgrading by end of FY19




# Data Management System Implementation

## Original System

- Data collection initiated by operator (on screen toggle)
- CSV formatted files generated for each unit operation

## New System

- Uses built-in capabilities of the new control system software
- Data sent to SQL database (collection rate varies with equipment use)
- Manual input tags specific data associated with runs, equipment used, etc.
- Data queried and analyzed using Python (large data sets) or exported as CSV file



# Material Production




Thirty-six, 55-gal drums of deacetylated corn stover shipped to Andritz for off-site disk refining.

## FY19: 18 BETO projects are receiving materials from:

- 1,500 kg (dry basis) of DDR\* corn stover producing
  - 400 L of clarified and concentrated sugars from DDR stover
  - DMR solids
  - Black liquor
  - Lignin solids

\*DDR: Deacetylated and Disk Refined



# Task 2 Future Work Plans




More details on DMR system (green shaded area) are provided in following slides.



# New Capabilities – Advanced Pretreatment System




# DMR System Process Design




## Plans (\$300 k currently available)

- HC disk refiner ordered (delivery, summer 2019)
- Place design subcontract (3/30/19)
- Receive HC disk refiner (8/1/19)
- Complete design (9/30/19)
- **Install equipment (6/30/20-Funding TBD)**
- **Complete functional test (9/30/20-Funding TBD)**
- **Add continuous deacetylation (TBD)**



22" HC Disk Refiner

# Future Work—Possible Path To Biochemical 2022 Verification and Beyond



\*Portions or all of this effort may be in collaboration with other national laboratories or industry partners.

# Summary

## Objectives:

- Perform plant maintenance, repair, and upgrading
- Acquire new capabilities and unit operations
- Produce process-relevant materials

## Approach:

- Structured management of resources and activities
- Collaborative approach to identify new capabilities

## Accomplishments:

- Control system upgrade/new data management system
- New separations capabilities
- New DMR capability in progress

## Relevance:

- Facility for process development, evaluation, and verification
- De-risk technologies and identify/solve scale-up issues

## Future work:

- Finish control system upgrade and data management system
- Acquire capabilities to support technology evaluation/verification



# Acknowledgments

## Team Members

- Colby Cleavenger
- Ryan Ferguson
- Matt Fowler
- Casey Gunther
- Wes Hjelm
- Ed Jennings
- Bob Lyons
- Jim McMillan
- Marykate O'Brien
- Dave Sievers



## Funding

- US Department of Energy Office of Energy Efficiency and Renewable Energy Bioenergy Technologies Office
- Beau Hoffman – BETO Bioconversion Technology Manager
- Jim Spaeth – ADO Program Manager

# Thank You

---

[www.nrel.gov](http://www.nrel.gov)

This work was authored by the National Renewable Energy Laboratory, operated by Alliance for Sustainable Energy, LLC, for the U.S. Department of Energy (DOE) under Contract No. DE-AC36-08GO28308. Funding provided by U.S. Department of Energy Office of Energy Efficiency and Bioenergy Technologies Office. The views expressed in the article do not necessarily represent the views of the DOE or the U.S. Government. The U.S. Government retains and the publisher, by accepting the article for publication, acknowledges that the U.S. Government retains a nonexclusive, paid-up, irrevocable, worldwide license to publish or reproduce the published form of this work, or allow others to do so, for U.S. Government purposes.



# Additional Slides

# Responses to Reviewers' Comments

## **Reviewers' Comments (from 2017 peer review meeting report):**

- The pilot scale facility is a must step in any scale-up and as such very important part of BETO's mission to validate near demo scale ready technologies. The team is specialized and know their work and used good practices of mixture designs and scale-up/down models to address scale-up issues. The challenge of lacking publicly available data is understood. The project has good cross talk with the bench-scale integration and analytics team and work closely with the separation consortia. Overall good management and technical approach. It is recommended though that a community of pilot plant facility and know-how (APBDU, NREL, SCADA, bench scale validation and the separation and analytics consortia) will be integrated somehow as they all are continued needed support functions.
- Management structure is rather loose. The team is working on multiple projects as well as doing scale-up work for industry. One clear (and necessary) focus is developing capabilities and equipment to match the needs of BETO efforts. This is another great industry-supporting project.

## **Response to Reviewer Comments:**

We appreciate the reviewers' comments and their efforts reviewing this project. We will continue to evaluate pilot-scale processing needs and acquire capabilities with BETO's support to make the biochemical pilot plant a relevant facility for industry and BETO to develop and test new hydrocarbon biofuel production technologies. As technology development continues and process options for pilot-scale verification are identified we will continue to increase our collaborations with other BETO projects, in particular the Biochemical Bench Scale Integration (BSI) project. An even closer collaboration is planned between BSI and this project beginning in FY20 and indirectly with industrial and academic stakeholders. A capabilities workshop with all BETO facilities performing pilot-scale work that would include industry representation might be useful for soliciting recommendations for new equipment and how best to use these various facilities.



- Crater, J.; Galleher, C.; Lievense, J. (2017) “Consultancy on Large-Scale Submerged Aerobic Cultivation Process Design - Final Technical Report” SR-5100-67963, NREL, <http://www.nrel.gov/docs/fy17osti/67963.pdf>.
- Humbird, D.; Davis, R.; McMillan, J. 2017. “Aeration Costs in Stirred-Tank and Bubble Column Bioreactors.” Biochemical Engineering Journal. 127, 161-166.



# DOE Bioenergy Technologies Office (BETO) 2019 Project Peer Review

## WBS 2.4.1.103 Biochemical Pilot-Scale Integration (BPSI) Project

---

Advanced Development and Optimization

March xx, 2019

Dan Schell

National Renewable Energy Laboratory

# Project Scope Change Table

Scope Changes	Date	Logic / Reasoning	Approval / Rejection Date
No scope changes			


# Risk Registry Table

		Risk Identified		Mitigation Strategy		Current Status
Risk ID	Process Step	Risk Description	Severity (High/Med/Low)	Mitigation Response	Planned Action Date	Active/Closed
	n/a	Sufficient funds are needed to acquire new pilot-scale equipment and capabilities for process development efforts needed for BETO and industry projects or possible verification runs.	Med	Reduce cost by acquiring used equipment, finding other funds, or reducing scope of research efforts. 2nd strategy is to scale back on possible verification runs or demonstrate some unit operations at a smaller scale.	n/a	n/a
	n/a	Delays in submitting equipment requisitions are possible due to uncertainties in funding, inability to find available equipment within target funding, and lack of response from vendor.	Low	Schedule delays may be accepted and/or mitigation strategies can be developed once the magnitude of delays are known.	n/a	n/a
	n/a	Equipment failures can lead to significant production delays.	Low	Preventive maintenance as needed to maintain key equipment, but random/unexpected failures still occur particularly with equipment handling solids.	n/a	n/a

# Risk Registry Table - Continued

	Risk Identified			Mitigation Strategy		Current Status
Risk ID	Process Step	Risk Description	Severity (High/Med/Low)	Mitigation Response	Planned Action Date	Active/Closed
Feed Handling						
1	Milling	Fire hazard from sparking	High	Suppression system		
2	Dust collection	Explosion mitigation	High	Suppression or deflection system		
3	Feed delivery	Fall into feed hopper hazard	High	Interlocks and barriers	9/30/19	
4	Feed delivery	Hopper failure	Low	New hopper design		
5	Feed handling	Dust accumulation	Med	Dust control and mitigation strategy	6/30/19	
Pretreatment						
1	Feeding reactor	Bridging above plug screw feeder	Low	Automatic bridge breaking system	9/30/20	
2	Reaction	Reactor fouling	Low	New pretreatment option		
Separations						
1	Lignin recovery	Separation failure	Low	Accept more costly option		

# Biochemical Pilot Plant



# Pilot Plant



## North High Bay (1994)

- Integrated 1 ton/d process train
- Feed handling through product separation
- Houses utilities systems

## South High Bay (2010)


- Two integrated 0.5–1.0 ton/d process trains
- Feed handling through high solids enzymatic hydrolysis
- Space for expansion



# North High Bay Equipment

## Pretreatment

- 1.0 ton/d vertical reactor
- 0.2 ton/d horizontal screw reactor
- 160-L batch reactor
- 1-L and 4-L batch reactors



## Fermentation

- 30-L seed vessel
- Two 160-L vessels
- Two 1500-L vessels
- Four 9000-L vessels



## Separations

- Distillation column (19-sieve trays)
- Perforated 100-L basket centrifuge
- Forced recirculation evaporator





# South High Bay Equipment

## Feed Handling

- Two knife mills
- Continuous conveyance systems
- Multiple hoppers and weigh belts

## Pretreatment

- 1.0 ton/d vertical reactor
- 0.5 ton/d horizontal screw reactor

## Enzymatic Hydrolysis


- 1900-L paddle reactor
- Four 4000-L paddle reactors

## Separations

- Screw presses
- Perforated 450-L basket centrifuge
- Rotary vacuum drum filter
- Cross flow filter



Baghouse



Vertical reactor



4000-L Paddle Reactor



Horizontal Reactor



1900-L Paddle Reactor



Centrifuge


# Pilot Plant Utilities Systems

- Steam
  - 500 psi, 3400 lb/h boiler
  - 300 psi, 1200 lb/h backup boiler
  - Distributed in high (up to boiler pressure) and low pressure (35 psi) headers
- Cooling water
- Process water
- Chilled water
- Deionized water
- Hot process water
- Plant compressed air



# DMR System P&ID

- H-01**  
**Feed Hopper**  
 Type: Live Bottom
- CV-02**  
**Conveyor**  
 Type: Belt
- WB-03**  
**Weigh Belt**
- DR-04**  
**Disc Refiner**  
 Type: High Consistency
- B-05**  
**Vent Blower**
- CV-06**  
**Conveyor**  
 Type: Belt
- I-07**  
**Mix Tank**  
 MAWP: ATM  
 MOC: FRP/PE
- A-08**  
**Mix Tank Agitator**  
 MOC: 316 SS
- P-09**  
**Pump**  
 Type: Lobe
- DR-10**  
**Disk Refiner**  
 Type: Low Consistency
- P-11**  
**Pump**  
 Type: Lobe



- Notes:
- 1) Large diameter chute, possible crane drum lifting
  - 2) Snorkel/Hood for steam takeoff
  - 3) Minimize distance to WB-03 or consider switching CV-02 and WB-03 positions

NO. REVISIONS						FILE INFORMATION						ENGINEERING REVIEW		
NO.	DATE	BY	APPR'D.	BAE	NO.	DATE	BY	APPR'D.	BAE	NO.	DATE	APPROVAL	DATE	
01	4/25/18	CC			1	DATE				1	DATE			
						2				2				
						3				3				
						4				4				
						5				5				
						6				6				
						7				7				
						8				8				
						9				9				
						10				10				

**CONREL**  
 National Renewable Energy Laboratory  
 15013 Colorado Avenue  
 Golden, CO 80501  
 U.S. Department of Energy  
 Office of Biological Energy

IBRF INTEGRATED BIOREFINERY RESEARCH FACILITY PROPOSED SHB DD/DMSR SYSTEM PIPING & INSTRUMENT DIAGRAM		
DRAWING NO. 18-018	DRAWING NO.	REVISION NO.
0		0
DWG. PROJECT NO.	DWG. TYPE	APPROVAL NO.
		0