

DOE Bioenergy Technologies Office (BETO) 2021 Project Peer Review

**An Advanced Pretreatment/Anaerobic Digestion (APAD)
Technology for Increased conversion of Sewage Sludge
to Bio-natural gas in small-scale
wastewater plants of less than five dry ton sewage
sludge per day**

3/10/2021

Organic waste

Principal Investigator: Birgitte K. Ahring
Washington State University

Information on Timeline of the APAD Project

- The project was submitted for the BETO 2019 call FOA-0002029 under the area AOI 9: Rethinking Anaerobic Digestion July 2019
- The selection of the proposal was October 2019

BP 1 moved slowly due to Covid-19

- The PI worked with the BETO Project Managers (Mark Philbrick and Ian Rowe) on revision of the SOPO until end of January 2020
- The Review meeting was in April 2020 with positive outcome
- The final contract was received by WSU in the end of August 2020 with a DOE start date for BP2 of July 1, 2020
- The sub-awards were finalized and the project started work on October 1, 2020

BP2 has now been under way for 4 months

- A no-cost extension of the BP2 end date will be applied for in the Fall 2021

This Project is 4 month into execution

Project Overview

Problem: Energy production from sewage sludge especially at small-scale using Anaerobic Digestion (AD) typically do not produce significant value with the current available AD technology due to low Carbon Conversion Efficiency (CCE) (generally less than 50%). We propose a novel concept, which will overcome this problem and produce significant more energy product in a more valuable form as Bio-natural gas.

Project goals:

1. *Significantly increase the CCE of conventional AD (from 45 to 70% end of BP2 and to 75% end of BP3)*
2. *Upgrade biogas (60% CH₄/40% CO₂) to RNG. Converting 80% of CO₂ with H₂ to more CH₄ end of BP2 and 95% of CO₂ end of BP3.*


Importance:

The project could significantly reduce cost and energy consumption of treating and disposal of sewage sludge along with greenhouse gas emission. Production of RNG expand the use of sewage sludge as a feedstock for producing transportation biofuels from organic waste.

Risk:

The risk of the project is that the defined milestones will not be met. However, the baseline data forming the background for the project showed a CCE improvement of 30% well above the current state of art for AD of sewage sludge.

Project Overview




In the USA there are far more Wastewater Treatment Plants (WWTPs) with small wastewater and Sludge volumes (ca. 30% of all sludge is produced here and ready for exploitation)

Production of RNG at small WWTP could stimulate local economy in rural areas while reducing disposal cost for sewage sludge

1. Management

Traditional Management Phases- we are now in the Execute Phase



1. Management

APAD Partners

Washington State University (WSU)

B. Ahring (PI), **M. Garcia-Perez**

Role: Lead Task 4 (AD), Task 5 (CO₂ conversion), Task 6 (Pilot testing)

CleanVantage LLC

R. Garrison (lead), **P. Teller**

Role: Lead Task 2 (Collection/dewatering of sludge), Task 3 (Pretreatment), Task 6 (Pilot testing)

PNNL

R. Zheng (lead), **T. Seiple**

Role: Lead Task 7 (TEA, LCA and Bio-solids disposal model)

Jacobs Engineering

W. Breshears (lead), **Jarrold Burden**

Role: Operates WW WTP, Providing sewage sludge, Input on Operations, Upscaling

City of Walla Walla

F. Nicholson (lead)

Role: Provides data for WW and engaged in the upscaling of the APAD into WW WTP

Richland WWTP is further connected to the project

1. Management



All partners are members of the management team.
Items such as those shown are addressed at our monthly meetings.


1. Management

Project Risks and Proposed Abatements

Project Risk	Project Abatement
Concentration of AD digested sewage sludge to 25% or more is found to be difficult	We will solve this by using other flocculants and concentration methods
AWOex pretreatment do not produce the CCE's as anticipated	We will use other oxidants than oxygen to enhance the effect
The CO ₂ conversion with H ₂ to CH ₄ do not produce the expected reductions in CO ₂	We will operated the methanogenic fermentation in two steps after each other to increase the overall efficiency

2. Approach

The APAD Process



The boxes are the innovate steps of the APAD Process



2. Approach

Advanced Wet Explosion Pretreatment

AWOex was originally developed for pretreating lignocellulosic biomass materials for producing biofuels

AWOex has been tested with 26 different types of biomass and shown a superior ability to produce a pretreated homogenized material at 30% DW, which can produce high sugar yield (150 g/L) with low cellulolytic enzyme doses

AWOex scaled up with manure/straw:
AD-Booster (3 ton/hour),
Ribe Biogas Denmark (30% increased roduction CH4 production).



2. Approach

Advantages of pretreating remaining solids after AD1


- Reduces the volume of biomass to be pretreated, which lower cost of pretreatment
- Performing the pretreatment only on the recalcitrant portion of the sludge
- The pretreatment is more effective after a biological conversion process
- The AD2 reactor can operate at low retention time and high solids loading due to changed rheology of the pretreated sludge
- Economically sound and efficient (uses max. 15% of extra energy produced)

2. Approach

Evolving Development of Technology Configuration to Enable Success


Base Case

Base Case (28.6% CH₄ Increase compared to conventional AD)




Intermediate Case

Intermediate Case (85% CH₄ Increase compared to conventional AD)



End Case (135% CH₄ Increase compared to conventional AD)

End Case




2. Approach

Tasks	Milestone Type	Milestone Description	Responsibility	Anticipated months
Task 1	Milestone	Verification by DOE team; intermediate and final visit	DOE Team/ project Partners	Months 1-5, 6-21, 22-36
Go/No-Go#1		Demonstrating the baseline goal: 30% higher Carbon conversion efficiency and methane yield compared to Conventional AD.	Verification Team	April 1, 2020
Go/No-Go#2		Demonstration of the intermediate goals: 40% higher Carbon conversion efficiency and 80% CO ₂ conversion from biogas giving 85% higher CH ₄ yield compared to conventional AD.	Verification Team	December 31, 2021
End Goal Verification		Demonstration of the end goal: 50% higher Carbon conversion efficiency and 95% CO ₂ conversion from biogas giving 135% higher CH ₄ yield compared to conventional AD	Verification Team	April 31, 2023

Overall Milestones for the APAD project

Gantt Chart over APAD project



2. Approach


Process Work Flow

BP 2:

- Examining and optimizing each process stepwise separately in the laboratory starting with concentration of sludge after AD 1. Development of a Mass and Energy balance for the optimized process
- Using TEA to guide the way and for selection of the best overall operational conditions for each step.

BP 3:

- Testing and optimization of the integrated process operated at the optimal operational conditions in small pilot scale corresponding to 11 Gallons AD 1 sludge/day
- Verification of the final Mass and Energy Balance
- Input from pilot will be used for the final TEA, LCA and Sludge disposal model



3. Impact

- The project will allow for systematic testing and optimization of the APAD process and for an understanding of the potential of this process compared to conventional AD
- The project will further allow for a better understanding of biological biogas upgrading to bio-natural gas using a realistic set-up with real materials
- Our stake-holders in the project are small wastewater treatment plants (WWTP in Walla Walla and Richland) and our focus is on designing realistic processes, which are economically viable in small scale (max. 5 ton/day sewage sludge).
- However, the results will further be interesting for larger WWTP plants situated in larger cities where the RNG can be integrated with the natural gas grid.

3. Impact

Dissemination of Insights

- We will publish data from the project on an ongoing basis. The PI has over 500 papers with review, an H-index of 87 and ca. 30,000 citations.
- The data we produced in the fourth quarter of 2020 (our first period) along with the preliminary results from BP1 is now being collected for publication. We expect to submit this paper in the second quarter of 2021.
- We are always on the forefront of patent opportunities- the PI has 12 international patent and new inventions will be covered along the way.
- Our plan is to present results from the project at conferences in the end of 2021/2022.
- We are planning on hosting a Workshop for a broader group of stakeholders when the integrated pilot plant is up in operation (BP 3).

“We have great expectations for the APAD project and the opportunity of producing more biogas from our sewage sludge” Frank Nicholson, City of Walla Walla

4. Progress and Outcome


Results from Task 2: Collection and concentration of sewage sludge

- We have collected sewage sludge from Walla Walla WWTP and tested the dewatering ability with different methods. Decanter centrifugation was found to be superior for concentrating digested sludge- but need another flocculent than used at Walla Walla WWTP today for reaching the goal of 25% dry matter or more
- Sludge flocculated at Walla Walla WWTP using T-Floc B-135, an aluminum chlorohydrate, showed problems with decanter centrifugation due to clumping of the material.
- We have established a collaboration with Thatcher Company (major flocculants producer) and will test 4 other cost-effective flocculants in the first quarter of 2021 (based on polyacrylamide).

Overall: Task 2 has established a significant link between flocculation technique, performance, and cost.

4. Progress and Outcome

Results from testing of flocculent T-Floc B-135 on methane yield from digested sewage sludge show no inhibition at normal concentrations of the flocculent.





4. Progress and Outcome

TASK 3:

Pretreatment of dewatered digested sewage sludge by Wet oxidation. Methane Yield from pretreated (180°C-left) and (210°C-right) AD1 sewage sludge at different oxygen levels (H₂O₂ addition) compared to control without pretreatment

Overall: Pretreatment at 180°C gives higher methane yields and the highest yield is with 9% H₂O₂




4. Progress and Outcome


Task 7.1 – Model biosolids disposal practices and costs

► Distribution of 1-5 Mgal/d (small) WWTPs

Flow Range (Mgal/d)	Total WWTP	% WWTP	Total Flow (Bgal/d)	% Flow
<1	11392	76	2.3	7
1 -5	2511	17	5.9	17
>5	1105	7	26.2	76
Total	15008	1	34.4	1



► Transportation cost modeling approach selected – Adoption of approach by Marufuzzaman et al. (2015) and Berwick and Farooq (2013) to estimate the scaled delivery costs of post-APAD biosolids for representative wastewater treatment plants ranging in size from 1 to 5 Mgal/d of average dry weather influent flow.



4. Progress and Outcome

Task 7.1 – Model biosolids disposal practices and costs

- ▶ **Hauling Costs** – Truck transport costs to include fixed and variable costs. Fixed costs are independent of travel distance and are incurred regardless of truck utilization. Variable costs depend on the total distance travelled per trip.
- ▶ **National Average Tipping Fees** – Tipping fees are a major cost component of the landfill disposal pathway. A recent national survey conducted by the Environment Research & Education Foundation (EREF, 2019) indicated a national average landfill tipping fee of \$55.36 per wet ton.
- ▶ **Spreading Costs** – Pending completion of cost models calibrated using publicly available reporting data, input from regional biosolids managers and wastewater experts, and recent municipal budget and planning info.

4. Progress and Outcome

Task 7.2 – LCA/TEA

- ▶ **Process model development** – Literature survey conducted on published anaerobic digester process models. Model selection for APAD will be finalized with input from project teams. AWOEx and biogas upgrade reactor model development will start next quarter.
- ▶ **Process economics** – Costs associated with thermophilic anaerobic digestors, biogas cleanup unit, and APAD derived additional wastewater streams are best sourced using wastewater treatment industry specific simulation and costing tools, rather than Aspen. Subcontract with a US wastewater treatment consulting firm is being explored to produce independent and realistic cost estimates.

Summary

- **Overview.** The APAD project uses AWOex to enhance the CCE of digested sewage sludge and a biological upgrading process for converting CO₂ from biogas into pure methane.
- **Management.** The project is managed through a monthly project meeting included all partners where issues related to the Task, Resources and Risk etc. are discussed and resolved.
- **Approach.** The major process step will first be optimized separately and then integrated in the laboratory/pilot to provide input for the Mass and Energy Balance, TEA, LCA and Sludge Disposal Model.
- **Impact.** The project could significantly increase energy production of sewage sludge as well as reduce cost of disposal of sewage sludge. Production of RNG expands the use of sewage sludge as a feedstock for producing transportation biofuels from organic waste
- **Progress and Outcomes (4 month)**
- Have established a significant link between flocculation technique, performance, and cost of concentrating digested sewage sludge to 25% DW or more
- Developed new partnership with the flocculent producer Thatcher Company
- Pretreatment at 180°C with/without Oxygen (6-9%) was found superior over 210°C and the methane yield increased 2.6 times over control (no pretreatment) and 1.4 time over samples pretreated with heat (180°C), but no oxygen
- Work on the sewage sludge disposal model has established hauling and tipping fees while spreading costs are in progress

Quad Chart Overview (Competitive Project)

Timeline

- Project start date: Our date is October 1, 2019
- Project end date: Our date is April 31, 2023

	FY20 Costed	Total Award
DOE Funding	(10/01/2019 – 4/30/2023)	\$2,428,281
Project Cost Share	\$607,070	\$3,035,351

- Partner 1: Washington State University
- Partner 2: Clean-Vantage, LLC
- Partner 3: PNNL
- Partner 4: Jacobs Engineering
- Partner 5: City of Walla Walla

Project Goal

The main goal of this project is to develop and demonstrate a concept for significant increased Carbon Conversion Efficiency of sewage sludge compared to conventional Anaerobic Digestion. A second goal is to develop a biological process for cost-effective conversion of CO2 from biogas into pure methane with hydrogen addition.

End of Project Milestone

End case: 50% improved Carbon conversion efficiency with conversion of 95% of the CO2 in the biogas with hydrogen to results in a total increase of 135% CH4 compared to conventional AD. A comprehensive techno-economic analysis (TEA) and a Life-cycle assessment will be available along with a Biosolids disposal model .

Funding Mechanism

BETO 2019 April call FOA-0002029 under the area AOI 9: Rethinking Anaerobic Digestion. The requirements for the call was a process showing 50% increase in CCE or a 50% decrease in disposal cost.

Appendix

WSU Pilot facility used for APAD



The Team In-front of one AD1 at Walla Walla WWTP

