


VacuGlass: Low-cost, Reliable, High Performance Vacuum Insulated Glazings (VIGs)



University of Maryland, Dept. of Mechanical Engineering
Jungho Kim (Professor) and Ratnesh Tiwari (Assistant Research Professor)
301-405-5437, kimjh@umd.edu

Project Summary

Timeline:

Start date: March 1, 2019

Planned end date: April 30, 2022

Key Milestones

- Demonstrate R10 insulation and vacuum retention; March 2020
- Vacuum retention in 12" x 12" sample, reliability test setup completed. R10 insulation; Mar 2021

Budget:

Total Project \$ to Date:

- DOE: \$543,627
- Cost Share: \$117,804

Total Project \$:

- DOE: \$902,567
- Cost Share: \$225,642

Key Partners: None

Project Outcome:

- Develop high-performance vacuum insulated glass (VIG) which can be used as a direct replacement for single pane window and other IGUs.

Team



Jungho Kim
Professor



Ratnesh Tiwari
Assistant Research Professor


Dept. of Mechanical Engineering, U. of Maryland

Challenge and Impact

Energy Use in US Buildings (35% of US CO₂ Emissions)

Heat loss through windows:
7% total US carbon emission

\$7.8 billion/year



US Energy Information Administration, Annual Energy Outlook 2018, www.eia.gov/outlooks/aeo

GOAL: CUT ENERGY LOSS THROUGH WINDOWS BY >75%

Challenge: Window Performance

Walls of your home: R-20 to R-30




Image: brennancorp


R-1

R-2 to R-4


R-7




Current VIG Technology



Vacuum insulating glass structure diagram



Approach: Triple Pane VIG Technology





Advantages:

- Many individually sealed cells
- Seal redundancy
- Distributed stresses
- Can cut larger panes to size
- Thin window

Disadvantages:

- High cost?



Progress: Thermal Simulations

Base Case Geometry:


Inner and outer glass: 5.7 mm thick

Middle glass: 1.1 mm thick







Fibers: square cross section 0.3 mm spaced 150 mm apart

Emissivity: 0.022 on surfaces 2 and 5 with other surfaces 0.88


R-11.2



Progress: Thermal Simulations





Progress: Stress Analysis Results





Deflection of the middle pane

Stress concentration in the middle pane

Progress: Thermal and Stress Analysis



Progress: Experimental Results for TPVIG



Measured center of Glass **R-value = 13.2**



Simulations



Experiment

Progress: Refocus Research to Address VIG Problems

TPVIG Pros:

- Demonstrated High R-value
- Reliable seal
- Less stresses

Drawbacks:

- Lines are visible
- Manufacturability issues
- Higher stresses in the middle pane need thin tempered glass

Progress: Challenges for VIGs

High cost

- Low throughput at temperatures (400-500C)
- ~ \$20-\$40/ft²


Large thermal stresses on the seal

- Temperature differential between inside and outside panes



Progress: Metal Seals


- Low temperature sealing
- Flexible seal hence minimal seal stress
- Low cost



Progress: Reliability Testing

- **Accelerated thermal cyclic testing as per ISO 19916-1**
- **Thermal cycling between 25C and 150C**
- **Completed more than 500 cycles**
- **Currently making 14"x20" windows to send out for third party testing**

Thermal cycle testing example.



Stakeholder Engagement

- **Customer validation (I-corps)**
- **State of Maryland commercialization grant**
- **Discussion with possible first market partners in place**
- **Discussion with manufacturing partners**
- **Identifying buildings to demonstrate the VIGs**

Remaining Project Work

- Further reliability testing
- Third party inspection
- Manufacturing analysis
- Setup a small-scale demonstration line

Thank You !



Jungho Kim (Professor)
301-405-5437
kimjh@umd.edu

Ratnesh Tiwari (Assistant Research Professor)
301-405-7098
ratnesht@umd.edu

REFERENCE SLIDES

Project Budget

Project Budget: Total budget of \$1.12M (no change)


Variances: Glass coated fiber concept was modified and hence the budget was reallocated to creating low temperature seal.

Cost to Date: \$661,431

Additional Funding: We received MII funding \$115K (frit paste development and commercialization)

Budget History					
5/1/2019 – FY 2020 (past)		FY 2021 (current)		FY 2022 – 4/30/2022 (planned)	
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share
\$461,469	\$126,849	\$342,475	\$77,008	\$98,623	\$21,785

Project Plan and Schedule



Project Plan and Schedule

- Project original initiation date & Project planned completion date: 5/1/2019 to 4/30/2022
- Schedule and Milestones:
- Explanation for slipped milestones and slips in schedule
- Go/no-go decision points
- Current and future work

