

San Pasqual Band of Mission Indians Microgrid



Tribal DOE Conference | November 13, 2023

Project Team

SPBMI

John Flores, Environmental
Director

David Martinez, Public Works
Director

Desiree Morales, Utilities
Manager

Owner's Representatives

Josh Simmons

[Prosper Sustainably](#)

Michael Burr

[Microgrid Institute](#)

Dustin Jolley

[OurEnergy](#)

Design Build Contractor

Ralph Ciarlanti III

[Green Realities](#)

Vipul Gore

[Gridscape Solutions](#)

Code Compliance

[EsGil Corporation](#)


San Pasqual General Information

- Reservation was established in 1910
- The Reservation encompasses approximately 3,446 acres
- 152 Tribal members and over 1,600 lineal descendants
- Reservation population is 2,100
- 415 homes on the reservation
- 108 homes have solar
- 96 EV Charging Stations




Trust and Fee Lands

 Trust Land (2,001 US Acres)

 Fee Land (1,445 US Acres)

[3,446 Total US Acres]



Date Created: 5/24/2023


Source: San Pasqual Band of Mission Indians Planning Department



San Pasqual Solar Homes

Installed Solar on Built Residential Addresses

Source: San Pasqual Band of Mission
Indians Planning Department
Date Created: 7/19/2023





- Installed Solar (93/415)
- No Solar (322/415)

- Street
- Trust Land




EV Chargers


San Pasqual Reservation




Horizon Fuel Center



Native Oaks Golf Course



Inset Map Context




Legend

SPBMI Needs and Microgrid Goals



Resilience: Maintain electric power during outages



Economic: Reduce electricity costs



Environmental:
100% renewables,
reduce emissions

Power Supply Threats & Impacts




THREATS

- Severe weather
- High winds
- Wildfires
- Earthquakes
- Localized physical damage to utility distribution systems
- SDG&E system upgrades (planned outages)

IMPACTS

- Inability to Use Facilities
- Lost Productivity & Revenues
- Equipment Damage


San Pasqual and Wildfire



Reduced Costs and Emissions



**Energy Costs Saved:
\$1.1 million over 25 years**



**Grid Power Displaced:
272,000 kWh (Year 1)**



**GHG Footprint: Reduced
by 193 metric tons (Year 1)**

Resilient Microgrids

Definition: A group of interconnected loads and distributed energy resources within clearly defined electrical boundaries that acts as a single controllable entity with respect to the grid (U.S. DOE)

A true microgrid serves **multiple facilities** with a single power system; A typical battery backup or standby generator is NOT a microgrid

An advanced microgrid integrates **multiple types of energy supplies**, actively **manages demand**, and performs other functions

Most modern microgrids use **renewable energy** and battery storage

Priority/Critical Electricity Loads

Facility	Emergency Purpose	Critical Electric Loads
Tribal Administration	Red Cross evacuation center; emergency public shelter; tribal command and control; first aid	HVAC, lighting, telecom/IT, food storage, food service
Housing & Security	First response (police); public safety and security monitoring	Telecom/IT, security camera monitoring, lighting
Fire Department	First response (residential fire station); 911 emergency dispatch	Telecom/IT, lighting, overhead door operation
Education Building	Emergency public shelter	HVAC, food storage, food service, lighting
Preschool	Emergency public shelter	HVAC, lighting

SPBMI Microgrid Components



Solar PV Systems

157 kW DC (new)
24 kW DC (existing)



Propane Generator (planned)



Battery Energy Storage
Systems (BESS)

240 kW / 480 kWh



Microgrid Controls (onsite + remote)



Energy Management Controls (HVAC)



EV Chargers (six chargers, three locations)


Changes in Service and Configuration



Upgrade utility service from single-phase to three-phase



Remove existing utility meters and install master meter and building submeters



New underground cables tie site together

Funding Sources

U.S. DOE Office of Indian Energy:
\$703,716 grant

CA Self Generator Incentive Program
(SGIP): \$600,000 battery rebate

Grid Alternatives: \$150,000 grant

Indian Water Authority: \$703,716

COVID impacts

- Process delays
- Supply chain delays

Interconnection Process

- Complexities
- Delays with SDGE

Technical Issues

- Functional testing
- Shakedown testing




San Pasqual Tribal Government Complex Microgrid Project OVERVIEW

- Master Meter (Added)
- Utility Meters (Removed)
- New Solar PV Carports
- Existing Solar PV Panels
- BESS Location
- LP Genset Location (planned)
- Point of Interconnection
- Underground Cable Run
- Building Cable Run
- Existing Propane Tank
- New Propane Tank

San Pasqual Microgrid

Government Complex Area

Source: San Pasqual Band of Mission
Indians Planning Department
Date Created: 7/19/2023



Project Status & Accomplishments



Contracted Design Build Contractor



Completed SDGE applications for 3-phase service and interconnection



Completed design engineering



Construction activities complete



Government center tied into microgrid December 31, 2021; SDGE PTO September 30, 2022

Microgrid Functionality

On-Grid Functions:

- Offset utility power consumption w/solar energy
- Store excess solar production in batteries
- Optimize use of stored renewable energy for cost savings and resilience

Off-Grid Functions:

- Automatic islanding and re-connection to grid
- Autonomous operation w/solar, storage, and HVAC control
- Seamless synchronization of (planned) LP generation



Solar Canopies

- 156.25 kW Peak Output
- Capable of charging batteries from 0 to 100% in ~3 hours
- 272,000 kWh Year 1 production
- Equivalent to annual electric usage of ~37.5 homes



PV Lighting under the canopy






6 BTCPower EV Charging Stations



- Installed 3 units (6 EV charging ports) at Administration, Education, and Tribal Hall
- Charging is free of charge, all power to the EV charging stations provided by PV and battery storage
- If you build it, they will come...



SDGE Transformer

Installed on October 29, 2021



Battery Storage

- GridScape EnergyScope microgrid in a box system
- Onsite and remote controls
- Lithium ferro-phosphate (LFP) batteries
- 240 kW/ 480 kWh (~4 hours at average load)



Propane Generator

Installed on July 3, 2023

Q&A



Closing Remarks

John Flores

Environmental Director

760 – 310 – 6697

johnf@sanpasqualtribe.org

