
A Resilient and Autonomous Microgrid Powered by Marine Renewable Energy


Karl Hill, Igiugig Village Council

November 15, 2023

Project Location







Fuel and Freight Delivery





Annual Cost to Operate Igiugig Electric Co. 2022

| Fuel | 73.40% |
|------------------------|--------------|
| Payroll Expenses | 10.48 |
| Power Plant | 7.01 |
| General Administrative | e 3.72 |
| Internet | 1.21 |
| Utilities | 1.12 |
| Casual Labor | 0.96 |
| Merchant deposit fees | 0.78 |
| Miscellaneous | 0.63 |
| Equipment | 0.57 |
| Other | 0.12 |
| Total | \$304,578.61 |



Fuel Prices in Igiugig

#1 Diesel \$10.00 per gal

Gasoline \$9.92 per gal

Electricity

\$0.91/kWh \$0.72/kWh power cost equalization subsidy up to 750kWh





lgiugig, Alaska

RivGen deployment site



Regional Detail (Alaska)

Local Detail (Iguigig, Alaska)



Project Summary



Project Need

- Igiugig has very high energy costs. Like most remote northern communities, we are not connected to a centralized electrical power grid or fuel supply pipelines
- The power plant is comprised of three diesel generators, each with 65 kW generators, which produce 325 MWh/year using a total of 24,789 gallons of diesel

Project Objective

 To acquire and install a smart microgrid and energy storage system, capable of managing high-penetration renewable energy sources that will provide power to all Igiugig homes and facilities for sustainable energy supply and resilient operations

Igiugig Hydrokinetic Project: Phase I

Technology Selection

Ensuring long-term viability through local ownership





Local Involvement

Ownership

- Long-term viability
- Scalability

Phase I Project Funding and Technology Partner





- Funded by the Department of Energy Water Power Technology Office
- Igiugig Village Council selected ORPC for its patented marine renewable energy technology which seemed viable for river conditions and ease of deployment



Igiugig Hydrokinetic Project



Phase I Highlights



- First tribal entity to hold a FERC hydrokinetic pilot license
- Deployed and tested Rivgen 2.0 over two Alaskan winters (-40°C) and two frazil ice events
- Recorded tens of millions of sockeye salmon transiting past the device, with no observed injuries or mortalities
- During spring ice break-up, over 2 ft of lake ice flowed safely over device



Phase I Highlights



- Smolt outmigration monitoring
- Adaptive Management Meetings
- Monitoring
 - Igiugig Village Council
 - ADF&G
 - University of Alaska Fairbanks
 - Pacific Northwest National Laboratory
 - AquaAcoustics 2022





Igiugig Hydrokinetic Project: Phase II

Phase II Project Funding and Technology Partners Funded by the U.S. Department of Energy Office of Indian Energy






- ORPC, Schneider Electric, Alaska Energy Authority
- Energy Transitions Initiative Partnership Project
- National Renewable Energy Labs

A microgrid delivers baseload renewable energy from free-flowing rivers

- A RivGen-powered smart microgrid can relegate diesel generators to backup only.
- RivGen provides predictable baseload power.
- Energy storage and smart controls, coupled with RivGen baseload power, improve the value proposition of intermittent sources like wind and solar.



16






Work Completed to Date and Lessons Learned





- Phase I: RivGen 2.0 Power System device, cabling, anchor, shore station with electronics, and interconnect to Igiugig Electric Company.
- Phase II: RivGen 2.1 Installation with similar infrastructure and connection





 Mooring anchor deployment





 Power and data cable deployment





Work Completed to Date: Battery Energy Storage System


- Installed fall 2021, commissioning began spring 2022...still underway
- Ability to be grid following or forming
- Rated for 253 kWh, 125kW inverter





Work Completed to Date: Generator Control Upgrades

- Installed summer 2022
- Remote view
- SCADA access



23



Lessons Learned



- Phase II of the project is still happening...we're continuing to learn lessons
 - Weather and seasonality can impact project timelines
 - Communication between project teams is key
 - Interconnection and commissioning will never go as planned
 - Supply chain issues continue to impact project schedule
 - Expect frazil ice conditions

Winter Operations





Frazil Event





Frazil Ice





Interconnection Short

- Several millisecond anomalies occurred
- Blackout ensued
- Safety protocols
- Adjust and keep moving forward





River Debris Increase From Storm Events





River Debris Increase From Storm Events





River Debris Increase From Storm Events





Future Activities



- Implement solution to diesel generator waste heat loop
- Complete Power Purchase Agreement/Service Agreement
- Complete commissioning Battery Energy Storage System and Microgrid
- Continue salmon smolt monitoring





ARARA



Thank You