

WEST VALLEY DEMONSTRATION PROJECT ANNUAL SITE ENVIRONMENTAL REPORT CALENDAR YEAR 2004



**WEST VALLEY NUCLEAR SERVICES COMPANY
AND
URS GROUP, INC.**



Prepared by: West Valley Nuclear Services Co. and URS Group, Inc.
Prepared for: U.S. Department of Energy
Ohio Field Office OH/WVDP

Under: Contract DE-AC24-81NE44139

August 2005
10282 Rock Springs Road
West Valley, New York 14171-9799



Department of Energy
Ohio Field Office
West Valley Demonstration Project
10282 Rock Springs Road
West Valley, NY 14171-9799

To the Reader:

This report, prepared by the U.S. Department of Energy (DOE) Ohio Field Office West Valley Demonstration Project (OH/WVDP), summarizes the environmental protection program at the West Valley Demonstration Project (WVDP) for calendar year 2004.

Monitoring and surveillance of the WVDP facilities are conducted to verify that public health and safety and the environment are protected. The quality assurance requirements applied to the environmental monitoring program by the DOE ensure the validity and accuracy of the monitoring data. Also included in this report are groundwater and ambient air data from the New York State Energy Research and Development Authority's New York State-licensed Disposal Area.

At the WVDP, radiological air emissions are controlled and permitted by the U.S. Environmental Protection Agency (EPA) under National Emission Standards for Hazardous Air Pollutants, Subpart H, regulations. Nonradiological liquid effluent discharges are controlled and permitted through the New York State Pollutant Discharge Elimination System.


Air, surface water, groundwater, drinking water, soil, sediment, and biological samples are collected and analyzed for radiological and nonradiological constituents. The resulting data are evaluated to assess effects of activities at the WVDP. Monitoring of treated water effluents and facility ventilation system emissions verified that the dose received by off-site residents continues to be minimal.

Calculated doses to the hypothetical maximally exposed off-site individual from airborne radiological releases in 2004 were less than one-tenth of one (1) percent of the EPA limit. Combined airborne and waterborne radiological releases in 2004 to the same individual were less than one-tenth of one (1) percent of the DOE limit.

The Project's continuing commitment to safety was reaffirmed in 2004 when it was recertified as a DOE-Voluntary Protection Program (VPP) STAR site and approved for renewed membership in the EPA's National Environmental Performance Track. The WVDP is one of the few DOE sites to be awarded both the VPP STAR and National Environmental Performance Track membership. In 2004, West Valley Nuclear Services Company (WVNSCO) was awarded the DOE's Legacy of Stars Award, which was given in recognition of the continuance of three consecutive years as a Star of Excellence contractor.

If you have any questions or comments about the information in this report, please contact the WVNSCO Community Relations Department at (716) 942-2152 or complete and return the enclosed survey.

Sincerely,



John H. Swales, Director
West Valley Demonstration Project

SUMMARY OF CHANGES TO THE 2004 WVDP ANNUAL SITE ENVIRONMENTAL REPORT FROM THE 2003 ANNUAL SITE ENVIRONMENTAL REPORT

This report, prepared by the U.S. Department of Energy (DOE) West Valley Demonstration Project (WVDP) office, summarizes the environmental protection program at the WVDP for calendar year (CY) 2004. Monitoring and surveillance of the facilities used by the DOE for the WVDP are conducted in order to protect public health and safety and the environment. The quality assurance requirements applied to the environmental monitoring program by the DOE ensure the validity and accuracy of the monitoring data. Also included in this report are groundwater and ambient air data from the New York State Energy Research and Development Authority's New York State-licensed Disposal Area.

Changes in content for the 2004 Annual Site Environmental Report (ASER) are summarized below.

REVISIONS AND ADDITIONS

- The Environmental Compliance Summary was updated for CY 2004 to describe implementation of the WVDP environmental management system (EMS), compliance with DOE Orders, status of regulatory compliance, and permits effective during the year.
- Data and text were updated throughout to reflect results from the CY 2004 environmental monitoring program. Tables, graphs, maps, supplemental information sections, and references were updated.
- In an effort to further improve the readability of the ASER, sections were condensed by removing and referencing historical information and supplemental commentary and visual aids.
- To clarify the scope of the various super solid waste management units (SSWMUs) included in the groundwater program, one (1) new table that defines constituent solid waste management units for each SSWMU was added to Chapter 4.
- Data tables from three (3) air monitoring locations that were discontinued in 2003 (ANSEISK, ANLLW2V, and AFNASHV) were deleted from Appendix D. A data table for a new monitoring location at the Remote-Handled Waste Facility (ANRHWFK) was added.
- In Appendix E, Table E-1, that summarizes the groundwater monitoring network, was condensed and reformatted. Data formerly in two groundwater data tables that summarized indicator results from north plateau seeps and well points, respectively, were merged into other tables and the two tables were deleted from Appendix E.
- A data table summarizing analytical results for rail bed soil sampling was added to Appendix G.
- Two tables summarizing temperature and barometric pressure data were deleted from Appendix I.
- A new data table summarizing results of the Mixed Analyte Performance Evaluation Program, a crosscheck program in which the WVDP began participating in 2004, was added to Appendix J.

SPECIAL ISSUES IN CY 2004

- Construction of the Remote-Handled Waste Facility was completed. Processing of radioactive waste in the facility began in June 2004.
- In the main plant, the head end cells and extraction cell #2 were decontaminated.
- Major vessels were removed from the vitrification cell and packaged in secure containers. Decontamination of the vitrification cell continued throughout the year.
- Portable air samplers were used to monitor outdoor ventilation enclosures and portable ventilation units that were used in an expanded role to ventilate decontamination activities in the main plant.
- Processing, packaging, and shipping of low-level radioactive waste continued throughout the year.
- Sodium-bearing wastewater consisting of flushed liquid retrieved from the waste tank farm was solidified with cement into 17 containers that await off-site shipment.
- In preparation for future waste shipments by rail, the on-site railroad spur was repaired. Before repairs were completed, the rail bed soils were characterized for chemical constituents to identify appropriate soil management practices.
- In preparation for eventual site closure, several temporary office trailers and other structures that were no longer needed were dismantled and moved off site.
- The WVDP Waste Management Final Environmental Impact Statement was issued in January 2004.

West Valley Demonstration Project
Annual Site Environmental Report
for
Calendar Year 2004

Prepared for the U.S. Department of Energy

Ohio Field Office

West Valley Demonstration Project Office

under contract DE-AC24-81NE44139

August 2005

West Valley Nuclear Services Company and URS Group, Inc.

10282 Rock Springs Road


West Valley, New York 14171-9799

This page intentionally left blank

Preface

Environmental monitoring at the West Valley Demonstration Project (WVDP) is conducted by the West Valley Nuclear Services Company (WVNSCO), under contract to the U.S. Department of Energy. The data collected provide an historical record of radionuclide and radiation levels and chemical data from natural and man-made sources in the survey area. The data also document the chemical and radiological quality of the groundwater on and around the WVDP and of the air and water released by the WVDP. Meteorological data are also presented.

It is the policy of the WVDP to conduct all activities, including design, construction, testing, start-up, commissioning, operation, maintenance, and decontamination and decommissioning, in a manner that is appropriate to the nature, scale, and environmental effects of these activities. The WVDP is committed to full compliance with applicable federal and New York State laws and regulations for the protection of the environment, to continual improvement, to the prevention and/or minimization of pollution, and to public outreach, including stakeholder involvement.

This report represents a single, comprehensive source of off-site and on-site environmental monitoring data collected during 2004 by environmental monitoring personnel. The environmental monitoring program and results are discussed in the body of this report. Additional monitoring information is presented in the appendices. Appendix A contains maps of on-site and off-site sampling locations. Appendices B through L can be found in electronic format on the compact disk (as indicated by the  icon) located inside the back cover. Appendix B is a summary of the site environmental monitoring schedule. Appendices C through J contain summaries of data obtained during 2004 and are intended for those readers interested in more detail than is provided in the main body of the report. Appendix K lists laws and regulations pertaining to the WVDP. Appendix L provides groundwater monitoring data from the New York State-licensed Disposal Area.

Requests for additional copies of the 2004 Annual Site Environmental Report and questions regarding the report should be referred to the WVDP Community Relations Department, 10282 Rock Springs Road, West Valley, New York 14171 (telephone: 716-942-2152). Additional Project information, including WVDP site environmental reports, is available on the internet at <http://www.wv.doe.gov>.

This page intentionally left blank

Table of Contents

PREFACE _____	iii
EXECUTIVE SUMMARY _____	EXE-1
Purpose of This Report _____	EXE-1
Major Site Programs _____	EXE-1
Operation of the Remote-Handled Waste Facility _____	EXE-1
Decontamination of Facilities _____	EXE-1
Waste Management _____	EXE-2
Preparation for Eventual Site Closure _____	EXE-2
Environmental Monitoring _____	EXE-2
Key Initiatives _____	EXE-2
Environmental Performance Indicators _____	EXE-2
Pollution Prevention/Waste Minimization Goals _____	EXE-2
Environmental Management System _____	EXE-3
Recognition and Awards _____	EXE-3
Compliance _____	EXE-3
Environmental Monitoring _____	EXE-3
Groundwater Monitoring _____	EXE-4
Quality Assurance _____	EXE-4
Conclusion _____	EXE-5
INTRODUCTION _____	INT-1
Site Location _____	INT-1
General Environmental Setting _____	INT-1
Site Mission _____	INT-3
Primary Operations and Activities _____	INT-3
Relevant Demographics _____	INT-4

Table of Contents

ENVIRONMENTAL COMPLIANCE SUMMARY _____	ECS-1
Compliance Program _____	ECS-1
Compliance Status _____	ECS-2
Environmental Protection Program (DOE Order 450.1) _____	ECS-2
Radiation Protection of the Public and the Environment (DOE Order 5400.5) _____	ECS-2
Radioactive Waste Management (DOE Order 435.1) _____	ECS-2
Resource Conservation and Recovery Act _____	ECS-2
Clean Air Act _____	ECS-6
Emergency Planning and Community Right-to-Know Act _____	ECS-7
Clean Water Act _____	ECS-8
Safe Drinking Water Act _____	ECS-12
Toxic Substances Control Act _____	ECS-13
National Environmental Policy Act _____	ECS-13
Decommissioning and/or Long-Term Stewardship at the WVDP and WNYNSC _____	ECS-14
Migratory Bird Treaty Act _____	ECS-14
Endangered Species Act _____	ECS-14
Current Achievements and Program Highlights _____	ECS-14
Vitrification Cell Dismantlement _____	ECS-14
Process Cells in the Main Plant Decontaminated _____	ECS-14
Remote-Handled Waste Facility Started Up _____	ECS-15
Sodium-Bearing Wastewater Solidified _____	ECS-15
Waste Shipping Continued _____	ECS-15
Integrated Safety Management System _____	ECS-15
STAR Status _____	ECS-15
EPA National Environmental Performance Track _____	ECS-15
Environmental Management System _____	ECS-15
Environmental Issues and Actions _____	ECS-15
Closed Landfill Maintenance _____	ECS-15
Railroad Spur Rehabilitation _____	ECS-16
Decommissioning and/or Long-Term Stewardship at the WVDP and WNYNSC _____	ECS-16
Project Assessment Activities in 2004 _____	ECS-16

Table of Contents

CHAPTER 1. ENVIRONMENTAL PROGRAM INFORMATION _____	1-1
Introduction _____	1-1
Radiation and Radioactivity _____	1-1
Measurement of Radioactivity _____	1-3
Measurement of Dose _____	1-3
Environmental Monitoring Program Overview _____	1-4
Data Reporting _____	1-4
Changes in the 2004 Environmental Monitoring Program _____	1-6
Completion of Vitrification _____	1-6
2004 Activities at the WVDP _____	1-6
Decontamination and Dismantlement _____	1-6
Sodium-Bearing Waste Management _____	1-7
Rail Spur Repairs _____	1-7
Infrastructure Footprint Reduction _____	1-7
Remote-Handled Waste Facility Construction _____	1-7
Environmental Management of Aqueous Radioactive Waste _____	1-7
North Plateau Groundwater Recovery System _____	1-7
Environmental Management of Airborne Radioactive Emissions _____	1-8
Environmental Management of Radiological Exposure _____	1-8
Unplanned Radiological Releases _____	1-8
NRC-Licensed Disposal Area Interceptor Trench and Pretreatment System _____	1-8
Waste Minimization Program _____	1-9
Pollution Prevention Awareness Program _____	1-9
Waste Management _____	1-9
Low-Level Radioactive Waste Shipping Program _____	1-9
National Environmental Policy Act Activities _____	1-10
Self-Assessments _____	1-11
Occupational Safety and Environmental Training _____	1-11
Voluntary Protection Program STAR Status _____	1-12
Environmental Management System Implementation _____	1-12
Integrated Safety Management System Implementation _____	1-13
Performance Measures _____	1-13
Radiation Doses to the Maximally Exposed Off-Site Individual _____	1-14
State Pollutant Discharge Elimination System Permit Limit Exceptions _____	1-14
Waste Minimization and Pollution Prevention _____	1-15
Spills and Releases _____	1-16

Table of Contents

CHAPTER 2. ENVIRONMENTAL RADIOLOGICAL PROGRAM INFORMATION _____	2-1
RADIATION IN THE ENVIRONMENT _____	2-1
Sources of Radiation _____	2-1
Exposure Pathways _____	2-1
Land Use Survey _____	2-3
Dose to the Public _____	2-3
Release of Materials Containing Residual Radioactivity _____	2-5
ROUTINE MONITORING PROGRAM _____	2-6
Radiological Sampling Program Overview _____	2-6
Overview of Water Effluent and Ambient Surface Water Monitoring _____	2-6
Low-Level Waste Treatment Facility Effluent _____	2-7
Northeast Swamp and North Swamp Drainage _____	2-7
Other North Plateau Surface Waters and Water Effluent _____	2-8
South Plateau Surface Water and Nuclear Regulatory Commission-Licensed Disposal Area Interceptor Trench _____	2-8
Ponded (Standing) Waters _____	2-9
Off-Site Surface Water _____	2-9
Overview of Drinking Water Monitoring _____	2-10
On-Site Tap Water _____	2-10
Off-Site Drinking Water Wells _____	2-11
Overview of Sediment Monitoring _____	2-11
On-Site Sediments _____	2-11
Off-Site Sediments _____	2-12
Overview of Air Emission and Ambient Air Monitoring _____	2-12
Ventilation and Emission Systems _____	2-12
Perimeter and Remote Ambient Air Monitoring _____	2-14
Atmospheric Deposition and Soil Monitoring _____	2-15
Fallout Pots _____	2-15
Off-Site Surface Soil _____	2-15
Overview of Food Chain Monitoring _____	2-15
Fish _____	2-15
Venison _____	2-15
Beef _____	2-16
Milk _____	2-16
Vegetables and Fruit _____	2-16

Table of Contents

Chapter 2 (concluded)

Direct Environmental Radiation Monitoring _____	2-16
On-Site Radiation Monitoring _____	2-16
Perimeter and Off-Site Radiation Monitoring _____	2-16
Confirmation of Results _____	2-17
Meteorological Monitoring _____	2-17
Special Monitoring _____	2-18
RADIOLOGICAL EFFLUENTS AND DOSE _____	2-19
Dose Assessment Methodology _____	2-19
Measurement of Radionuclide Concentrations in Liquid and Air Releases _____	2-19
Measurement of Radionuclide Concentrations in Food _____	2-19
Predicted Dose From Airborne Emissions _____	2-21
Maximum Dose to an Off-Site Individual _____	2-21
Collective Population Dose _____	2-21
Iodine Emissions From the Main Stack _____	2-21
Predicted Dose From Waterborne Releases _____	2-23
Maximum Dose to an Off-Site Individual _____	2-25
Collective Dose to the Population _____	2-25
Calculated Dose From Local Foodstuff Tests _____	2-25
Predicted Dose From All Pathways _____	2-26
Risk Assessment _____	2-27
Dose to Biota: Aquatic and Terrestrial Wildlife _____	2-27
Summary _____	2-29
CHAPTER 3. ENVIRONMENTAL NONRADIOLOGICAL PROGRAM INFORMATION _____	3-1
Overview of New York State Water Classifications, Water Quality Standards, and Water Effluent Limits _____	3-1
Surface Water, Subsurface Drainage Water, and Water Effluent Monitoring _____	3-2
SPDES Permit-Required Monitoring _____	3-2
Mercury Analytical Method Study _____	3-2
South Plateau Surface and Subsurface Water _____	3-3
Other On-Site and Off-Site Surface Water Monitoring _____	3-4
Drinking Water Monitoring _____	3-4
Soil and Sediment Monitoring _____	3-5
Air Emission Monitoring _____	3-6

Table of Contents

CHAPTER 4. SITE HYDROLOGY AND GROUNDWATER MONITORING _____	4-1
Groundwater Monitoring Program Overview _____	4-1
Surface Water Hydrology _____	4-1
Geology _____	4-1
Hydrogeology _____	4-2
Kent Recessional Sequence _____	4-2
Lavery Till _____	4-2
Sand and Gravel and Till-Sand Units _____	4-4
Routine Groundwater Monitoring Program _____	4-4
Monitoring Well Network _____	4-4
Groundwater Monitoring Program Highlights 1982 Through 2004 _____	4-7
Analytical Trigger Level Evaluation _____	4-8
Results of Routine Groundwater Monitoring _____	4-8
Long-Term Trends of Gross Beta and Tritium at Selected Groundwater Monitoring Locations _____	4-8
North Plateau Seeps _____	4-9
North Plateau Well Points _____	4-9
Results of Radioisotopic Sampling _____	4-9
Results of Monitoring at the NDA _____	4-11
Off-Site Groundwater Monitoring _____	4-11
Results for Volatile and Semivolatile Organic Compounds _____	4-11
Special Groundwater Monitoring _____	4-12
Gross Beta Plume on the North Plateau _____	4-12
North Plateau Groundwater Recovery System _____	4-12
Permeable Treatment Wall _____	4-13
Northeast Swamp Drainage Monitoring _____	4-13
North Plateau Groundwater Quality Early Warning Monitoring _____	4-13
Investigation of Chromium and Nickel in the Sand and Gravel Unit and Evaluation of Corrosion in Groundwater Monitoring Wells _____	4-13
Ten-Year Sampling Pump Inspections _____	4-14

Table of Contents

CHAPTER 5. QUALITY ASSURANCE _____	5-1
Quality Assurance Program _____	5-1
Responsibility _____	5-1
Planning _____	5-1
Training _____	5-1
Control of Design, Procedures, Items, and Documents _____	5-2
Corrective Action _____	5-2
Documentation _____	5-2
Audits and Assessments _____	5-2
Quality Control _____	5-2
Field QC _____	5-2
Laboratory QC _____	5-3
Independent Comparisons and Crosschecks _____	5-3
Data Management _____	5-4
Data Verification and Validation _____	5-4
Data Assessment and Reporting _____	5-5
Audits, Appraisals, and Self-Assessments _____	5-5
Lessons Learned _____	5-5
Conclusion _____	5-5
REFERENCES AND BIBLIOGRAPHY _____	R&B-1
GLOSSARY _____	GLO-1
ACRONYMS AND ABBREVIATIONS _____	A&A-1
UNITS OF MEASURE _____	UOM-1
UNIT PREFIXES _____	UOM-1
SCIENTIFIC NOTATION _____	UOM-2
CONVERSION CHART _____	UOM-2
DISTRIBUTION _____	DST-1
APPENDIX A. ENVIRONMENTAL MONITORING PROGRAM MAPS _____	A-i

Table of Contents

List of Figures

INT-1. Location of the Western New York Nuclear Service Center _____	INT-2
ECS-1. WVDP SPDES Effluent Limit Exceptions _____	ECS-11
1-1. Annual Effective Dose Equivalent to the Maximally Exposed Off-Site Individual _____	1-14
1-2. Yearly SPDES Effluent Limit Exceptions _____	1-15
1-3. Percentage of Waste-Reduction-Exceeding Goals _____	1-16
1-4. Number of Immediately Reportable Spills or Releases _____	1-16
2-1. Comparison of Doses From Natural and Man-Made Sources to the Dose From 2004 WVDP Effluents _____	2-3
2-2. Ten-Year Trends of Gross Alpha, Gross Beta, and Tritium Concentrations at Sampling Location WFFELBR _____	2-10
2-3. Ten-Year Trends of Cesium-137 in Stream Sediments at One Location Upstream and One Location Downstream of the WVDP _____	2-11
2-4. Ten-Year Trends of Gross Alpha and Gross Beta Concentrations at Rock Springs Road (AFRSPRD) _____	2-14
2-5. Ten-Year Trends of Environmental Radiation Levels at Perimeter TLDs _____	2-17
2-6. Effective Dose Equivalent From Liquid and Airborne Effluents to a Maximally Exposed Individual Residing Near the WVDP _____	2-25
2-7. Collective Effective Dose Equivalent From Liquid and Airborne Effluents to the Population Residing Within 50 Miles (80 km) of the WVDP _____	2-26

Table of Contents

List of Figures (concluded)

4-1. Geologic Cross Section Through the North Plateau _____	4-3
4-2. Geologic Cross Section Through the South Plateau _____	4-3
4-3. North Plateau Gross Beta Plume Area: Fourth-Quarter 2004 Results _____	4-10
4-4. Average Yearly Gross Beta Concentrations at Locations Closer to the Source of the North Plateau Plume _____	4-15
4-5. Average Yearly Gross Beta Concentrations at Locations Closer to the Leading Edges of the North Plateau Plume _____	4-15
4-6. Average Yearly Gross Beta Concentrations at Locations Near Former Lagoon 1 _____	4-16
4-7. Average Yearly Tritium Concentrations at Selected Locations in the Sand and Gravel Unit _____	4-16
4-8. Concentrations of 1,2-DCE-t, 1,1,1-TCA, and 1,1-DCA at Well 8612 in the Sand and Gravel Unit _____	4-17
4-9. Concentrations of Tributyl Phosphate at Selected Locations in the Sand and Gravel Unit _____	4-17
4-10. Annualized Average Strontium-90 Concentrations at WNSWAMP _____	4-18
A-1. West Valley Demonstration Project Base Map _____	A-1
A-2. On-Site Surface Water and Soil/Sediment Sampling Locations _____	A-2
A-3. Off-Site Surface Water and Soil/Sediment Sampling Locations _____	A-3
A-4. On-Site Air Monitoring and Sampling Locations _____	A-4
A-5. Off-Site Air and Fallout Sampling Locations _____	A-5
A-6. Active WVDP Groundwater Monitoring Locations _____	A-6
A-7. North Plateau On-Site Groundwater Monitoring Network _____	A-7
A-8. South Plateau On-Site Groundwater Monitoring Network _____	A-8
A-9. Near-Site Drinking Water and Biological Sampling Locations _____	A-9
A-10. Location of On-Site Thermoluminescent Dosimeters (TLDs) _____	A-10
A-11. Location of Off-Site Thermoluminescent Dosimeters (TLDs) Within 5 Kilometers of the WVDP _____	A-11
A-12. Environmental Sampling Locations Between 5 and 10 Kilometers From the WVDP _____	A-12
A-13. Environmental Sampling Locations More Than 10 Kilometers From the WVDP _____	A-13
A-14. Estimated 2002 Population by Sector Within 80 Kilometers of the WVDP _____	A-14

Table of Contents


List of Tables

Compliance Tables:

ECS-1. Elements of the Environmental Management System Implementation at the WVDP _____	ECS-17
ECS-2. West Valley Demonstration Project Environmental Permits _____	ECS-21
ECS-3. West Valley Demonstration Project 2004 Air Quality Noncompliance Episodes _____	ECS-23
ECS-4. Status of EPCRA Reporting in 2004 _____	ECS-23
ECS-5. Reportable Chemicals Above Threshold Planning Quantities Stored at the WVDP in 2004 _____	ECS-23
ECS-6. West Valley Demonstration Project 2004 NPDES/SPDES Permit Noncompliance Episodes _____	ECS-24
ECS-7. West Valley Demonstration Project Migratory Bird Nest Depredation Episodes in 2004 _____	ECS-24
2-1. Potential Local Off-Site Exposure Pathways Under Existing WVDP Conditions _____	2-4
2-2. Release of Property Containing Residual Radioactive Material _____	2-5
2-3. Summary of Annual Effective Dose Equivalents to an Individual and Population From WVDP Releases in 2004 _____	2-22
2-4. 2004 Evaluation of Dose to Aquatic and Terrestrial Biota _____	2-30
2-5. WVDP Radiological Dose and Release Summary _____	2-31
4-1. Summary of Groundwater Monitoring Program by Geographic Area; Monitoring Year 2004 _____	4-5
4-2. Summary of Groundwater Monitoring Program by Monitoring Purpose; Monitoring Year 2004 _____	4-5
4-3. WVDP RCRA SSWMUs and Constituent SWMUs _____	4-6

Table of Contents


List of Figures

(Available only on CD, as indicated by the  icon.)

H-1.	2004 Average Yearly Gamma Exposure Rates Around the WVDP _____	H-6
H-2.	2004 Average Yearly Gamma Exposure Rates on the WVDP _____	H-6
I-1.	Regional Monitoring Station Wind Frequency Rose: 10-Meter _____	I-3
I-2.	Primary Monitoring Station Wind Frequency Rose: 10-Meter _____	I-4
I-3.	Primary Monitoring Station Wind Frequency Rose: 60-Meter _____	I-5
I-4.	Calendar Year 2004 Weekly Precipitation _____	I-6
I-5.	Calendar Year 2004 Cumulative Precipitation _____	I-6

Table of Contents

List of Tables

(Available only on CD, as indicated by the  icon.)

APPENDIX B. 2004 ENVIRONMENTAL MONITORING PROGRAM _____	B-i
APPENDIX C-1. SUMMARY OF WATER LIMITS, GUIDELINES, AND STANDARDS _____	C-1
C-1A. West Valley Demonstration Project State Pollutant Discharge Elimination System Sampling Program _____	C-3
C-1B. New York Water Quality Standards and Guidelines _____	C-5
C-1C. New York State Department of Health/U.S. Environmental Protection Agency MCLs, MCLGs, and Raw Water Standards _____	C-7
C-1D. U.S. Department of Energy Derived Concentration Guides _____	C-8
APPENDIX C-2. PROCESS EFFLUENT DATA _____	C-9
C-2A. Total Radioactivity of Liquid Effluents Released From Lagoon 3 (WNSP001) in 2004 _____	C-11
C-2B. Comparison of 2004 Lagoon 3 (WNSP001) Liquid Effluent Radioactivity Concentrations With U.S. Department of Energy Guidelines _____	C-12
C-2C. 2004 SPDES Results for Outfall 001 (WNSP001): Water Quality _____	C-13
C-2D. 2004 SPDES Results for Outfall 001 (WNSP001): Metals _____	C-15
C-2E. 2004 SPDES Results for Outfall 001 (WNSP001): Organics _____	C-17
C-2F. 2004 SPDES Results for Outfall 007 (WNSP007): Water Quality and Iron _____	C-18
C-2G. 2004 SPDES Results for Outfall 008 (WNSP008): Water Quality _____	C-19
C-2H. 2004 SPDES Results for Sums of Outfalls 001, 007, 008, and 116: Water Quality _____	C-20
C-2I. 2004 Quarterly/Semiannual/Annual SPDES Results for Outfall 001 (WNSP001): Water Quality, Metals, and Organics _____	C-21
C-2J. 2004 Annual SPDES Results for Outfall 007 (WNSP007): Water Quality _____	C-21
C-2K. 2004 Annual SPDES Results for Outfall 008 (WNSP008): Water Quality _____	C-22
C-2L. 2004 Annual SPDES Results for Outfall 01B (WNSP01B): Water Quality _____	C-22
C-2M. 2004 Radioactivity at Sewage Treatment Outfall (WNSP007) _____	C-22
APPENDIX C-3. SITE SURFACE DRAINAGE, SUBSURFACE DRAINAGE, AND CONTAINED WATER _____	C-23
C-3A. 2004 Radioactivity and pH in Surface Water at Facility Yard Drainage (WNSP005) _____	C-25
C-3B. 2004 Radioactivity in Surface Water at French Drain (WNSP008) _____	C-25
C-3C. 2004 Water Quality of Surface Water at the North Swamp (WNSW74A) _____	C-26

Table of Contents

List of Tables (continued)

C-3D. 2004 Water Quality of Surface Water at the Northeast Swamp (WNSWAMP) _____	C-29
C-3E. 2004 Indicator Results at Storage and Disposal Area Drainage (WNNDADR) _____	C-32
C-3F. 2004 Indicator Results in Subsurface Water at the NDA Interceptor Trench (WNNDATR) _____	C-32
C-3G. 2004 Indicator Results at SDA Drainage (WNSDADR) _____	C-33
C-3H. 2004 Indicator Results in Surface Water at Cooling Tower Basin (WNCOOLW) _____	C-33
APPENDIX C-4. AMBIENT SURFACE WATER DATA _____	C-35
C-4A. 2004 Radioactivity and pH in Surface Water Downstream of the WVDP in Cattaraugus Creek at Felton Bridge (WFFELBR) _____	C-37
C-4B. 2004 Water Quality of Surface Water Downstream of the WVDP in Buttermilk Creek at Thomas Corners Bridge (WFBCTCB) _____	C-37
C-4C. 2004 Water Quality of Surface Water Downstream of the WVDP at Frank’s Creek (WNSP006) _____	C-40
C-4D. 2004 Total Dissolved Solids From Outfall WNSP116 _____	C-43
C-4E. 2004 Indicator Results in Surface Water at Erdman Brook (WNERB53) _____	C-43
C-4F. 2004 Indicator Results in Surface Water at Frank’s Creek East of the SDA (WNFRC67) ____	C-44
C-4G. 2004 Indicator Results in Surface Water at Drum Cell Drainage (WNDCELD) _____	C-44
C-4H. 2004 Water Quality of Surface Water at the Standing Water (WNSTAW-Series) Locations _____	C-45
APPENDIX C-5. POTABLE WATER (DRINKING WATER) DATA _____	C-47
C-5A. 2004 Indicator Results in Potable Well Water Around the WVDP _____	C-49
C-5B. 2004 Indicator Results in Main Plant Potable Water (WNDNKMP); 2004 Indicator Results in Environmental Laboratory Potable Water (WNDNKEL); and 2004 Indicator Results in Maintenance Shop Potable Water (WNDNKMS) _____	C-50
C-5C. 2004 Water Quality Results in Utility Room Potable Water (WNDNKUR) _____	C-51
C-5D. 2004 Water Quality Results in Utility Room Raw (Untreated) Water (WNURRAW) _____	C-52
C-5E. 2004 Biological and Chlorine Results From Various Site Tap Water Locations _____	C-52
C-5F. 2004 Tap Water Nitrate Results From WVDP Restroom Sink _____	C-52

Table of Contents

List of Tables (continued)

APPENDIX D. SUMMARY OF AIR MONITORING DATA _____	D-1
D-1. 2004 Effluent Airborne Radioactivity at Main Stack (ANSTACK) _____	D-3
D-2. 2004 Effluent Airborne Radioactivity at Vitrification System HVAC (ANVITSK) _____	D-4
D-3. 2004 Effluent Airborne Radioactivity at 01-14 Building (ANCSSTK) _____	D-5
D-4. 2004 Effluent Airborne Radioactivity at Contact Size-Reduction Facility (ANCSRFK) _____	D-5
D-5. 2004 Effluent Airborne Radioactivity at Supernatant Treatment System (ANSTSTK) _____	D-6
D-6. 2004 Effluent Airborne Radioactivity at Container Sorting and Packaging Facility (ANCSPFK) _____	D-7
D-7. 2004 Effluent Airborne Radioactivity at Outdoor Ventilation Enclosures/Portable Ventilation Units _____	D-8
D-8. 2004 Effluent Airborne Radioactivity at Remote-Handled Waste Facility Stack (ANRHWFK) _____	D-9
D-9. 2004 Ambient Airborne Radioactivity at Lag Storage (ANLAGAM) _____	D-10
D-10. 2004 Ambient Airborne Radioactivity at the NDA (ANNDAAM) _____	D-11
D-11. 2004 Ambient Airborne Radioactivity at SDA Trench 9 (ANSDAT9) _____	D-11
D-12. 2004 Ambient Airborne Radioactivity at Rock Springs Road (AFRSPRD) _____	D-12
D-13. 2004 Ambient Airborne Radioactivity at Dutch Hill Road (AFBOEHN) _____	D-13
D-14. 2004 Ambient Airborne Radioactivity at Fox Valley Road (AFFXVRD) _____	D-13
D-15. 2004 Ambient Airborne Radioactivity at the Bulk Storage Warehouse (AFBLKST) _____	D-14
D-16. 2004 Ambient Airborne Radioactivity at Route 240 (AFRT240) _____	D-14
D-17. 2004 Ambient Airborne Radioactivity at Thomas Corners Road (AFTCORD) _____	D-15
D-18. 2004 Ambient Airborne Radioactivity at West Valley (AFWEVAL) _____	D-15
D-19. 2004 Ambient Airborne Radioactivity at Springville (AFSPRVL) _____	D-16
D-20. 2004 Radioactivity in Fallout: Dutch Hill (AFDHFOP) _____	D-17
D-21. 2004 Radioactivity in Fallout: Rain Gauge (ANRGFOP) _____	D-17
D-22. 2004 Radioactivity in Fallout: Route 240 (AF24FOP) _____	D-17
D-23. 2004 Radioactivity in Fallout: Thomas Corners (AFTCFOP) _____	D-18
D-24. 2004 Radioactivity in Fallout: Fox Valley Road (AFFXFOP) _____	D-18

Table of Contents

List of Tables (continued)

APPENDIX E. SUMMARY OF GROUNDWATER MONITORING DATA _____	E-1
Groundwater Sampling Methodology _____	E-2
2004 Groundwater Sampling and Analysis Agenda _____	E-3
E-1. Groundwater Monitoring Network: Super Solid Waste Management Units _____	E-4
E-2. 2004 Indicator Results From the Sand and Gravel Unit _____	E-7
E-3. 2004 Indicator Results From the Lavery Till-Sand Unit _____	E-11
E-4. 2004 Indicator Results From the Weathered Lavery Till Unit _____	E-12
E-5. 2004 Indicator Results From the Unweathered Lavery Till Unit _____	E-13
E-6. 2004 Indicator Results From the Kent Recessional Sequence _____	E-14
E-7. 2004 Volatile Organic Compound Results at Selected Groundwater Monitoring Locations ____	E-15
E-8. 2004 Tributyl Phosphate Results at Selected Groundwater Monitoring Locations _____	E-15
E-9. 2004 Results for Metals in Groundwater _____	E-16
E-10. 2004 Metals Indicator Results for Early Warning Monitoring Wells _____	E-18
E-11. 2004 Radioactivity in Groundwater From Selected Monitoring Locations _____	E-19
E-12. Practical Quantitation Limits _____	E-23
APPENDIX F. SUMMARY OF BIOLOGICAL DATA _____	F-1
F-1. 2004 Radioactivity Concentrations in Milk _____	F-3
F-2. 2004 Radioactivity Concentrations in Meat _____	F-4
F-3. 2004 Radioactivity Concentrations in Food Crops _____	F-5
F-4. 2004 Radioactivity Concentrations in Fish Flesh From Cattaraugus Creek _____	F-6
APPENDIX G-1. SUMMARY OF SOIL AND AQUATIC SEDIMENT GUIDELINES AND STANDARDS _____	G-1
G-1A. Eastern U.S.A. Background Concentrations for Elements in Soils _____	G-3
G-1B. Screening Concentrations for Elements in Contaminated Sediments _____	G-4
G-1C. Elemental Screening Thresholds for In-Water and Riparian Management of Sediment and Dredge Material _____	G-4

Table of Contents

List of Tables (continued)

APPENDIX G-2. SOIL AND SEDIMENT DATA _____	G-5
G-2A. 2004 Contaminants in On-Site Soils Downstream of the WVDP at Frank’s Creek (SNSP006) _____	G-7
G-2B. 2004 Contaminants in On-Site Soils From North Swamp (SNSW74A) _____	G-8
G-2C. 2004 Contaminants in On-Site Soils From Northeast Swamp (SNSWAMP) _____	G-9
G-2D. 2004 Radioactivity in Surface Soils Collected at Air Stations Around the WVDP _____	G-10
G-2E. 2004 Radioactivity in Stream Sediments Around the WVDP _____	G-12
G-2F. 2004 Contaminants in Rail Bed Soil Material _____	G-13
APPENDIX H. SUMMARY OF DIRECT RADIATION MONITORING DATA _____	H-1
H-1. Summary of 2004 Quarterly Averages of Off-Site TLD Measurements _____	H-3
H-2. Summary of 2004 Quarterly Averages of On-Site TLD Measurements _____	H-4
H-3. Third-Quarter 2004 TLD Results and Instantaneous Exposure Rate Readings With a High- Pressure Ion Chamber at Each Monitoring Location _____	H-5
APPENDIX I. SUMMARY OF METEOROLOGICAL DATA _____	I-1
I-1. 2004 Site Precipitation Collection Data _____	I-7
APPENDIX J. SUMMARY OF QUALITY ASSURANCE CROSSCHECK ANALYSES _____	J-1
J-1. Crosscheck Sample Comparisons From the DOE Environmental Measurements Laboratory Quality Assessment Program 60; QAP 0403; June 2004 _____	J-3
J-2. Crosscheck Sample Comparisons From the DOE Mixed Analyte Performance Evaluation Program; May 2004 _____	J-5
J-3. Crosscheck Sample Comparisons From the DOE Mixed Analyte Performance Evaluation Program; November 2004 _____	J-7
J-4. Crosscheck Sample Comparisons of Results Analyzed for Water Quality Parameters as Part of the EPA’s 2004 Discharge Monitoring Report - Quality Assurance Study 24 for the National Pollutant Discharge Elimination System _____	J-10

Table of Contents

List of Tables (concluded)

APPENDIX K. ENVIRONMENTAL LAWS, REGULATIONS, STANDARDS, AND ORDERS _____	K-1
K-1. U.S. Department of Energy Radiation Protection Standards and Derived Concentration Guides _____	K-3
K-2. Environmental Laws, Regulations, Standards, and Orders _____	K-4
K-3. West Valley Demonstration Project Act _____	K-7
APPENDIX L. SUMMARY OF NEW YORK STATE ENERGY RESEARCH AND DEVELOPMENT AUTHORITY GROUNDWATER MONITORING DATA FOR THE NEW YORK STATE-LICENSED DISPOSAL AREA _____	L-1
L-1. 2004 Contamination Indicator Results From SDA Monitoring Wells _____	L-3
L-2. 2004 Radiological Indicator Results From SDA Monitoring Wells _____	L-5
L-3. 2004 Radioisotopic Results From SDA Monitoring Wells _____	L-7

This page intentionally left blank

EXECUTIVE SUMMARY

Purpose of This Report

The Annual Site Environmental Report for the West Valley Demonstration Project (WVDP or Project) is published to provide information about environmental conditions at the WVDP to members of the public living near the site and to other interested stakeholders. The WVDP is located in western New York State, about 30 miles (50 km) south of Buffalo, within the New York State-owned Western New York Nuclear Service Center. In accordance with U.S. Department of Energy (DOE) Order 231.1A, "Environment, Safety, and Health Reporting," this report summarizes calendar year (CY) 2004 environmental monitoring data so as to describe the performance of the WVDP's environmental management system (EMS), confirm compliance with standards and regulations, and highlight important programs. Activities at the WVDP are being conducted in conjunction with the New York State Energy Research and Development Authority.

Major Site Programs

The WVDP is located on the site of a former commercial nuclear fuel reprocessing plant, which was shut down in 1976. In 1980, Public Law 96-368 (the WVDP Act) was passed. This Act authorized the DOE to demonstrate a method for so-

lidifying 600,000 gallons (2.3 million liters) of liquid high-level radioactive waste (HLW) that remained at the West Valley site. Vitrification of the HLW, begun in 1996, was completed in September 2002. Activities for decontaminating the vitrification and support facilities and for disposing of wastes were then initiated and continued through CY 2004. Major activities that occurred in 2004 were as follows.

Operation of the Remote-Handled Waste Facility (RHWF). Construction of the RHWF, a facility used to prepare higher-activity wastes for shipment and disposal, was completed in early 2004. Extensive start-up/readiness reviews were performed to assess readiness to begin radioactive operations. In June 2004 the facility began processing radioactive waste.

Decontamination of Facilities. Decontamination of three major cells in the main plant (the process mechanical cell, the general purpose cell, and extraction cell 2), including removal of equipment, vessels, and process piping, was completed in

A reader opinion survey has been inserted in this report. If it is missing, please contact the Community Relations Department at (716) 942-2152. Additional Project information is available on the internet at <http://www.wv.doe.gov>.

2004. Major vessels were removed from the vitrification cell and packaged in secure containers. Decontamination activities in the vitrification cell continue.

Waste Management. Management of HLW, transuranic waste, mixed waste (i.e., waste that is both hazardous and radioactive), low-level radioactive waste (LLW), hazardous waste, and non-hazardous regulated waste continued to be a priority at the WVDP in 2004. Processing of LLW continued, and sodium-bearing waste originally from the waste tank farm and stored in the main process plant was solidified with cement into 17 containers that are currently stored on site.

In preparation for future waste shipments by rail, the on-site railroad spur was repaired in the summer of 2004.

No mixed or hazardous waste was shipped in 2004, however, 104,427 cubic feet (about 3,000 cubic meters) of LLW were sent off site. Approximately 20 tons (18 metric tons) of nonradioactive, non-hazardous material were sent off site to solid waste management facilities in 2004. Of this amount, about one ton was recycled. The WVDP also shipped 1,070 tons (971 metric tons) of digested sludge and treated wastewater from the site sanitary and industrial wastewater treatment facility to the Buffalo Sewer Authority for disposal.

In 2004, as part of the site's EMS, the WVDP continued a long-term waste minimization and pollution prevention program to promote affirmative procurement and minimize the generation of LLW, mixed waste, hazardous waste, industrial waste, and sanitary waste.

Preparation for Eventual Site Closure. In 2004, preparation of the Decommissioning and/or Long-Term Stewardship Environmental Impact Statement continued. To reduce the site "footprint,"

several temporary office trailers and other structures that were no longer needed were dismantled and moved off site.

Environmental Monitoring. As part of the EMS, the WVDP continued to monitor the environment on and near the site to detect and evaluate changes in the environment resulting from Project (or pre-Project) activities and to assess the effect of any such changes on the environment or human population.

Key Initiatives

Environmental Performance Indicators. In 2004, the WVDP re-applied to the U.S. Environmental Protection Agency for continued membership in the National Environmental Performance Track program. The WVDP renewal request was accepted in December 2004. Three new commitments were established for the three-year period of CY 2004–2006: (1) elimination of halon 1301 from fire-suppression systems on site, (2) a 10% reduction in total energy usage, and (3) a 10% reduction in total radiological curies discharged in wastewater. The first commitment was completed in 2004. The other commitments are on track to be met during the three-year period.

Pollution Prevention/Waste Minimization Goals. In 2004, the WVDP continued its program of reducing and eliminating the amount of waste generated from site activities. Emphasis on good business practices, source reduction, and recycling continued to reduce the generation of LLW, mixed waste, hazardous waste, sanitary wastes, and industrial wastes (such as paper, glass, plastic, wood, and scrap metal). Waste minimization goals for 2004 in three of the above five waste categories (LLW, mixed, and hazardous) were met or exceeded. Although generation of both industrial waste and sanitary waste was reduced in 2004, target reductions from the 1993 baselines were

not met. (The industrial reduction target was 60%; actual reduction was 11%. The sanitary waste reduction target was 75%; actual reduction was 58%.)

Environmental Management System

The WVDP EMS satisfies the requirements of DOE Order 450.1, Environmental Protection Program. The WVDP EMS is an integral part of the WVDP Integrated Safety Management System. In 2004, the WVDP continued to demonstrate its commitment to an all-inclusive approach to safety, coordinating the EMS with other safety management and work planning processes through the integrated environmental, health, and safety management program.

Recognition and Awards. The DOE's Legacy of Stars Award was presented to the WVDP by the Voluntary Protection Program (VPP) Participants Association in 2004. The WVDP is the first (and only) site to receive the Legacy of Stars designation, which is given to sites in recognition of the continuance of three consecutive years as a Star of Excellence contractor. The Star of Excellence, the highest VPP award for safety, is awarded to sites that have full commitment to maintaining quality, safety, and health programs.

In 2004, the West Valley Nuclear Services Company was recognized by its parent company, Washington Group International, with a Safe Project of the Year Award. Both awards were given in a year that saw the WVDP achieve its best safety record in more than 20 years, reaching more than 2.5 million consecutive work hours without a lost time work injury or illness.

Compliance. Management at the WVDP continued to provide strong support for environmental compliance in 2004. DOE Orders and applicable

state and federal statutes and regulations are integrated into the Project's compliance program.

In CY 2004:

- no notices of violation or inspection findings from any environmental regulatory agencies were received by the WVDP.
- inspections by the New York State Department of Environmental Conservation and the local department of health verified Project compliance with the applicable environmental and health regulations.
- the WVDP continued to successfully monitor waste management areas at the site to comply with the Resource Conservation and Recovery Act §3008(h) Administrative Order on Consent.
- the Project met the requirements of the Emergency Planning and Community Right-to-Know Act by collecting information about hazardous materials used at the Project and making this information available to the local community.
- an updated New York State Pollutant Discharge Elimination System (SPDES) permit was received. The updated permit, which took effect on January 1, 2005, added 20 storm water monitoring points to the five effluent points already included in the permit. In May 2004, one exceedence of a permit limit occurred when total suspended solids exceeded the daily maximum limit.

Environmental Monitoring. As part of the EMS, the WVDP monitors on-site facilities and the surrounding environment. Radionuclides present at the WVDP are primarily residues from the reprocessing of commercial nuclear fuel during the 1960s and early 1970s. A very small fraction of these radionuclides is released off site during the year through ventilation systems and liquid dis-

charges. Potential pathways of exposure include inhalation of gases and particulates, ingestion of locally-grown food products, consumption of fish, beef, and venison, and exposure to external penetrating radiation emitted from contaminated materials. These exposure pathways are routinely monitored at the WVDP.

Radiological Releases. The primary source of airborne radionuclide emissions at the WVDP is the main stack of the process building.

The largest single source of waterborne radioactivity in effluents from the WVDP is lagoon 3, from which treated water is released in batches. Eight batches totaling approximately 15.0 million gallons (56.6 million liters) were released from the Project in 2004. Seepage of groundwater contaminated with strontium-90 from pre-Project operations across the north plateau in an elongated plume was another waterborne source of radioactivity in 2004.

Estimated Dose. In 2004, the estimated dose to a maximally exposed off-site individual (MEOSI) from airborne emissions at the WVDP was 0.0015 mrem (0.000015 mSv), about 0.02% of the 10 mrem EPA standard. Estimated dose from waterborne sources in 2004 was about 0.047 mrem (0.00047 mSv), with 0.016 mrem attributable to liquid effluent releases and 0.031 mrem attributable to the north plateau drainage.

Total estimated dose to the MEOSI from both airborne and waterborne sources in 2004 was 0.049 mrem (0.00049 mSv), about 0.05% of the annual 100 mrem DOE standard. In comparison, the typical dose to a member of the public from natural background sources is 295 mrem per year. Estimated dose to the population within a 50-mile (80-kilometer) radius of the WVDP from DOE activities in 2004 was 0.20 person-rem (0.002 person-Sv). This same population would have received

approximately 453,000 person-rem from natural background radiation in 2004.

Dose to Biota. An evaluation of dose to biota for CY 2004, as part of the WVDP environmental monitoring program, resulted in the conclusion that populations of aquatic and terrestrial biota (both plants and animals) are not being exposed to doses in excess of the existing DOE dose standard for aquatic animals and the recommended standards for terrestrial biota.

Nonradiological Releases. Nonradiological releases from Project waste water were measured under the site's SPDES permit. In 2004, one measurement for total suspended solids exceeded the maximum daily limit.

Groundwater Monitoring. Monitoring of groundwater at the WVDP continued in 2004, including evaluation of new wells installed around the RHWF. Also, monitoring of strontium-90 activity in and around the groundwater plume on the north plateau continued.

Quality Assurance. In 2004, the WVDP continued to implement a quality assurance program for activities supporting the environmental monitoring program. As part of this ongoing effort, on-site and subcontract laboratories that analyze environmental samples for the WVDP participated in independent performance evaluation studies for both radiological and nonradiological constituents. In these studies, test environmental samples with concentrations known by the testing agency, but unknown by the laboratory, are analyzed. Of 101 radiological performance evaluation samples analyzed by and for the WVDP, a total of 96% fell within acceptance limits. Of 80 nonradiological performance evaluation samples analyzed, about 98% were acceptable.

Several inspections, audits, and assessments of components of the environmental monitoring program were conducted in 2004. Although actions were recommended to improve the program, nothing was found that would compromise the quality of the data in this report or the environmental monitoring program in general.

Conclusion

In addition to demonstrating compliance with environmental regulations and directives, evaluation of data collected in 2004 continued to indicate that WVDP activities pose no threat to public health or safety or to the environment.

This page intentionally left blank

INTRODUCTION

Site Location

The West Valley Demonstration Project (WVDP or Project) is located in western New York State, about 30 miles (50 kilometers [km]) south of Buffalo, New York (Fig. INT-1). The WVDP facilities occupy a security-fenced area of about 167 acres (68 hectares [ha]) within the 3,338-acre (1,351 ha) Western New York Nuclear Service Center (WNYNSC) located primarily in the town of Ashford in northern Cattaraugus County. The security-fenced area is referred to as the Project premises.

General Environmental Setting

Climate. Although extremes of 98.6°F (37°C) and -43.6°F (-42°C) have been recorded in western New York, the climate is moderate, with an average annual temperature (1971–2000) of 48°F (8.9°C). Precipitation is markedly influenced by Lake Erie to the west and, to a lesser extent, by Lake Ontario to the north. Regional winds are generally from the west and south at about 9 mph (4 m/sec).

Ecology. The WNYNSC lies within the northern deciduous forest biome, and the diversity of its vegetation is typical of the region. Equally divided

between forest and open land, the site provides a habitat especially attractive to white-tailed deer and various indigenous migratory birds, reptiles, and small mammals. No species on the federal endangered species list are known to be present on the WNYNSC.

Geology and Hydrology. The Project lies on New York State's Allegheny Plateau at an average elevation of about 1,300 feet (400 m). The underlying geologic sediments include a sequence of glacial sediments above shale bedrock. The Project is drained by several small streams and is divided by a stream valley into two general areas: the north plateau and the south plateau.

Frank's Creek, which enters the WVDP site from the south and flows northward, receives drainage from the south plateau. As Frank's Creek progresses northward, it is joined by tributaries Erdman Brook (between the south and north plateaus) and Quarry Creek (north of the Project's fenceline). Frank's Creek continues northward across the WNYNSC and flows into Buttermilk Creek, which leaves the WNYNSC and enters Cattaraugus Creek. (See Figs. A-2 and A-3.) Cattaraugus Creek ultimately drains into Lake Erie, to the northwest.

Introduction

f:\gis\laser.apr fig 1 location of wnyjsc, r0 (02/10/03) - fig




Figure INT-1. Location of the Western New York Nuclear Service Center

Site Mission

From 1966 until 1972, the facility which later became the WVDP was the site of a commercial nuclear fuel reprocessing plant run by Nuclear Fuel Services, Inc. (NFS). Uranium and plutonium were recovered from spent nuclear fuel for reuse. In 1972 the reprocessing facility closed for expansion, but in 1976 NFS notified the New York State Energy Research and Development Authority that it was no longer economically feasible to continue in the fuel-reprocessing business and the plant was shut down. In 1980, Public Law 96-368 (the West Valley Demonstration Project Act) was passed. This Act authorized the U.S. Department of Energy (DOE) to demonstrate a method for solidifying 600,000 gallons (2.3 million liters) of liquid high-level radioactive waste (HLW) that remained at the West Valley site. (For a detailed history of the site, see the Introduction of the 2003 Annual Site Environmental Report. See Appendix K-3⁶⁰ for the complete text of the WVDP Act.)

The purposes of the WVDP Act were to carry out the following activities: solidify the HLW that was left at the site from the original nuclear fuel reprocessing activities; develop suitable containers for holding and transporting the solidified waste; transport, in accordance with application provisions of law, the waste solidified at the Center to an appropriate Federal repository for permanent disposal; dispose of any low-level and transuranic radioactive waste resulting from the solidification of HLW; and decontaminate and decommission Project facilities used for solidification of radioactive waste.

Vitrification of the HLW, begun in 1996, was completed in September 2002. Activities for decontaminating the vitrification and support facilities and for disposing of wastes were then initiated and continue through the present.

Primary Operations and Activities

The following projects were initiated, continued, or completed in 2004:

Remote-Handled Waste Facility (RHWF). Construction of the RHWF, a facility used to prepare higher-activity wastes for shipment and disposal, was completed in early 2004. In June 2004 the facility began processing radioactive waste.

Decontamination of Facilities. Decontamination of three major cells in the main plant (the process mechanical cell, the general purpose cell, and extraction cell 2), including removal of equipment, vessels, and process piping, was completed in 2004. Major vessels were removed from the vitrification cell in 2004 and decontamination activities continued.

Waste Management. Part of the DOE's cleanup mission at the West Valley site is the disposal of low-level radioactive waste (LLW) that is generated through WVDP operations. In 2004, waste continued to be shipped off site to disposal facilities. (See a discussion of the LLW shipping program in Chapter 1.)

Environmental Monitoring. The primary goal of the WVDP's environmental monitoring program is to detect and evaluate changes in the environment resulting from Project (or pre-Project) activities and to assess the effect of any such changes on the human population.

Among the factors considered in designing the environmental monitoring program were the types of wastes and other by-products resulting from the processing of HLW; possible pathways for movement of contaminants into the environment; geologic, hydrologic, and meteorologic site conditions; quality assurance standards for monitoring

and sampling procedures and analyses; and the limits and standards set by federal and state governments and agencies. (For more information on the design of the environmental monitoring program, see Environmental Monitoring Program and Exposure Pathway Monitoring in the Introduction of the 2003 Annual Site Environmental Report.) Results of the 2004 monitoring program are discussed in Chapters 2, 3, and 4 of this report.

Relevant Demographics

Although several roads and a railway approach or pass through the WNYNSC, the public does not have access to the Project grounds. Deer hunting may be allowed (a year-to-year decision), but fishing and human habitation on the WNYNSC are prohibited.

Land near the WNYNSC is used primarily for agriculture and arboriculture. Downstream of the WNYNSC, Cattaraugus Creek is used locally for swimming, canoeing, and fishing. Although some water is taken from the creek to irrigate nearby golf course greens and tree farms, no public drinking water is drawn from the creek before it flows into Lake Erie. Water from Lake Erie is used as a public drinking water supply.

The communities of West Valley, Riceville, Ashford Hollow, and the village of Springville are located within approximately 5 miles (8 km) of the Project. The nearby population, approximately 9,200 residents within 6.2 miles (10 km) of the Project, relies largely on an agricultural economy. No major industries are located within this area. The WVDP is one of the largest employers in Cattaraugus County.

ENVIRONMENTAL COMPLIANCE SUMMARY

CALENDAR YEAR 2004

Compliance Program

The West Valley Demonstration Project (WVDP or Project) is currently focusing on several goals that will lead to completion of the WVDP Act. (See Appendix K⁶⁰.) Construction of the remote-handled waste facility, used to process and package radioactive Project waste into shipping containers, was completed in early 2004 and processing of waste began in June 2004. Dismantlement of processing equipment in the vitrification facility began in 2004 and major vessels, including the melter, were removed. Decontamination of several former reprocessing cells within the main process building was completed and management of radioactively contaminated groundwater continued.

In January 2003, the U.S. Department of Energy (DOE), the federal agency that manages the WVDP, issued a directive (DOE Order 450.1) requiring implementation of an environmental management system (EMS) for conducting work at DOE sites, including the WVDP. In response to this directive, the existing WVDP EMS is continuously reviewed and enhanced. Elements of the WVDP EMS are summarized in Table ECS-1.

Activities at the WVDP are regulated by various federal and state laws that protect the public, workers, and the environment.

Major federal environmental laws and regulations applicable to the WVDP are: the Resource Conservation and Recovery Act; the Clean Air Act; the Emergency Planning and Community Right-to-Know Act (enacted as Title III of the Superfund Amendments and Reauthorization Act); the Clean Water Act; the Safe Drinking Water Act; the Toxic Substances Control Act; the Migratory Bird Treaty Act; and the National Environmental Policy Act. These laws are administered primarily by the U.S. Environmental Protection Agency (EPA), the U.S. Fish and Wildlife Service, the U.S. Army Corps of Engineers (ACOE), the New York State Department of Environmental Conservation (NYSDEC), and the New York State Department of Health (NYSDOH) through programs and regulatory requirements for permitting, reporting, inspecting, self-monitoring, and audits.

Because release of radiological and nonradiological materials from an active facility cannot be completely prevented, the EPA, NYSDEC, and DOE have established standards for such emissions and discharges that are intended to protect human health, safety, and the environment. The WVDP applies to the EPA for permits to release limited amounts of radiological constituents to the air and applies to NYSDEC for a permit to release limited amounts of nonradiological constituents to the air and water through controlled and monitored

effluent releases in concentrations determined to be safe for humans and the environment. In general, the permits describe release points, specify management and reporting requirements, list discharge limits on those pollutants likely to be present, and define the sampling and analysis regimen. A summary of permits may be found in Table ECS-2.

Compliance Status

The following summary describes WVDP compliance with DOE Orders 450.1, 5400.5, and 435.1 and federal and state laws and regulations applicable to the Project.

Environmental Protection Program (DOE Order 450.1). DOE Order 450.1, issued in January 2003, requires DOE sites to implement an EMS by December 31, 2005. An EMS is a continuing cycle of systematic planning, implementing, evaluating, and improving processes and actions undertaken to achieve environmental goals. Since 1999, the WVDP has implemented an EMS via policies and procedures that provide for accomplishing work through proactive management, environmental stewardship, and integration of appropriate technologies across all Project functions. The West Valley Nuclear Services Co. (WVNSCO) EMS satisfies the requirements of both the “Code of Environmental Management Principles” for federal agencies and the International Organization for Standardization 14001, “Environmental Management Systems: Specifications for Guidance and Use.”

Radiation Protection of the Public and the Environment (DOE Order 5400.5). DOE Order 5400.5, issued in February 1990, established standards and requirements for protection of the public and the environment against undue risk from radiation resulting from activities of the DOE and DOE contractors. The objectives of the Order were to ensure that (1) operations are conducted so that radiation exposures to members of the public are

maintained within the limits established in the Order, (2) potential exposures to members of the public are as far below the limits as is reasonably achievable, (3) routine and non-routine releases are monitored and dose to the public is assessed, and (4) the environment is protected from radioactive contamination to the extent practical.

This report summarizes radiological releases from the WVDP in 2004, presents estimates of dose to the public and the environment in 2004, and compares these values with release and dose standards established by DOE Order 5400.5. (See Appendix K⁶⁰.) In 2004, both releases and estimates of dose to the public were well within applicable limits.

Radioactive Waste Management (DOE Order 435.1). DOE Order 435.1 was issued in July 1999, and updated in August 2001, to ensure that all DOE radioactive waste – including high-level waste (HLW), transuranic waste, low-level waste (LLW), and the radioactive component of mixed waste – is managed to (1) protect the public from exposure to radioactive materials, (2) protect the environment, (3) protect workers, and (4) comply with applicable federal, state, and local laws and regulations, as well as applicable Executive Orders and other DOE directives. The “WVDP Radioactive Waste Acceptance Program,” a formal document describing how radioactive waste is managed at the WVDP, was updated in August 2004.

Resource Conservation and Recovery Act (RCRA). RCRA was enacted to ensure that hazardous wastes are managed in a manner that protects human health, safety, and the environment. RCRA and its implementing regulations govern the life cycle of hazardous waste from “cradle-to-grave” and mandate that generators take responsibility for ensuring the proper treatment, storage, and ultimate disposal of their wastes. The EPA is the federal agency responsible for issuing guide-

lines and regulations for the proper management of solid and hazardous waste (including mixed [radioactive and hazardous] waste).

In New York, the EPA has delegated the authority to issue permits and enforce these regulations to NYSDEC. In addition, the U.S. Department of Transportation is responsible for issuing guidelines and regulations for labeling, packaging, and spill-reporting for hazardous and mixed wastes while in transit.

A hazardous waste permit is required for facilities that treat or store large quantities of hazardous waste for more than 90 days or dispose of hazardous waste at the facility. New York State facilities in existence on the date that hazardous waste regulations impacting their operations took effect were required to apply for interim status from NYSDEC by submitting a RCRA Part A Permit Application. Facility operations during interim status are limited to those described in the Part A Permit Application and must comply with the Interim Status Standards regulations.

In 1984, the DOE notified the EPA of hazardous waste activities at the WVDP and identified the WVDP as a generator of hazardous waste. In June 1990, the effective date of the New York State regulations governing treatment, storage, and disposal of mixed (i.e., RCRA hazardous and Atomic Energy Commission radioactive) waste, the WVDP filed a RCRA Part A Permit Application with NYSDEC for storage and treatment of hazardous and mixed wastes, and has been operating under interim status ever since.

The WVDP updates its RCRA Part A Permit Application as changes to the site's interim status waste-management operations occur. An updated RCRA Part A Permit Application was submitted to NYSDEC on March 6, 2001. On November 13, 2001, NYSDEC responded that the RCRA Part

A Permit modifications met the requirements for changes to interim status treatment and storage operations at the WVDP.

In a July 16, 2003 letter to the DOE, NYSDEC made an official request for the submittal of a Part 373 Permit Application for the WVDP. The complete Part 373 Permit Application was transmitted to NYSDEC on December 23, 2004. Facilities with interim status are treated as having been issued a permit until a final determination by NYSDEC on the Part 373 Permit Application is made.

Hazardous Waste Management Program. Hazardous wastes at the WVDP are managed in accordance with 6 NYCRR Parts 370–374 and 376. Hazardous and mixed waste activities must be reported to NYSDEC each year through the submittal of the facility's annual Hazardous Waste Report. This report summarizes the hazardous waste activities for the previous year, specifies the quantities of waste generated, treated, and/or disposed, and identifies the treatment, storage, and disposal facilities used. The annual Hazardous Waste Report, which reported that the WVDP made no hazardous waste shipments in CY 2004, was submitted to NYSDEC in February 2005.

In addition, a hazardous waste reduction plan must be updated annually and filed every two years. This plan, first submitted to NYSDEC in 1990, documents efforts to minimize the generation of hazardous waste. The hazardous waste reduction plan was updated in 2004, as required. The most recent Annual Status Report for the Hazardous Waste Reduction Program was submitted to NYSDEC in June 2003.

Annual inspections to assess compliance with hazardous waste regulations were conducted by NYSDEC on March 31, 2004 and the EPA on September 23, 2004. No deficiencies were noted.

Mixed Waste Management Program. Mixed waste contains both a radioactive component, regulated under the Atomic Energy Act, and a hazardous component, regulated under RCRA. Both the EPA and NYSDEC oversee mixed waste management at the WVDP.

The Federal Facility Compliance Act of 1992, an amendment to RCRA, requires DOE facilities to prepare plans (specifically, the Site Treatment Plan) for treating their mixed waste inventories and to update these plans annually to account for development of treatment technologies, capacities, and changes in mixed waste inventories. Each plan is approved by the respective state agency or the EPA after consultation with other affected states and after consideration of public comments.

The WVDP's Site Treatment Plan is comprised of two volumes: the Background Volume provides information on each mixed waste stream and information on the preferred treatment method for the waste, and the Plan Volume contains proposed schedules for treating the mixed waste to meet the land disposal restriction requirements of RCRA.

The DOE and NYSDEC entered into a Consent Order on August 27, 1996 that requires the completion of the milestones identified in the Plan Volume. The WVDP began implementing its Site Treatment Plan immediately and updates it annually to bring waste stream, inventory, and treatment information current through September 30, the end of the DOE fiscal year. The final update of fiscal year 2004 activities was sent by the DOE to NYSDEC by the due date of February 15, 2005.

In 2004, the WVDP made no mixed waste shipments.

RCRA §3008(h) Administrative Order on Consent. The DOE and the New York State Energy Research and Development Authority

(NYSERDA) entered into a RCRA §3008(h) Administrative Order on Consent with NYSDEC and the EPA in March 1992. The Consent Order required NYSERDA and the DOE's West Valley Demonstration Project Office to conduct RCRA-facility investigations (RFIs) at on-site solid waste management units (SWMUs) to determine if there had been a release or if there is a potential for release of RCRA-regulated hazardous constituents from SWMUs. The final RFI reports were submitted in 1997, completing the investigative activities associated with the Consent Order. No corrective actions were required as a result of the RFIs. Groundwater monitoring, as specified in the RFI reports, continued during 2004. The WVDP also continued to monitor SWMUs and to comply with the requirements of the RCRA §3008(h) Administrative Order on Consent. Groundwater monitoring results are detailed in Chapter 4.

One SWMU was investigated in 2004: a breach in the laundry wastewater line. Notification had been submitted to the EPA and to NYSDEC, as required in 2003.

Pursuant to a request from NYSDEC in a January 2004 correspondence, a report entitled "West Valley Demonstration Project Solid Waste Management Unit Assessment and Current Conditions Report" was submitted to NYSDEC in November 2004. This report summarized the historic activities of individual SWMUs through the RFI activities and provided current environmental monitoring data and information on site activities performed since the completion of the RFI reports.

Nonhazardous, Regulated Waste Management Program. The WVDP shipped approximately 20 tons (18.1 metric tons) of nonradioactive, nonhazardous material off site to solid waste management facilities in 2004. Of this amount, 0.97 tons (0.88 metric tons) of lead-acid batteries and spent lamps (i.e., universal wastes), were reclaimed or

recycled at off-site, authorized reclamation and recycling facilities. The WVDP also shipped approximately 1,070 tons (971 metric tons) of digested sludge and treated wastewater from the site sanitary and industrial wastewater treatment facility to the Buffalo Sewer Authority for disposal.

Waste Minimization and Pollution Prevention. The WVDP continued a long-term program to minimize the generation of LLW, mixed waste, hazardous waste, industrial waste, and sanitary waste, and to promote affirmative procurement as directed by Executive Order 13101 (“Greening the Government Through Waste Prevention, Recycling, and Federal Acquisition”) and Executive Order 13148 (“Greening the Government Through Leadership in Environmental Management”), which promote the Affirmative Procurement Program and RCRA §6002, “Federal Procurement.” These Executive Orders are also supported by DOE Order 450.1. The Affirmative Procurement Program specifies responsibilities and direction for federal agencies in acquiring recycled and environmentally preferable products and services designated by the EPA in 40 CFR Part 247, “Comprehensive Procurement Guideline for Products Containing Recovered Material.” WVNSCO annually reports challenges and successes associated with the purchase and use of these materials and services to the DOE.

For purposes of waste-reduction tracking, waste streams are separated into either waste from sources directly associated with the vitrification process or from nonvitrification sources. See Chapter 1 for further discussion of waste minimization activities from all sources in 2004.

Underground Storage Tanks Program. RCRA regulations also cover the use and management of underground storage tanks and establish minimum design requirements to protect groundwater resources from releases. The regulations, specified in 40 CFR Part 280, require underground stor-

age tanks to be equipped with overfill protection, spill prevention, corrosion protection, and leak detection systems. New tanks must comply with regulations at the time of installation.

New York State also regulates underground storage tanks through two programs – petroleum bulk storage (6 NYCRR Parts 612–614) and chemical bulk storage (6 NYCRR Parts 595–599). State registration and minimum design requirements are similar to those of the federal program except that petroleum tank fill ports must be color coded, using American Petroleum Institute standards, to indicate the product being stored.

A 550-gallon, double-walled, steel underground storage tank, upgraded in 1998 to bring it into compliance with the most recent EPA requirements (40 CFR Part 280.21), is used to store diesel fuel for the supernatant treatment system/permanent ventilation system standby power unit. This tank is equipped with aboveground piping, an upgraded interstitial leak-detection system, and a high-level warning device, and therefore meets the state requirements of 6 NYCRR Parts 612–614. This is the only underground petroleum storage tank currently in use at the WVDP.

A former underground petroleum storage tank, closed in place before the New York State underground storage tank program closure requirements were implemented in 1985, was removed in 1997. In accordance with a stipulation agreement with NYSDEC, a soil bioventing system was installed in August 1999 to remediate localized petroleum contaminated soils in the vicinity of the tank. The system stimulated natural in-situ biodegradation of petroleum hydrocarbons in the soil by providing an abundant oxygen supply to existing soil microorganisms within the contaminated soil zone. Soil and groundwater samples were collected in 2002 to evaluate whether an adequate level of remediation had been achieved. Based on the sample results,

NYSDEC determined that no further remediation was required. Final disposition is pending the Decommissioning and/or Long-Term Stewardship Environmental Impact Statement.

There are no underground chemical bulk storage tanks at the WVDP.

New York State-Regulated Aboveground Storage Tanks. New York State regulates aboveground petroleum bulk storage under 6 NYCRR Parts 612–614, and aboveground hazardous bulk chemical storage under 6 NYCRR Parts 595–599. These regulations require secondary containment, external gauges to indicate the content levels, monthly visual inspections of petroleum tanks, and documented daily, annual, and five-year inspections of chemical tanks. Documentation relating to these periodic inspections is maintained by the WVDP and is available for regulatory agencies to review. Petroleum tank fill ports also must be color-coded, and chemical tanks must be labeled to indicate the product stored.

WVDP registration at the end of 2004 included nine aboveground petroleum tanks: three containing No. 2 fuel oil, one containing unleaded gasoline, and the others containing diesel fuel.

Also registered are eight aboveground chemical storage tanks used as needed to contain nitric acid or nitric acid mixtures. These tanks were emptied in the fall of 2002, and seven of the tanks were permanently closed near the end of 2004. The required submittals were made to NYSDEC to remove these seven tanks from the registration and a new registration certificate is anticipated to be received by the WVDP in early 2005.

In summary, there is one remaining chemical bulk storage tank at the WVDP, with plans under development for closure in 2005.

All the tanks are equipped with gauges and secondary containment systems. The WVDP is in compliance with the most recent requirements to upgrade chemical bulk storage tanks that went into effect in December 1999. The most current inspections by NYSDEC determined that the chemical bulk storage tanks and the petroleum bulk storage tanks were in compliance with New York State regulations.

Medical Waste Tracking. Medical waste can potentially expose humans to infectious diseases and pathogens from contact with bodily fluids. Medical evaluations, inoculations, and laboratory work at the on-site Health Services office regularly generate potentially infectious medical wastes that must be tracked in accordance with NYSDEC requirements (6 NYCRR Part 364.9).

The WVDP has retained the services of a permitted waste hauler and disposal firm to manage these medical wastes. Medical wastes are sterilized with an autoclave by the disposal firm to remove the associated hazard and are then disposed. Fifty-four pounds (25 kg) of medical waste consisting of dressings, protective clothing (such as rubber gloves), and needles, syringes, and other sharps were generated and disposed in 2004.

Clean Air Act (CAA). The CAA, including Titles I through VI, establishes a framework for the EPA to regulate air emissions from both stationary and mobile sources. These amendments mandate that each state establish a program to permit operation of sources of air pollution. In 1996, NYSDEC amended 6 NYCRR Parts 200, 201, 231, and 621 to implement the requirements of the new EPA CAA Title V permitting processes.

In New York State, NYSDEC issues permits for stationary sources that emit regulated pollutants, including hazardous air pollutants. Sources requiring permits are those that emit regulated pollutants

from a particular source (e.g., a stack, duct, vent, or other similar opening), if the pollutants are in quantities above a predetermined threshold.

Radiological Emissions. Air emissions of radionuclides at the WVDP are regulated by the EPA under the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations, 40 CFR Part 61, Subpart H, "National Emission Standards for Emission of Radionuclides other than Radon from Department of Energy Facilities." The WVDP currently has permits for six radionuclide sources.

In 2004, in compliance with updated stack inspection requirements of 40 CFR 61, Appendix B, Method 114, sampling systems in use for major emission points were inspected and the results were documented. Visual inspections, leak checks, and cleaning were carried out, as appropriate.

Other less-significant sources of radionuclide emissions, such as those from the on-site laundry, do not require permits. Non-point radiological sources of air emissions, such as open-air lagoons, also do not require permits. The WVDP reports the radionuclide emissions from its non-permitted and permitted sources to the EPA annually, in accordance with NESHAP regulations. The annual NESHAP Report is submitted to the EPA by June 30th of the following calendar year. Calculations to demonstrate compliance with NESHAP radioactive dose limits showed CY 2004 doses to be approximately 0.02% of the 10 millirem standard.

Nonradiological Emissions. Nonradiological point sources of air emissions are regulated by NYSDEC. Major source facilities are required by 6 NYCRR Part 201 to file a Title V Permit Application unless emissions are capped below operating limits. The WVDP submitted – and received NYSDEC's approval of – a plan for capping oxides of nitrogen (NO_x) and sulfur dioxide (SO₂) at 99 tons each.

Shutdown of the melter in September 2002 significantly reduced levels of NO_x and SO₂ at the WVDP, leaving site boilers and generators as the remaining contributors. An application made to NYSDEC to change the New York State Facility Air Permit to an Air Facility Registration Certificate was approved on October 28, 2004.

Air permits that were in effect at the WVDP in 2004 are included in Table ECS-2, West Valley Demonstration Project Environmental Permits. There were no air permit or regulatory exceedances in 2004. (See also Table ECS-3.)

Emergency Planning and Community Right-to-Know Act (EPCRA). EPCRA was designed to create a working partnership between industry, business, state and local governments, public health and emergency response representatives, and interested citizens. EPCRA is intended to address concerns about the effects of chemicals used, stored, and released in local communities.

Executive Order 13148, Greening the Government Through Leadership in Environmental Management, requires all federal agencies to comply with the following EPCRA provisions: planning notification (Sections 302–303), extremely hazardous substance (EHS) release notification (Section 304), material safety data sheet (MSDS)/chemical inventory (Sections 311–312), and toxic release inventory (TRI) reporting (Section 313). The WVDP continued to comply with these provisions in 2004, as shown in Table ECS-4.

- WVDP representatives participated in semi-annual meetings of the Cattaraugus County Local Emergency Planning Committee (EPCRA Sections 302–303). WVDP representatives also attended meetings held by the Cattaraugus and Erie County Emergency Management Services concerning WVDP and other local emergency planning activities. Area hospitals and the West Valley

Volunteer Hose Company continued to participate in on-site briefings, emergency response exercises, and information exchanges concerning hazardous-substance management at the WVDP. The WVDP continues to interface with off-site organizations with which Memoranda of Understanding or Letters of Agreement exist. These organizations are annually provided an opportunity to participate in a site tour and update to better understand on-site hazards for emergency response.

- Compliance with all EPCRA reporting requirements was maintained and all required reports were submitted within the required timeframe. There were no releases of EHS at the WVDP that triggered the release notification requirements of EPCRA Section 304.

- Under EPCRA Section 311 requirements, the WVDP reviews information about reportable chemicals every quarter. If a hazardous chemical not previously reported is present on site in an amount exceeding the threshold planning quantity, an MSDS and an updated hazardous chemical list are submitted to the state and local emergency response groups. This supplemental reporting ensures that the public and emergency responders have current information about hazardous chemicals at the WVDP. No new chemicals were added to the hazardous chemicals list in 2004 and no additional EPCRA Section 311 notifications were required.

- Under EPCRA Section 312 regulations, the WVDP submits annual reports to state and local emergency response organizations and fire departments specifying the quantity, location, and hazards associated with chemicals stored on site. In 2004, nine reportable chemicals were stored at the WVDP above threshold planning quantities. A list of reportable chemicals is provided in Table ECS-5.

- Under EPCRA Section 313, the WVDP provides information about releases to all environmental media of EPA-listed TRI chemicals used at or above specified regulatory thresholds at the WVDP. In 2004, no chemical exceeded the reporting threshold for the EPCRA Section 313 report.

Clean Water Act (CWA). Section 404 of the CWA regulates the development of areas in and adjacent to waters of the United States. Supreme Court interpretations of Section 404 have resulted in the inclusion of certain non-isolated wetlands in the regulatory definition of waters of the United States. Section 404 regulates the disposal of solids, in the form of dredged or fill material, into these areas by granting the Army Corps of Engineers the authority to designate disposal areas and issue permits for these activities. Executive Order 11990, "Protection of Wetlands," directs federal agencies to "avoid to the extent possible the long- and short-term adverse impacts associated with the destruction or modification of wetlands and to avoid direct or indirect support of new construction in wetlands wherever there is a practical alternative." Article 24 of the New York State Environmental Conservation Law also contains requirements for the protection of freshwater wetlands.

Also, Section 401 of the CWA requires applicants for a federal license or permit pursuant to Section 404 to obtain certification from the state that the proposed discharge complies with effluent- and water-quality-related limitations, guidelines, and national standards of performance, identified under Sections 301–303, 306–307, and 511(c) of the CWA. The EPA delegated administration of this program to New York State.

Section 1102 of the CWA regulates process, sanitary, and other effluent discharges to surface waters. Administration of Section 402 in New York is delegated to NYSDEC.

Wetlands. Jurisdictional wetlands are defined in Section 404 of the CWA as those satisfying specific technical criteria related to vegetation, soils, and hydrologic conditions. The WVDP notifies the ACOE and NYSDEC of proposed actions that could affect wetland units not specifically exempted from regulation or notification.

As a result of field assessments completed in 1998, 1999, and 2000, 83 jurisdictional wetlands ranging in size from 0.01 to 8.6 acres, a total of approximately 53 acres (22 ha) of wetland, were identified within the WVDP and adjacent parcels. This wetland delineation was submitted to the ACOE for verification of the wetland boundaries.

In 2003, remapping of site parcels to delineate wetland boundaries was initiated and completed to renew the five-year wetland map. A wetland map report was prepared and submitted to the ACOE for review and approval in the fall of 2004.

State Pollutant Discharge Elimination System (SPDES) Permit Modification. In response to a permit application filed in July 2003, NYSDEC issued a draft modification to the SPDES permit in May 2004 for public comment. The final modified permit was issued in November 2004 to take effect January 1, 2005. In addition to five existing permitted monitoring points, the modified permit authorizes discharges at 20 storm water outfalls. These outfalls receive storm water runoff from inactive waste disposal areas, areas where materials or wastes are stored or handled, and areas where construction or structure dismantlement or other soil disturbance activities may be performed. The modified SPDES permit contains sampling and analysis requirements and limits for storm water discharges at these outfalls.

Other changes to the SPDES permit that took effect January 1, 2005 include reduced monitoring at outfall 001 (WNSP001), reduced reporting fre-

quency for the mercury analytical method study, new requirements for reporting water treatment chemical usage, added monitoring for chemical substances used for weed control, and a new requirement to prepare and implement a Storm Water Pollution Prevention Plan.

NYSDEC SPDES Inspection. In May and September 2004, NYSDEC completed its annual facility inspections of the WVDP with observations of the SPDES outfalls, the site sanitary and industrial wastewater treatment facility (WWTF), low-level waste treatment facility (LLWTF), and discharge monitoring records. No deficiencies were identified.

Process Sewer Integrity Evaluation. In 2002, NYSDEC requested that the integrity of the site process sewer system be assessed. This assessment was requested after an unplanned release occurred in 2001, when boiler wastewater was released through a suspected leaking underground sanitary sewer. Later in 2002, the WVDP issued a report evaluating the condition of the process sewer system, with a plan for an inspection of accessible lines between the main process building and the LLWTF.

Video camera inspection of the process sewer lines was initiated in 2003. During this inspection, a hole was discovered in a tributary line where laundry wastewater was released. The breached line was removed from service and laundry wastewater flow was diverted to another line with known integrity. Reports of this discovery were filed with NYSDEC in November and December 2003. Video inspection of process sewer lines was completed in the fall of 2004 and no other sewer integrity issues were identified. The final report and video recordings were submitted to NYSDEC for review in the fall of 2004.

SPDES-Permitted Outfalls. Point-source liquid effluent discharges to surface waters of New York

State are permitted through the New York SPDES program. In 2004, the WVDP had five SPDES-permitted compliance points for discharges to Erdman Brook and Frank's Creek.

- Outfall 001 (WNSP001) discharges treated wastewater from the LLWTF and the north plateau groundwater recovery system. The treated wastewater is held in lagoon 3, sampled and analyzed, then periodically released after notifying NYSDEC. In 2004, eight batches totaling 15.0 million gallons (56.6 million liters) were released. The annual average concentration of radioactivity at the point of release was approximately 21.2% of DOE-derived concentration guides (DCGs). None of the individual releases exceeded the DCGs.

- Outfall 01B (WNSP01B) is an internal process compliance point established by the final SPDES permit modification issued on July 15, 2002. This internal outfall receives effluent from the liquid waste treatment system (LWTS) evaporator process after passing through a mercury pretreatment system. The LWTS pretreats residual radioactive wastes from the main process building and the HLW storage tanks before final polishing treatment at the LLWTF. Effluent is sampled and tested at this location to determine compliance with Federal Great Lakes Initiative and SPDES permit requirements for total mercury. In 2004 the LWTS was not operated, therefore no discharges were released from outfall WNSP01B.

- Outfall 007 (WNSP007) discharges the effluent from the WWTF, which treats sewage and various nonradioactive wastewaters from physical plant systems (e.g., water plant production residuals and boiler blowdown). The average daily flow at WNSP007 in 2004 was approximately 24,000 gallons (91,000 liters).

- Outfall 008 (WNSP008) formerly discharged groundwater and surface water runoff directed


from the northeast side of the site's LLWTF lagoon system through a French drain to Erdman Brook. This outfall was capped off in May 2001, and no discharges were released from the outfall in 2004.

- Monitoring point 116, located in Frank's Creek, represents the confluence of discharge from outfalls 001, 007, and 008; base stream flow; wet weather flows (e.g., surface water runoff); groundwater seepage; and augmentation water (untreated water from the site reservoirs). Monitoring point 116 is not a physical outfall but a location where the combination of source-flow inputs is used to calculate values for determining compliance with SPDES permit limits for total dissolved solids (TDS) during discharge of lagoon 3. Before discharge of lagoon 3, sample data for TDS and flow measurements from upstream sources are used to calculate the amount of augmentation water and lagoon 3 flow needed to maintain compliance with SPDES-permitted TDS limits.

As shown in Figure ECS-1, the annual number of effluent exceptions specified in the site's SPDES Permit have been substantially reduced, especially when compared to the peak of 35 exceptions noted in 1986. As indicated in this figure, there was one permit effluent limit exception recorded during 2004.

A test result for total suspended solids (TSS) for a sample obtained at outfall 001 in May 2004 was reported above the allowable (daily maximum) effluent limit. The increased TSS was caused by a storm event that resulted in runoff that carried soil and sediment down the sides of the effluent-holding lagoon and into the effluent water during the discharge.

In June 2004, the minimum permit requirement for monitoring total recoverable hexavalent chromium at outfall 001 was not met. An analytical interference resulted in an inaccurate and invalid test re-



sult for one sample that was analyzed for this chemical substance. As a consequence, the number of valid sample analyses was one short of that required. (See Table ECS-6.)

North Plateau Groundwater Recovery System. In November 1995, the WVDP installed a groundwater recovery system to mitigate the movement of strontium-90 in groundwater and reduce groundwater seepage northeast of the process building. Three recovery wells, installed near the leading edge of the groundwater plume, collect contaminated groundwater from the underlying sand and gravel unit for treatment at the low-level waste treatment building using ion-exchange to remove strontium-90. After the groundwater is processed, it is discharged to lagoon 4 or 5 of the LLWTF. Approximately 39 million gallons (148 million liters) of groundwater have been processed through the system since its inception, including about 4.8 million gallons (18 million liters) in 2004.

In 1999, the Project installed a pilot-scale permeable treatment wall (PTW) to test this in-situ passive technology for treating contaminated groundwater. Analytical data collected from within and around the wall indicate that only a portion of the contaminated groundwater in this area is be-

ing treated by the PTW. The hydrogeologic evaluation of the pilot test, completed in 2002, concluded that complex hydrogeologic conditions and disturbances from the installation are influencing groundwater flow into and around the pilot PTW.

Petroleum- and Chemical-Product Spill Reporting. The WVDP has a Spill Notification and Reporting Policy to ensure all spills are properly managed, documented, and remediated in accordance with applicable regulations. This policy identifies departmental responsibilities for spill management and proper spill-control procedures. The policy stresses the responsibility of each employee to notify the plant systems operations shift supervisor upon discovery of a spill. This first-line reporting requirement helps to ensure spills are properly evaluated and managed.

Under a 1996 agreement with NYSDEC, the WVDP is not required to report a spill of petroleum products onto an impervious surface if the spill is less than 5 gallons (19 liters) and is cleaned up within two hours of discovery. Any spill of 5 gallons or less onto the ground is entered into a petroleum spill log that is submitted monthly to NYSDEC on the fifteenth day following the subject month. A spill of more than 5 gallons on any surface must also be logged and reported within two hours to the NYSDEC hotline. A spill of any amount that enters state waters must be reported to the NYSDEC hotline within two hours of discovery and, if it has reached navigable state waters, also reported to the National Response Center. No reportable spills of over 5 gallons of petroleum products to an impervious surface, or to the ground or waters of the state, occurred at the WVDP in 2004.

The WVDP also reports spills or releases of hazardous substances in accordance with reporting requirements of RCRA, the Comprehensive Environmental Response, Compensation, and Liability Act (if a reportable quantity has been exceeded), and the CAA, EPCRA, CWA, and Toxic Substances Control Act (TSCA). No chemical spills or releases exceeded reportable quantities and, thus, no reporting during CY 2004 was required.

Any spill or release is cleaned up in a timely manner in accordance with the "WVDP Spill Notification and Reporting Policy," thereby minimizing any effects on the environment. Debris generated during cleanup is characterized and dispositioned appropriately.

Safe Drinking Water Act (SDWA). The SDWA requires that each federal agency operating or maintaining a public water system must comply with all federal, state, and local requirements regarding safe drinking water. Compliance with regulations promulgated under the SDWA in the state of New York is overseen by NYSDOH through county health departments.

The WVDP obtains its drinking water from surface water reservoirs on the Western New York Nuclear Service Center (WNYNSC) and is considered a non-transient, non-community public water supplier. The WVDP's drinking water treatment facility purifies the water by clarification, filtration, and chlorination before it is distributed on site.

Monitoring. As an operator of a drinking water supply system, the WVDP routinely collects and analyzes drinking water samples to monitor water quality. Results of these analyses are reported to the Cattaraugus County Health Department (CCHD), which also independently analyzes a monthly sample of WVDP tap water to determine bacterial and residual chlorine content, and an annual WVDP tap water sample for nitrate (as nitrogen).

Results for microbiological analysis of monthly tap water samples collected in 2004 indicated that total coliform and *E. coli* were not present in the potable water distribution system. Monthly tap water sample results for residual chlorine were positive on all occasions, indicating proper disinfection. The annual result for nitrate was also within the drinking water limit.

In the fall of 2004, the CCHD agreed to reduce monitoring for disinfection by-products (DBPs) to an annual collection as test results continued to indicate that the site is of low risk to exceed the maximum contaminant levels (MCLs) for these substances. Quarterly sample results for DBP precursors, including total trihalomethanes and five haloacetic acids, were below MCLs for these parameters. Monthly sample results for DBP precursors, including total organic carbon and alkalinity, were also below treatment system performance standards.

Cross-Connection Control. The SDWA requires that public water suppliers prevent cross-connections between the potable water supply and systems containing hazardous or infectious substances. Cross-connection control devices, such as double check valves and reduced-pressure zone valves, must be installed, inspected, and maintained at strategic locations at facilities where hazardous materials are used in a manner that could result in their introduction into the potable water distribution system under low pressure conditions. The WVDP has a total of 13 backflow prevention devices, all of which were tested and repaired as necessary by a NYSDOH-licensed tester (in 2003) to ensure that all devices are functioning properly.

NYSDOH and CCHD Inspection. In September 2004, the CCHD and NYSDOH completed an inspection of the drinking water production and supply facilities. No deficiencies were identified.

Toxic Substances Control Act. TSCA regulates the manufacture, processing, distribution, and use of chemicals, including asbestos-containing material (ACM) and polychlorinated biphenyls (PCBs).

Asbestos-Containing Material. In 2004, the WVDP continued to maintain compliance with all TSCA requirements pertaining to asbestos by managing ACM at the site in accordance with the Asbestos Management Plan (WVNSCO, revised December 6, 2002). The plan was prepared to ensure compliance with TSCA requirements and includes requirements for limiting worker exposure to ACM and for asbestos-abatement projects, maintenance activities, and periodic surveillance inspections (at least once every three years). The plan also identifies the inventory and status of on-site ACM.

Activities in 2004 included the repair or abatement of damaged/friable ACM, removal of less than 34 linear feet of ACM insulation from abandoned lines, and maintenance of signs and labels to warn workers of ACM. All activities associated with ACM are completed by personnel who are certified by the New York State Department of Labor (NYSDOL). WVNSCO maintains an asbestos-handling license issued by NYSDOL.

Polychlorinated Biphenyls. Because PCBs are regulated as a hazardous waste in New York State, the WVDP continued in 2004 to manage radioactively contaminated PCB waste as mixed waste and nonradioactive PCB waste as hazardous waste. Details concerning PCB-contaminated radioactive waste management, including a description of the waste, proposed treatment technologies, and schedules, can be found in Section 3.1.5 of the Site Treatment Plan, Fiscal Year 2004 Update (WVNSCO, February 10, 2005).

To comply with TSCA and PCB regulations, all operations associated with PCBs comply with the

PCB and PCB-Contaminated Material Management Plan. The WVDP also maintains an annual document log that details PCB use, appropriate on-site storage, and any changes in storage or disposal status. The WVDP complies with regulations for disposal of PCBs, which conditionally allow radioactive and nonradioactive PCBs to be stored for more than one year (40 CFR Parts 750 and 761).

National Environmental Policy Act (NEPA). NEPA, as amended, establishes a national policy to ensure protection of the environment is included in federal planning and decision-making (Title I). Its goals are to prevent or eliminate potential damage to the environment that could arise from federal legislative actions or proposed federal projects.

Nationwide Management of Waste. In May 1997, DOE Headquarters issued the Final Waste Management Programmatic Environmental Impact Statement (EIS) to evaluate nationwide management and siting alternatives for treatment, storage, and disposal of five types of radioactive and hazardous waste. The alternatives address waste generated, stored, or buried over the next 20 years at 54 sites in the DOE complex.

The Final Waste Management Programmatic EIS was issued with the intent of developing and issuing separate records of decision for each type of waste analyzed. In 1998, the DOE issued records of decision for transuranic and non-wastewater hazardous waste. In 1999, the DOE issued the record of decision for HLW. This decision specifies that WVDP vitrified HLW will remain in on-site storage until it is accepted for disposal at a geologic repository.

On February 25, 2000, the DOE issued its record of decision for the management of LLW and mixed LLW, including West Valley's wastes. Hanford and the Nevada Test Site (NTS) were identified as

designated national DOE disposal sites for these waste types (Volume 65, Federal Register [FR], p. 10061 [65 FR 10061]). In 2001, West Valley successfully completed the program approval process for access to the NTS, and on July 17, 2001 received approval to ship. Twenty LLW shipments were sent to NTS in 2004.

Decommissioning and/or Long-Term Stewardship at the WVDP and WNYNSC. DOE published a Federal Register Notice of Intent (NOI) on March 26, 2001 (66 FR 16447) formally announcing its rescoping plan and preparation of the waste management EIS. DOE published an NOI on March 13, 2003 (68 FR 12044) announcing its intent to prepare, in cooperation with NYSERDA, a Decommissioning and/or Long-Term Stewardship EIS. The DOE and NYSERDA are joint lead agencies on this EIS, while the EPA, U.S. Nuclear Regulatory Commission, and NYSDEC are cooperating agencies. Work on preparation of the Decommissioning and/or Long-Term Stewardship EIS continued in 2004.

In May 2003, the DOE issued a draft of the Waste Management EIS (68 FR 26587) for public comment. The DOE considered public comments and issued the final EIS in January 2004.

Migratory Bird Treaty Act. The WVDP monitors wildlife activity near WVDP work areas and, where possible, implements controls to prevent and minimize nesting of migratory birds within radiologically contaminated areas of the site.

In July 2004, the U.S. Fish and Wildlife Service and NYSDEC renewed the bird depredation permit and license to allow for the removal of migratory bird nests. See Table ECS-7 for a summary of the bird depredation action taken at the WVDP during 2004.

Endangered Species Act. The WVDP periodically updates its information about the potential for federally listed or proposed endangered or threatened species in the vicinity of Project activities. This was last done via correspondence with the U.S. Fish and Wildlife Service in October 2003. Their reply on October 23, 2003 reconfirmed that, "except for occasional transient individuals," no plant or animal species protected under the Endangered Species Act were known to exist at the WVDP.

In December 2003, the WVDP submitted an inquiry to the NYSDEC's Natural Heritage Program seeking information in the state database of the potential for rare or endangered species or threatened ecological communities within the site premises. Corollary information was received from NYSDEC on January 26, 2004 confirming the absence of known New York State protected or endangered species at the WVDP.

Current Achievements and Program Highlights

Vitrification Cell Dismantlement. The WVDP's successful HLW vitrification program was the first program of that type in the nation to reach completion. The vitrification facility was closed in September 2002 after a total of 275 containers of vitrified HLW had been produced. Dismantlement of the vitrification cell continued through 2004. By the end of the year, all major vessels had been removed and packaged. Removal of remaining components is planned for 2005.

Process Cells in the Main Plant Decontaminated. Decontamination of three former process cells in the main plant, the process mechanical cell, the general purpose cell, and extraction cell 2, was completed in 2004.

Remote-Handled Waste Facility Started Up.

Construction of the remote-handled waste facility was completed in early 2004, readiness reviews were conducted, and processing of radioactive waste in the facility began in June 2004.

Sodium-Bearing Wastewater Solidified.

Sodium-bearing wastewater, a mixed LLW, was solidified into storage containers in the fall of 2004.

Waste Shipping Continued.

Off-site shipments of LLW continued in 2004. The rail spur to the site was repaired in the summer of 2004 to facilitate rail shipments of waste.

Integrated Safety Management System (ISMS).

In August 2003, a self-assessment was conducted to confirm that the WVDP's integrated environmental, safety, and health management system continues to be effectively implemented at the WVDP. Results from the self-assessment were verified in the DOE's annual review, conducted in November 2004.

The WVDP continues to demonstrate its commitment to an all-inclusive approach to safety through its safety programs and through ongoing efforts to strengthen its integrated safety management program by encouraging worker involvement.

STAR Status. The WVDP has reaffirmed its commitment to DOE's Voluntary Protection Program (VPP). During the reporting period, the VPP was reviewed as part of the annual ISMS review. The DOE has also completed a programmatic review of the VPP and has recertified the WVDP as a DOE-VPP STAR site. At the annual VPP Participants National Conference, WVNSCO was awarded the DOE's Legacy of Stars Award, which is given to sites that maintain an outstanding safety record over a three-year period. WVNSCO is the first and only DOE contractor to receive this award.

In addition, the WVDP has been actively promoting VPP in the community by mentoring local businesses and providing assistance to support the Occupational Safety and Health Administration with VPP evaluations of other sites.

EPA National Environmental Performance Track.

The WVDP was recognized as a top environmental leader in 2000 and was accepted into the EPA's National Environmental Performance Track. The WVDP was awarded Charter Member status as part of the first group of applicants. To qualify for the award, the WVNSCO had to demonstrate that it voluntarily has adopted and implemented an EMS, has attained previously specified environmental objectives, has made a commitment to achieve four future goals, has a public outreach program, and has a sustained record of environmental compliance.

In 2004 the WVDP re-applied to the EPA for continued membership in the Performance Track program. The WVDP renewal request was accepted in December 2004. Three new commitments have been established and are outlined in Table ECS-1.

Environmental Management System.

The WVDP EMS is integrated with other safety management and work planning processes at the WVDP. In August 2004, a self-assessment of the WVDP environmental compliance program was completed by WVNSCO and it was concluded that required elements of the program are being implemented. An annual review by the DOE in November 2004 confirmed the results of the WVNSCO self-assessment.

Environmental Issues and Actions

Closed Landfill Maintenance. Closure of the on-site nonradioactive construction and demolition debris landfill (CDDL) was completed in August

1986. The landfill area was closed in accordance with NYSDEC requirements for this type of landfill, following a closure plan (Standish, 1985) approved by NYSDEC. To meet routine post-closure requirements, the CDDL cover was inspected twice in 2004 and found to be in generally good condition. The grass cover on the clay and soil cap is routinely maintained and cut, and drainage is maintained to ensure that no obvious ponding or soil erosion occurs.

Railroad Spur Rehabilitation. In 2004, a section of the bed for the railroad spur on the WNYNSC was rehabilitated to support future use of this rail line for waste shipments. Prior to removal, the rail bed soil material was sampled and tested for chemical constituents that are typically found in soils associated with rail lines, to identify appropriate soil management practices. The test results indicated the soil did not have any appreciable contamination, with all results within soil cleanup objectives specified in NYSDEC guidance, Technical Administrative Guidance Memorandum #4046, "Determination of Soil Clean-Up Objectives and Clean-Up Levels." The removed soil material was placed at the southeast corner of the WVDP premises, where it was subsequently stabilized with a vegetative cover to prevent sediment transport by storm water runoff.

Decommissioning and/or Long-Term Stewardship at the WVDP and WNYNSC. Although negotiations conducted between the DOE and NYSERDA to date have not resulted in agreement on long-term cleanup responsibilities, both parties remain committed to accomplishing important goals. These include completing EIS analyses to support decisions on site decommissioning and/or long-term stewardship. Other important Project goals include safely managing LLW, operating the remote-handled waste facility, and managing contaminated groundwater on the north plateau.

Project Assessment Activities in 2004

As the primary contractor for the DOE at the WVDP, WVNSCO maintains a comprehensive review program for proposed and ongoing operations. Assessments are conducted through formal surveillances and informal programs. Formal surveillances monitor compliance with regulations, directives, and DOE Orders. The informal program is used to identify issues or potential problems that can be corrected immediately.

The local DOE Project office and other agencies with responsibilities for the WVDP also independently review various aspects of the environmental and waste management programs, as discussed in preceding sections. In 2004, overall results reflected continuing, well-managed environmental programs at the WVDP.

Compliance Tables

DOE Headquarters uses environmental compliance summary information from sites across the DOE complex to compile national environmental summary reports. The tables on the following pages were prepared to assist in this compilation.

Table ECS-1 Elements of the Environmental Management System (EMS) Implementation at the WVDP

Environmental Policy	<p>The WVDP environmental policy is to conduct all activities, including design, construction, testing, startup, commissioning, operation, maintenance, and decontamination and decommissioning in a manner appropriate to the nature, scale, and environmental impacts of these activities. The WVDP is committed to full compliance with applicable federal and New York State laws and regulations for the protection of the environment, continual improvement, the prevention and/or minimization of pollution, and public outreach, including stakeholder involvement.</p>
Environmental Aspects and Impacts	<p>When operations have an environmental aspect, WVDP implements the EMS to minimize or eliminate any adverse potential impact. The EMS is a prerequisite for the EPA National Environmental Performance Track awarded by the EPA to the WVDP. Using the EMS, the WVDP evaluates its operations, identifies the aspects of operations that can impact the environment, and determines those impacts that are significant. The WVDP has determined that the following operational aspects have the potential to affect the environment:</p> <ul style="list-style-type: none">• Waste generation and management• Atmospheric emissions• Liquid effluents• Storage or use of chemicals and radioactive materials• Natural resource usage - power and water consumption• Noise• Soil disturbance• Disturbances to endangered species/protected habitats• Contamination areas from historical operations• Facility operations, maintenance, and decontamination activities• Other facility-specific compliance aspects.

Table ECS-1 (continued)
Elements of the Environmental Management System
Implementation at the WVDP

Legal and Other Requirements	<p>The WVDP has implemented an environmental regulatory review and assessment process to deliver WVDP-level requirements and guidance to all staff. New or revised requirements (e.g., new regulations) are analyzed to determine their applicability to the WVDP and to identify whether actions are required to achieve compliance. This may involve developing or revising WVDP documents or operating procedures, implementing administrative controls, providing training, installing engineered controls, or increasing monitoring.</p>
Objectives and Targets	<p>The performance-based management system is designed to develop, align, balance, and implement the WVDP's strategic objectives, including environmental objectives. Objectives and targets are developed by calendar year (CY). For the three-year period of CY 2004–2006, the following objectives were also commitments made under the EPA National Environmental Performance Track:</p> <ul style="list-style-type: none"><li data-bbox="630 898 1373 1020">• Commitment 1 - Reduce the amount of Halon 1301 on site. The 2003 baseline was 580 pounds. <p style="margin-left: 40px;">Results: CY 2004 - Exceeded commitment by shipping 603 lbs.</p><li data-bbox="630 1058 1373 1245">• Commitment 2 - Reduce total energy usage by 10%. The 2003 baseline was about 166,000 million British thermal units (MMBTUs). <p style="margin-left: 40px;">Results: CY 2004 - Exceeded commitment by reducing to about 144,000 MMBTUs, a reduction of 13%.</p><li data-bbox="630 1283 1373 1434">• Commitment 3 - Reduce radiological curies in wastewater discharges by 10%. The 2003 baseline was 0.0145 curies (Ci). <p style="margin-left: 40px;">Results: CY 2004 - Exceeded commitment by reducing to 0.0125 Ci, a reduction of 14%.</p>
Environmental Management Program	<p>The WVDP has a pollution prevention program to conserve resources and minimize waste generation. The WVDP budgeting system is designed to ensure that priorities are balanced and that resources essential to the implementation and control of the EMS are provided.</p>
Structure and Responsibility	<p>All employees at the WVDP have specific roles and responsibilities in key areas, including environmental protection. Environmental and waste management technical support personnel assist the line organization with their environmental responsibilities.</p>

Table ECS-1 (continued)
Elements of the Environmental Management System
Implementation at the WVDP

Training, Awareness and Competence	Training on EMS requirements has been provided to staff whose responsibilities include environmental protection. The training program includes general environmental awareness for all employees, regulatory compliance training for select staff, and specific courses for managers, internal assessors, EMS implementation teams, and operations personnel whose work can impact the environment.
Communication and Community Involvement	The WVDP continues to improve processes for internal and external communications on environmental issues. Communications with the local community include monthly meetings with the local Citizen Task Force and meetings with the general public on a quarterly basis. Notable community involvement activities by the WVDP in 2004 included the Annual Food Drive and participation in the United Way Day of Caring.
EMS Documentation	The WVDP has comprehensive, up-to-date written environmental policies describing the EMS. Written procedures and manuals inform staff how to control processes and perform work at the WVDP in a manner that protects the environment.
Document Control	The WVDP maintains a comprehensive electronic document control system to ensure the effective management of procedural documents. When facilities require additional procedures to control their work, document-control protocols are implemented to ensure that workers have access to the current version of procedures.
Operational Control	WVDP operations are evaluated for the adequacy of current controls to prevent impacts to the environment. As needed, additional administrative or engineered controls are identified and plans for upgrades and improvements are developed and implemented.
Emergency Preparedness and Response	The WVDP has an emergency preparedness and response program and specialized staff to provide timely response to hazardous material releases or other environmental emergencies. This program includes procedures for preventing, as well as responding to, emergencies.

Table ECS-1 (concluded)
Elements of the Environmental Management System
Implementation at the WVDP

Monitoring and Measurement	Liquid effluent and air-emission monitoring helps ensure the effectiveness of controls, adherence to regulatory requirements, and timely identification and implementation of corrective measures. The WVDP has a comprehensive, sitewide environmental monitoring program. Results are reported to regulatory agencies and summarized in this Annual Site Environmental Report. In addition, the WVDP assesses monitoring data for adverse trends to determine site performance, impacts from site conditions, and the need for proactive or corrective measures.
Nonconformance and Corrective and Preventive Actions	The WVDP continues to implement processes that identify and correct problems. This includes a lessons learned program to prevent recurrences, robust self-assessment and environmental assessment programs, and an electronic action tracking system.
Records	EMS-related records, including audit and training records, are maintained to ensure integrity, facilitate retrieval, and protect from loss.
EMSAudit	To periodically verify that the EMS is operating as intended, assessments are conducted by the DOE and its contractors. These assessments are designed to ensure that nonconformances are identified and addressed. In addition, compliance with regulatory requirements is verified through routine inspections, operational evaluations, and periodic assessments and self-assessments.
Management Review	In addition to audits, a management review process has been established to involve top management in the overall assessment of environmental performance, the EMS, and progress toward achieving environmental goals. This review also identifies, as necessary, the need for changes to and continual improvement of the EMS.

Table ECS-2
West Valley Demonstration Project Environmental Permits

Permit Name and Number	Agency/Permit Type	Description	2004 Changes	Status
West Valley Demonstration Project RCRA Part A Permit Application	NYSDEC/Hazardous Waste	Provides interim status under RCRA for treatment and storage of hazardous waste	No changes to Part A. A Part B Permit Application was submitted on December 23, 2004.	No expiration date.
Air Facility Registration Certificate (9-0422-00005/00099)	NYSDEC/Air Emissions	Sitewide permit includes: <ul style="list-style-type: none"> • 2 boilers 	The State Facility Air Permit was changed to an Air Facility Registration Certificate.	Effective 10/28/04. No expiration date.
Slurry-fed ceramic melter (modification to WVDP-687-01) process building ventilation	EPA/NESHAP	Slurry-fed ceramic melter radionuclide emissions — main plant stack modified 2/18/97	None	Permit approved 2/18/97. No expiration date. Request to modify submitted to the EPA 8/99.
Vitrification Facility Heating, Ventilation, and Air-Conditioning (HVAC) System	EPA/NESHAP	Vitrification facility HVAC system for radionuclide emissions	None	Permit approved 2/18/97. No expiration date.
01-14 Building Ventilation System (WVDP-187-01)	EPA/NESHAP	Liquid waste treatment system ventilation of radionuclide emissions in the 01-14 building	Charcoal filters were temporarily installed to treat emissions from sodium-bearing waste for a three-month period. Upon completion, the system was returned to normal.	Issued 10/5/87. Modified 5/25/89. No expiration date.
Contact Size-Reduction Facility (WVDP-287-01)	EPA/NESHAP	Contact size-reduction and decontamination facility radionuclide emissions	None	Issued 10/5/87. No expiration date.
Supernatant Treatment System/Permanent Ventilation System (WVDP-387-01)	EPA/NESHAP	Supernatant treatment system ventilation for radionuclide emissions	None	Revised 1/1/97. No expiration date.
Outdoor Ventilated Enclosures (WVDP-587-01)	EPA/NESHAP	Ten portable ventilation units for removal of radionuclides	None	Issued 12/22/87. No expiration date.
State Pollutant Discharge Elimination System (NY0000973)	NYSDEC/Water	Covers discharges to surface waters from various on-site sources	None	An amended permit addressing storm water discharges, monitoring modifications, and other items takes effect 1/1/05. Expires 02/01/09.

Table ECS-2 (concluded)
West Valley Demonstration Project Environmental Permits

<i>Permit Name and Number</i>	<i>Agency/Permit Type</i>	<i>Description</i>	<i>2004 Changes</i>	<i>Status</i>
Buffalo Pollutant Discharge Elimination System (04-05-TR096)	Buffalo Sewer Authority/sanitary sewage and sewage sludge disposal	Permit issued to hauler of waste from the wastewater treatment facility	Renewed 6/30/04.	Hauler must renew permit by 6/30/05.
Fill Discharge Permit (94-973-29[4])	U.S. Army Corps of Engineers/water	Buttermilk Creek culvert repairs and railroad spur improvements	None	Issued 4/27/00. Expires 4/27/05.
Freshwater Wetlands Permit and Water Quality Certification (9-0422-00005/00093)	NYSDEC/Water	Buttermilk Creek culvert repairs and railroad spur improvements	None	Issued 3/31/00. Expires 4/1/05.
Chemical Bulk Storage (9-000158)	NYSDEC/chemical bulk storage tank	Registration of bulk storage tanks used for listed hazardous chemicals	Cold chemical tanks 65D05 and 65D06 were permanently closed and deleted from the registration on 2/20/04. Cold chemical tanks 65D02, 65D03, 65D04, 65D07, 65D08, 65D09, and 63-V-048 were permanently closed on 11/10/03. A new registration certificate reflecting these closures is anticipated in early 2005.	Registration expires 7/5/05.
Petroleum Bulk Storage (9-008885)	NYSDEC/petroleum bulk storage tank registration	Registration of bulk storage tanks used for petroleum	None	Registration expires 9/2/06. Will be renewed before expiration.
Bird Depredation License (DWP04-041)	New York State Division of Fish and Wildlife	State license for the removal of all nests of migratory birds	License amended and renewed on 7/27/04.	NYS license expires 6/30/05.
Bird Depredation Permit (MB747595-0)	U.S. Fish and Wildlife Service	Federal permit for the limited taking of migratory birds and active bird nests	Permit renewed and modified on 7/16/04.	Permit expires 6/30/05.

Table ECS-3
West Valley Demonstration Project 2004 Air Quality
Noncompliance Episodes

Permit Type	Facility	Parameter	Date(s) Exceeded	Description/Solutions
<i>EPA NESHAP</i>	<i>All</i>	<i>All</i>	<i>None</i>	<i>None</i>
<i>NYSDEC Air</i>	<i>All</i>	<i>All</i>	<i>None</i>	<i>None</i>

There were no episodes of noncompliance in 2004.

Table ECS-4
Status of EPCRA Reporting in 2004

EPCRA Section	Description of Reporting	Status*
<i>EPCRA 302-303</i>	<i>Planning Notification</i>	<i>Not Required</i>
<i>EPCRA 304</i>	<i>Extremely Hazardous Substance Release Notification</i>	<i>Not Required</i>
<i>EPCRA 311</i>	<i>Material Safety Data Sheet</i>	<i>Not Required</i>
<i>EPCRA 312</i>	<i>Chemical Inventory</i>	<i>Yes</i>
<i>EPCRA 313</i>	<i>Toxic Release Inventory Reporting</i>	<i>Not Required</i>

* "Yes" indicates that the site reported under the provision.
 "No" indicates that the site should have reported but did not.
 "Not Required" indicates that the site was not required to report under the provision.

Table ECS-5
Reportable Chemicals Above Threshold Planning
Quantities Stored at the WVDP in 2004

<i>Hydrogen peroxide solution (35%)</i>	<i>Gasoline</i>
<i>Liquid nitrogen</i>	<i>Ion-exchange media</i>
<i>Oils - various grades</i>	<i>Sodium hydroxide</i>
<i>Portland cement</i>	<i>Sulfuric acid</i>
<i>Diesel fuel #2</i>	

Table ECS-6
West Valley Demonstration Project 2004 NPDES/SPDES*
Permit Noncompliance Episodes

Permit Type	Outfall(s)	Parameter	No. of Permit Exceptions	No. of Samples Taken	No. of Compliant Samples**	Percent Compliance Samples	Description/ Solutions
SPDES	All	All	2	1,231	1,229	99.8%	TSS from sediment in a storm event; minimum monitoring frequency for total recoverable hexavalent chromium not met.
SPDES	001	TSS	1	16	15	93.8%	See above.
SPDES	001	Hexavalent Chromium, Total Recoverable	1	16	15	93.8%	See above.

* Radionuclides are not regulated under the site's SPDES permit. However, special requirements in the permit specify that the concentration of radionuclides in the discharge is subject to requirements of DOE Order 5400.5.

** Sample count provided for outfall(s) identified in the second column, and parameters identified in the third column.

Table ECS-7
West Valley Demonstration Project Migratory Bird Nest Depredation Episodes in 2004

Permit/License Type	Parameter	Permit/License Limit	Total Removed in 2004
U.S. Fish and Wildlife - Bird Depredation Permit	Removal of Active Barn Swallow Nests	15	0
U.S. Fish and Wildlife - Bird Depredation Permit	Removal of Active American Robin Nests	15	0
U.S. Fish and Wildlife - Bird Depredation Permit	Removal of Active Eastern Phoebe Nests	5	0
U.S. Fish and Wildlife - Bird Depredation Permit	Removal of Active Canada Goose Nests	5	0
NYSDEC - Bird Depredation License	Removal of Migratory Bird Nests	Not limited	5

ENVIRONMENTAL PROGRAM INFORMATION

Introduction

The vitrified high-level radioactive waste (HLW) presently stored at the Western New York Nuclear Service Center (WNYNSC) on the West Valley Demonstration Project (WVDP or Project) premises is the by-product of the reprocessing of spent nuclear fuel during the late 1960s and early 1970s. At that time, the WNYNSC was leased by Nuclear Fuel Services, Inc. (NFS) for a commercial nuclear fuel reprocessing facility.

As the WNYNSC is no longer an active nuclear fuel reprocessing facility, the WVDP environmental monitoring program focuses on measuring radioactivity and chemicals associated with the residual by-products of the former NFS operations, the Project's former HLW treatment operations, and the Project's operations for management of HLW, transuranic waste, and low-level radioactive waste (LLW). The following information about the operations at the WVDP and about radiation and radioactivity will be useful in understanding the activities of the Project and the terms used in reporting the results of environmental test measurements.

Radiation and Radioactivity. Radioactivity is a characteristic of some elements that have unstable atomic nuclei, which spontaneously disintegrate or "decay" into atomic nuclei of another isotope or

element. The nuclei decay until only a stable, non-radioactive isotope remains. Depending on the isotope, this process can take anywhere from less than a second to billions of years.

As atomic nuclei decay, radiation is released in three main forms: alpha particles, beta particles, and gamma rays. By emitting energy or particles, the nucleus becomes more stable.

Alpha Particles. An alpha particle is a fragment of a much larger nucleus. It consists of two protons and two neutrons (similar to the nucleus of a helium atom) and is positively charged. Compared to beta particles, alpha particles are relatively large and heavy and do not travel very far when ejected by a decaying nucleus. Therefore, alpha radiation is easily stopped by a thin layer of material such as paper or skin. However, if radioactive material is ingested or inhaled, the alpha particles released inside the body can damage soft internal tissues because their energy can be absorbed by tissue cells in the immediate vicinity of the decay. An example of an alpha-emitting radionuclide is the uranium isotope with an atomic weight of 232 (uranium-232). Uranium-232 was in the HLW mixture at the WVDP as a result of a thorium-based nuclear fuel reprocessing campaign conducted by NFS. Uranium-232 has been detected in liquid waste streams.

Radioactivity

Atoms that emit radiation are called radionuclides. Radionuclides are unstable isotopes of an element that have the same number of protons but different numbers of neutrons, resulting in different atomic masses. For example, the element hydrogen has two stable isotopes, hydrogen-1 (H^1) and hydrogen-2 (H^2) (deuterium), and one radioactive isotope, hydrogen-3 (H^3) (tritium). The numbers following the element's symbol identify the atomic mass, which is the number of protons plus neutrons in the nucleus. Thus, H^1 has one proton and no neutrons, H^2 has one proton and one neutron, and H^3 has one proton and two neutrons.

When radioactive atoms decay by emitting radiation, the daughter products that result may be either radioactive or stable. Generally, radionuclides with high atomic numbers, such as uranium-238 and plutonium-239, have many generations of radioactive progeny. For example, the radioactive decay of plutonium-239 creates uranium-235, thorium-231, protactinium-231, and so on, through 11 progeny until only the stable isotope lead-207 remains.

Radionuclides with lower atomic numbers often have no more than one daughter. For example, strontium-90 has one radioactive daughter, yttrium-90, which finally decays into stable zirconium; cobalt-60 decays directly to stable nickel with no intermediate nuclide.

The time required for half of the radioactivity of a radionuclide to decay is referred to as the radionuclide's half-life. Each radionuclide has a unique half-life; both strontium-90 and cesium-137 have half-lives of approximately 30 years while plutonium-239 has a half-life of 24,110 years. Knowledge of radionuclide half-lives is often used to estimate past and future inventories of radioactive material. For example, a 1.0-millicurie source of cesium-137 in 2000 would have measured 2.0 millicuries in 1970 and will be 0.5 millicuries in 2030.

Radiation emitted by radionuclides may consist of electromagnetic rays, such as x-rays and gamma rays, or charged particles, such as alpha and beta particles. A radionuclide may emit one or more of these radiations at characteristic energies that can be used to identify them.

Background Radiation

Background radiation is always present, and everyone is constantly exposed to low levels of such radiation from both naturally occurring and man-made sources. In the United States the average total annual exposure to low-level background radiation is estimated to be about 360 millirem (mrem) or 3.6 millisieverts (mSv). Most of this radiation, approximately 295 mrem (2.95 mSv), comes from natural sources. The rest comes from medical procedures, consumer products, and other man-made sources (National Council on Radiation Protection and Measurements Report 93, 1987). (See Figure 2-1 in Chapter 2, Environmental Radiological Program Information.)

Background radiation includes cosmic rays; the decay of natural elements, such as potassium, uranium, thorium, and radon; and radiation from sources such as chemical fertilizers, smoke detectors, and televisions. Actual doses vary depending on such factors as geographic location, building ventilation, and personal health and habits.

Beta Particles. A beta particle is an electron emitted during the breakdown of a neutron in a radioactive nucleus. Compared to alpha particles, beta particles are smaller, have less of a charge, travel at a higher speed (close to the speed of light), and can be stopped by wood or less than an inch of aluminum. If released inside the body, beta particles do much less damage than an equal number of alpha particles because beta particles deposit energy in tissue cells over a larger volume than alpha particles. Strontium-90, a fission product found in the stabilized supernatant, is an example of a beta-emitting radionuclide.

Gamma Rays. Gamma rays are high-energy “packets” of electromagnetic radiation, called photons, that are emitted from the nucleus. Gamma rays are similar to x-rays but generally are more energetic. If an alpha or beta particle released by a decaying nucleus does not carry off all the energy generated by the nuclear disintegration, the excess energy may be emitted as gamma rays. If the released energy is high, a very penetrating gamma ray is produced that can be effectively reduced only by shielding consisting of several inches of a dense material, such as lead, or of water or concrete several feet thick. Although large amounts of gamma radiation are dangerous, gamma rays are also used in lifesaving medical procedures. An example of a gamma-emitting radionuclide is barium-137m, a short-lived daughter product of cesium-137. Both barium-137m and its precursor, cesium-137, are major constituents of the WVDP HLW.

Measurement of Radioactivity. The rate at which radiation is emitted from a disintegrating nucleus can be described by the number of decay events or nuclear transformations that occur in a radioactive material over a fixed period of time. This process of emitting energy, or radioactivity, is measured in curies (Ci) or becquerels (Bq).

The curie is based on the decay rate of the radionuclide radium-226. One gram of radium-226 decays at the rate of 37 billion nuclear disintegrations per second (3.7×10^{10} d/s), so one curie equals 37 billion nuclear disintegrations per second. One becquerel equals one decay, or disintegration, per second. (See the Scientific Notation section at the back of this report or the Data Reporting section in this chapter for information on exponentiation [i.e., the use of “E” to mean the power of 10].)

Very small amounts of radioactivity are sometimes measured in picocuries. A picocurie is one-trillionth (1×10^{-12}) of a curie, equal to 3.7×10^{-2} d/s (3.7×10^{-2} Bq), or 2.22 disintegrations per minute.

Measurement of Dose. The amount of energy absorbed by the receiving material is measured in rads (radiation absorbed dose). A rad is 100 ergs of radiation energy absorbed per gram of material. (An erg is the approximate amount of energy necessary to lift a mosquito one-sixteenth of an inch.) “Dose” is a means of expressing the amount of energy absorbed, taking into account the effects of different kinds of radiation.

Alpha, beta, and gamma radiation affect the body to different degrees. Each type of radiation is given a quality factor that indicates the extent of human cell damage it can cause compared with equal amounts of other ionizing radiation energy. Alpha particles cause 20 times as much damage to internal tissues as x-rays, so alpha radiation has a quality factor of 20, compared to gamma rays, x-rays, or beta particles, all of which have a quality factor of one.

The unit of dose measurement to humans is the rem (roentgen equivalent man). The number of rem are equal to the number of rads multiplied by the quality factor for each type of radiation. Dose can also be expressed in sieverts. One sievert equals 100 rem.

Environmental Monitoring Program Overview

Human beings are exposed to radioactivity from site activities primarily through air, water, and food. At the WVDP all three pathways are monitored, but air and surface water pathways are the two primary means by which radioactive material can move off site.

Site geology (types of soil and bedrock), hydrology (location and flow of surface water and groundwater), and meteorology (wind speed, patterns, and direction) are all considered when evaluating potential exposure through the major pathways.

The on-site and off-site monitoring program at the WVDP includes measuring the concentration of alpha and beta radioactivity, conventionally referred to as “gross alpha” and “gross beta,” in air and water effluents. Measuring the total alpha and beta radioactivity from key locations produces a comprehensive picture of on-site and off-site levels of radioactivity from all sources. For a U.S. Department of Energy (DOE) site such as the WVDP, frequent updating and tracking of the overall radioactivity levels in effluents is an important tool in maintaining acceptable operations.

More-detailed measurements are also made for specific radionuclides. Strontium-90 and cesium-137 are measured because they have been previously detected in WVDP waste materials. Radiation from other important radionuclides, such as tritium or iodine-129, is not sufficiently energetic to be detected by gross measurement techniques, so these must be analyzed separately using methods with greater sensitivity. Heavy elements, such as uranium, plutonium, and americium, require special analysis because they exist in such small concentrations in the WVDP environs.

The radionuclides monitored at the Project are those that might produce relatively higher doses or that are most abundant in air and water effluents. Because man-made sources of radiation at the Project have been decaying for more than 30 years, the monitoring program does not routinely include short-lived radionuclides, that is, isotopes with a half-life of less than two years, which would be present at less than 1/1,000 of the original radioactivity levels. (See Appendix B⁶⁰ for the schedule of samples and radionuclides measured and Appendix K⁶⁰ for a listing of the half-lives of radionuclides measured in WVDP samples and related DOE protection standards, such as the derived concentration guides [DCGs]. See also the discussion of DCGs in this chapter.)

Data Reporting. Because the decay of radioactive atoms is a random process, an inherent uncertainty is associated with all measurements of environmental radioactivity. This can be demonstrated by repeatedly measuring the number of atoms that decay in a radioactive sample over some fixed period of time. The result of such an experiment would be a range of values for which the average value would provide the best indication of how many radioactive atoms were present in the sample.

In actual practice, an environmental sample is usually measured for radioactivity only once. The inherent uncertainty of the measurement, then, stems from the fact that it cannot be known whether the result from one measurement is higher or lower than the “true” value.

The term *confidence interval* is used to describe the range of measurement values above and below the test result within which the “true” value is expected to lie. This interval is derived statistically. The width of the interval is based primarily on a predetermined confidence level, that is, the probability that the confidence interval actually en-

Derived Concentration Guides

A derived concentration guide (DCG) is defined in DOE Order 5400.5 as the concentration of a radionuclide in air or water that, under conditions of continuous exposure by one exposure mode (i.e., ingestion of water, immersion in air, or inhalation) for one year, would result in an effective dose equivalent of 100 mrem (1 mSv) to a “reference man.” These concentrations – DCGs – are used as reference screening levels to enable WVDP personnel reviewing effluent and environmental data to decide if further investigation is needed. (See Appendix K^{6D} for a list of DCGs.)

For liquid effluent screening purposes, the percentages of the DCGs for all radionuclides present are summed. If the total is less than 100%, then the effluent complies with the DOE guideline. DCGs are also compared with radionuclide concentrations from these sources to verify that Best Available Technology standards for treatment of water are being met.

The DOE provides DCGs for airborne radionuclides in locations where members of the public could, over an extended period of time, breathe air containing contaminants. DCGs are only applicable to radionuclides in air breathed by members of the public. DCGs may be used as a comparative basis for screening concentrations from air emission points.

DOE Orders and federal regulations require that the hypothetical dose to the public from facility effluents be estimated using specific computer codes. (See Dose Assessment Methodology in Chapter 2, Environmental Radiological Program Information.) Doses estimated for WVDP activities are calculated using actual site data and are not related directly to summed DCG values. Dose estimates for liquid effluents are based on the product of radionuclide quantities released and the site-specific dose equivalent effects for that radionuclide. Although airborne DCGs are used for comparison purposes, the more stringent U.S. Environmental Protection Agency (EPA) National Emission Standards for Hazardous Air Pollutants regulate Project airborne effluents at the point of release. For a consistent guide to relative concentrations, both air and water sampling results are compared with DCGs throughout this report.

compasses the “true” value. The WVDP environmental monitoring program uses a 95% confidence level for all radioactivity measurements and calculates confidence intervals accordingly.

The confidence interval around a measured value is indicated by the plus-or-minus (\pm) value following the result (e.g., $5.30 \pm 3.6E-09$ microcuries per milliliter [$\mu\text{Ci/mL}$]), with the exponent of 10^{-9} expressed as “E-09.” Expressed in decimal form, the result $5.30 \pm 3.6E-09$ would be $0.0000000530 \pm 0.000000036 \mu\text{Ci/mL}$. A sample

measurement expressed this way is correctly interpreted to mean “there is a 95% probability that the concentration of radioactivity in this sample is between $1.7E-09 \mu\text{Ci/mL}$ and $8.9E-09 \mu\text{Ci/mL}$.” (See also Scientific Notation at the end of this report.) If the confidence interval for the measured value includes zero (e.g., $5.30 \pm 6.5E-09 \mu\text{Ci/mL}$), the value is considered to be below the detection limit. The values listed in tables of radioactivity measurements in the appendices include the confidence interval regardless of the detection limit value.

In general, the detection limit is the minimum amount of constituent or material of interest detected by an instrument or method that can be distinguished from background and instrument noise. Thus, the detection limit is the lowest value at which a sample result shows a statistically positive difference from a sample in which no constituent is present.

Nonradiological data are conventionally presented without an associated uncertainty and are expressed by the detection limit prefaced by a “less-than” symbol (<) if that analyte was not measurable.

Units of measure, as used in this document, are listed in the Units of Measure section in the back of this report. In the text, traditional radiological units (e.g., rem, rad, curie, roentgen) are presented first, followed by Systeme Internationale (S.I.) units. Nonradiological measurements are presented in metric units. A conversion chart for comparing traditional and S.I. radiological units and English and metric nonradiological units is presented in the Units of Measure section.

Changes in the 2004 Environmental Monitoring Program. Two modifications to the environmental sampling and surveillance network were made in 2004.

- A new air sampling location (ANRHWFK) at the recently constructed remote-handled waste facility (RHWF) was brought on line in May 2004 and radiological operations began at this facility in June 2004.
- Portable air samplers were used to monitor outdoor ventilated enclosures/portable ventilation units, which were used in an expanded role in 2004 to ventilate decontamination activities in the main plant.

See Appendix B⁶⁰ for a detailed summary of the program changes and the sample points and parameters measured in 2004.

Completion of Vitrification

HLW from NFS operations was originally stored in two of four underground tanks (tanks 8D-2 and 8D-4). Contents in the tanks were pretreated to remove sodium salts and sulfates and most of the radioactive cesium, and resulting wastes were fixed into about 20,000 drums of cemented LLW between 1988 and 1990. Vitrification of the HLW began in 1996 and continued through September 2002. (See the 2002 WVDP Annual Site Environmental Report [West Valley Nuclear Services Company [WVNSCO] and URS, 2003] for a complete description of the vitrification process.)

Over the course of vitrification, more than 12.2 million cesium/strontium curies were transferred to the vitrification facility and 275 canisters were filled. Two additional waste canisters were generated when the melter was evacuated. Canisters are in temporary storage in a shielded cell in the main plant, the former chemical processing cell, and are being maintained until a disposal facility becomes available.

2004 Activities at the WVDP

The WVDP’s environmental management system (EMS) is an important factor in the environmental monitoring program and the accomplishment of its mission. Significant components, initiatives, and accomplishments at the WVDP in 2004 are summarized below.

Decontamination and Dismantlement. Decontamination of the head end cells (including the general purpose cell and the process mechanical cell) and in extraction cell 2 continued and was completed in 2004 with the removal of excess

equipment. Decontamination of the vitrification cell continued and dismantlement began with removal of the jumpers and major equipment and vessels, including the melter. More than 150 waste containers of dismantled hardware were successfully removed. This work will continue in 2005.

Sodium-Bearing Waste Management. Sodium-bearing wastewater consisting of flushed liquid retrieved from the waste tank farm was solidified on site during 2004. A portable system was used to solidify approximately 11,500 gallons (43,500 liters) of this LLW. The solidified material was placed into 17 ten-ton steel containers for off-site transport to the Nevada Test Site (NTS).

Rail Spur Repairs. Reconstruction of a 750-foot-long section of the rail spur that services the WVDP was completed during 2004 to support waste shipments from the site. The work included lifting rails and ties, removing loose soil under the rail bed, installing drainage, and grading and compacting with new stone. Before removal, the rail bed soils were characterized for chemical constituents in order to identify appropriate soil management practices.

Infrastructure Footprint Reduction. Personnel were relocated to available on-site locations, which enabled the removal of several office and storage trailers from the WVDP site. Similar reductions of the site's infrastructure footprint will continue in 2005.

Remote-Handled Waste Facility Construction. As part of project operations, various contaminated materials and components were removed from the former process building and stored awaiting disposal. As work progresses toward eventual decommissioning, additional materials and components will be removed from the waste tank farm and the former process building. Before these waste materials can be shipped for

disposal, they must be characterized, sorted, processed as necessary, and packaged to meet regulatory requirements for transportation. Construction of the RHWF, where these activities take place, was completed in 2004. DOE authorized the startup of radioactive processing on June 3, 2004 and two waste processing campaigns were completed by the end of 2004.

Environmental Management of Aqueous Radioactive Waste. Water containing radioactive material from site process operations is collected and treated in the low-level waste treatment facility (LLWTF), which includes the LLW treatment building and associated holding lagoons. (Water from the sanitary system, which does not contain added radioactive material, is managed in a separate system.)

The treated process water is held, sampled, and analyzed before its release through a New York State Pollutant Discharge Elimination System (SPDES)-permitted outfall. In 2004, about 15.0 million gallons (56.6 million liters) of water were treated in the LLWTF system and discharged through outfall 001, the lagoon 3 weir. The total 2004 discharge waters contained an estimated 12.6 millicuries of gross alpha plus gross beta radioactivity. Comparable releases during the previous 19 years averaged about 32 millicuries per year. The 2004 release was about 40% of this average. (See "Overview of Water Effluent and Ambient Surface Water Monitoring" in Chapter 2.)

Approximately 0.083 curies of tritium were released in WVDP-controlled liquid effluents in 2004 – about 7% of the 19-year annual average of 1.12 curies.

North Plateau Groundwater Recovery System (NPGRS). The NPGRS operated throughout 2004, recovering groundwater from an area near the leading edge of the strontium-90 plume on the north plateau. For a more detailed discus-

sion of the plume and the NPGRS, see Chapter 2, “Northeast Swamp and North Swamp Drainage,” and Chapter 4, “Results of Routine Groundwater Monitoring” and “Special Groundwater Monitoring.”

Environmental Management of Airborne Radioactive Emissions. Ventilated air from the various WVDP facilities is sampled continuously during operation for particulate matter and for gaseous radioactivity. In addition to monitors that alarm if particulate matter radioactivity increases above preset levels, the sample media are analyzed in the laboratory for the specific radionuclides that are present in the radioactive materials being handled.

Air used to ventilate the facilities undergoing radioactive material cleanup is passed through filtration devices before being emitted to the atmosphere. These filtration devices are generally more effective for particulate matter than for gaseous radioactivity. For this reason, facility air emissions tend to contain a greater amount of gaseous radioactivity (e.g., tritium and iodine-129) than radioactivity associated with particulate matter (e.g., strontium-90 and cesium-137). However, gaseous radionuclide emissions still remain so far below the most restrictive regulatory limit for public safety that additional treatment technologies beyond those already provided are not necessary.

Gaseous radioactivity emissions from the main plant in 2004, the second full year since vitrification was completed, included approximately 5.57 millicuries of tritium (as hydrogen tritium oxide) and 0.028 millicuries of iodine-129. (See Chapter 2 for a discussion of iodine-129 emissions from the main plant stack.) As expected, these 2004 values are quite low in comparison to values from 1997, the first full year the vitrification system operated at a relatively high rate of production. In 1997, tritium and iodine-129 emissions were 140 millicuries and 7.43 millicuries, respectively.

Particulate matter radioactive emissions from the main plant in 2004 included approximately 0.13 millicuries of gross beta-emitting radioactivity and 0.004 millicuries of gross alpha-emitting radioactivity. In 1997, beta-emitting and alpha-emitting radioactivity emissions were 0.4 millicuries and 0.001 millicuries, respectively. Increased alpha-emitting radioactivity in main stack air effluent in 2004 was related to ongoing decontamination and decommissioning activities in the main process building.

Environmental Management of Radiological Exposure. Environmental radiation is measured with thermoluminescent dosimeters (TLDs) at on-site and off-site locations. (See Figs. A-10 and A-11 for the locations of on-site and off-site TLD monitoring points.) Although exposure rates at many on-site locations were elevated with respect to background, results from perimeter TLDs that would be more representative of exposure to the public were statistically indistinguishable from background results. (See “Direct Environmental Radiation Monitoring” in Chapter 2.)

Unplanned Radiological Releases. There were no unplanned airborne radiological releases on site or off site to the environment from the Project in 2004. In addition, there were no unplanned releases to the off-site environment of waterborne radioactivity in 2004. (See “RCRA 3008(h) Administrative Order on Consent” and “Process Sewer Integrity Evaluation” in the Environmental Compliance Summary section.)

Nuclear Regulatory Commission (NRC)-Licensed Disposal Area (NDA) Interceptor Trench and Pretreatment System. Radioactively-contaminated n-dodecane, in combination with tributyl phosphate (TBP), was discovered at the northern boundary of the NDA in 1983, shortly after the DOE assumed control of the WVDP. Extensive sampling and monitoring through 1989 revealed the possibility that the n-dodecane/TBP

could migrate. To contain migration of this subsurface radioactive organic contaminant, an interceptor trench and liquid pretreatment system (LPS) were built.

As in previous years, no water containing TBP was encountered in the trench and no water was treated by the LPS in 2004. More than 404,000 gallons (1,530,000 liters) of radiologically contaminated water were collected from the interceptor trench and transferred to the LLWTF for treatment during the year. Results of surface and groundwater monitoring in the vicinity of the trench are discussed in Chapter 2 under "South Plateau Surface Water and NDA Interceptor Trench" and in Chapter 4 under "Results of Monitoring at the NDA."

Waste Minimization Program. The WVDP formalized a waste minimization program in 1991 to reduce the generation of LLW, mixed waste, and hazardous waste. This program is a comprehensive and continual effort to prevent or minimize pollution, with the overall goals of reducing health and safety risks, protecting the environment, and complying with all federal and state regulations. (See also the "Waste Minimization" and "Pollution Prevention" sections in the Environmental Compliance Summary and later in this chapter.)

Pollution Prevention Awareness Program. The WVDP's Pollution Prevention (P2) Awareness Program is a significant part of the Project's waste minimization program. The goal of the program is to make all employees aware of the importance of pollution prevention both at work and at home.

A crucial component of the P2 Awareness Program at the WVDP is the Pollution Prevention Coordinators group. This group communicates, shares, and publicizes prevention, reduction, reuse, and recycling information to all departments

at the WVDP. The P2 Coordinators identify and facilitate the implementation of effective source reduction, reuse, recycling, and procurement of recycled products. The WVDP employs an incentive-based program (the Bright Ideas Program) to encourage waste stream reduction/elimination, energy savings, and affirmative procurement. This program continues to foster cost savings and avoidances resulting from waste minimization and P2 activities.

Waste Management. The WVDP continued its accomplishments in reducing and eliminating waste generated by site activities. Reductions in the generation of LLW, mixed waste, hazardous waste, industrial wastes, and sanitary waste, such as paper, plastic, wood, and scrap metal were targeted.

Waste minimization and recycling activities during 2004 resulted in cost savings and reduced waste generation. To accomplish this, the following items were recycled:

- paper and paper products - 115 tons (104 metric tons)
- scrap metals - 30.2 tons (27.4 metric tons)
- other materials - 18.0 tons (16.3 metric tons).

Low-Level Radioactive Waste Shipping Program. The WVDP initiated the LLW shipping program in 1997 to reduce the inventory of legacy and newly-generated waste stored on site. Most waste was sent to commercial disposal facilities until July 2001, when the WVDP was approved to ship LLW to the NTS, a DOE facility. During calendar year (CY) 2004, a total of 20 shipments (about 104,000 cubic feet [about 3,000 cubic meters]) were safely shipped for off-site disposal. An accelerated LLW shipping schedule is planned for 2005.

National Environmental Policy Act (NEPA) Activities. Under NEPA, the DOE is required to consider the overall environmental effects of its proposed actions or federal projects. The President's Council on Environmental Quality established a screening system of analyses and documentation that requires each proposed action to be categorized according to the extent of its potential environmental effect. The levels of documentation include categorical exclusions (CXs), environmental assessments (EAs), and environmental impact statements (EISs).

CXs evaluate and document actions that will not have a significant effect on the environment. EAs evaluate the extent to which the proposed action will affect the environment. If a proposed action has the potential for significant effects, an EIS is prepared that describes proposed alternatives to an action and explains the effects.

Facility maintenance, decontamination activities, and minor projects that support HLW vitrification are documented and submitted for approval as CXs, although EAs occasionally are necessary for larger-scale activities.

In December 1988, the DOE published a joint Notice of Intent (NOI) with the New York State Energy Research and Development Authority (NYSERDA) to prepare an EIS for the completion of the WVDP and closure of the facilities at the WNYNSC.

The draft EIS, which describes the potential environmental effects associated with Project completion and various site closure alternatives, was completed in 1996 and released without a preferred alternative for a six-month public review and comment period. Having met throughout 1997 and 1998 to review alternatives presented in the draft EIS, the West Valley Citizen Task Force (see inset) issued the West Valley Citizen Task Force

Final Report (July 29, 1998). This report provided recommendations and advice on the development of a preferred alternative. The Task Force continues to meet and discuss issues related to Project completion and site closure decision-making.

In 2001, the DOE formally initiated its plan to split the scope of the 1996 draft EIS into two phases – one for near-term waste management decision-making and one for final decommissioning and/or long-term stewardship decision-making. Each phase will be covered by a separate EIS.

DOE published a Federal Register (FR) NOI on March 26, 2001 (66 FR 16447) formally announcing its rescoping plan and preparation of the waste management EIS. The DOE also published an Advance NOI on November 6, 2001 (66 FR 56090) announcing its commitment to begin work, in cooperation with NYSERDA, on the Decommissioning and/or Long-Term Stewardship EIS.

West Valley Citizen Task Force

In addition to the public comment process required by the National Environmental Policy Act, the New York State Energy Research and Development Authority, with participation from the DOE, formed the West Valley Citizen Task Force in January 1997. The mission of the Task Force is to provide advice on the completion of the West Valley Demonstration Project and cleanup, closure, and/or long-term management of the facilities at the site. The Task Force process has helped illuminate the various interests and concerns of the community, increased the two-way flow of information between the site managers and the community, and provided an effective way for the Task Force members to establish mutually-agreed-upon recommendations for the site managers to consider in their decision-making process.

On May 16, 2003, the DOE issued the draft Waste Management EIS (68 FR 26587) for public comment. The DOE considered public comments received and issued the final Waste Management EIS in January 2004.

Because the NRC is authorized by the WVDP Act to prescribe decommissioning criteria for the WVDP, from 1998 until early 2002 the NRC worked to develop those decommissioning criteria through a series of draft policy papers and public meetings. On February 1, 2002, the NRC issued its "Decommissioning Criteria for the West Valley Demonstration Project (M-32) at the West Valley Site; Final Policy Statement" in the Federal Register (67 FR 5003). The Final Policy Statement applies the NRC's License Termination Rule (10 Code of Federal Regulations Part 20, Subpart E) as the decommissioning criteria for the WVDP and as the decommissioning goal for the entire WNYNSC.

The DOE published an NOI on March 13, 2003 (68 FR 12044) announcing its intent to prepare, in cooperation with NYSERDA, the Decommissioning and/or Long-Term Stewardship EIS. The DOE and NYSERDA are joint lead agencies on this EIS. The EPA, the NRC, and the New York State Department of Environmental Conservation (NYSDEC) are cooperating agencies on the Decommissioning and/or Long-Term Stewardship EIS. Work on preparation of this EIS continued in 2004.

The DOE and NYSERDA continue efforts to reach agreement on a preferred alternative and agency responsibilities for decommissioning and/or long-term stewardship at the WVDP and the WNYNSC.

Self-Assessments. Self-assessments continued to be conducted in 2004 to review the management and effectiveness of the WVDP environ-

mental protection and monitoring programs. Results of these self-assessments are evaluated and corrective actions are tracked through to completion. Overall results of these self-assessments found that the WVDP continued to implement quality requirements and, in some cases, improve the quality of the environmental protection and monitoring program. (See the Environmental Compliance Summary and Chapter 5, Quality Assurance.)

Occupational Safety and Environmental Training. The safety of personnel who are involved in industrial operations under DOE cognizance is protected by standards mandated by DOE Order 440.1A, "Worker Protection Management for DOE Federal and Contractor Employees," which directs compliance with specific Occupational Safety and Health Act (OSHA) requirements. This act governs diverse occupational hazards ranging from electrical safety and protection from fire to the handling of hazardous materials. The purpose of OSHA is to maintain a safe and healthy working environment for employees.

Hazardous waste operations and emergency response regulations require that employees at treatment, storage, and disposal facilities, particularly those who may be exposed to health and safety hazards during hazardous waste operations, receive training appropriate to their job function and responsibilities. The WVDP environmental, health, and safety training matrix identifies the specific training requirements for such employees.

The WVDP provides basic 24-hour hazardous waste operations and emergency response training. (Emergency response training includes spill response measures and controlling contamination of groundwater.) The WVDP trains decontamination workers and their supervisors according to the 40-hour program for hazardous waste operations and emergency response to meet the additional

OSHA training requirements of a cleanup site. The additional training provides workers with information and techniques for decontamination operations.

Training programs also contain information on waste minimization, pollution prevention, and the WVDP environmental management program. In addition to this standard training, employees working in radiological areas receive training on subjects such as understanding radiation and radiation warning signs, dosimetry, and respiratory protection. Qualification standards for specific job functions at the site are required and maintained. Training programs have evolved into a comprehensive curriculum of knowledge and skills necessary to maintain the health and safety of employees and ensure the continued compliance of the WVDP.

Medical emergencies on site are handled by the WVDP Emergency Medical Response Team. This team consists of on-site professional medical staff and volunteer New York State-certified emergency medical technicians.

Any person working at the WVDP who has a personal photo badge receives general employee training that covers health and safety, emergency response, and environmental compliance issues. All visitors to the WVDP receive a site-specific briefing on safety and emergency procedures before being admitted to the site.

Voluntary Protection Program STAR Status. On May 5, 2000 the WVDP received Voluntary Protection Program (VPP) STAR status. This prestigious award was granted in recognition of the WVDP's excellent worker safety and health programs. (See also the Environmental Compliance Summary.)

The WVDP has reaffirmed its commitment to DOE's VPP and was reviewed as part of the an-

nual integrated safety management system (ISMS) review. The DOE recertified the WVDP as a DOE-VPP STAR site. At the annual VPP Participants National Conference, WVNSCO was awarded the DOE's Legacy of Stars Award, which is given to sites with an outstanding safety record over a three-year period.

In addition, the WVDP has been actively promoting VPP in the community by mentoring local businesses and providing assistance to support OSHA with VPP evaluations of other sites.

Employees of the WVDP reached 2.5 million safe work hours and two years without a lost-time work accident on November 30, 2004. In recognition of this safety record, WVNSCO employees were awarded the President's Award for Safety for the second consecutive year.

Environmental Management System Implementation. The Project's EMS provides the basic policy and direction for work at the WVDP through procedures that support proactive management, environmental stewardship, and the integration of appropriate technologies throughout all aspects of work at the WVDP. EMS implementation is summarized in Table ECS-1.

The WVDP EMS satisfies requirements of the new DOE Order 450.1, "Environmental Protection Program." (See the discussion of new DOE Order 450.1 in the Environmental Compliance Summary.) The EMS is also in compliance with the "Code of Environmental Management Principles" (CEMP) for federal agencies and International Organization for Standardization 14001, Environmental Management Systems: "Specification for Guidance and Use," which is being implemented worldwide. The CEMP was developed by the EPA in response to Executive Order (EO) 12856, "Federal Compliance with Right-to-Know Laws and Pollution Prevention Requirements," to

serve as the basis for responsible environmental management. (EO 12856 was revoked in April 2000 by EO 13148, “Greening the Government Through Leadership in Environmental Management.”)

Following the principles and performance objectives of the CEMP helps to ensure that a federal facility’s environmental performance is proactive, flexible, cost-effective, and sustainable. The WVDP has been renewed for membership in the EPA’s National Environmental Performance Track program for implementation of this EMS. New objectives were developed for the three-year period of 2004–2006. (See National Environmental

Performance Track inset in this chapter.) The most recent self-assessment by WVNSCO, performed in December 2004, verified that the EMS continues to be effectively implemented at the WVDP.

Integrated Safety Management System Implementation. A plan to integrate environmental, safety, and health (ES&H) management programs at the WVDP was developed and initiated in 1998. During this development, the EMS was identified as an integral part of the ISMS. Environmental subject matter experts participate in a sitewide work review group to review work plans, identify ES&H concerns, and specify practices that ensure work is performed safely.

Implementation of an ISMS at the WVDP, including the EMS, was verified by the DOE Ohio Field Office in November 1998. The most recent self-assessment by WVNSCO, performed in August 2004, verified that the ISMS continues to be effectively implemented at the WVDP. An annual ISMS review by the DOE occurred in November 2004. The DOE specifically evaluated the integration of EMS into the ISMS and confirmed results of the WVNSCO self-assessment.

Performance Measures

Performance measures can be used to evaluate effectiveness, efficiency, quality, timeliness, productivity, safety, or other areas that reflect achievements related to organization or process goals, and can be used as a tool to identify the need to institute changes.

The performance measures applicable to operations conducted at the WVDP, discussed here, reflect process performance related to wastewater treatment in the LLWTF, the identification of spills and releases, the reduction in waste generation, the potential radiological dose received by the maximally exposed off-site individual (MEOSI),




and the transfer of HLW to the vitrification system.


Radiation Doses to the Maximally Exposed Off-Site Individual. One of the most important pieces of information derived from environmental monitoring program data is the potential radiological dose to an off-site individual from on-site activities. As an overall assessment of Project activities and the effectiveness of the as-low-as-reasonably-achievable concept, the potential radiological dose to the MEOSI is an indicator of well-managed radiological operations. The effective dose equivalents for air effluent emissions, liquid effluent discharges, and other liquid releases (such as swamp drainage) from 1995 through 2004 are graphed in Figure 1-1. Note that the sum of these values is well below the DOE standard of 100 mrem per year. These consistently low results indicate that radiological activities at the site are well-controlled. (See also Table 2-3 in Chapter 2, Environmental Radiological Program Information.)

State Pollutant Discharge Elimination System Permit Limit Exceptions. Effective operation of the site wastewater treatment facilities is indicated by compliance with the applicable discharge permit limitations. Approximately 60 parameters are monitored regularly as part of the SPDES permit requirements. The analytical results are reported to NYSDEC via Discharge Monitoring Reports, required under the SPDES program.

Although the goal of the LLWTF and wastewater treatment facility operations is to maintain effluent water quality consistently within the permit requirements, occasionally SPDES permit limit exceptions do occur. All SPDES permit limit exceptions are evaluated to determine their cause and to identify corrective measures.

A Water Task Team, composed of WVDP personnel with expertise in wastewater engineering, treatment plant operations and process monitoring, and National Pollutant Discharge Elimination System/SPDES permitting and compliance, was





formed in 1995 to address the causes of these exceptions. The Water Task Team's efforts produced three consecutive years (1998, 1999, and 2000) with no permit limit exceptions. In 2001, one permit limit exception for total recoverable lead occurred at outfall 008 – the french drain for the LLWTF lagoon system. One SPDES limit exception occurred in May 2004 when a test result for total suspended solids (TSS) for a sample obtained at outfall 001 was reported above the allowable (daily maximum) effluent limit. (See Fig. 1-2.) The increased TSS was caused by a storm event that resulted in runoff carrying soil and sediment down the sides of the effluent-holding lagoon and into the effluent water during the discharge.

In June 2004, the minimum permit requirement for monitoring total recoverable hexavalent chromium at outfall 001 was not met. An analytical interference resulted in an inaccurate and invalid test result for one sample that was analyzed for this chemical substance. As a consequence, the number of valid sample analyses was one short of that required.

Although exceptions are not always related to operating deficiencies, corrective actions may include improved operation or treatment techniques. In 1997, the WVDP notified NYSDEC of the presence of mercury in the influent wastewater to the

LLWTF and of its likely presence at outfall 001 at concentrations below the detectable level of 0.2 micrograms per liter ($\mu\text{g/L}$). In 2002, a modification to the SPDES permit required that samples being collected for measurement of mercury be analyzed in duplicate by EPA Method 245.1 (with a method detection level of 0.2 $\mu\text{g/L}$) and by newer, more-sensitive, EPA Method 1631E. Results of the comparison are reported to NYSDEC on a quarterly basis. Results from EPA Method 1631E in 2004 were consistent with those from EPA Method 245.1. (See Chapter 3, Mercury Analytical Method Study, for a discussion of this study.)

Waste Minimization and Pollution Prevention. In 2004, the WVDP continued its program of reducing and eliminating the amount of waste generated from site activities. Emphasis on good business practices, source reduction, and recycling continued to promote reduction of LLW, mixed waste, hazardous waste, industrial wastes, and sanitary wastes, such as paper, glass, plastic, wood, and scrap metal.

To demonstrate effectiveness of the waste minimization program, a graph of the percentage of waste reduction achieved above the annual goal for each category is presented in Figure 1-3 for CYs 1996 through 2004.

The WVDP set the following cumulative nonvitri-fication waste-reduction goals for fiscal year (FY) 2004: a 75% reduction in the generation of LLW, an 80% reduction in the generation of mixed waste, a 70% reduction in the generation of hazardous waste, a 60% reduction in the generation of industrial waste, and a 75% reduction in the generation of sanitary waste. These goals were based on quantities of routine waste generated in 1993. (As of FY 2002, all WVDP pollution prevention




Figure 1-3. Percentage of Waste-Reduction-Exceeding Goals

goals are in alignment with the DOE’s pollution prevention goals, which are based on a federal fiscal year.)

All but two of these goals were exceeded during FY 2004. LLW generation was reduced by 83%. Mixed waste generation was reduced by 91%, hazardous waste by 95%, industrial waste by 11% (below the goal of 60%), and sanitary waste generation was reduced by 58% (below the goal of 75%). Industrial and sanitary waste generation during FY 2004 exceeded expectations due to numerous activities to support site closure milestones and efforts to improve housekeeping and eliminate unnecessary paper.

Hazardous waste and industrial waste volumes have been tracked separately for vitrification-related and nonvitrification-related waste streams since vitrification began in 1996. To maintain historical comparability, the percentages in Figure 1-3 include only the nonvitrification portions of these two waste streams.

Spills and Releases. Chemical spills greater than the applicable reportable quantity must be reported immediately to NYSDEC, the National Response Center, and other agencies as required. There were no reportable chemical spills during 2004.

Petroleum spills greater than five gallons – or of any amount that travel to waters of the state – must be reported immediately to the NYSDEC spill hotline and entered in the WVDP’s monthly log. There were no reportable petroleum spills in




Figure 1-4. Number of Immediately Reportable Spills or Releases

2004. Figure 1-4 is a bar graph of immediately-reportable spills from 1996 to 2004.

Prevention is the best means of protection against oil, chemical, and hazardous substance spills or releases. WVDP employees are trained in applicable standard operating procedures for equipment that they use, and best management practices have been developed that identify potential spill sources and preventive measures that will reduce the likelihood of releases. Spill training, notification, and reporting policies have also been developed to emphasize the responsibility of each employee to report spills immediately upon discovery. This first-line reporting helps to ensure that spills will be properly documented and mitigated in accordance with applicable regulations.

This page intentionally left blank

ENVIRONMENTAL RADIOLOGICAL PROGRAM INFORMATION

Radiation in the Environment

Sources of Radiation

Members of the public are routinely exposed to ionizing radiation from both natural and man-made sources. An individual living in the United States (U.S.) is estimated to receive an average annual effective dose equivalent of about 360 millirem (mrem) (3.6 millisieverts [mSv]) (National Council on Radiation Protection and Measurements Report 93 [1987b]).

While most of the radiation dose received by the general public is from natural background sources, man-made sources of radiation also contribute to the average dose. Such sources include diagnostic and therapeutic x-rays, nuclear medicine, fallout residues from atmospheric nuclear weapons tests, effluents from nuclear fuel-cycle facilities, and consumer products such as smoke detectors and cigarettes (Fig. 2-1).

Routine activities at the West Valley Demonstration Project (WVDP or Project) have the potential to release radioactive or hazardous substances that could affect the environment.

Exposure Pathways

The radionuclides present at the WVDP site are residues from the reprocessing of commercial nuclear fuel during the 1960s and early 1970s by a previous site operator. A very small fraction of these radionuclides is released off site during the year through ventilation systems and liquid discharges. These releases make a negligible contribution to the radiation dose to the surrounding population through several exposure pathways.

An exposure pathway consists of a route for a source of contamination or radiation to be transported by environmental media to a receptor where exposure may occur. For example, a member of the public could be exposed to low concentrations of radioactive particles carried by prevailing winds.

The potential pathways of exposure from Project emissions are inhalation of gases and particulates, ingestion of locally grown food products, consumption of fish, beef, and venison, and exposure to external penetrating radiation emitted from contaminated materials. Table 2-1 summarizes the potential exposure pathways for the local off-site population and describes the rationale for includ-

Ionizing Radiation

Radiation can be damaging if, in colliding with other matter, the alpha or beta particles or gamma rays knock electrons loose from the absorber atoms. This process is called ionization, and the radiation that produces it is referred to as ionizing radiation. Ionization changes an electrically neutral atom, in which the positively charged protons and the negatively charged electrons balance each other, into a charged atom called an ion. An ion can be either positively or negatively charged. Various kinds of ionizing radiation produce different degrees of damage.

Potential Effects of Radiation

Biological effects of radiation can be either somatic or genetic. Somatic effects of radiation exposure are limited to the exposed individual. For example, sufficiently high exposure to radiation can cause clouding of the lens of the eye or a decrease in white blood cells.

Radiation can also cause chromosomes to break or rearrange themselves or to join incorrectly with other chromosomes. These changes may produce genetic effects and may show up in future generations. Radiation-produced genetic defects and mutations in the offspring of an exposed parent, while not positively identified in humans, have been observed in some animal studies.

The effect of radiation depends on the amount absorbed within a given exposure time. The only observable effect of an instantaneous whole-body dose of 50 rem (0.5 Sv) might be a temporary reduction in white blood cell count. An instantaneous dose of 100–200 rem (1–2 Sv) might cause additional temporary effects, such as vomiting, but usually would have no long-lasting side effects. Assessing biological damage from low-level radiation is difficult because other factors can cause the same symptoms as radiation exposure. Moreover, the body is able to repair damage caused by low-level radiation. There have been no documented effects from exposures of less than 10 rem.

The effect most often associated with exposure to relatively high levels of radiation appears to be an increased risk of cancer. However, scientists have not been able to demonstrate with certainty that exposure to low-level radiation causes an increase in injurious biological effects, nor have they been able to determine if there is a level of radiation exposure below which there are no adverse biological effects.

Health Effects of Low-Level Radiation

Radionuclides entering the body through air, water, or food are distributed in different organs of the body. For example, isotopes of iodine concentrate in the thyroid. Strontium, plutonium, and americium isotopes concentrate in the skeleton. When inhaled, particulate uranium and plutonium isotopes may remain in the lungs for a long period of time. Some radionuclides such as tritium, carbon-14, or cesium-137 are distributed uniformly throughout the body. Thus, depending on the radionuclide, some organs may receive quite different doses. Moreover, at the same dose levels, certain organs (such as the breast) are more prone to developing a fatal cancer than other organs (such as the thyroid).

Because of the uncertainty and difficulty in measuring the incidence of increased cancer resulting from exposure to ionizing radiation, to be conservative, a linear model is used to predict health risks from low levels of radiation. This model assumes that there is a risk associated with all dose levels even though the body may effectively repair damage incurred from low levels of alpha, beta, and gamma radiations.

ing or excluding each pathway when calculating dose from the WVDP. For instance, drinking water is not considered a pathway for exposure from the WVDP because surveys revealed that local residents do not use Cattaraugus Creek as a source of drinking water.

Land Use Survey

Periodic surveys of local residents provide information about local family sizes, sources of food, and gardening practices. In early 2003, census information from calendar year (CY) 2000 was used to update population files used for dose assessment. Information from the most recent land use survey, conducted in early 2002, was used to confirm the locations of the nearest residences. These parameters are required for computer models that are used for the annual dose assessments. (See the discussion of Dose Assessment Methodology later in this chapter for more information on calculation of dose to the public.)

Dose to the Public

Each year the potential radiological dose to the public that is attributable to operations and effluents from the WVDP is assessed to verify that no individual could credibly have received a dose exceeding the limits established by the regulatory agencies.

Estimated doses are compared directly with current radiation standards established by the U.S. Department of Energy (DOE) and the U.S. Environmental Protection Agency (EPA) for protection of the public. These values are also compared with the annual dose an average U.S. resident receives from natural background radiation and to doses reported in previous years for the Project. Figure 2-1 shows the relative contribution to the annual dose in mrem from natural and man-made sources in comparison with the estimated CY 2004 maximum individual dose from the WVDP. (Units of dose measurement are explained in detail later in this chapter.)




Figure 2-1. Comparison of Doses From Natural and Man-Made Sources to the Dose From 2004 WVDP Effluents

As can be seen in Figure 2-1, natural sources of radiation contribute 295 mrem (2.95 mSv) and man-made sources contribute 65 mrem (0.65 mSv) of the total annual U.S. average dose of 360 mrem (3.60 mSv). In 2004, the WVDP contributed a very small amount (0.049 mrem [0.00049 mSv]) of the total annual man-made radiation dose to the maximally exposed off-site individual (MEOSI) residing near the WVDP. This is much less than the average dose received from using consumer products and is insignificant compared to the federal standard of 100 mrem allowed from any DOE site operations in a calendar year and the 295 mrem received annually from natural sources. The dose from WVDP operations also is small compared to the estimated average additional dose an airline

crew member typically receives from cosmic radiation (200–900 mrem/year).

The results of these conservative dose calculations demonstrate that the potential maximum dose to an off-site resident is well below permissible standards and is consistent with the as-low-as-reasonably-achievable philosophy of radiation protection.

The following sections describe the monitoring program used to measure radiation in the environment near the WVDP and the methods used and results of dose assessments using these measurements.

Table 2-1
Potential Local Off-Site Exposure Pathways Under Existing WVDP Conditions

Exposure Pathway and Transporting Medium	Reason for Inclusion/Exclusion
Inhalation: gases and particulates in air (included)	Off-site transport of contaminants from WVDP stacks or resuspended particulates from soils or water
Ingestion: cultivated crops (included)	Local agricultural products irrigated with potentially contaminated surface or groundwater; foliar deposition and uptake of deposited airborne contaminants
Ingestion: surface and groundwater (excluded)	No documented use of local surface water or downgradient groundwater wells as drinking water by local residents
Ingestion: fish, beef, venison, and milk (included)	Fish exposed to contaminants in water or sediments may be consumed; beef, venison, and milk consumption following deposition of transported airborne and surface water contaminants
External exposure: radiation from particulates and gases directly from air or surface water or indirectly from surface deposition (included)	Transport of air particulates and gases to off-site receptors; transport of contaminants in surface water and direct exposure during stream use and swimming

Release of Materials Containing Residual Radioactivity. The release of property containing residual radioactivity from DOE facilities is carefully controlled by DOE guidelines and procedures. In two special memoranda issued in January and July of 2000, the Secretary of Energy placed a moratorium on release of contaminated materials and on unrestricted release, for metal recycling from radiological areas within DOE facilities. The moratorium will remain in effect until directives clarifying the release criteria have been developed and implemented. Any transfer that places property (real property, structures, equipment, or scrap metal) containing radioactivity into public use is classified as a type of environmental release.

In keeping with DOE initiatives to expand environmental information provided to the public, certain details of transfers of property containing residual radioactivity are to be included in Annual Site Environmental Reports. The information provided should include, among other things, the type of material and amount of residual radioactivity, the basis for releasing the property for public use (including release limits and when the property was released), the end use and cost savings associated with release of the property, and potential doses to individuals and potential collective dose to the public associated with each release. As indicated in Table 2-2, the WVDP did not release any property classified per DOE Order 5400.5 as material containing residual radioactivity in 2004.

Table 2-2
Release of Property Containing Residual Radioactive Material

Approved Limit	Rationale	Date of Approval	Type of Material	Basis for Release	End Use	Volume of Material	Total Activity	Maximum Individual Dose	Collective Dose
NA	NA	NA	None	NA	NA	0	0	0	0
<i>No property containing residual radioactivity was released in 2004.</i>									

Routine Monitoring Program

Radiological Sampling Program Overview

Samples from environmental media listed in Table 2-1 are collected each year and measured for radioactivity. Environmental sampling locations are shown on maps in Appendix A and the complete environmental monitoring schedule is summarized in Appendix B⁶⁰. This schedule provides information on monitoring and reporting requirements and the types and extent of sampling and monitoring at each location. An explanation of the codes that identify the sample medium and the specific sampling or monitoring location is also found in Appendix B⁶⁰. For example, a sample location code such as AFGRVAL indicates an air sample (A), collected off-site (F), at the Great Valley (GRVAL) sampling station. These codes are used throughout this report for ease of reference and to be consistent with the data reported in the appendices.

The food pathway is monitored by collecting samples of beef, milk, and produce at near-site and remote locations, samples of fish upstream and downstream of the site, and samples of venison from deer from near-site and background locations. Stream sediments are sampled upstream and downstream of the WVDP, and both on-site groundwater and off-site drinking water are routinely sampled. Direct radiation is monitored on site, at the perimeter of the site, in communities near the site, and at background locations.

The primary focus of the monitoring program, however, is on surface water and air pathways, as these are the principal means of transport of radionuclides from the WVDP.

Liquid and air effluents are monitored on site by collecting samples at locations where radioactivity or other regulated substances are released or might be released. Release points include water effluent outfalls and plant ventilation stacks.

Surface water samples are collected within the Project area from ponds, swamps, seeps, and drainage channels that flow through the Western New York Nuclear Service Center (WNYNSC) and then off site into Cattaraugus Creek.

Both surface water and air samples are collected at perimeter locations where the highest off-site concentrations of transported radionuclides might be expected. Samples are also collected at remote locations to provide background concentration data for comparison with data from on-site and near-site samples.

Overview of Water Effluent and Ambient Surface Water Monitoring

The Project is drained by several small streams. Frank's Creek flows along and receives drainage from the south plateau. As Frank's Creek flows northward, it is joined by a tributary, Erdman Brook, which receives effluent from the low-level waste treatment facility (LLWTF). On the north plateau, beyond the Project fence line, the north and northeast swamp areas and Quarry Creek drain into Frank's Creek. Frank's Creek continues across the WNYNSC and flows into Buttermilk Creek, which leaves the WNYNSC and enters Cattaraugus Creek (Figs. A-2 and A-3).

Liquid effluents from three locations (the LLWTF and the two natural drainages from the northeast

and north swamps) are primary contributors to site dose estimates. (See Predicted Dose From Waterborne Releases later in this chapter for an estimate of the dose attributable to these waterborne effluents.)

Low-Level Waste Treatment Facility Effluent. The discharge from the LLWTF through the lagoon 3 weir (WNSP001 on Fig. A-2) into Erdman Brook is the largest single source of radioactivity released to surface waters from the Project. There were eight batch releases totaling about 15.0 million gallons (56.6 million liters) in 2004.

The total amounts of radioactivity from specific radionuclides in the lagoon 3 effluent are listed in Appendix C-2⁶⁰. The annual average concentration of each radionuclide is divided by its corresponding DOE derived concentration guide (DCG) to determine what percentage of the DCG was released. (DCGs are discussed in Chapter 1. DOE DCGs for radionuclides of interest at the WVDP are listed in Appendix K⁶⁰.) As a DOE policy, the sum of the percentages calculated for all radionuclides released should not exceed 100%. The combined annual average of radionuclide concentrations from lagoon 3 effluent in 2004 was approximately 21.2% of the DCGs.

The LLWTF was designed to efficiently remove strontium-90 and cesium-137, the more prevalent of the long-lived fission products in WVDP wastewaters. Other radionuclides, such as uranium isotopes, are also removed to a lesser extent. Uranium isotopes are found in WVDP liquid waste because they were present in the nuclear fuel that was once reprocessed at the site. Uranium-232, a major contributor to the combined DCG in lagoon 3 effluent, averaged about 8% of its DCG in 2004. Variations in liquid effluent radionuclide ratios continue to reflect the dynamic nature of the waste streams being processed through the LLWTF.

Outfall WNSP001 and other selected discharge points are also monitored for nonradiological parameters under the New York State Pollutant Discharge Elimination System program. See Chapter 3, Environmental Nonradiological Program Information.

Northeast Swamp and North Swamp Drainage. These two drainages conduct surface water and emergent groundwater off site. The northeast swamp sampling location (WNSWAMP) is used to monitor surface water drainage from the northeastern portion of the site's north plateau. The north swamp sampling point (WNSW74A) is used to monitor drainage to Quarry Creek from the northern portion of the plateau (Fig. A-2).

Data summaries from these two locations are found in Appendix C-3⁶⁰. Elevated gross beta concentrations at WNSWAMP, first noted in 1993, continued to be observed in 2004. Gross beta activity at this location is largely attributable to strontium-90. Concentrations of all radioisotopic parameters detected at the two locations, other than strontium-90 at WNSWAMP, were less than 1% of the respective DCGs for these parameters.

Strontium-90 concentrations at WNSWAMP in 2004 averaged 1.31E-06 microcuries per milliliter ($\mu\text{Ci/mL}$) (48.5 Becquerels per liter [Bq/L]), higher than the average result in 2003. (See Chapter 4 for a graph of annualized average strontium-90 concentrations at WNSWAMP in 2004.) Even though waters with elevated strontium-90 concentrations drain from WNSWAMP into Frank's Creek, concentrations in waters collected from Cattaraugus Creek downstream at the first point of access by the general public (WFFELBR) were only slightly higher than those at background location WFBIGBR, upstream of the location where site drainage enters Cattaraugus Creek.

Other North Plateau Surface Waters and Water Effluent. Discharges from WNSP001 and WNSP007 leave the site through point WNSP006. Radiological results of analyses from WNSP006 and WNSP007 are summarized in Appendices C-4⁶⁰ and C-2⁶⁰, respectively.

WNSP006. WNSP006 is located more than 2.5 miles (4.0 km) upstream from Thomas Corners Road, the last monitoring point before Buttermilk Creek leaves the WNYNSC and before the public has access to the creek waters. Many of the constituents detected in effluent from WNSP001 were not detectable a short distance downstream at location WNSP006. Radionuclides that were detected were found at concentrations at small percentages of the respective DCGs. The highest strontium-90 concentration at WNSP006 in 2004 was 3.52E-08 $\mu\text{Ci/mL}$ (1.30 Bq/L), which is less than 4% of its DCG (1E-06 $\mu\text{Ci/mL}$).

Average concentrations for the radiological parameters detected at WNSP007 in 2004 were also at small percentages of their respective DCGs.

WNSP005 and WNCoolW. Sampling point WNSP005 monitors overland drainage and groundwater seepage on the east side of the main plant and WNCoolW monitors coolant water from a contained basin within the facility. Summaries of radiological data for WNSP005 and WNCoolW are found in Appendix C-3⁶⁰.

Although most radiological concentrations for both locations were below detection levels in 2004, gross beta and strontium-90 were detected at WNSP005. The gross beta and strontium-90 levels at WNSP005 may be influenced by inactive Lagoon 1. (See Chapter 4, "Long-Term Trends of Gross Beta and Tritium at Selected Groundwater Monitoring Locations.") Although elevated with respect to background, gross beta and strontium-90 concentrations at WNSP005 were well below the strontium-90 DCG.

South Plateau Surface Water and Nuclear Regulatory Commission (NRC)-Licensed Disposal Area (NDA) Interceptor Trench. Two inactive underground radioactive waste disposal areas, the NDA and the New York State-Licensed Disposal Area (SDA), lie on the south plateau of the site. (The SDA is managed by the New York State Energy Research and Development Authority [NYSERDA].) The drum cell, an aboveground structure used to store approximately 20,000 drums of processed low-level radioactive waste, is located nearby. Surface waters, which flow from the south to the north, are routinely monitored at several points around these areas (Fig. A-2). In addition to routine samples collected by the WVDP, samples are collected and analyzed by the New York State Department of Health (NYSDOH) at the two stream sampling points that receive drainage from the south plateau, WNFRC67 and WNERB53.

NRC-Licensed Disposal Area. Sampling point WNNDATR is a sump at the lowest point in the collection trench system that intercepts groundwater from the northeastern and northwestern sides of the NDA. Water collected underground at this location is pumped to the LLWTF for treatment prior to discharge at outfall WNSP001. (See Chapter 1 and Chapter 4 for an explanation of the NDA Interceptor Trench and Pretreatment System.) If contamination were to migrate through the NDA, it would most likely be first detected in samples from WNNDATR.

Surface water drainage downstream of the NDA is monitored at WNNDADR. Further downstream, water from sampling point WNERB53 in Erdman Brook, which represents surface waters from the NDA before they join with drainage from the main plant and lagoon areas, is also monitored. Some drainage from western and northwestern portions of the SDA also passes through sampling points WNNDADR and WNERB53. (See Appendix C-4⁶⁰.)

Annual concentrations from WNNDATR are listed in Appendix C-3⁶² and quarterly results are listed under “NDATR” in Appendix E⁶².

No gross alpha or cesium-137 activity was detected at WNNDATR, WNNDADR, and WNERB53 in 2004. No iodine-129 was detected at WNNDATR and WNNDADR in 2004. (Samples from WNERB53 are not analyzed for iodine-129.) Strontium-90 and associated gross beta results at all three locations were elevated with respect to background (WFBCBKG), but all were far below the strontium-90 DCG. Residual soil contamination from past waste burial activities is thought to be the source of the strontium-90 activity. The NDA is thought to be the predominant source of gross beta activity observed at WNNDATR.

Although tritium concentrations at WNNDATR and WNNDADR were also elevated with respect to background values (those from WNERB53 were not), the maximum concentrations from both WNNDATR and WNNDADR were less than 1% of the DCG for tritium in water (2E-03 $\mu\text{Ci/mL}$). Allowing for seasonal variations, tritium concentrations seem to be generally decreasing at both WNNDATR and WNNDADR. Since the half-life of tritium is slightly longer than 12 years, decreasing tritium concentrations may be partially attributable to radioactive decay.

New York State-Licensed Disposal Area. Point WNSDADR is used to monitor drainage from trench covers on the southwestern area of the SDA. Immediately south of the SDA, and upstream of WNSDADR, sampling point WNDCELD is used to monitor surface drainage from the area around the drum cell (Fig. A-2). To the northeast, sampling point WNFRC67, in Frank’s Creek, is used to monitor drainage downstream of the drum cell and the eastern and southern borders of the SDA. Summaries of results from

WNSDADR, WNDCELD, and WNFRC67 may be found in Appendices C-3⁶² and C-4⁶².

Gross beta and tritium concentrations at WNSDADR, although higher than background concentrations, were a small percentage of the DCGs. All other radiological results from surface waters at the SDA were statistically indistinguishable from background.

Ponded (Standing) Waters. Four ponds near the site were tested in 2004. For comparison, a background pond 8.8 miles (14.1 kilometers [km]) north of the Project was also tested. (See Figs. A-2, A-3, and A-13 for the locations of the five ponds and Appendix C-4⁶² for a summary of sampling results.) All radiological results were statistically the same as concentrations in the background pond.

Off-Site Surface Water. Samples of surface water are collected at four off-site locations, two on Buttermilk Creek and two on Cattaraugus Creek. Off-site sampling locations are shown on Fig. A-3.

Fox Valley Road and Thomas Corners Bridge Sampling Locations. Buttermilk Creek is the major surface drainage from the WNYNSC. One monitoring station is located upstream of the WVDP at Fox Valley Road (WFBCBKG) and one is located downstream at Thomas Corners Bridge (WFBCTCB). The Thomas Corners Bridge sampling location is upstream of Buttermilk Creek’s confluence with Cattaraugus Creek. This sampling location represents an important intercept point in the pathway to humans because dairy cattle have access to the water here. A listing of radionuclide concentrations at background location WFBCBKG compared with those downstream at WFBCTCB may be found in Appendix C-4⁶².

Gross alpha, tritium, technetium-99, and cesium-137 concentrations at Thomas Corners Bridge were statistically indistinguishable from background con-

centrations in 2004. Gross beta and strontium-90 concentrations at Thomas Corners Bridge, although detected at less than 2% of the strontium-90 DCG, were elevated in comparison to background. These elevated concentrations may be attributed to small amounts of radioactivity moving from the site via Frank's Creek.

Cattaraugus Creek at Felton Bridge and Bigelow Bridge Sampling Locations. Radiological data from samples taken at Felton Bridge (WFFELBR), downstream of the point where Buttermilk Creek enters Cattaraugus Creek, and from Bigelow Bridge (WFBIGBR), upstream of this point, are summarized in Appendix C-4⁶⁰.

No statistically significant differences were noted between upstream and downstream concentrations of gross alpha, tritium, strontium-90, and cesium-137. Gross beta concentrations at Felton Bridge (WFFELBR), however, were slightly higher than background concentrations, although detected at less than 1% of the DOE DCG for strontium-90.

Figure 2-2 shows gross alpha, gross beta, and tritium results over the past ten years at Felton Bridge. For the most part, tritium concentrations represent detection limits and not detected radioactivity. Taking into account seasonal fluctuations, gross beta activity appears to have remained relatively constant at this location over the last decade.

Overview of Drinking Water Monitoring

Drinking water (potable water) is sampled both off site (near the WVDP) and on site. Off-site drinking water samples are taken from wells that represent the nearest unrestricted use of groundwater near the Project; none of these wells draw from groundwater units underlying the site. Drinking water and utility water for the Project are drawn from two on-site surface water reservoirs.

On-Site Tap Water. On-site drinking water sources were monitored for radionuclides at four




Figure 2-2. Ten-Year Trends of Gross Alpha, Gross Beta, and Tritium Concentrations at Sampling Location WFFELBR


locations: the entry point at the utility room (WNDNKUR), the Environmental Laboratory (WNDNKEL), the maintenance shop (WNDNKMS), and the main plant (WNDNKMP). No differences were noted between control values at the utility room and those from other site locations. Data tables may be found in Appendix C-5⁶⁰.

Off-Site Drinking Water Wells. Nine off-site private, residential groundwater wells between 0.9 miles (1.5 km) and 4.3 miles (7 km) from the facility (WFWEL01 through WFWEL05 and WFWEL07 through WFWEL10) were sampled for radiological parameters in 2004. A tenth private well (WFWEL06), 18 miles (29 km) south of the site, provides a background sample. Sampling locations are shown in Figures A-9, A-12, and A-13 and results are presented in Appendix C-5⁶⁰. Radiological results in 2004 were close to or statistically indistinguishable from background.

Overview of Sediment Monitoring

Particulate matter in streams can adsorb radiological constituents in liquid effluents, settle on the bottom of the stream as sediment, and subsequently be eroded or resuspended, especially during periods of high stream flow. These resuspended sediments may provide a pathway for radiological constituents to reach humans either directly via exposure or indirectly through the food pathway.

On-Site Sediments. Sediments are collected at three on-site surface water sampling points where liquid effluents leaving the site are most likely to be radiologically contaminated: Frank's Creek where it leaves the security fence (SNSP006), the north swamp drainage swale (SNSW74A), and the northeast swamp drainage swale (SNSWAMP) (Fig. A-2). (Note that swamp sediment samples may be partially composed of soils.) Results from radiological analyses of these samples are listed in Appendix G-2⁶⁰. As in previous years, gross beta,



strontium-90, cesium-137, and certain alpha isotopic results higher than background were noted.

Off-Site Sediments. Sediments are collected off site at three locations downstream of the WVDP: Buttermilk Creek at Thomas Corners Road (SFTCSSED), Cattaraugus Creek at Felton Bridge (SFCCSED), and Cattaraugus Creek at the Springville dam (SFSDSED). The first two points are at water sampling locations. The third is behind the Springville dam where significant sediments accumulate, including sediments that may have adsorbed radionuclides from the site. Sediments are also collected at two locations upstream of waters receiving effluents from the WVDP, Buttermilk Creek at Fox Valley Road (SFBCSED) and Cattaraugus Creek at Bigelow Bridge (SFBISED). The two upstream locations provide background data for comparison with downstream points (Fig. A-3).

Most radiological results from downstream sediment sampling sites were statistically the same as those from background locations, except for cesium-137 concentrations that were statistically higher than background. A comparison of annual averaged cesium-137 concentrations from 1995 through 2004 for two off-site sampling locations is illustrated in Figure 2-3. As the figure indicates, cesium-137 concentrations are relatively stable at the background location (SFBISED) and are generally higher at the location downstream of the WVDP (SFCCSED). Although cesium-137 activity historically is elevated in downstream Cattaraugus Creek sediments relative to upstream sediments, the levels are far lower than those of naturally occurring gamma emitters, such as potassium-40.

Overview of Air Emission and Ambient Air Monitoring

Permits obtained from the EPA allow air containing small amounts of radioactivity to be released from plant ventilation stacks during normal operations. The air released must meet criteria specified in the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations to ensure that the environment and the public's health and safety are protected. Dose-based comparisons of WVDP emissions against NESHAP criteria are presented later in this chapter. (See Predicted Dose From Airborne Emissions, later in this chapter.)

Unlike NESHAP dose criteria, the DOE DCGs are expressed in units of $\mu\text{Ci/mL}$ and therefore can be directly compared with concentrations of radionuclides in WVDP air emissions. DOE standards and DCGs for radionuclides of interest at the WVDP are found in Appendix K⁶⁰. When isotopic data are not available, gross alpha and beta measurements are assumed to come from americium-241 and strontium-90, respectively, because the DCGs for these radionuclides are the most limiting for major particulate emissions at the WVDP.

Ventilation and Emission Systems. The exhaust from each EPA-permitted ventilation system on site is continuously filtered and the permanent systems are monitored as air is released to the atmosphere. Because radionuclide concentrations in air emissions are quite low, a large volume of air must be sampled at each point to measure the quantity of specific radionuclides released from the facility. Emissions are sampled for both particulate (e.g., strontium-90 and americium-241) and gaseous forms of radioactivity (e.g., tritium and iodine-129). The total release of each radionuclide (in curies) varies from year to year in response to changing site activities. For instance, releases of

iodine-129 decreased after vitrification was completed, while releases of tritium, strontium-90, cesium-137, and alpha isotopes generally increased when decontamination and dismantlement activities began. (Note that calculated dose has remained a small fraction of the standard. See “Predicted Dose From Airborne Emissions” later in this chapter.)

The Main Plant Ventilation Stack. The main plant ventilation stack (ANSTACK) is the primary source of airborne releases at the WVDP. This stack, which vents to the atmosphere at a height of approximately 200 feet (more than 60 meters), releases ventilation exhaust from several facilities, including the liquid waste treatment system, the analytical laboratories, and off-gas from the former vitrification system.

Total curies released from the main stack in 2004 are listed in Appendix D⁶⁰, together with annual averages, maxima, and a comparison of average isotopic concentrations with the applicable DCGs. As in previous years, the 2004 average radioactivity levels at the stack discharge point were already below concentration guidelines for airborne radioactivity in an unrestricted environment. Airborne concentrations from the stack to the site boundary are further reduced via dispersion by a factor of more than 200,000. Results from air samples taken just outside the site boundary confirm that WVDP operations had no discernible effect on off-site air quality. (See “Perimeter and Remote Ambient Air Monitoring,” later in this chapter.)

Other On-Site Air Sampling Systems. Sampling systems similar to those of the main stack monitor airborne effluents from the former vitrification heating, ventilation, and air-conditioning system (ANVITSK), the 01-14 building ventilation stack (ANCSSTK), the contact size-reduction facility ventilation stack (ANCSRFK), the supernatant treatment system ventilation stack (ANSTSTK), the

container sorting and packaging facility ventilation stack (ANCSPFK), and the remote-handled waste facility (ANRHWFK), which began “hot” operations in June 2004 (Fig. A-4).

Appendix D⁶⁰ presents total radioactivity released for specific radionuclides (as available) at each of these sampling locations. Samples from locations ANVITSK, ANCSSTK, ANSTSTK, ANCSPFK, and ANRHWFK occasionally showed detectable concentrations of gross radioactivity, as well as specific beta- and alpha-emitting radionuclides, but none approached any DOE effluent limitations. (ANCSRFK did not operate in 2004, therefore no samples were taken.)

Permitted portable outdoor ventilation enclosures (OVEs) are used occasionally to provide the ventilation necessary for the safety of personnel working with radioactive materials in areas outside permanently ventilated facilities or in areas where permanent ventilation needs to be augmented. In 2004, decontamination of extraction cell 2 in the main plant was monitored by OVEs. Air samples from OVEs are collected continuously while those emission points are discharging, and data from these portable ventilation units are included in annual airborne emission evaluations. Average discharges from OVEs were well below DOE guidelines.

Three air samplers monitor ambient air near three on-site waste storage units – the lag storage area (ANLAGAM), the NDA (ANNDAAAM), and the SDA (ANSDAT9) (Fig. A-4). These samplers were put in place to monitor potential diffuse releases of radioactivity. Monitoring data from these locations are presented in Appendix D⁶⁰.

With the exception of tritium results at ANSDAT9, radiological data sets for the three locations were statistically indistinguishable from results for the background air monitoring location at Great Val-

ley (AFGRVAL). Although tritium results at ANSDAT9 were elevated with respect to background, even the highest result ($5.51\text{E-}12 \mu\text{Ci/mL}$ [$2.04\text{E-}01 \text{Bq/m}^3$]) was less than 0.01% of the DOE DCG for tritium in air ($1\text{E-}07 \mu\text{Ci/mL}$).

Perimeter and Remote Ambient Air Monitoring. In 2004, samples for radionuclides in air were collected at six locations around the perimeter of the site and at three remote locations. Maps of the sampling locations are found on Figures A-5, A-12, and A-13.

The perimeter locations on Fox Valley Road (AFFXVRD), Rock Springs Road (AFRSPRD), Route 240 (AFRT240), Thomas Corners Road (AFTCORD), Dutch Hill Road (AFBOEHN), and at the site's bulk storage warehouse (AFBLKST) were chosen because they provide historical continuity (as former Nuclear Fuel Services, Inc. sampling locations) or because they represent the most likely locations for detecting off-site airborne concentrations of radioactivity.

The remote locations provide data from nearby communities (West Valley [AFWEVAL] and Springville [AFSPRVL]) and from a more distant background area (Great Valley [AFGRVAL], 18 miles [29 km] south of the site), which is considered representative of regional background air. Data from these locations are presented in Appendix D⁶⁹.

Ten-year gross alpha and gross beta concentrations at the Rock Springs Road location are shown in Figure 2-4. Within a range of seasonal and weekly fluctuations, the concentrations have been relatively constant over the past ten years.

Radioisotopic results from samples taken at the two near-site communities and from the site perimeter were statistically indistinguishable from results from the background samples, suggesting that there is no adverse site influence on the air quality at these near-site locations.




Figure 2-4. Ten-Year Trends of Gross Alpha and Gross Beta Concentrations at Rock Springs Road (AFRSPRD)

Atmospheric Deposition and Soil Monitoring

Fallout Pots. Fallout samples are analyzed to monitor short-term deposition of radionuclides at four of the perimeter air sampler locations and at one on-site location near the rain gauge outside of the Environmental Laboratory (Figs. A-4 and A-5). The data from precipitation analyses are presented in Appendix D⁶⁰. The low levels of radioactivity released in main stack emissions did not measurably affect on-site or perimeter fallout pot samples in 2004.

Off-Site Surface Soil. Surface soil near the off-site air samplers is collected to assess long-term deposition of radionuclides. Maps of the off-site surface soil sampling locations are on Figures A-3, A-12, and A-13.

The measured concentrations of most site-related radionuclides in soils from the perimeter and community locations (Appendix G-2⁶⁰) were statistically indistinguishable from regional background concentrations. Elevated gross beta concentrations were noted at Thomas Corners, consistent with historical data from this soil sampling location.

Overview of Food Chain Monitoring

Each year food samples are collected from locations near the site (Fig. A-9) and from remote locations (Figs. A-12 and A-13). Fish and deer are collected during periods when they would normally be taken by sportsmen for consumption. Corn, apples, and beans are collected annually at the time of harvest. (See Measurement of Radionuclide Concentrations in Food, later in this chapter, for a discussion of estimating doses from foodstuffs.) Results are listed in Appendix F⁶⁰.

Fish. Fish are obtained under a collector's permit by electrofishing, a method that temporarily stuns the fish, allowing them to be netted for collection. Electrofishing allows more efficient species-selective control than sport fishing, with unwanted fish being returned to the creek essentially unharmed.

Fish were collected from three locations in Cattaraugus Creek in 2004: ten fish were collected at each of two locations downstream of WNYNSC drainage – one above the Springville dam (BFFCATC) and one below the Springville dam (BFFCATD). Ten more fish were collected upstream of the site (BFFCTRL). The fish taken below the dam (BFFCATD) included species that migrate about 40 miles (more than 60 km) upstream from Lake Erie.

Strontium-90 results from fish downstream of the site (BFFCATC) were elevated in comparison with the background results (BFFCTRL). No other results were statistically higher than background. All results were within the range of historical values.

Venison. Radionuclide data for venison samples were taken from vehicle-deer accidents around the WNYNSC and from deer collected far from the site in the towns of Farmersville, Allegany, and Machias, New York.

Although the cesium-137 results for one near-site deer was elevated with respect to background, the result was consistent with historical results. The remainder of the data from 2004 show no statistical differences between concentrations of radionuclides in near-site and control samples.

From 1994 through 2004 (except 2001), during the big-game hunting season, hunters were allowed access to designated areas within the WNYNSC, excluding the WVDP premises, in a controlled hunting program established by NYSERDA. (The hunt

was canceled in 2001 because of heightened security concerns.) Data from previous hunts have shown that concentrations of radioactivity in deer flesh have been very low, indicating that Project activities have little or no effect on the local herd.

Beef. No significant differences were found between results from near-site and background samples.

Milk. Near-site sample results were indistinguishable from background control sample results.

Vegetables and Fruit. WVDP-related nuclides in results from sweet corn, beans, and apples collected at harvest time were statistically the same as measurements from background samples.

Direct Environmental Radiation Monitoring

Monitoring points are located on site at the waste management units, at the site security fence, around the WNYNSC perimeter and the access road, and at a background location remote from the WVDP (Figs. A-10 through A-13). The identification numbers associated with each location were assigned in chronological order of original installation.

Quarterly and annual averages of thermoluminescent dosimeter (TLD) measurements at off-site and on-site locations are noted in Appendix H^{6a}. The results of measurements in 2004 show typical seasonal variations and are similar to results from previous years.

On-Site Radiation Monitoring. As in past years, the on-site monitoring point with the highest dose readings was location #24. Sealed containers of radioactive components and debris from the plant decontamination work are stored nearby.

The average exposure rate at location #24 was about 475 milliroentgens (mR) per quarter (216 microroentgen per hour [$\mu\text{R/hr}$]) during 2004, slightly lower than the exposure rate in 2003 (231 $\mu\text{R/hr}$). Exposure rates at this location have been generally decreasing over time because the radioactivity in the materials stored nearby is decaying.

The on-site monitoring point with the second highest dose readings (location #40) was near the waste tank farm. The average exposure rate at location #40 in 2004 was about 112 mR/quarter (51 $\mu\text{R/hr}$), the same as in 2003. As expected, results from TLDs located near on-site facilities are generally higher than background results, however, these TLD locations are well within the WNYNSC boundary and are not accessible by the public.

In 2004, increases in exposure rates near the drum cell and at another location near the main plant (DNTLD38) were thought to be attributable to the movement past and storage of sodium-bearing radioactive waste containers near these monitoring points. Even though increases were noted at these two locations, no comparable exposure increases were noted at TLDs on the site perimeter.

Perimeter and Off-Site Radiation Monitoring. The perimeter TLDs (TLDs #1–16 and #20) are distributed in the 16 compass sectors around the facility near the WNYNSC boundary. Results from the perimeter and community TLDs were statistically the same as results from the background TLD. The perimeter TLD quarterly averages shown on Figure 2-5 indicate seasonal fluctuations but no long-term trends. The quarterly average of the 17 WNYNSC perimeter TLDs was 16.1 mR per quarter (7.4 $\mu\text{R/hr}$) in 2004, slightly lower than in 2003.

Confirmation of Results. Performance of the environmental TLDs is confirmed periodically using a portable high-pressure ion chamber (HPIC) detection system. The TLD results include the entire third quarter of 2004; the HPIC results were collected over a period of less than 30 minutes.

Since these measurements are made with different systems and over differing periods of time, they are not directly comparable. The average relative percent difference between the two sets of measurements was about 28%, indicating general agreement between these two different measurement methods. (Guidance in American National Standards Institute N545-1975, the standard for environmental dosimetry, uses measurement agreement within 30% total uncertainty as a performance specification for TLD measurements.)

Meteorological Monitoring

Meteorological monitoring at the WVDP provides representative and verifiable data that characterize the local and regional climatology. These data are used primarily to assess potential effects of routine and nonroutine releases of airborne radioactive materials and to develop dispersion models used to calculate the effective dose equivalent to off-site residents. Since dispersive capabilities of the atmosphere are dependent upon wind speed, wind direction, and atmospheric stability (which includes a function of the difference in temperature between two elevations), these parameters are closely monitored and are available to the emergency response organization at the WVDP. The on-site 197-ft (60-m) meteorological tower (Fig. A-1) continuously monitors wind speed, wind direction, and temperature at both the 197-ft (60-m) and 33-ft (10-m) elevations. In addition, an independent, remote 33-ft (10-m) meteorological station, located approximately 5 miles (8 km) south of the site on a hillcrest on Dutch Hill Road (Fig.




Figure 2-5. Ten-Year Trends of Environmental Radiation Levels at Perimeter TLDs

A-12), continuously monitors wind speed and wind direction. Dewpoint, precipitation, and barometric pressure are also monitored on site.

The two meteorological locations supply data to the primary digital and analog data acquisition systems located within the Environmental Laboratory. On-site systems are provided with either uninterruptible or standby power backup in case of site power failures. In 2004, the on-site system data recovery rate (the time valid data were logged versus the total elapsed time) was approximately 93.1%. Regional data at the 33-ft (10-m) elevation and mean wind speed and wind direction at the 33-ft and 197-ft (10-m and 60-m) elevations at the on-site tower during 2004 are shown in Appendix I⁶⁰.

Weekly and cumulative total precipitation data are presented in Appendix I⁶⁰. Precipitation in 2004 was approximately 43.2 inches (110 cm), about 5% more than the long-term annual average (41.0 inches [104 cm]).

Documentation, such as meteorological system calibration records, site log books, and analog strip charts, is stored in protected archives. Meteorological towers and instruments are examined three times per week for proper function and are calibrated semiannually and/or whenever instrument maintenance might affect calibration.

Special Monitoring

Special monitoring comprises sampling and analyses not covered by the routine environmental monitoring program but that address items of environmental interest. Special monitoring programs are used to verify and/or track these items. Some special environmental monitoring was carried out in 2004 associated with a breach of the laundry waste water line (see “RCRA 3008[h] Administrative Order on Consent” and “Process

Sewer Integrity Evaluation” in the Environmental Compliance Summary) and with rehabilitation of the railroad spur (see “Soil and Sediment Monitoring” in Chapter 3).

Radiological Effluents and Dose

Dose Assessment Methodology

The potential radiation dose to the general public from activities at the WVDP is evaluated by using a two-part methodology applied in a manner consistent with the requirements of DOE Order 5400.5. The first part uses the measurements of radionuclide concentrations in liquid and air released from the Project to determine annual total effect. The second part uses measurements of radioactivity in food from locations near the Project boundaries to evaluate the impact of the annual total release.

Radiological dose is evaluated for all major exposure pathways, including external irradiation, inhalation, and ingestion of local food products. The dose contributions from each radionuclide and pathway combination are then combined to obtain the total dose estimates reported in Table 2-3.

Measurement of Radionuclide Concentrations in Liquid and Air Releases. Because it is difficult to distinguish the health effects of the small amount of radioactivity originating from the Project and naturally occurring radiation in the environment, computer codes are used to model the environmental dispersion of radionuclides that originate from on-site monitored ventilation stacks and liquid discharge points.

Actual data from release-monitoring samples are collected, together with annual weather measurements and the most recent demographic information. (See Appendices C, D, and I^{tbl}.) The effective dose equivalent (EDE) to the maximally exposed off-site individual (MEOSI) and the collective EDE to the population within a 50-mile (80-km) radius

are then calculated using conservative models that have been approved by the DOE and the EPA to demonstrate compliance with radiation standards. (See the inset on Radiation Dose and Units of Dose Measurement.)

Measurement of Radionuclide Concentrations in Food. The second part of the dose assessment is based on actual measurements of radioactivity in samples of foodstuffs grown in the vicinity of the WVDP and the comparison of these values with measurements of samples collected from locations well beyond the potential influence of site effluents.

If any of the near-site food samples contain radionuclide concentrations that are statistically higher than the concentrations in control samples, separate dose calculations are performed to verify that the calculated foodstuff dose is within the dose range estimated by computer modeling. (See Calculated Dose From Local Foodstuff Tests, later in this chapter.)

These estimates show that the concentrations of radioactivity, whether from sites near the WVDP or from distant locations, are small – usually near the analytical detection limits – thereby providing additional assurance that operations at the WVDP are not adversely affecting the public.

These calculated doses are used as an independent confirmation of (not added to) the computer-modeled estimates (Table 2-3) because the models already include contributions from all environmental pathways.

Radiation Dose

The energy released from a radionuclide is eventually deposited in matter encountered along the path of the radiation. The radiation energy absorbed by a unit mass of material is referred to as the absorbed dose. The absorbing material can be either inanimate matter or living tissue.

Alpha particles leave a dense track of ionization as they travel through tissue and thus deliver the most dose per unit path-length. However, alpha particles are not penetrating and must be taken into the body by inhalation or ingestion to cause harm. Beta and gamma radiation can penetrate the protective dead skin layer of the body from the outside, resulting in exposure of the internal organs to radiation.

Because beta and gamma radiations deposit much less energy in tissue per unit path-length relative to alpha radiation, they produce fewer biological effects for the same absorbed dose. To allow for the different biological effects of different kinds of radiation, the absorbed dose is multiplied by a quality factor to yield a unit called the dose equivalent. A radiation dose expressed as a dose equivalent, rather than as an absorbed dose, permits the risks from different types of radiation exposure to be compared with each other (e.g., exposure to alpha radiation compared with exposure to gamma radiation). For this reason, regulatory agencies limit the dose to individuals in terms of total dose equivalent.

Units of Dose Measurement

The unit for dose equivalent in common use in the U.S. is the rem, which stands for roentgen equivalent man. The international unit of dose equivalent is the sievert (Sv), which is equal to 100 rem. The millirem (mrem) and millisievert (mSv), used more frequently to report the low dose equivalents encountered in environmental exposures, are equal to one-thousandth of a rem or sievert, respectively. Other radioactivity unit conversions are found on p. UOM-2 at the back of this report.

The effective dose equivalent (EDE), also expressed in units of rem or sievert, provides a means of combining unequal organ and tissue doses into a single "effective" whole body dose that represents a comparable risk probability. The probability that a given dose will result in the induction of a fatal cancer is referred to as the risk associated with that dose. The EDE is calculated by multiplying the organ dose equivalent by the organ-weighting factors developed by the International Commission on Radiological Protection (ICRP) in Publications 26 (1977) and 30 (1979). The weighting factor is a ratio of the risk from a specific organ or tissue dose to the total risk resulting from an equal whole body dose. All organ-weighted dose equivalents are then summed to obtain the EDE.

The dose from internally deposited radionuclides calculated for a fifty-year period following intake is called the fifty-year committed effective dose equivalent (CEDE). The CEDE sums the dose to an individual over fifty years to account for the biological retention of radionuclides in the body. The total EDE for one year of exposure to radioactivity is calculated by adding the CEDE to the dose equivalent from external, penetrating radiation received during the year. Unless otherwise specified, all doses discussed here are total EDE values, which include the CEDE for internal emitters.

A collective population dose is expressed in units of person-rem or person-sievert because the individual doses are summed over the entire potentially exposed population. The average individual dose can therefore be estimated by dividing the collective dose by the population.

Predicted Dose From Airborne Emissions

Airborne emissions of radionuclides are regulated by the EPA under the Clean Air Act and its implementing regulations. DOE facilities are subject to 40 Code of Federal Regulations (CFR) 61, Subpart H, NESHAP. Subpart H contains the national emission standards for emissions of radionuclides other than radon from DOE facilities. The applicable standard for radionuclides is a maximum of 10 mrem (0.1 mSv) effective dose equivalent to any member of the public in any year.

Releases of airborne radioactive materials in 2004 from nominal ground-level stacks (1 to 24 meters high) and from the main 60-meter-high stack were modeled using the EPA-approved CAP88-PC computer code (Parks, June 1997). This air dispersion code estimates effective dose equivalents for the ingestion, inhalation, air immersion, and ground surface pathways.

Site-specific data for CY 2004 non-radon radionuclide releases in curies per year are listed in Appendix D⁶⁰. Applicable information from these tables was used as input to the CAP88-PC code, as were wind data collected from the on-site meteorological tower during 2004 and current local population distribution information.

Resulting output from the CAP88-PC code was then used to determine the total EDE from air emissions to a maximally exposed individual and the collective dose to the population within a 50-mile (80-km) radius of the WVDP.

Maximum Dose to an Off-Site Individual. Based on the non-radon airborne radioactivity released from all sources at the site during 2004 (i.e., permitted stacks, stacks that do not require permits, and non-point sources), it was estimated that a person living in the vicinity of the WVDP could

have received a total EDE of 0.0015 mrem (0.000015 mSv) from airborne releases. The computer model estimated that this MEOSI was located 1.2 miles (1.9 km) north-northwest of the site and was assumed to eat only locally-produced foods. More than 50% of the dose from main plant stack emissions was from iodine-129.

The maximum total EDE of 0.00078 mrem (0.0000078 mSv) from the permitted stacks and vents is far below levels that could be directly measured at the exposed individual's residence. This dose is comparable to about one and one-half minutes of natural background radiation received by an average member of the U.S. population and is well below the 10 mrem (0.1 mSv) NESHAP limit promulgated by the EPA and mandated by DOE Order 5400.5.

Collective Population Dose. The CAP88-PC program was used to estimate the collective EDE to the population. Based upon the latest U.S. census population data collected in CY 2000, 1.54 million people were estimated to reside within 50 miles (80 km) of the WVDP. This population received an estimated 0.012 person-rem (0.00012 person-Sv) total EDE from radioactive non-radon airborne effluents released from WVDP point and diffuse sources during 2004. (See the discussion of radon-220 later in this chapter.) The resulting average EDE per individual was 0.000008 mrem (0.00000008 mSv).

Iodine Emissions From the Main Stack. In the ten-year period before the startup of vitrification, iodine-129, a long-lived radionuclide, was found in main stack emissions at levels of approximately 0.007 to 0.057 mCi/year. In 1996, when vitrification operations began, 1.20 mCi of iodine-129 were released and in 1997, the first full year of vitrification, a maximum release of 7.4 mCi was observed. The increase occurred because gaseous iodine was not as efficiently removed by the vitri-

Table 2-3
**Summary of Annual Effective Dose Equivalents to an Individual
and Population From WVDP Releases in 2004**

Exposure Pathways	Annual Effective Dose Equivalent	
	Maximally Exposed Off-Site Individual ¹ mrem (mSv)	Collective Effective Dose Equivalent ² person-rem (person-Sv)
Airborne Releases³	1.5E-03 (1.5E-05)	1.2E-02 (1.2E-04)
% EPA standard (10 mrem)	0.02%	NA
Waterborne Releases⁴		
Effluents only	1.6E-02 (1.6E-04)	1.5E-02 (1.5E-04)
Effluents plus north plateau drainage	4.7E-02 (4.7E-04)	1.9E-01 (1.9E-03)
Total from all Pathways	4.9E-02 (4.9E-04)	2.0E-01 (2.0E-03)
% DOE standard (100 mrem) – air and water combined	0.05%	NA
% of natural background (295 mrem; 453,000 person-rem) – received from air and water combined	0.02%	0.00005%
Estimated Airborne Radon-220⁵	1.2E-02 (1.2E-04) ⁶	3.4E-01 (3.4E-03)

NA - Not applicable. Numerical regulatory standards are not set for the collective EDE to the population.

¹ The maximum exposure to air discharges is estimated to occur at a residence 1.9 kilometers north-northwest of the main plant building.

² A population of 1.54 million is estimated to reside within 80 kilometers of the site.

³ Releases are from atmospheric non-radon point and diffuse sources. Calculations use CAP88-PC to estimate individual and population doses. EPA and DOE limits for individual airborne dose are the same.

⁴ Estimates are calculated using the methodology described in the WVDP Manual for Radiological Assessment of Environmental Releases at the WVDP (WVNSCO, 2003).

⁵ Estimated airborne releases are based on indicator measurements and process knowledge. Dose estimates are calculated using CAP88-PC.

⁶ The estimated dose from radon-220 is specifically excluded by rule from NESHAP totals.


Radon-220

Radon-220 is a naturally occurring gaseous decay product of thorium-232 present in the airborne emissions from the WVDP main plant. Radon-220, also known as thoron, is associated with the thorium reduction extraction (THOREX)-related thorium-232 and uranium-232 in the high-level waste.

As reported in Chapter 2 of the 1996 WVDP Site Environmental Report (WVNSCO and Dames & Moore, June 1997), thoron levels were observed to increase during startup of the 1996 high-level waste vitrification process. An estimate of the thoron released during each waste concentration cycle was developed and used to determine a theoretical annual release. During the vitrification phase, an average of about 12 curies per day were released. In 2004, with the vitrification process completed, the average was about three curies of thoron released per day.

Although large numbers of curies were released relative to other radionuclides, the calculated dose from thoron is quite small because of its short decay half-life and other characteristics. The NESHAP rule specifically excludes thoron from air emission dose calculations, so a dose estimate using CAP88-PC was calculated separately. The theoretical dose to the MEOSI located 1.2 miles (1.9 km) north-northwest of the site in 2004 would have been 0.012 mrem, and the collective dose to the population within an 80-kilometer radius would have been 0.34 person-rem. (See Table 2-3.) These theoretical doses are within the same range as doses from the man-made radionuclides found in WVDP effluents.

With vitrification completed, thoron releases have decreased to pre-vitrification levels. The figure presented here provides a relative indication of recent trends in the estimated annual thoron releases.



fication process off-gas treatment system as were most other radionuclides. As more high-level radioactive waste was vitrified, iodine-129 levels decreased and in 2003, the first full year since vitrification was completed, the total annual release had dropped to 0.065 mCi. In 2004, the total annual release decreased even further to 0.028 mCi. Even so, in 2004, iodine-129 continued to account for the largest proportion of dose to an off-site individual from main stack airborne emissions.

Predicted Dose From Waterborne Releases

Currently there are no EPA standards establishing limits on the radiation dose to members of the public from liquid effluents except as applied in 40 CFR 141 and 40 CFR 143, Drinking Water Guidelines (EPA, 1984a; 1984b). Corollary limits for community water supplies are set by NYSDOH in the New York State Sanitary Code (Title 10 of the Official Compilation of Codes, Rules, and Regulations of the State of New York [NYCRR] 5-

1.52). The private residential potable water wells sampled for radionuclides are upgradient of the WVDP and therefore do not represent a potential source of exposure to radiation from routine Project activities.

Since Cattaraugus Creek is not used as a drinking water supply, a comparison of the predicted concentrations and doses with the 4-mrem/year (0.04-mSv/year) EPA and NYSDOH drinking water limits established in 40 CFR 141 and 40 CFR 143, and in 10 NYCRR §5-1.52, respectively, is not truly appropriate (although the values in creek samples are well below the EPA drinking water limits). The estimated radiation dose was compared to the applicable guidelines provided in DOE Order 5400.5. The EDE to the MEOSI and the collective EDE to the population due to routine waterborne releases and natural drainage are calculated using dose conversion factors as tabulated in the “WVDP Manual for Radiological Assessment of Environmental Releases at the WVDP” (WVNSCO, 2003).

Since the Project’s liquid effluents eventually reach Cattaraugus Creek, the most important individual exposure pathway is the consumption of fish from this creek by local sportsmen. It is conservatively assumed that a person may consume annually as much as 46 pounds (21 kg) of fish caught in the creek. Exposure to external radiation from shoreline or water contamination is also included in the model for estimating radiation dose. Population dose estimates assume that radionuclides are further diluted in Lake Erie before reaching municipal drinking water supplies.

The computer codes GENII version 1.485 (Pacific Northwest Laboratory, 1988), which implements the models in NRC Regulatory Guide 1.109 (NRC, 1977), and LADTAPII (Simpson and McGill, 1980) were used to calculate site-specific unit dose factors for routine waterborne releases and dispersion of these effluents. Input data included local stream

flow and dilution, drinking water usage, and stream usage factors. (See “WVDP Manual for Radiological Assessment of Environmental Releases at the WVDP” [WVNSCO, 2003] for a detailed description of the GENII code.)

Eight batches of liquid effluents were released from lagoon 3 (point WNSP001) during 2004. Measurements of the radioactivity discharged in these effluents, listed in Appendix C-2⁶⁰, were combined with the unit dose factors to calculate the EDE to the MEOSI and the collective EDE to the population living within a 50-mile (80-km) radius of the WVDP.

In addition to measurements from WNSP001, radioactivity measurements from sewage treatment facility effluents (WNSP007) were included in the EDE calculations. Results from the sewage treatment facility are also presented in Appendix C-2⁶⁰. (The french drain at WNSP008, a third release point, has been sealed off since 2001 and was not included in this evaluation.)

Besides the two release points at WNSP001 and WNSP007, waters from two natural drainage channels originating on the Project premises contain measurable concentrations of radioactivity: the northeast swamp (WNSWAMP) and north swamp (WNSW74A). (See Northeast Swamp and North Swamp Drainage discussed earlier in this chapter.) The measured radioactivity from these points is reported in Appendix C-3⁶⁰. These results are included in the EDE calculations for the MEOSI and the collective population.

There were no unplanned releases of waterborne activity to the off-site environment in 2004. (See “RCRA 3008(h) Administrative Order on Consent” and “Process Sewer Integrity Evaluation” in the Environmental Compliance Summary.)

Maximum Dose to an Off-Site Individual.

Based on the radioactivity in liquid effluents discharged from the WVDP (lagoon 3 and the sewage treatment plant) during 2004, an off-site individual could have received a maximum EDE of 0.016 mrem (0.00016 mSv). About 90% of this dose was from cesium-137. The maximum off-site individual EDE due to drainage from the north plateau (north swamp and northeast swamp) was 0.031 mrem (0.00031 mSv).


The combined EDE to the maximally exposed individual from liquid effluents and drainage was 0.047 mrem (0.00047 mSv). This annual dose is very small in comparison to the 295 mrem (2.95 mSv) dose that is received by an average member of the U.S. population from natural background radiation.


Collective Dose to the Population. As a result of radioactivity released in liquid effluents from the WVDP (primarily from lagoon 3) during 2004, the population living within 50 miles (80 km) of the site received a collective EDE of 0.015 person-rem (0.00015 person-Sv). The collective dose to the population from the effluents plus the north plateau drainage was 0.19 person-rem (0.0019

person-Sv). The resulting average EDE from effluent releases and north plateau drainage (north swamp and northeast swamp) per individual is 0.00013 mrem (0.0000013 mSv). This dose is an inconsequential addition to the dose that an average person receives in one year from natural background radiation.

Calculated Dose From Local Foodstuff Tests

As noted in the discussion of food chain monitoring earlier in this chapter, most radionuclide concentrations in near-site food samples were statistically indistinguishable from concentrations in background samples. Strontium-90 concentrations higher than background were noted in fish taken in Cattaraugus Creek downstream of the WVDP (BFFCATC) and cesium-137 higher than background was noted in one near-site deer. Even so, conservative estimates of dose due to consuming near-site fish, deer, beef, milk, beans, corn, and apples were all less than 0.2 mrem/year. These independent estimates confirm the modeled dose estimates based on air and water effluent sampling results as summarized in Table 2-3.





Predicted Dose From All Pathways

The potential dose to the public from both airborne and liquid effluents released from the Project during 2004 is the sum of the individual dose contributions. The calculated maximum EDE from all pathways to a nearby resident was 0.049 mrem (0.00049 mSv). This dose is 0.05% of the 100-mrem (1-mSv) annual limit in DOE Order 5400.5. The estimated dose from radon-220 to the same nearby resident was about 0.01 mrem.

The total collective EDE to the population within 50 miles (80 km) of the site was 0.20 person-rem (0.0020 person-Sv), with an average EDE of 0.0001 mrem (0.000001 mSv) per individual. The estimated radon-220 dose to the population was approximately 0.3 person-rem.

Table 2-3 summarizes the dose contributions from all pathways and compares the individual doses with the applicable standards. The low doses calculated using computer modeling were corroborated by the low or non-detectable doses calculated from local foodstuff test data.

rated by the low or non-detectable doses calculated from local foodstuff test data.

Figure 2-6 shows the calculated annual dose to the hypothetical maximally exposed individual over the last ten years. The estimated dose for 2004 (0.05 mrem) is higher than the annual dose reported for 2003 (0.03 mrem). The decrease in dose fraction from air emissions in 2003 is attributed to the continuing decrease in iodine-129 emissions. Liquid doses, however, were slightly higher in 2004 than in 2003 (0.047 versus 0.032 mrem, respectively).

Figure 2-7 shows the collective dose to the population over the last ten years. (See Fig. A-14 for a map of the population sectors.) The overall radioactivity represented by these data confirms the continued inconsequential addition to the natural background radiation dose that individuals and population around the WVDP receive from Project activities.

Risk Assessment

Estimates of cancer risk from ionizing radiation have been presented by the National Council on Radiation Protection and Measurements (NCRP) (1987b) and the National Research Council's Committee on Biological Effects of Ionizing Radiation (1990).

The NCRP estimates that the probability of fatal cancer occurring is between one and five per 10,000 people who each are exposed to one rem (i.e., a risk coefficient of between 0.0001 and 0.0005). DOE guidance has, in the past, recommended using a risk coefficient of 0.0005 (ICRP, 1991) to estimate risk to a MEOSI. Recent DOE guidance recommends using the even more conservative risk coefficient of 0.0006 provided by the Interagency Steering Committee on Radiation Standards (January 2003). The estimated risk to the hypothetical individual residing near the WVDP from airborne and waterborne releases in 2004 was 3 chances in 100 million (a risk coefficient of 0.00000003). This risk is well below the range of 0.000001 to 0.00001 per year considered by the ICRP in Report Number 26 (1977) to be a reasonable risk for any individual member of the public.

Dose to Biota: Aquatic and Terrestrial Wildlife

Radionuclides from both natural and man-made sources may be found in environmental media such as water, sediments, and soils. In the past, it has been assumed that if radiological controls are sufficient to protect humans, other living things are also likely to be sufficiently protected. This assumption is no longer considered adequate, since populations of plants and animals residing in or near these media or taking food or water from these media may be exposed to a greater extent than are humans. For this reason, the DOE prepared a technical standard which provides meth-

ods and guidance to be used to evaluate doses of ionizing radiation to populations of aquatic animals, riparian animals (i.e., those that live along banks of streams or rivers), terrestrial plants, and terrestrial animals.

Methods in this technical standard, "A Graded Approach for Evaluating Radiation Doses to Aquatic and Terrestrial Biota" (DOE-STD-1153-2002, July 2002), were used in 2004 to evaluate radiation doses to aquatic and terrestrial biota within the confines of the WYNSC, which includes the WVDP. Doses were assessed for compliance with the limit in DOE Order 5400.5 for native aquatic animal organisms (1 rad per day) and for compliance with the thresholds for terrestrial plants (also 1 rad per day) and for terrestrial animals (0.1 rad per day), as proposed in DOE-STD-1153-2002. Note that the absorbed dose unit (rad) is used for biota instead of the units used for indicating human risk (rem).

The RESRAD-BIOTA Code, a calculation tool provided by the DOE for implementing the technical standard, was used to compare existing radionuclide concentration data from environmental sampling with biota concentration guide (BCG) screening values and to estimate upper bounding doses to biota. Data collected from surface waters, sediments, and soils on and around the WYNSC over a ten-year period (1991–2000) were used as a baseline. For a more near-term assessment, a second evaluation was completed using surface water data from 2004, sediment data from the last five years (2000–2004), and soil data from the last ten years (1995–2004). Differing time periods were used because radionuclide concentrations change more rapidly over time in surface waters than in sediments and soils, as reflected in their sampling frequencies (weekly or monthly for water, annually for sediments and soils). Longer time periods were also required for sediments and soils to obtain sufficient data points to produce

reliable annual averages. (See Appendices A and B⁶⁰ for maps and descriptions of monitoring and surveillance locations. Radionuclides analyzed for each medium at each location are listed in Appendix B⁶⁰. See Appendices C and G⁶⁰ for a summary of results from these locations in 2004.)

Concentration data for radionuclides in each medium were entered into the RESRAD-BIOTA Code. The value for each radionuclide was automatically divided by its corresponding BCG in order to calculate a partial fraction for each nuclide for each medium. Partial fractions for each medium were added to produce a sum of fractions.

It was found that the isotopes with the highest sums of fractions – the radionuclides that contributed the largest component of both aquatic and terrestrial dose to biota – were strontium-90 and cesium-137. Per guidance in DOE-STD-1153-2002, the populations of organisms most sensitive to strontium-90 and cesium-137 in this evaluation – that is, those populations residing on the WNYNSC that were most likely to be adversely affected via the aquatic and terrestrial pathways – were determined to be populations of the raccoon (aquatic dose) and the deer mouse (terrestrial dose). As such, this study does not pertain to pathways to humans, which were addressed earlier in this chapter.

Exposures from the aquatic pathway may be assumed to be less than the aquatic dose limit from DOE Order 5400.5 if the sum of fractions for the water medium plus that for the sediment medium is less than 1.0. Similarly, exposures from the terrestrial pathway may be assumed to be less than the proposed dose limits for both terrestrial plants and animals if the sum of fractions for the water medium plus that for the soil medium is less than 1.0.

In accordance with the approach described in DOE-STD-1153-2002, a general screening was

first conducted using the maximum radionuclide concentrations from surface waters, sediments, and soils. Maximum radionuclide concentrations exceeded applicable general screening BCG limits for both aquatic and terrestrial evaluations.

As recommended in DOE-STD-1153-2002, a site-specific screening was then done using estimates of average radionuclide concentrations derived from measurements in surface waters, sediments, and soils. Results are summarized in Table 2-4.

At the site-specific screening level for the full ten-year period, the sums of fractions for the aquatic and terrestrial system evaluations were 0.45 and 0.57, respectively. The comparable sums of fractions using the more near-term data were 0.17 and 0.31, respectively. The sum of fractions for each assessment was less than 1.0, indicating that applicable BCGs were met for both the aquatic and terrestrial evaluations.

Upper bounding doses associated with the aquatic system evaluation were 0.0059 rad/day to an aquatic animal and 0.017 rad/day to a riparian animal, far below the 1 rad/day standard from DOE Order 5400.5 for dose to a native aquatic animal. Upper bounding doses associated with the terrestrial system evaluation were 0.031 and 0.0027 rad/day to terrestrial animals and plants, again well below the guidance thresholds (0.1 and 1.0 rad/day, respectively).

It was therefore concluded that populations of aquatic and terrestrial biota (both plants and animals) on the WNYNSC are not being exposed to doses in excess of the existing DOE dose standard for native aquatic animals (U.S. DOE, February 1990) and the international standards for terrestrial organisms (International Atomic Energy Agency [IAEA], 1992).

Summary

Predictive computer modeling of airborne and waterborne releases resulted in estimated hypothetical doses to the maximally exposed individual that were orders of magnitude below all applicable EPA standards and DOE Orders, which place limitations on the release of radioactive materials and dose to individual members of the public. The collective population dose was also assessed and found to be orders of magnitude below the natural background radiation dose. Additionally, estimates of dose to biota indicated that biota at the WVDP are exposed at a fraction of the DOE and IAEA guidelines for dose to biota.

Based on the overall dose assessment, the WVDP was found to be in compliance with applicable effluent radiological guidelines and standards during calendar year 2004. Table 2-5 provides a summary of WVDP releases and calculated doses in the specified DOE format.

Table 2-4
2004 Evaluation of Dose to Aquatic and Terrestrial Biota

<u>Aquatic System Evaluation (Near-Term Data Set)</u>							
Nuclide	Water BCG* (pCi/L)	Mean Water Value (pCi/L)	Ratio	Sediment BCG* (pCi/g)	Mean Sediment Value (pCi/g)	Ratio	Water and Sediment Sum of Fractions
Cesium-137	42.7	2.98	6.98E-02	3,130	6.43	2.06E-03	0.072
Strontium-90	279	26.9	9.65E-02	583	0.691	1.19E-03	0.10
All Others	NA	NA	<u>7.47E-04</u>	NA	NA	<u>5.31E-04</u>	<0.01
Sum of Fractions (Near-Term Data)			1.67E-01			3.77E-03	0.17
Sum of Fractions (Long-Term [10-Yr] Data)			4.47E-01			5.65E-03	0.45
Estimated upper bounding dose to an aquatic animal = 0.0059 rad/day; to a riparian animal = 0.017 rad/day.							
<u>Terrestrial System Evaluation (Near-Term Data Set)</u>							
Nuclide	Water BCG* (pCi/L)	Mean Water Value (pCi/L)	Ratio	Soil BCG* (pCi/g)	Mean Soil Value (pCi/g)	Ratio	Water and Soil Sum of Fractions
Cesium-137	599,000	2.98	4.97E-06	20.8	4.82	2.32E-01	0.23
Strontium-90	54,500	26.9	4.94E-04	22.5	1.70	7.56E-02	0.076
All Others	NA	NA	<u>2.39E-06</u>	NA	NA	<u>7.91E-04</u>	<0.001
Sum of Fractions (Near-Term Data)			5.01E-04			3.08E-01	0.31
Sum of Fractions (Long-Term [10-Yr] Data)			7.20E-04			5.66E-01	0.57
Estimated upper bounding dose to a terrestrial plant = 0.0027 rad/day; to a terrestrial animal = 0.031 rad/day.							

* The biota concentration guides (BCGs) are calculated values. Except for the sums of fractions and dose estimates, which are rounded to two significant digits, all values are expressed to three significant digits.

Table 2-5
WVDP Radiological Dose and Release Summary

WVDP Radiological Dose Reporting Table CY 2004

Dose to the Maximally Exposed Individual		% of DOE 100-mrem Limit	Estimated Population Dose		Population Within 50 Miles (2000 census)	Estimated Natural Radiation Population Dose
0.049 <i>mrem</i>	0.00049 <i>(mSv)</i>	0.049	0.20 <i>person-rem</i>	0.0020 <i>(person-Sv)</i>	1,536,000	453,000 <i>person-rem</i>

WVDP Radiological Atmospheric Emissions^a CY 2004 in Curies (Bq)

Tritium	Kr-85	Noble Gases (T _{1/2} <40 dy)	Short-Lived Fission and Activation Products (T _{1/2} <3 hr)	Fission and Activation Products (T _{1/2} >3 hr)	Total Radioiodine	Total Radiostrontium	Total Uranium ^b	Total Plutonium	Total Other Actinides	Other (Rn-220)
5.60E-03 (2.07E+08)	NA	NA	NA	5.50E-05 (2.04E+06)	4.22E-05 (1.56E+06)	3.15E-05 (1.17E+06)	2.07E-07 (7.66E+03)	1.58E-06 (5.86E+04)	2.12E-06 (7.84E+04)	1.10E+03 (4.05E+13)

WVDP Liquid Effluent Releases^a of Radionuclide Material CY 2004 in Curies (Bq)

Tritium	Fission and Activation Products (T _{1/2} >3 hr)	Total Radioiodine	Total Radiostrontium	Total Uranium ^c	Total Plutonium	Total Other Actinides
9.55E-02 (3.54E+09)	7.14E-03 (2.64E+08)	1.78E-04 (6.58E+06)	2.00E-01 (7.39E+09)	1.07E-03 (3.95E+07)	1.63E-05 (6.05E+05)	2.95E-05 (1.09E+06)

NA - Not applicable

^a The WVDP air and water releases are from point source and controlled liquid effluent releases, respectively.

^b Total uranium (grams) = 2.10E-01

^c Total uranium (grams) = 7.86E+02

This page intentionally left blank

ENVIRONMENTAL NONRADIOLOGICAL PROGRAM INFORMATION

Overview of New York State Water Classifications, Water Quality Standards, and Water Effluent Limits

The objective of the Clean Water Act of 1972 (CWA) (as stated in Section 101 of the Act) is to restore and maintain the integrity of the nation's waters and ensure that, wherever attainable, waters be made useful for fishing and swimming. To achieve this goal, New York State is delegated with authority under Sections 118, 303, and 510 of the CWA to (1) classify and designate the best uses for receiving waters, such as streams and rivers, within its jurisdiction; and (2) establish and assign water quality standards – goals for achieving the designated best uses for these classified waters. In addition to achieving CWA goals for fishing and swimming, New York has further classified its jurisdictional waters and established ambient water standards, guidelines, and maximum contaminant levels (MCLs) to achieve objectives under the Safe Drinking Water Act for drinking water. These standards serve as the basis for periodic evaluation of the integrity of the receiving waters and identification of needed controls, such as New York State Pollutant Discharge Elimination System (SPDES) permits and effluent limitations.

The definitions for best usage classifications of New York's jurisdictional waters and the water quality standard goals for these classifications are provided in Title 6 of the Official Compilation of Codes, Rules, and Regulations of the State of New York (NYCRR) Parts 701–704. Mapping of the Cattaraugus Creek drainage basin and assignment of best usage designations and classification to each receiving water segment within this drainage basin are described in 6 NYCRR Part 838. According to these regulations, Frank's Creek, Quarry Creek, and segments of Buttermilk Creek under the influence of West Valley Demonstration Project (WVDP) water effluents are identified as Class "C" receiving waters with a minimum designated best usage for fishing with conditions suitable for fish survival. Cattaraugus Creek, in the immediate downstream vicinity of the Western New York Nuclear Service Center (WNYNSC), is identified as a Class "B" receiving water with best designated usages for swimming and fishing. All fresh (non-saline) groundwaters within New York are assigned a "GA" classification with a designated best usage as a potable water supply source.

Presented in Appendix C-1[□] is a summary of the numerical water quality standards, guidelines, and MCLs assigned to these water classifications for those substances and parameters that are included

in the WVDP environmental monitoring program for ambient water. Also included in Appendix C-1⁶⁰ are SPDES permit discharge limits for site effluents.

Surface Water, Subsurface Drainage Water, and Water Effluent Monitoring

Appendix C-2⁶⁰ contains process effluent data with SPDES permit limits provided for comparison with these data. Appendices C-3 through C-5⁶⁰ present data for ambient surface water, subsurface drainage water, contained water, and potable water monitoring locations. Also provided for side-by-side comparison with these data are reference values, where available, including background ambient water monitoring data and/or pertinent ambient water quality standards (AWQS), guidelines, or MCLs.

SPDES Permit-Required Monitoring. Liquid discharges are regulated under the SPDES permit. The WVDP holds a SPDES permit that identifies the outfalls where liquid effluents are released to Erdman Brook (Fig. A-2) and specifies the sampling and analytical requirements for each outfall. In August 2003, the WVDP filed an application with the New York State Department of Environmental Conservation (NYSDEC) for renewal of the SPDES permit. In October 2003, NYSDEC issued a renewed permit, subsequently modified in February 2004, which will expire in 2009. The conditions and requirements of the SPDES permit are summarized in Appendix C-1⁶⁰. The permit identifies five outfalls:

- outfall WNSP001, discharge from the low-level waste treatment facility (LLWTF)
- outfall WNSP007, discharge from the sanitary and industrial wastewater treatment facility

- outfall WNSP008, groundwater effluent from the perimeter of the LLWTF storage lagoons (closed in May 2001 but still in the permit)

- outfall 116, a location in Frank's Creek that represents the confluence of outfalls WNSP001, WNSP007, and WNSP008, as well as storm water runoff, groundwater seepage, and augmentation water. (Samples from upstream sources are used to calculate total dissolved solids at this location and to demonstrate compliance with the SPDES permit limit for this parameter. Outfall 116 is referred to as a "pseudo-monitoring" point on the SPDES permit.)

- outfall WNSP01B, an internal monitoring point for the liquid waste treatment system evaporator effluent, being monitored for flow and total mercury.

Some of the more significant features of the SPDES permit are the requirements to report five-day biochemical oxygen demand, total dissolved solids, iron, and ammonia data as flow-weighted concentrations and to apply a net discharge limit for iron. The net limit allows the Project to account for the iron that is naturally present in the site's incoming water. The flow-weighted limits apply to the flow-proportioned sum of the Project effluents.

One SPDES effluent limit exception for total suspended solids was observed in May 2004.

Mercury Analytical Method Study. The modified SPDES permit received by the WVDP in July 2002 required a comparison study of mercury determination by two analytical methods: U.S. Environmental Protection Agency (EPA) Method 245.1 (or 245.2) with a detection level of 0.2 µg/L (parts per billion) and EPA Method 1631E, which allows determination of mercury at a minimum level of 0.5 ng/L (parts per trillion). The latter ("ultraclean")

method supports the EPA's effort to make available an additional analytical method capable of measuring mercury accurately at ambient water quality criteria levels.

Since the SPDES permit enforcement compliance limit of 0.2 µg/L for total mercury is several orders of magnitude higher than the AWQS of 0.0007 µg/L for dissolved mercury, the WVDP is required to conduct a mercury study using both methods (1631 and 245.1 or 245.2) whenever mercury samples are required under the terms of the SPDES permit. A report summarizing the analytical results from these two methods and its findings is required to be submitted quarterly to NYSDEC.

Sixteen sets of samples from outfall 001 were analyzed for mercury by the two test methods in 2004. Samples were analyzed at Severn Trent Laboratories using Method 245.1 and at General Engineering Laboratories using Method 1631E.

All sample results from Method 245.1 were less than 0.2 µg/L, the practical quantitation limit for Method 245.1. Results generated with Method 1631E were consistent with results generated with Method 245.1. That is, all sample results generated with Method 1631E were reported at levels below 0.2 µg/L. The average concentration for samples collected at outfall 001 using Method 1631E was 0.0134 µg/L.

South Plateau Surface and Subsurface Water.

An inactive underground radioactive waste disposal site, the U.S. Nuclear Regulatory Commission (NRC)-Licensed Disposal Area (NDA), lies on the south plateau of the site. Surface waters, which flow from the south to the north, are routinely monitored at several points around this area (Fig. A-2). Two of these points, WNNDATR and WNNDADR, are used to monitor (respectively) waters within the NDA water collection trench

system and surface runoff and seepage immediately downstream of the NDA. Sampling point WNNDATR is an underground sump at the lowest point in the collection trench system that intercepts groundwater from the NDA. If radiological or nonradiological contamination were to migrate through the NDA, it would most likely be first detected in samples from WNNDATR.

Interceptor Trench and Pretreatment System.

Radioactively-contaminated n-dodecane (similar to kerosene) in combination with tributyl phosphate (TBP) was discovered at the northern boundary of the NDA in 1983. To contain migration of this subsurface radioactive organic contaminant, an interceptor trench and a liquid pretreatment system (LPS) were built. (See "NRC-Licensed Disposal Area [NDA] Interceptor Trench and Pretreatment System" in Chapter 1.)

The trench was designed to intercept and collect subsurface water, which could be carrying n-dodecane/TBP, to prevent the material from entering the surface water drainage ditch leading into Erdman Brook, and to prevent contamination of downgradient groundwater. The LPS was installed to separate the n-dodecane/TBP and to remove iodine-129 from the collected water before its transfer to the LLWTF. The separated n-dodecane/TBP would be stored for subsequent treatment and disposal.

In 2004, as in previous years, no water containing TBP was encountered in the trench. Results of surface and groundwater monitoring in the vicinity of the trench are discussed in Chapter 2 ("South Plateau Surface Water and NDA Interceptor Trench") and in Chapter 4 ("Results of Monitoring at the NDA").

Total Organic Halides. Total organic halides (TOX) measurements are used as a screening

mechanism to detect the presence of certain organic compounds and associated radionuclides. In 2004, concentrations of TOX at both WNNDATR and WNNDADR remained within the range of historical values.

Other On-Site and Off-Site Surface Water Monitoring. As part of the routine monitoring program, two sets of grab samples for nonradiological parameters at WNSP006 (Frank's Creek at the security fence), WNSWAMP (northeast swamp drainage), WNSW74A (north swamp drainage), WFBCTCB (Buttermilk Creek at Thomas Corners), and WFBCBKG (Buttermilk Creek at Fox Valley) were taken in 2004. These samples were screened for organic and inorganic constituents and selected anions, cations, and metals. Results of measurements for these locations are found in Appendices C-3⁶⁰ and C-4⁶⁰.

At surface water monitoring locations WFBCTCB, WNSP006, and background reference location WFBCBKG, the maximum concentrations of total iron exceeded the water quality standard (0.30 mg/L). NYSDEC, in its 2002 CWA 303(d) report to the EPA, indicated it found the scientific basis for the 0.30 mg/L standard to be insufficient. NYSDEC also indicated that its upcoming standards review is expected to include a proposed replacement of the 0.30 mg/L standard with a 1.0 mg/L guidance value, based on 1976 EPA criteria. Nonetheless, iron concentrations at these locations also exceeded this replacement value. Elevated iron concentrations are thought to be largely attributable to elevated background concentrations. However, they may further be elevated due to the influence of water runoff from industrial activities.

The maximum observed concentrations of dissolved aluminum at surface water locations WFBCTCB, WNSP006, and WFBCBKG exceeded the water quality standard for this param-

eter. As seen with iron, elevated aluminum concentrations are thought to be largely attributable to elevated background concentrations. However, they also may further be elevated due to the influence of water runoff from industrial activities.

Monitoring results for the standing water locations (WNSTAW series) are presented in Appendix C-4⁶⁰. The total iron concentrations at WNSTAW4, WNSTAW5, and WNSTAW9 (0.63, 0.68, and 0.48 mg/L, respectively) exceeded the 0.3 mg/L standard for Class "D" surface waters. The elevated iron concentrations at these standing water locations are thought to be attributable to naturally elevated background concentrations of iron.

Monitoring results for pH at locations WNSP005, WFFELBR, WFBCTCB, WNFRC67, and WNDCELD are provided in Appendices C-3⁶⁰ and C-4⁶⁰. Although most pH values were within applicable standards, the minimum result at WFFELBR (6.23) in 2004 was below the lower pH limit of 6.5. Low pH of precipitation in the western New York region may suppress pH in ambient surface waters, especially during times of high rainfall when precipitation runoff may account for a large proportion of stream flow.

Drinking Water Monitoring

Site drinking water is monitored to verify compliance with EPA and New York State Department of Health (NYSDOH) regulations. (See "Safe Drinking Water Act" in the Environmental Compliance Summary.) Samples are collected annually and analyzed for nitrate, fluoride, cyanide, and metals concentrations. In addition, an annual sample was obtained for principal organic contaminants. The 2004 monitoring results indicated that the Project's drinking water met NYSDOH, EPA, and Cattaraugus County Health Department MCLs and drinking water quality standards.

Conductivity and pH in off-site and on-site drinking water are presented in Appendix C-5⁶⁰. With the exception of turbidity results measured in January 2004, including a peak value of 1.6 NTU on January 18, 2004, all results were within applicable limits during 2004. Elevated turbidity results in January 2004 occurred as a result of inclement weather that caused excessive ice formation and mechanical failure of the clarifier equipment. The clarifier is a step in the process for treating incoming source water to produce drinkable water.

Results for inorganic, organic, and indicator analyses of utility room potable water at the distribution system entry point, location WNDNKUR, are listed in Appendix C-5⁶⁰, as are monthly results for biological and residual chlorine analyses at site tap water locations. All results were within NYSDOH MCLs and EPA maximum contaminant level goals. The annual result for nitrate-nitrogen in a tap water sample from the WVDP restroom sink, as analyzed by the Cattaraugus County Department of Health, was also below the MCL.

Soil and Sediment Monitoring

Sediments are found at the bottom of surface waters, including streams located within the WVDP and WNYNSC premises. Sediments provide habitat for a wide variety of benthic organisms, as well as juvenile forms of pelagic organisms. These organisms in sediments are in constant contact with substances that may be adsorbed to sediment particles. Contaminated sediments are potential diffuse sources of contamination to the overlying water body.

In 1999, NYSDEC issued updated guidance for screening contaminated aquatic sediments. This guidance includes sediment quality criteria correlated to the severity of environmental impact. These criteria, which are derived from National

Oceanic and Atmospheric Administration (Long and Morgan, 1990) and 1992 Ministry of Ontario "Guidelines for the Protection and Management of Aquatic Sediment Quality in Ontario" (Persaud et al., 1992), are presented in Appendix G-1⁶⁰.

Contaminants in soils are potential sources for contamination of groundwater, ambient air, flora, and fauna. Appendix G-1⁶⁰ includes a summary of reference criteria, including background concentration ranges for eastern United States soils and sediment screening levels. Data for soil and sediment monitoring locations are provided in Appendix G-2⁶⁰. Also, provided for side-by-side comparison with these data, are available reference values, including background concentrations and/or sediment screening levels.

At SNSP006, all analytical results for sediments were below the Severe Effect Level and No Appreciable Contaminant Levels specified in the NYSDEC guidance. According to the NYSDEC "Technical Guidance for Screening Contaminated Sediments," these results suggest there is no pronounced disturbance of the sediment-dwelling biological community and that there is no significant harm to benthic aquatic life at this location.

The result for manganese in the sediment sample obtained at SNSP006 exceeded the Lowest Effect Level but was below the Severe Effect Level. Based on the NYSDEC sediment screening guidance, moderate impacts to benthic life could be expected at this location.

At SNSW74A and SNSWAMP, concentrations of zinc exceeded the eastern United States background soil concentration range identified in the NYSDEC Technical Administrative Guidance Memorandum (TAGM) #4046 "Determination of Soil Clean-Up Objectives and Clean-Up Levels." Calcium and magnesium at SNSW74A also exceeded the eastern background soil concentration

range. Concentrations of these naturally occurring metals above the natural background ranges may be indicative of localized, naturally elevated background concentrations of metals in soils or deposition of sediment from runoff from areas where industrial activities are occurring.

In 2004, a section of the bed for the railroad spur on the WNYNSC was rehabilitated to support future use of this rail line for waste shipments. Prior to removal, the railbed soil material was sampled, and tested for chemical constituents that are typically found in soils associated with rail lines, to identify appropriate soil management practices. The test results indicated the soil did not have any appreciable contamination, with all results within soil cleanup objectives specified in NYSDEC guidance, TAGM 4046. Refer to Appendix G-2⁶⁰ for the results for these constituents.

Air Emission Monitoring

Nonradiological air emissions are permitted under NYSDEC and EPA regulations. (The regulations that apply to the WVDP are listed in Appendix K⁶⁰. The New York State Air Facility Registration Certificate held by the WVDP is described in a listing of West Valley Demonstration Project Environmental Permits in the Environmental Compliance Summary.)

The nonradiological air certificate covers emissions of regulated pollutants that include nitrogen oxides and sulfur dioxide.

The main contributing source of oxides of nitrogen and sulfur at the WVDP was the vitrification system melter, which was shut down in September 2002. Site boilers and standby diesel generators were left as the only contributors of nitrogen and sulfur oxides, at levels much lower than those emitted by the melter.

SITE HYDROLOGY AND GROUNDWATER MONITORING

Groundwater Monitoring Program Overview

Groundwater at the West Valley Demonstration Project (WVDP or Project) is monitored to comply with all applicable state and federal regulations and to meet the requirements of U.S. Department of Energy (DOE) Order 450.1. The program enables the WVDP to obtain data to determine baseline conditions, to allow the early detection of groundwater contamination, to identify existing and potential groundwater contamination sources and maintain surveillance of these sources, and to provide data for decision-making.

The WVDP's "Groundwater Monitoring Plan" outlines groundwater characterization, current groundwater sampling requirements, and support of long-term monitoring requirements identified in the Resource Conservation and Recovery Act (RCRA) facilities investigation (RFI) and DOE programs. The "WVDP Groundwater Protection Management Program Plan" provides additional information regarding protection of groundwater from on-site activities.

Surface Water Hydrology

The Western New York Nuclear Service Center (WNYNSC) lies within the Cattaraugus Creek

watershed, which empties into Lake Erie about 27 miles (43 km) southwest of Buffalo. Buttermilk Creek, a tributary of Cattaraugus Creek, drains most of the WNYNSC and all of the Project.

The WVDP lies within the watershed of Frank's Creek, which is a tributary of Buttermilk Creek and is located near the eastern and southern boundary of the WVDP; Quarry Creek, a tributary of Frank's Creek, is located near the northern boundary (Fig. A-1).

Another tributary of Frank's Creek, Erdman Brook, bisects the WVDP into a north and south plateau. The main plant, waste tanks, and lagoons are located on the north plateau. The drum cell, the U.S. Nuclear Regulatory Commission (NRC)-Licensed Disposal Area (NDA), and the New York State-Licensed Disposal Area (SDA) are located on the south plateau.

Geology

The 167-acre (68-hectare [ha]) Project site is located within the WNYNSC, which comprises approximately 3,338 acres (1,351 ha) and is located near the northern border of Cattaraugus County. Beneath the WNYNSC is a sequence of recent and older glacial-age sediments filling a steep-sided valley incised in the bedrock, which is composed

of shales and interbedded siltstones (Rickard, 1975).

Pleistocene sediments overlying the bedrock typically consist of a sequence of three glacial tills of Lavery, Kent, and possibly Olean age. The tills are separated by stratified fluvio-lacustrine deposits. In the northern part of the site, the Lavery till is capped by coarse-grained alluvial-fluvial deposits.

Hydrogeology

The sediments above the Kent till – the Kent recessional sequence, the Lavery till, the intra-Lavery till-sand, and the surficial sand and gravel – are generally regarded as containing all of the potential routes for the contaminant migration via groundwater from the Project. (Figs. 4-1 and 4-2 show the relative locations of these sediments on the north and south plateaus.) The Lavery till, the Kent recessional sequence, and the Kent till are common to both the north and south plateaus. The bottommost layer, the Kent till, is less permeable than the other geological units and does not provide a pathway for contaminant movement from the WVDP, therefore it is not discussed here.

The WVDP does not use groundwater for drinking or operational purposes, nor does it discharge effluent directly to groundwater. No public water supplies are drawn from groundwater downgradient of the site or from downstream Cattaraugus Creek. Upgradient of the site, groundwater is used for drinking water by local residents.

Kent Recessional Sequence. The Kent recessional sequence consists of a fine-grained lacustrine unit of interbedded clay and silty clay layers locally overlain by coarse-grained sands and gravels. These deposits underlie the Lavery till beneath most of the site, pinching out along the southwest-

ern margin of the site where the walls of the bedrock valley intersect the sequence.

Groundwater flow in the Kent recessional sequence is predominantly to the northeast, toward Buttermilk Creek. Mean hydraulic conductivity is 2E-01 ft/day (8E-05 cm/sec) or 2.6 in/day, based on recent testing. Recharge comes from the overlying Lavery till and inflow from the bedrock to the southwest. Discharge is to Buttermilk Creek.

Lavery Till. The Lavery till is predominantly an olive-gray, silty clay glacial till with scattered lenses of silt and sand. It underlies both the north and south plateaus and ranges up to 130 feet (40 m) in thickness beneath the active areas of the site, slightly increasing northeastward toward Buttermilk Creek and the center of the bedrock valley. Groundwater flow in the unweathered Lavery till is predominantly vertically downward at a relatively slow rate. Mean hydraulic conductivity is 1E-04 ft/day (3.5E-08 cm/sec) or 0.001 in/day, based on recent testing.

On the south plateau, the upper zone of the Lavery till is exposed at the ground surface and is weathered and fractured to a depth of 3 to 16 feet (0.9 to 4.9 m). This layer, referred to as the weathered Lavery till, is unique to the south plateau. The weathered Lavery till has been oxidized to a brown color and contains numerous desiccation cracks and root tubes.

Groundwater flow in the weathered till has both horizontal and vertical components. This enables groundwater to move laterally across the south plateau before moving downward into the unweathered Lavery till or discharging to nearby incised stream channels. Mean hydraulic conductivity is 5E-02 ft/day (2E-05 cm/sec) or 0.6 in/day, based on recent testing. The highest conductivities are associated with dense fracture zones found within the upper 7 feet (2 m) of the unit.




Figure 4-1. Geologic Cross Section Through the North Plateau (Vertical Exaggeration Approx. 2:1)




Figure 4-2. Geologic Cross Section Through the South Plateau (Vertical Exaggeration Approx. 2.5:1)

On the north plateau, the weathered till layer is much thinner or nonexistent and the unweathered Lavery till is overlain by the sand and gravel unit.

Sand and Gravel and Till-Sand Units. The sand and gravel unit and the Lavery till-sand are unique to the north plateau. The sand and gravel unit is a silty sand and gravel layer composed of younger Holocene alluvial deposits that overlie older Pleistocene-age glaciofluvial deposits. Together these two layers range up to 41 feet (12.5 m) in thickness near the center of the plateau and pinch out along the northern, eastern, and southern edges of the plateau, where they have been truncated by downward erosion of stream channels.

Groundwater in this unit generally flows northeastward across the plateau toward Frank's Creek. Groundwater near the northwestern and southeastern margins of the sand and gravel layer also flows radially outward toward Quarry Creek and Erdman Brook, respectively. There is minimal groundwater flow downward into the underlying Lavery till. Mean hydraulic conductivity is 16.4 ft/day (6E-03 cm/sec) or 200 in/day, based on recent testing.

Within the unweathered Lavery till on the north plateau is another unit, the Lavery till-sand. This thin, sandy unit of limited areal extent and variable thickness is found primarily beneath the southeastern portion of the north plateau. Groundwater flows through this unit in an east-southeast direction. Surface discharge locations have not been observed. Mean hydraulic conductivity is 3.8 ft/day (1E-03 cm/sec) or 46 in/day (117 cm/day), based on recent testing.

Hydrologic conditions of the site are more fully described in "Environmental Information Document, Volume III: Hydrology, Part 4" (West Valley Nuclear Services Co. [WVNSCO], March 1996) and in the "RCRA Facility Investigation Re-

port Vol. 1: Introduction and General Site Overview" (WVNSCO and Dames & Moore, July 1997).

Routine Groundwater Monitoring Program

Groundwater is monitored in the five hydrogeologic units previously described: the sand and gravel, the weathered Lavery till, the unweathered Lavery till, the Lavery till-sand, and the Kent recessional sequence. In 2004, a total of 69 groundwater monitoring locations were sampled. These locations included 63 monitoring wells (including driven well points), five groundwater seepage points, and one sump/manhole. (See Tables 4-1 and 4-2 for a summary of groundwater monitoring activities in 2004.)

Monitoring Well Network. Most of the routine groundwater monitoring wells were originally assigned to monitor one (or more) of the super solid waste management units (SSWMUs) on the WVDP premises. Table 4-3 describes the SSWMUs and their constituent solid waste management units (SWMUs) on site. (See "RCRA §3008(h) Administrative Order on Consent" in the Environmental Compliance Summary.)

Figures A-7 and A-8 in Appendix A show boundaries of ten of the WVDP SSWMUs. The eleventh SSWMU, the SDA, is a closed radioactive waste landfill. The SDA is contiguous with the Project premises and is owned and managed by the New York State Energy Research and Development Authority (NYSERDA). Groundwater monitoring results from the SDA are reported in Appendix L⁶² but are not discussed here.

Appendix E⁶³ lists the wells in the network, sorted by the geologic unit monitored, and the analytes measured in 2004. Note that monitoring of certain wells, marked by an asterisk, are specified in RFI reports prepared in accordance with the RCRA

Table 4-1
Summary of Groundwater Monitoring Program by Geographic Area;
Monitoring Year 2004

NUMBER OF...	TOTAL WVDP	NORTH PLATEAU	SOUTH PLATEAU	OFF-SITE RESIDENTIAL
Monitoring Points Sampled - Analytical*	79	54	15	10
Monitoring Points - Water Elevations Only	42	26	16	0
Monitoring Events	5	4	4	1
Analyses	1,353	1,146	160	47
Results	10,987	9,679	1,197	111
Percent of Nondetectable Results	85%	85%	85%	65%
Water Elevation Measurements	412	288	124	0

* Total number includes 69 on-site and 10 off-site points.

Table 4-2
Summary of Groundwater Monitoring Program by Monitoring Purpose;
Monitoring Year 2004

NUMBER OF...	REGULATORY/ WASTE MANAGEMENT	ENVIRONMENTAL SURVEILLANCE
Monitoring Points Sampled - Analytical*	34	45
Monitoring Points - Water Elevations Only	0	42
Monitoring Events	4	5
Analyses	265	722
Results	4,740	5,666
Percent of Nondetectable Results	84%	84%
Water Elevation Measurements	128	280
Ranges of Results For Positive Detections		
Organic Compounds (µg/L)		
1,1-Dichloroethane	8.2-11	NA
1,2-Dichloroethylene (total)	21-26	NA
Tributyl phosphate	2.0-410	NA
Maximum Concentrations For		
Radiological Parameters (µCi/mL)		
Gross Beta	2.92E-04	1.61E-04
Strontium-90	1.25E-04	6.85E-05
Tritium	4.68E-06	5.35E-05

NA - Not applicable

* Total number includes 69 on-site and 10 off-site points.

Table 4-3
WVDP RCRA SSWMUs and Constituent SWMUs

SSWMU	CONSTITUENT SWMUs
SSWMU #1 – Low-Level Waste Treatment Facilities (LLWTF)	Former Lagoon 1 LLWTF Lagoons LLWTF Building Interceptors Neutralization Pit
SSWMU #2 – Miscellaneous Small Units	Sludge Ponds Solvent Dike Equalization Mixing Basin Paper Incinerator
SSWMU #3 – Liquid Waste Treatment System (LWTS)	Liquid Waste Treatment System Cement Solidification System Main Process Building (specific areas)
SSWMU #4 – High-Level Waste (HLW) Storage and Processing Area	Vitrification Facility Vitrification Test Tanks HLW Tanks Supernatant Treatment System
SSWMU #5 – Maintenance Shop Leach Field	Maintenance Shop Leach Field
SSWMU #6 – Low-Level Waste Storage Area	Lag Storage Additions 1, 2, 3, 4 Hardstands (old and new) Lag Storage
SSWMU #7 – Chemical Process Cell (CPC) Waste Storage Area	CPC Waste Storage Area
SSWMU #8 – Construction and Demolition Debris Landfill	Former Construction and Demolition Debris Landfill
SSWMU #9 – NRC-Licensed Disposal Area	NRC-Licensed Disposal Area Container Storage Area Trench Interceptor Project
SSWMU #10 – Integrated Radwaste Treatment System (IRTS) Drum Cell	IRTS Drum Cell
SSWMU #11 – New York State-Licensed Disposal Area (SDA)	State-Licensed Disposal Area (NYSERDA)

§3008(h) Administrative Order on Consent for the WVDP.

In addition to analytical samples, potentiometric (water level) measurements also are collected from wells listed in Table E-1⁶⁰ in conjunction with the quarterly analytical sampling schedule (Appendix E⁶⁰). Groundwater elevation data are used to produce groundwater contour maps, which delineate flow directions and gradients, and long-term trend graphs, which illustrate seasonal fluctuations and other changes to the groundwater system. In 2004, water levels were routinely measured at 42 locations in addition to those that were sampled. (See Figures A-6 and A-7 in Appendix A.)

Surface water elevation measurements are also collected at 11 locations on the north plateau where the water table in the sand and gravel unit intersects the ground surface in the form of standing water. These measurements are correlated with groundwater elevation measurements taken at nearby monitoring wells, and are used to help define groundwater flow direction and gradients in the sand and gravel unit in areas where monitoring well coverage is sparse or nonexistent.

Groundwater Monitoring Program Highlights 1982 Through 2004. Program content is dictated by regulatory requirements in conjunction with current operating practices and historical knowledge of previous site activities.

- Groundwater monitoring at the WVDP began in 1982 and continued to expand through 1992 with the addition of new wells, groundwater seep locations, a french drain outfall, and the NDA interceptor trench sump.
- An RFI expanded characterization program was conducted during 1993 and 1994 to fully assess potential releases of hazardous wastes or constituents from on-site SSWMUs. This investigation,

which consisted of two rounds of sampling for a wide range of radiological and chemical parameters, provided valuable information regarding the presence or absence of groundwater contamination near each SSWMU. Results were used to guide later monitoring program modifications.

- In 1993, monitoring results indicated elevated gross beta activity in groundwater from the sand and gravel unit on the north plateau. Subsequent investigation of this area delineated a plume of contamination with a southwest to northeast orientation. (See Special Groundwater Monitoring and Figure 4-3 in this chapter for more detail.)
- Long-term monitoring needs were the focus of a 1995 groundwater monitoring program evaluation. After a comprehensive assessment, the number of sampling locations was reduced from 91 to 65 and analytical parameters were tailored to each sampling location for a more focused, efficient, and cost-effective program.
- In 1996, several groundwater seep monitoring locations on the northeast edge of the north plateau were added to the monitoring program.
- Four new groundwater monitoring wells were installed during August 2003 to provide upgradient and downgradient monitoring coverage for the remote-handled waste facility.
- From 1996 through 2004, in response to current sampling results and DOE and RCRA monitoring requirements, specific monitoring locations, analytes, and sampling frequencies were modified.

Analytical Trigger Level Evaluation. A computerized data-screening program uses “trigger levels” – preset conservative values for chemical and radiological concentrations and groundwater elevation measurements – to identify and promptly respond to anomalies in monitoring results. These

levels, reviewed annually, are based on regulatory limits, detection limits, or statistically derived values.

Results of Routine Groundwater Monitoring

Tables in Appendix E⁶⁰ group the results of groundwater monitoring within the five monitored hydrogeologic units. These tables contain results of sampling for radiological and nonradiological analytes. Table E-12⁶⁰ lists the practical quantitation limits (PQLs) for individual Title 6 of the Official Compilation of Codes, Rules, and Regulations of the State of New York, Appendix 33 analytes. The PQL is the lowest level of an analyte that can be measured within specified limits of precision during routine laboratory operations (New York State Department of Environmental Conservation, 1991).

Data Tables. Groundwater monitoring data for 2004 are presented in Appendix E⁶⁰. The wells in each table are arranged by hydraulic position relative to other wells within the same hydrogeologic unit. Wells identified as “UP” refer to either background wells or wells that are upgradient of other wells in the same hydrogeologic unit. Wells identified as “DOWN” are downgradient of other wells in that unit. In each table, wells are presented from upgradient to furthest downgradient. Hydraulic position provides the basis for presenting groundwater monitoring data in the tables and figures in this report.

Trend-Line Graphs. Trend-line graphs are included for monitoring locations that have historically shown radiological concentrations above background values, or concentrations of volatile organic compounds (VOCs) or semivolatile organic compounds (SVOCs) above PQLs.

Long-Term Trends of Gross Beta and Tritium at Selected Groundwater Monitoring Locations. Figures 4-4 through 4-7 show the trends of gross beta and tritium concentrations at selected monitoring locations in the sand and gravel unit. Use of a logarithmic scale allows locations having widely differing concentrations to be compared to average background concentrations plotted on each graph.

Gross Beta. In 2004, 12 wells (104, 105, 111, 116, 408, 501, 502, 801, 8603, 8604, 8605, and 8609) showed gross beta concentrations that exceeded the DOE-derived concentration guide (DCG) for strontium-90 (1.0E-06 microcuries/milliliter [$\mu\text{Ci/mL}$]). Ten of the preceding wells are within the groundwater plume of gross beta activity in the sand and gravel unit on the north plateau (Fig. 4-3). This area continues to be monitored closely. The source of the plume’s activity can be traced to the soils beneath the southwest corner of the former process building. Lagoon 1, formerly part of the low-level waste treatment facility, has been identified as a source of the gross beta activity at the remaining wells, 8605 and 111.

- Figure 4-4 shows gross beta concentrations in wells 104, 408, 501, 502, and 8609 (that are somewhat centrally located on the north plateau and are closer to the plume’s suspected source beneath the main plant). Figure 4-5 shows gross beta concentrations in wells 105, 116, 801, 8603, and 8604 (that are located further downgradient from the plume’s suspected source and are closer to the leading edges). As in previous years, samples from well 408 continued to show the highest gross beta concentrations of all the wells within the north plateau gross beta plume. Except for short-term seasonal variations, gross beta results for well 408 progressively decreased from 2002 through 2004.

Wells 501 and 502 showed slight decreases relative to 2003 and 2002. Wells 105, 116, 8604, and

8609 showed slight increases relative to 2003 values. Results in wells 104, 801, and 8603 were similar to 2003 results. Well 105 shows the largest overall increase over the last ten years.

- Figure 4-6 is a graph of gross beta concentrations at sand and gravel unit monitoring locations 111 and 8605, located near the eastern edge of the north plateau adjacent to former lagoon 1. Gross beta concentrations at wells 111 and 8605 were slightly higher in 2004 than in 2003.

Tritium. Figure 4-7 shows the tritium concentrations in wells 111, 8603, 8604, 8605, and 8609. The figure indicates that tritium concentrations in these wells show slight decreases from 2003 to 2004.

North Plateau Seeps. Analytical results of sampling for radiological parameters from the sand and gravel unit seepage monitoring locations were compared with results from GSEEP, a seep monitored since 1991 that has not been affected by the gross beta plume. (Seep monitoring locations are noted on Figs. A-6 and A-7 in Appendix A.)

Gross Beta. Radiological monitoring results continue to indicate that the gross beta groundwater plume has not migrated to these seepage areas. With the exception of SP11, gross beta concentrations from all seep monitoring locations were less than or similar to GSEEP concentrations during 2004. Gross beta concentrations at SP11 show a slightly increasing trend since early 1999 and somewhat steeper increases during 2001 through 2004. Contamination observed at SP11 is believed to be attributable to re-infiltration of contaminated water that has surfaced from the strontium-90 groundwater plume. Although somewhat greater than values typically obtained at GSEEP, it is still well below the strontium-90 DCG (Table E-2^{6a}).

Gross Alpha. Gross alpha concentrations at all seep sampling locations were very low – gener-

ally below the associated uncertainty or less than the detection limit.

Tritium. Tritium concentrations at the seeps remained similar to or less than concentrations at GSEEP. Tritium concentrations in the north plateau seeps, including GSEEP, are slightly higher levels than reported in background wells of the sand and gravel unit. Concentrations are similar to those seen in sand and gravel unit wells monitoring the lagoon areas of the north plateau, but are still far lower than the DCG for tritium.

North Plateau Well Points. Sampling at well points A, C, and H (Fig. A-6 in Appendix A) monitors tritium concentrations in the area east of the process building and fuel receiving and storage facility and west of former lagoon 1. Samples from these locations have yielded concentrations of tritium that, while elevated with respect to historical monitoring of wells in the area, are well below the tritium DCG, 2.0E-03 $\mu\text{Ci}/\text{mL}$ (Table E-2^{6a}). Data from downgradient monitoring wells have not indicated similarly elevated levels of tritium.

Results of Radioisotopic Sampling. Groundwater samples for radioisotopic analyses are collected regularly from selected monitoring points in the sand and gravel unit and the weathered Lavery till (Table E-11^{6a}). Results in 2004 were generally similar to historical findings. Strontium-90 remained the major contributor to elevated gross beta activity in the north plateau plume, as indicated by the similarity between strontium-90 trends and gross beta trends in wells showing elevated gross beta results.

Carbon-14, technetium-99, and iodine-129, which have been detected at several monitoring locations at concentrations above background levels, contribute very small percentages to total gross beta concentrations. These detections have occurred at locations within the gross beta plume

j:\gis\laser.apr fig 4-3 gross beta plume, r4 (03/15/05) - fjc




Figure 4-3. North Plateau Gross Beta Plume Area: Fourth-Quarter 2004 Results

and downgradient of former lagoon 1 and the NDA. None of the carbon-14, technetium-99, or iodine-129 concentrations have been above DCGs, and quarterly gross beta analyses continue to provide appropriate trend surveillance.

Results of Monitoring at the NDA. A trench system was previously constructed along the northeast and northwest sides of the NDA to collect groundwater that may be contaminated with a mixture of n-dodecane and tributyl phosphate (TBP). (See also “Environmental Program Information, Nuclear Regulatory Commission [NRC]-Licensed Disposal Area [NDA] Interceptor Trench and Pretreatment System” in Chapter 1.) Monitoring results in 2004 indicated no TBP in groundwater near the NDA. Groundwater levels are monitored quarterly in and around the trench to ensure that an inward gradient is maintained, thereby minimizing outward migration of potentially contaminated groundwater.

Gross beta and tritium concentrations in samples from location WNNDATR, a sump at the lowest point of the interceptor trench, and from well 909 (Fig. A-6 in Appendix A), downgradient of WNNDATR, continued to be elevated with respect to background monitoring locations on the south plateau. Concentrations were still well below the DCGs.

WNNDATR. During 2004, gross beta concentrations at WNNDATR were similar to those seen during 2003. Tritium concentrations however, while still higher than at other NDA monitoring locations, were slightly lower than in 2003.

Well 909. Radiological indicator results have historically fluctuated at this location. In general, upward long-term trends in both gross beta and tritium were discernible until 1999, when both trends declined, followed by relatively consistent results during recent years. Gross beta concen-

trations from well 909 are slightly higher than those at WNNDATR. Residual soil contamination near well 909 is the suspected source of elevated gross beta concentrations.

Off-Site Groundwater Monitoring. Groundwater is used as a potable water supply at off-site private residences near the WVDP. Nine off-site residential supply wells located within 4.3 miles (7 km) of the facility were sampled for radiological parameters in 2004. A tenth private well, located 18 miles (29 km) south of the site, provided a background location. These monitoring results are discussed in Chapter 2, Overview of Drinking Water Monitoring.

Results for Volatile and Semivolatile Organic Compounds. VOCs and SVOCs were sampled at specific locations (wells 8612, 8609, 803, 8605, 111, and seep sampling location SP12 [Fig. A-6 in Appendix A]) that have shown historical results above the PQLs. (See Tables E-7^{cd} and E-8^{cd} for sampling results, and Table E-12^{cd} for a list of PQLs.) Other monitoring locations are sampled for VOCs and/or SVOCs because they are downgradient of locations that have shown positive results or to comply with the RCRA §3008(h) Administrative Order on Consent.

1,1-Dichloroethane (1,1-DCA). Concentrations of 1,1-DCA at well 8612 decreased during 1995–1998, with a lower rate of decrease during 1999–2004 (Fig. 4-8). The compound was not detected at wells 8609, 803, or groundwater seep SP12 during 2004.

Dichlorodifluoromethane (DCDFMeth). DCDFMeth was detected at well 8612 during 2004 at the PQL.

1,1,1-Trichloroethane (1,1,1-TCA). The compound 1,1,1-TCA was detected in well 8612 during 2004 at estimated levels below the PQL, but

was not detected in well 803, 8609, or in seep SP12. (See Fig. 4-8 for a graph of 1,1,1-TCA concentrations at well 8612.)

Total 1,2-Dichloroethylene (1,2-DCE-t). Positive detections of 1,2-DCE-t were first noticed at well 8612 in 1995. Concentrations of 1,2-DCE-t increased from 1995 through 2002, but the trend has leveled from 2002 through 2004.

The VOCs 1,1-DCA, DCDFMeth, and 1,1,1-TCA are often found in combination with 1,2-DCE-t. In well 8612, each compound first exhibited an increasing trend that, over the past few years, was followed by a decreasing trend. It is expected that 1,2-DCE-t will exhibit similar behavior.

Tributyl Phosphate. Concentrations of TBP were detected in 2004 groundwater samples from well 8605, near former lagoon 1, at concentrations somewhat higher than those in 2003, but within the range of historical results. TBP also was previously detected in well 111, located near well 8605, but at levels much lower than those at well 8605. TBP was detected at well 111 during 2004 at a concentration slightly above the PQL (Figure 4-9).

Ongoing detection of TBP in this localized area may be related to previously detected, positive concentrations of iodine-129 and uranium-232 in wells 111 and 8605, as noted in previous Annual Site Environmental Reports. The presence of these contaminants may reflect residual contamination from liquid waste management activities in the former lagoon 1 area during earlier nuclear fuel reprocessing.

Special Groundwater Monitoring

Gross Beta Plume on the North Plateau. Elevated gross beta activity has been detected in groundwater from the surficial sand and gravel unit

in areas northeast of the building where Nuclear Fuel Services, Inc. reprocessed nuclear fuel (Fig. 4-3). In December 1993, elevated gross beta concentrations were detected in surface water at former sampling location WNDMPNE, located near the edge of the plateau. This detection initiated a subsurface groundwater and soil investigation in 1994 using a Geoprobe[®] mobile sampling system, which helped to identify the location and extent of the gross beta plume beneath and downgradient of the former process building.

The highest gross beta concentrations in groundwater and soil were found near the southeast corner of the process building. Strontium-90 and its daughter product, yttrium-90, were identified as the major isotopic components of this elevated gross beta activity (WVNSCO, 1995).

More attention was given in 1998 to the core area of the plume, determined to be beneath and immediately downgradient of the former process building. The 1998 study noted that, while the overall distribution of strontium-90 in groundwater within the plume was similar to 1994, concentrations detected in 1998 samples were generally lower than in 1994 samples, due to radioactive decay and continuing migration and dispersion of the plume (WVNSCO, June 1999).

North Plateau Groundwater Recovery System. In 1995, the north plateau groundwater recovery system (NPGRS) was installed to minimize the advance of the gross beta plume. The NPGRS is located near the leading edge of the western lobe of the plume where groundwater flows preferentially toward the edge of the plateau, seeps into a ditch, and flows as surface water toward monitoring location WNSWAMP. (See Northeast Swamp Drainage Monitoring in this chapter.) The NPGRS consists of three wells that extract contaminated groundwater, which is then treated by ion exchange to remove strontium-90. Treated wa-

ter is transferred to the lagoon system and is ultimately discharged to Erdman Brook.

The NPGRS operated throughout 2004, processing about 4.8 million gallons (18 million liters). The system has recovered and processed approximately 39 million gallons (147 million liters) since November 1995.

Permeable Treatment Wall. A pilot-scale permeable treatment wall (PTW) was constructed in 1999 in the eastern lobe of the north plateau plume to test this passive, in-situ remediation technology. The PTW is a trench that is backfilled with clinoptilolite, a medium selected for its ability to adsorb strontium-90 ions from groundwater. The PTW extends vertically downward through the sand and gravel unit to the top of the underlying Lavery till and is approximately 30 ft long by 10 ft wide (9 m long by 3 m wide).

Additional test borings and monitoring well installations were completed in the vicinity of the PTW during the fall of 2001 to obtain improved definition of hydrogeologic conditions. Monitoring and evaluation of water levels and radiological concentrations upgradient, within, and downgradient of the PTW continued during 2004. The evaluation concluded that complex hydrogeologic conditions and disturbances from the installation are influencing groundwater flow into and around the pilot PTW.

Northeast Swamp Drainage Monitoring. Routine surface water sampling during 2004 continued to monitor radioactivity levels in surface water at location WNSWAMP (Appendix C^{6a}). Gross beta and strontium-90 concentrations continued to fluctuate due to seasonal effects. Annualized average strontium-90 concentrations were relatively consistent during the first quarter of 2004, followed by steady increases for the remainder of the year, exceeding the DOE DCG by about August (Fig. 4-10). The main source of the elevated strontium-

90 is seepage of groundwater affected by the north plateau plume into a ditch upstream of WNSWAMP.

The annualized average concentration of strontium-90 in surface water at sampling location WNSWAMP (on the WVDP premises) remained elevated with respect to background. Even so, monitoring downstream at the first point of public access (WFFELBR) continued to show strontium-90 concentrations that were only slightly higher than those at background location WFBIGBR. (See also Northeast Swamp and North Swamp Drainage in Chapter 2, Environmental Radiological Program Information.)

North Plateau Groundwater Quality Early Warning Monitoring. Early-warning monitoring of water recovered by the NPGRS is performed because this water is ultimately discharged off-site via the New York State Pollutant Discharge Elimination System (SPDES) outfall 001. Quarterly monitoring results from well 502, located directly upgradient of the NPGRS, can be used to identify analytical concentrations in groundwater that may affect compliance with the SPDES-permitted effluent limits. Results of sampling for metals at well 502 can be found in Appendix E^{6a}.

Investigation of Chromium and Nickel in the Sand and Gravel Unit and Evaluation of Corrosion in Groundwater Monitoring Wells. A 1997 and 1998 study of the effect of modifying sampling equipment and methodology on concentrations of chromium and nickel in groundwater samples from the sand and gravel unit noted that such modifications produced decreases in chromium and nickel concentrations. This supported the hypothesis (which is documented in the technical literature) that elevated concentrations were not representative of actual groundwater conditions, but were caused by release of metals from subsurface corrosion of stainless steel well mate-

rials (WVNSCO and Dames & Moore, June 1998).

To ensure continued monitoring well integrity and collection of high-quality samples representative of actual groundwater conditions, wells are periodically inspected for corrosion. Approximately three-fourths of the stainless-steel wells monitoring the sand and gravel unit were internally inspected for corrosion during 2001. Wells containing corrosion were cleaned and then reinspected to verify that corrosion had been removed. Wells previously containing corrosion were inspected during late 2004. Cleaning and reinspection are planned for 2005.

Ten-Year Sampling Pump Inspections. Dedicated bladder pumps were installed in many WVDP monitoring wells in 1991. (See Groundwater Sampling Methodology [Appendix E⁶⁰].) Pumps in all actively sampled wells were removed and inspected during 2001 to evaluate pump conditions after ten years of use. All pumps were found to be in good, serviceable condition during the 2001 inspection and during routine quarterly sampling activities through 2004.




Figure 4-4. Average Yearly Gross Beta Concentrations at Locations Closer to the Source of the North Plateau Plume




Figure 4-5. Average Yearly Gross Beta Concentrations at Locations Closer to the Leading Edges of the North Plateau Plume




Figure 4-6. Average Yearly Gross Beta Concentrations at Locations Near Former Lagoon 1




Figure 4-7. Average Yearly Tritium Concentrations at Selected Locations in the Sand and Gravel Unit




Figure 4-8. Concentrations of 1,2-DCE-t, 1,1,1-TCA, and 1,1-DCA at Well 8612 in the Sand and Gravel Unit





Figure 4-9. Concentrations of Tributyl Phosphate at Selected Locations in the Sand and Gravel Unit



QUALITY ASSURANCE

Quality Assurance Program

The quality assurance (QA) program at the West Valley Demonstration Project (WVDP or Project) provides for and documents consistency, precision, and accuracy in collecting and analyzing environmental samples and in interpreting and reporting environmental monitoring data. West Valley Nuclear Services Co. (WVNSCO), by contract with the U.S. Department of Energy (DOE), implements the QA program at the WVDP. Sub-contractor laboratories providing analytical services for the environmental monitoring program are contractually required to maintain a QA program consistent with WVNSCO requirements.

The quality requirements of Rule 10 Code of Federal Regulations Part 830, Subpart A, "Quality Assurance Requirements," Section 830.122, "Quality Assurance Criteria," and DOE Order 414.1A, "Quality Assurance" (DOE, 1999), provide the QA program policies and requirements applicable to activities at the WVDP. The WVDP QA program serves as an implementation process for meeting the DOE Order 450.1 requirement to provide "a consistent system for collecting, assessing, and documenting environmental data of known and documented quality." The integrated QA program also incorporates the requirements from the consensus standard "Quality Assurance Program

Requirements for Nuclear Facilities" (American Society of Mechanical Engineers NQA-1, 1989). Controlled documents specific to the WVDP are used to implement the integrated QA program. General areas addressed by the QA program include the following.

Responsibility. Responsibilities for overseeing, managing, and conducting an activity must be clearly defined. Personnel who verify that an activity has been completed correctly must be independent of those who performed it. Managers of programs, projects, and tasks at the WVDP are responsible for ensuring that QA requirements applicable to activities under their cognizance are implemented.

Planning. Work activities must be planned beforehand, the plan followed, and activities documented. Purchases of any equipment or items must be planned, specified precisely, and verified for correctness upon receipt.

Training. Anyone performing an activity in support of the WVDP environmental monitoring program must be trained in the appropriate procedures and qualified accordingly before carrying out the activity.

Control of Design, Procedures, Items, and Documents. Any activity, equipment, or construction must be clearly described or defined and tested. Changes in the design must be tested and documented. Procedures must clearly state how activities will be conducted. New procedures must be developed each time an activity is added to the monitoring program. Procedures are reviewed periodically, updated when necessary, and are controlled so that only approved and current procedures are used.

Equipment or particular items affecting the quality of environmental data must be identified, inspected, calibrated, and tested before use. Calibration status must be clearly indicated. Items that do not conform to requirements must be identified as a nonconformity and segregated so as to prevent inadvertent use.

Corrective Action. Conditions adverse to quality must be promptly identified, a corrective action planned, responsibility assigned, and the problem remedied.

Documentation. Records of all activities must be kept to verify what was done and by whom. Records must be clearly traceable to an item or activity. Records such as field data sheets, chain-of-custody forms, requests for analysis, sample shipping documents, sample logs, data packages, training records, and weather measurements, in addition to other records in both paper and electronic form, are maintained as documentation for the environmental monitoring program.

Audits and Assessments. Audits and assessments must be conducted to verify compliance with all aspects of the QA program and to determine its effectiveness. The WVDP environmental monitoring program is subjected to annual audits by external agencies and to internal management and self-assessments.

Quality Control

More than 13,000 environmental samples were collected and analyzed in 2004 as part of the WVDP environmental monitoring program. Quality control (QC), an integral part of QA, is used to ensure that samples are collected and analyzed in a consistent and repeatable manner. QC methods are applied both in the field and in the laboratory.

Field QC. Procedures are defined for collecting each type of sample, such as surface water, groundwater, soil, and air. Trained Environmental Laboratory field personnel collect the samples. Field sampling locations are clearly marked to ensure that routine samples are collected in the same location each time. Collection equipment that remains in the field is routinely inspected, calibrated, and maintained, and automated sampling stations are kept locked to prevent tampering. Samples are collected into certified pre-cleaned containers of an appropriate material and capacity. Containers are labeled with information about the sample, such as date and time of collection, sample collection personnel, and special field conditions. Collection information is documented and kept as part of the sample record.

Chain-of-custody documentation is maintained so as to trace sample possession from time of collection through analysis. Samples brought in from the field are transferred under signature to the sample custodian in the laboratory, where the samples are stored in a lockup before analysis or shipping. Samples sent off site for analysis are accompanied by an additional chain-of-custody form. Subcontract laboratories are required by contract to maintain internal chain-of-custody records and to store the samples under secure conditions.

Special field QC samples are collected and analyzed to assess the sampling process. Duplicate

field samples are used to assess sample homogeneity and sampling precision. Field and trip blanks (laboratory-deionized water in sample containers) are used to detect contamination potentially introduced during sampling or shipping. Environmental background samples (samples of air, water, vegetation, meat, and milk taken from locations remote from the WVDP) are collected and analyzed to provide baseline information for comparison with on-site or near-site samples so that site influences can be evaluated.

Laboratory QC. In 2004, environmental monitoring samples were analyzed at several on-site and off-site laboratories. On-site analyses were conducted by the Environmental Laboratory ([ELAB], radiological indicator parameters, gamma spectroscopy, strontium-90 in water, and field pH and conductivity), the Wastewater Treatment Facility Laboratory (total residual chlorine, pH, and settleable solids), and the Analytical and Process Chemistry Laboratory ([A&PC], total dissolved solids).

Off-site analyses were performed by General Engineering Laboratories (GEL, in Charleston, South Carolina) for multimedia radiochemical parameters and low-level mercury; Severn Trent Laboratories (STL, in Buffalo, New York) for chemical analyses; Lionville Laboratory, Inc. (in Lionville, Pennsylvania) for chemical analysis of radiologically contaminated samples; Fruit Grower Laboratories (in Santa Paula, California) for analysis of biological contaminants in potable water; and Bechtel BWXT Idaho, LLC (at the Idaho National Engineering and Environmental Laboratory) for environmental thermoluminescent dosimeters. Subcontract laboratories are required to maintain all relevant certifications, participate in applicable crosscheck programs, and maintain a level of QC as defined in their contracts with WVNSCO.

Laboratory QC practices specific to each analytical method are described in approved references or procedures. QC practices include proper training of analysts, maintaining and calibrating measuring equipment and instrumentation, and routinely processing laboratory QC samples such as standards and spikes (to assess method accuracy), duplicates and replicates (to assess precision), and blanks (to assess the possibility of contamination). Standard reference materials (materials with known quantities or concentrations of constituents of interest) traceable to the National Institute of Standards and Technology are used to calibrate counting and test instruments and to monitor their performance.

Independent Comparisons and Crosschecks.

To allow for independent confirmation of environmental monitoring data, samples of air filters, water, milk, fish, vegetation, and sediments are split or separately collected and sent to the New York State Department of Health (NYSDOH) for measurement and independent reporting to the public. Locations at which co-located samples are taken are listed in Appendix B⁶⁰ of this report.

Crosscheck samples (performance evaluation samples) contain a quantity or concentration of a constituent of interest known to the agency conducting the crosscheck, but unknown to the participating laboratory. Crosscheck programs provide an additional means of testing accuracy of environmental measurements. Subcontract laboratories are required to perform satisfactorily on crosschecks, with satisfactory performance defined as having at least 80% of reported results falling within control limits. Crosscheck results that fall outside of control limits are addressed by formal corrective actions to determine any conditions that could adversely affect sample data and to ensure that actual sample results are reliable.

The WVDP participates in formal crosscheck programs for both radiological and nonradiological analyses.

Radiological Crosschecks. Organizations performing radiological analyses as part of effluent or environmental monitoring are encouraged by the DOE to participate in formal crosscheck programs to test the quality of environmental measurements being reported to the DOE by its contractors. Crosscheck samples for radiological constituents are analyzed on site by the ELAB and off site by GEL.

In 2004, the WVDP participated in the DOE Environmental Measurements Laboratory Quality Assessment Program and the DOE Radiological Environmental Sciences Laboratory Mixed Analyte Performance Evaluation Program (MAPEP). Results are listed in Appendix J⁶⁰. A total of 101 radiological crosscheck analyses were performed by or for the WVDP. Of these results, a total of 97 (96%) were within acceptance limits.

Nonradiological Crosschecks. As a New York State Pollutant Discharge Elimination System (SPDES) Permittee, the WVDP is required to participate in the U.S. Environmental Protection Agency Discharge Monitoring Report - Quality Assurance performance evaluation studies for the National Pollutant Discharge Elimination System. Samples from this program are analyzed both on site and by subcontract laboratories. To achieve and maintain certification to analyze environmental samples from the state of New York, subcontract analytical laboratories are contractually required to demonstrate evidence of satisfactory performance on samples provided by the NYSDOH Environmental Laboratory Approval Program. In addition, subcontract laboratories performing nonradiological analyses of samples that contain radiological contamination participate in the

DOE MAPEP program. This mixed analyte program provides performance evaluation samples for both radiological and nonradiological constituents. In 2004, nonradiological crosschecks were analyzed by the WVDP Wastewater Treatment Facility Laboratory and by STL. Results are summarized in Appendix J⁶⁰. A total of 80 nonradiological crosscheck analyses were performed by or for the WVDP. Of these results, a total of 78 (97.5%) were within acceptance limits.

Data Management

The Environmental Laboratory Information Management System (LIMS) is a database system used at the WVDP for establishing sample identification number, maintaining the sample data log, tracking samples, managing field and analytical data, and recording status and results of data validation. The LIMS is used as a controlled-source database for generating reports and statistical evaluations of data sets to support environmental surveillance activities. Subcontract laboratories are requested to provide data in electronic format for direct entry into the LIMS by WVDP personnel.

All software packages used to generate data are verified and validated before use. All analytical data produced in the ELAB at the bench level are reviewed and signed off by a qualified person other than the one who performed the analysis. A similar in-house review is contractually required from subcontractor laboratories.

Data Verification and Validation

Data validation is the process by which analytical data from both on-site and off-site laboratories are reviewed to verify proper documentation of sample processing and data reporting, and to determine the quality and usability of the data. A graded ap-

proach is applied that, based upon data quality objectives, dictates the rigor of review of the documentation associated with sample collection and/or sample analysis. In the WVDP environmental program, each data point is validated per approved standard procedures before it is assigned approval status and made ready for data assessment.

Data Assessment and Reporting

Validated analytical data, field information, and historical project data are integrated and evaluated to determine whether the constituents of interest are actually present and, if so, at what concentrations. Data problems identified at this level are investigated and appropriately resolved.

Data from the environmental monitoring program are then evaluated to assess the effect, if any, of the site operations and activities on the environment and the public. Data from each sampling location are compared with historical results from the same location, with comparable background measurements, and (if applicable) with regulatory limits or guidance standards. Standard statistical methods are used to evaluate the data.

Before each technical report is issued, the final document is comprehensively reviewed by one or more persons who are knowledgeable in the technical aspects of the work.

Audits, Appraisals, and Self-Assessments

In 2004, the New York State Department of Environmental Conservation performed an inspection of WVDP's wastewater treatment facilities and the SPDES discharge monitoring program. The DOE conducted an on-site audit during which WVDP sampling practices were inspected. No findings were reported.

Two routine self-assessments of the environmental monitoring program were conducted in 2004. Topics examined were worker safety, compliance with Conduct of Operations requirements during field sampling activities, field safety, and reporting requirements associated with WVDP Animal Control Operations. WVDP self-assessments in 2004 also examined the air sampling program, general health and safety, general software QA, and the chemical storage facility at the A&PC Laboratory. Although actions were recommended to improve some program aspects, nothing was found that would compromise the quality of the data in this report or the environmental monitoring program in general.

Lessons Learned

Lessons learned data from audits, appraisals, and self-assessments are shared internally and externally through the WVDP lessons learned program. The WVDP maintains this system to promote the recurrence of desirable events and to minimize the recurrence of undesirable events.

Conclusion

The QA elements described in this chapter ensure that environmental monitoring data are consistent, precise, accurate, and complete. The multiple levels of scrutiny built into generating, verifying, validating, evaluating, and reporting data from the environmental monitoring program ensure that reliable data are reported. The effectiveness of the environmental monitoring program is evidenced by continuing favorable QA assessments.

This page intentionally left blank

REFERENCES AND BIBLIOGRAPHY

(For a bibliographical listing that includes basis documents not specifically cited in the text, see the WVDP Annual Site Environmental Report for 2003.)

- American National Standards Institute/American Society for Quality Control.** 1994. *Specifications and Guidelines for Quality Systems for Environmental Data Collection and Environmental Technology Programs.* ANSI/ASQC E4-1994.
- American National Standards Institute, Inc.** August 20, 1975. *American National Standard: Performance Testing, and Procedural Specifications for Thermoluminescent Dosimetry (Environmental Applications).* ANSI N545-1975.
- American Society of Mechanical Engineers.** 1989. *Quality Assurance Program Requirements for Nuclear Facilities.* ASME-NQA-1. New York: The American Society of Mechanical Engineers.
- Brookhaven National Laboratory.** January 2000. *Nuclear Wallet Cards.* National Nuclear Data Center. Upton, New York.
- Citizen Task Force.** July 29, 1998. *West Valley Citizen Task Force Final Report.*
- Executive Order 11990.** May 25, 1977. *Protection of Wetlands.* 42 FR 26961.
- Executive Order 13101.** September 16, 1998. *Greening the Government Through Waste Prevention, Recycling, and Federal Acquisition.* 63 FR 49643.
- Executive Order 13148.** April 26, 2000. *Greening the Government Through Leadership in Environmental Management.* 65 FR 24595. (This order revoked Executive Order 12856, *Federal Compliance with Right-To-Know Laws and Pollution Prevention Requirements.*)
- International Atomic Energy Agency (IAEA).** 1992. *Effects of Ionizing Radiation on Plants and Animals at Levels Implied by Current Radiation Protection Standards.* Technical Report Series No. 332, IAEA, Vienna, Austria.

References and Bibliography

- International Commission on Radiological Protection.** 1977. *Recommendations of the International Commission on Radiological Protection*. ICRP Publication 26. Oxford: Pergamon Press.
- _____. 1979. *Recommendations of the International Commission on Radiological Protection – Limits for Intakes of Radionuclides by Workers*. ICRP Publication 30. Oxford: Pergamon Press.
- International Organization for Standardization.** 1996. *Environmental Management Systems*. ISO 14001:1996.
- Long, E.R., and L.G. Morgan.** 1990. *The Potential for Biological Effects of Sediment-Sorbed Contaminants Tested in the National States and Trends Program*. National Oceanic Atmospheric Administration (NOAA) Technical Memorandum No. 5, OMA52, NOAA National Ocean Service, Seattle, Washington.
- National Council on Radiation Protection and Measurements.** 1987. *Ionizing Radiation Exposure of the Population of the United States*. NCRP-93. Bethesda, Maryland.
- National Research Council.** 1990. *Health Effects of Exposure to Low Levels of Ionizing Radiation*. Biological Effects of Ionizing Radiation (BEIR) V. Washington: National Academy Press.
- New York State Department of Environmental Conservation.** nd. Title 6, New York Codes, Rules, and Regulations (6 NYCRR). *Environmental Conservation Rules and Regulations*.
- _____. January 24, 1994. *Determination of Soil Cleanup Objectives and Cleanup Levels*. Technical and Administrative Guidance Memorandum (TAGM) #4046.
- _____. 1995. *Appendix 33 - Groundwater Monitoring List*. Title 6 NYCRR Subpart 373-2.
- _____. September 3, 1996. *Federal Facility Compliance Act: Order on Consent*.
- _____. June 1998. *Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations*. Technical and Operational Guidance Series (TOGS) 1.1.1.
- _____. January 25, 1999. *Technical Guidance for Screening Contaminated Sediments*.
- _____. March 19, 1999. *Stipulation of Agreement Pursuant to Section 17-0303 of the Environmental Conservation Law and Section 176 of the Navigation Law*.
- _____. February 1, 2004. *State Pollutant Discharge Elimination System (SPDES) Discharge Permit NY0000973*.

- _____. January 2003. Draft Technical and Operational Guidance Series (TOGS) #5.1.9. *In-Water and Riparian Management of Sediment and Dredge Material*.
- New York State Department of Health.** nd. *Environmental Laboratory Approval Program (ELAP) Certification Manual*.
- _____. nd. Title 10, New York Code, Rules, and Regulations (10 NYCRR). *Sources of Water Supply. Part 5 (Drinking Water Supplies) and Part 170 (Sources of Water Supply)*.
- Pacific Northwest Laboratory (PNL).** November 1988. Napier, B.A., Strenge, D.L., Pelequin, R.A., and Ramsdell, J.V. *GENII - The Hanford Environmental Radiation Dosimetry Software System*. Version 1.485, PNL-6584.
- Parks B.L.** March 1992. *User's Guide for CAP88-PC*. Version 1.0. Las Vegas, NV: U.S. Environmental Protection Agency Office of Radiation Programs. 402-B-92-001.
- _____. June 1997. *CAP88-PC Version 2.0 User's Guide*. Germantown, Maryland. U.S. Department of Energy.
- Persaud, D., Jaagumagi, R., and A. Hayton.** 1992. *Guidelines for the Protection and Management of Aquatic Sediment Quality in Ontario*. Ontario Ministry of the Environment, Queen's Printer for Ontario.
- Rickard, L.V.** 1975. *Correlation of the Silurian and Devonian Rocks in New York State*. New York State Museum and Science Service Map and Chart Series No. 24.
- Simpson, D.B., and B.L. McGill.** 1980. *LADTAP II: A Computer Program for Calculating Radiation Exposure to Man from Routine Release of Nuclear Reactor Liquid Effluents*. Technical Data Management Center. ORNL/NUREG/TDMC-1.
- Standish, P.N.** 1985. *Closure of the Construction Landfill Site*. Letter (WD:85:0434) to W.H. Hannum, Department of Energy, West Valley Project Office.
- U.S. Congress.** 1954. *Atomic Energy Act of 1954*. 42 United States Code (USC) §2011 et seq.
- _____. 1955. *Clean Air Act*. 42 USC §7401 et seq.
- _____. 1966. *National Historic Preservation Act of 1966*. 16 USC §470 et seq.
- _____. 1969. *National Environmental Policy Act of 1969*. 42 USC §4321 et seq.
- _____. 1973. *Endangered Species Act of 1973*. 16 USC §1531 et seq.

References and Bibliography

- _____. 1974. *Safe Drinking Water Act*. 42 USC §300f et seq.
- _____. October 23, 1976. *Resource Conservation and Recovery Act of 1976*. Public Law 94-580, 90 Stat. 2795, 42 USC §6901 et seq.
- _____. November 1976. *Migratory Bird Treaty Act*. 16 USC §703 et seq.
- _____. 1977. *Federal Water Pollution Control Act*. 33 USC §1251 et seq. (Also known as the Clean Water Act)
- _____. October 1, 1980. *An Act to Authorize the Department of Energy to Carry Out a High-Level Liquid Nuclear Waste Management Demonstration Project at the Western New York Service Center in West Valley, New York*. Public Law 96-368 [S. 2443]. Congressional Record, Vol. 126. (Also known as the WVDP Act)
- _____. December 11, 1980. *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*. Public Law 96-510, 42 USC §9601 et seq.
- _____. 1986a. *Toxic Substances Control Act*. 15 USC §2601 et seq.
- _____. 1986b. *Emergency Planning and Community Right-to-Know Act of 1986*. 42 USC §11001 et seq.
- _____. October 17, 1986. *Superfund Amendments and Reauthorization Act (SARA) of 1986*. Public Law 99-499, 100 Stat. 1613, Title 10.
- U.S. Department of Commerce.** U.S. Census Bureau. Census 2000.
- U.S. Department of Energy.** nd. *Quality Assurance Criteria*. 10 CFR 830.122.
- _____. July 1981. *A Guide for Environmental Radiological Surveillance at U.S. Department of Energy Installations*. DOE/EP-0023. Washington, D.C.
- _____. July 1983. *A Guide for Effluent Radiological Measurements at DOE Installations*. DOE/EP-0096. Washington, D.C.
- _____. February 8, 1990. *Radiation Protection of the Public and the Environment*. DOE Order 5400.5, including Change 2 (January 7, 1993). Washington, D.C.
- _____. January 1991. *Environmental Regulatory Guide for Radiological Effluent Monitoring and Environmental Surveillance*. DOE/EH-0173T. Washington, D.C.

- _____. January 1996. *Draft Environmental Impact Statement for Completion of the West Valley Demonstration Project and Closure or Long-Term Management of Facilities at the Western New York Nuclear Services Center*. DOE/EIS-0226-D.
- _____. May 1997. *Final Waste Management Programmatic Environmental Impact Statement for Managing Treatment, Storage, and Disposal of Radioactive and Hazardous Waste*. DOE/EIS-0200-F.
- _____. March 27, 1998. *Worker Protection Management for DOE Federal and Contractor Employees*. DOE Order 440.1A. Washington, D.C.
- _____. July 9, 1999. *Radioactive Waste Management*. DOE Order 435.1, including Change 1 (August 28, 2001). Washington, D.C.
- _____. September 29, 1999. *Quality Assurance*. DOE Order 414.1A, including Change 1 (July 12, 2001). Washington D.C. (DOE Order 414.1A was canceled by DOE Order 414.1B, April 29, 2004.)
- _____. February 25, 2000. *Record of Decision for the DOE's Waste Management Program: Treatment and Disposal of Low-Level Waste and Mixed Low-Level Waste; Amendment of the Record of Decision for the Nevada Test Site*. 65 FR 10061.
- _____. October 26, 2000. *National Environmental Policy Act Compliance Program*. DOE Order 451.1B, including Change 1 (September 28, 2001). Washington, D.C.
- _____. March 26, 2001. *Revised Strategy for the Environmental Impact Statement for Completion of the West Valley Demonstration Project and Closure or Long-Term Management of Facilities at the Western New York Nuclear Service Center and Solicitation of Scoping Comments*. 66 FR 16447.
- _____. November 6, 2001. *Advance Notice of Intent to Prepare an Environmental Impact Statement to Evaluate Decommissioning and/or Long-Term Stewardship at the West Valley Demonstration Project and Western New York Nuclear Service Center*. 66 FR 56090.
- _____. July 2002. *DOE Standard: A Graded Approach for Evaluating Radiation Doses to Aquatic and Terrestrial Biota*. DOE-STD-1153-2002. Washington, D.C.
- _____. September 23, 2002. *Radioactive Material Transportation Practices Manual*. DOE M 460.2-1.
- _____. January 2003. *Estimating Radiation Risk from Total Effective Dose Equivalent (TEDE)*. International Steering Committee on Radiation Standards (ISCORS) Technical Report No. 1. DOE/EH-412/0015/0502, Rev. 1.

References and Bibliography

- _____. January 15, 2003. *Environmental Protection Program*. DOE Order 450.1, including Change 1 (January 24, 2005). Washington, D.C. (Canceled DOE Order 5400.1, *General Environmental Protection Program*, November 9, 1988, including Change 1 [June 29, 1990].)
- _____. March 13, 2003. *Notice of Intent to Prepare an Environmental Impact Statement for Decommissioning and/or Long-Term Stewardship at the West Valley Demonstration Project and Western New York Nuclear Services Center*. 68 FR 12044.
- _____. May 16, 2003. *Notice of Availability of the West Valley Demonstration Project Draft Waste Management Environmental Impact Statement*. 68 FR 26587.
- _____. August 19, 2003. *Environment, Safety, and Health Reporting*. DOE Order 231.1A, including Change 1 (June 3, 2004). Washington, D.C.
- _____. December 2003. *West Valley Demonstration Project Waste Management Environmental Impact Statement*. DOE/EIS-0337F.
- _____. January 2004. Users Guide: *RESRAD-BIOTA: A Tool for Implementing a Graded Approach to Biota Dose Evaluation*. Version 1. DOE/EH-0676. (ISCORS Technical Report 2004-2).
- _____. March 19, 2004. *Environment, Safety, and Health Reporting Manual*. DOE M 231.1-1A.
- _____. April 29, 2004. *Quality Assurance*. DOE Order 414.1B. Washington, D.C.
- U.S. Department of Energy and New York State Energy Research and Development Authority.** 1981. *Cooperative Agreement between United States Department of Energy and New York State Energy Research and Development Authority on the Western New York Nuclear Service Center at West Valley, New York*, effective October 1, 1980, as amended September 18.
- U.S. Environmental Protection Agency.** nd. 40 Code of Federal Regulations, *Protection of the Environment*, Chapter 1, *Environmental Protection Agency*.
- _____. March 1983. *Mercury, Method 245.1 (Manual Cold Vapor Technique)*. Methods for Chemical Analysis of Water and Wastes. Environmental Monitoring and Support Laboratory. Cincinnati, Ohio.
- _____. 1984a. *Drinking Water Guidelines*. 40 CFR 141, National Secondary Drinking Water Regulations, Subpart B, Maximum Contaminant Levels.
- _____. 1984b. *Drinking Water Guidelines*. 40 CFR 143, National Secondary Drinking Water Regulations, Section 143.3, Secondary Maximum Contaminant Levels.

- _____. December 15, 1989. *National Emission Standards for Hazardous Air Pollutants: Standards for Radionuclides*. 40 CFR 61, including update of September 9, 2002. Washington, D.C.: U.S. Government Printing Office.
- _____. 1992. *Region II Administrative Order on Consent. Docket No. II RCRA 3008(h) - 92-0202. In the Matter of: Western New York Nuclear Service Center*.
- _____. October 16, 1996. *Code of Environmental Management Principles*. 61 FR 54062.
- _____. August 2002. Method 1631, Revision E: *Mercury in Water by Oxidation, Purge and Trap, and Cold Vapor Atomic Fluorescence Spectrometry*. EPA-821-R-02-019.
- U.S. Nuclear Regulatory Commission**. October 1977. *Regulatory Guide 1.109: Calculation of Annual Doses to Man from Routine Releases of Reactor Effluents for the Purpose of Evaluating Compliance with 10 CFR Part 50, Appendix I*.
- _____. July 1997. *Radiological Criteria for License Termination*. 10 CFR Part 20, Appendix E.
- _____. February 1, 2002. *Decommissioning Criteria for the West Valley Demonstration Project (M-32) at the West Valley Site; Final Policy Statement*. 67 FR 5003.
- URS Group, Inc.** April 8, 2002. *Land Use Survey*. Rev. 0. AR #2002-171.
- West Valley Nuclear Services Co., Inc.** May 1, 1995. *Subsurface Probing Investigation on the North Plateau at the West Valley Demonstration Project*. Rev. 0. WVDP-220.
- _____. March 1996. *Environmental Information Document, Volume III: Hydrology, Part 4*. WVDP-EIS-009.
- _____. June 11, 1999. *1998 Geoprobe[®] Investigation in the Core Area of the North Plateau Groundwater Plume*. Rev. 0. WVDP-346.
- _____. October 26, 1999. *Asbestos Management Plan*. Rev. 5. WVDP-072.
- _____. March 21, 2001 and December 28, 2004. *PCB and PCB-Contaminated Material Management Plan*. Rev. 6 and Rev. 7. WVDP-080.
- _____. April 15, 2003. *Manual for Radiological Assessment of Environmental Releases at the WVDP*. Rev. 4. WVDP-065.
- _____. July 10, 2003 and April 22, 2004. *WVDP Environmental Management System*. Rev. 15 and Rev. 16. WV-980.

References and Bibliography

- _____. November 25, 2003 and October 27, 2004. *WVDP Safety Management System (SMS) Description*. Rev. 9 and Rev. 10. WVDP-310.
- _____. December 2, 2003. *Environmental Monitoring Program Plan*. Rev. 12. WVDP-098.
- _____. December 2, 2003 and November 3, 2004. *WVDP Groundwater Protection Management Program Plan*. Rev. 5 and Rev. 6. WVDP-091.
- _____. December 3, 2003 and November 3, 2004. *Groundwater Monitoring Plan*. Rev. 7 and Rev. 8. WVDP-239.
- _____. December 23, 2003 and December 30, 2004. *Waste Minimization/Pollution Prevention Awareness Plan*. Rev. 7 and Rev. 8. WVDP-087.
- _____. July 1, 2004. *Annual Status Report for the Hazardous Waste Reduction Program*.
- _____. February 28, 2005. *New York State Department of Environmental Conservation Hazardous Waste Report for 2004*.
- _____. February 10, 2005. *Site Treatment Plan: Fiscal Year 2004 Update*. Rev. 7. WVDP-299.
- West Valley Nuclear Services Co., Inc. and Dames & Moore.** June 1997. *West Valley Demonstration Project Site Environmental Report, Calendar Year 1996*.
- _____. July 1997. *Resource Conservation and Recovery Act Facility Investigation Report, Vol.1: Introduction and General Site Overview*. WVDP-RFI-017.
- _____. June 1998. *Final Report: Evaluation of the Pilot Program to Investigate Chromium and Nickel Concentrations in Groundwater in the Sand and Gravel Unit*.
- West Valley Nuclear Services Co. and URS Group, Inc.** January 2001. *Results of Corrosion Evaluation in Selected Stainless Steel Monitoring Wells on the North Plateau and Recommendations for Long-Term Management*.
- _____. August 2003. *West Valley Demonstration Project Annual Site Environmental Report, Calendar Year 2002*.

GLOSSARY

A

accuracy. The degree of agreement between a measurement and its true value. The accuracy of a data set is assessed by evaluating results from standards or sample spikes containing known quantities of an analyte.

action plan. An action plan addresses assessment findings and root causes that have been identified in an audit or an assessment report. It is intended to define specific actions that the responsible group will undertake to remedy deficiencies. The plan includes a timetable and funding requirements for implementation of the planned activities.

alluvial fan. A cone-shaped deposit of alluvium made by a stream where it runs out onto a level plain.

alluvium. Sedimentary material deposited by flowing water, such as a river.

aquifer. A water-bearing unit of permeable rock or soil that will yield water in usable quantities to wells. Confined aquifers are bounded above and below by less permeable layers. Groundwater in a confined aquifer is under a pressure greater than the atmospheric pressure. Unconfined aquifers are bounded below by less permeable material, but are not bounded above. The pressure on the groundwater at the surface of an unconfined aquifer is equal to that of the atmosphere.

as low as reasonably achievable (ALARA). An approach to radiation protection that advocates controlling or managing exposures (both individual and collective) to the work force and the general public and releases of radioactive material to the environment as low as social, technical, economic, practical, and public policy considerations permit. As used in DOE Order 5400.5, ALARA is not a dose limit but, rather, a process that has as its objective the attainment of dose levels as far below the applicable limits of the Order as practicable.

B

background radiation. Natural and man-made radiation such as cosmic radiation and radiation from naturally radioactive elements and from commercial sources and medical procedures.

becquerel (Bq). A unit of radioactivity equal to one nuclear transformation per second.

British thermal unit (BTU, also MBTU, MMBTU). A standard unit of measurement used to denote both the amount of heat energy in fuels and the ability of appliances and air-conditioning systems to produce heating or cooling. A BTU is the amount of heat required to increase the temperature of a pint of water (which weighs exactly 16 ounces) by one degree Fahrenheit. One million BTUs may be expressed as one MBTU or one MMBTU (to represent a thousand thousand BTUs), which is occasionally used as a standard unit of measurement for natural gas and provides a convenient basis for comparing the energy content of various grades of natural gas and other fuels. One cubic foot of natural gas produces approximately 1,000 BTUs, so 1,000 cubic feet of gas is comparable to 1 MBTU.

C

categorical exclusion (CX). A proposed action that normally does not require an environmental assessment or an environmental impact statement and that the Department of Energy has determined does not individually or cumulatively have a significant effect on the human environment. See 10 CFR 1021.410.

Class A, B, and C low-level waste. Waste classifications from the Nuclear Regulatory Commission's 10 CFR Part 61 rule. Maximum concentration limits are set for specific isotopes. Class A waste disposal is minimally restricted with respect to the form of the waste. Class B waste must meet more rigorous requirements to ensure physical stability after disposal. Higher concentration limits are set for the same isotopes in Class C waste, which also must meet physical stability requirements. Moreover, special measures must be taken at the disposal facility to protect against inadvertent intrusion.

compliance findings. Conditions that may not satisfy applicable environmental or safety and health regulations, DOE Orders and memoranda, enforcement actions, agreements with regulatory agencies, or permit conditions.

confidence coefficient or factor. The chance or probability, usually expressed as a percentage, that a confidence interval includes some defined parameter of a population. The confidence coefficients usually associated with confidence intervals are 90%, 95%, and 99%.

confidence interval. The range of values within which some parameter may be expected to lie with a stated degree of confidence. For example, a value of 10 with an uncertainty of 5 calculated at the 95% confidence level (10 ± 5) indicates there is a 95% probability that the true value of the population parameter lies between 5 and 15.

consistency. The condition of showing steady conformity to practices. In the environmental monitoring program, approved procedures are in place so that data collection activities are carried out in a consistent manner to minimize variability.

cosmic radiation. High-energy subatomic particles from outer space that bombard the earth's atmosphere. Cosmic radiation is part of natural background radiation.

counting error. The variability caused by the inherent random nature of radioactive disintegration and by the detection process.

curie (Ci). A unit of radioactivity equal to 37 billion (3.7×10^{10}) nuclear transformations per second.

D

data set. A group of data (e.g., factual information such as measurements or statistics) used as a basis for reasoning, discussion, or calculation.

decay (radioactive). Disintegration of the nucleus of an unstable nuclide by spontaneous emission of charged particles and/or photons or by spontaneous fission.

derived concentration guide (DCG). The concentration of a radionuclide in air and water that, under conditions of continuous exposure for one year by one exposure mode (i.e., ingestion of water, submersion in air, or inhalation), would result in an effective dose equivalent of 100 mrem (1 mSv). See Table K-1⁶⁰ in Appendix K⁶⁰.

detection limit or level (DL). This term may also be expressed as "method detection limit" (MDL). The smallest amount of a substance that can be distinguished in a sample by a given measurement procedure at a given confidence level. (See *lower limit of detection*.)

dispersion (groundwater). The process whereby solutes are spread or mixed as they are transported by groundwater as it moves through the subsurface.

dosimeter. A portable device for measuring the total accumulated exposure to ionizing radiation.

downgradient. The direction of water flow from a reference point to a selected point of interest at a lower elevation than the reference point. (See *gradient*.)

E

effective dose. (See *effective dose equivalent* under *radiation dose*.)

effluent. Any treated or untreated air emission or liquid discharge to the environment, including storm water runoff.

effluent monitoring. Sampling or measuring specific liquid or gaseous effluent streams for the presence of pollutants.

enhanced work planning. A process used to evaluate and improve the program by which work is identified, planned, approved, controlled, and executed. The key elements are line management ownership, a graded approach to work management based on risk and complexity, worker involvement beginning at the earliest phases of work management, organizationally diverse teams, and organized, institution-wide communication.

environmental assessment (EA). An evaluation that provides sufficient evidence and analysis for determining whether an environmental impact statement or a finding of no significant impact is required. Detailed information found in 40 CFR 1508.9.

environmental impact statement (EIS). A detailed statement that includes the environmental impact of the proposed action, any adverse environmental effects that cannot be avoided should the proposal be implemented, and alternatives to the proposed action. Detailed information found in Section 102 (2) (C) of the National Environmental Policy Act.

environmental management system (EMS). The systematic application of business management practices to environmental issues, including defining the organizational structure, planning for activities, identifying responsibilities, and defining practices, procedures, processes, and resources.

environmental monitoring. The collection and analysis of samples or the direct measurement of environmental media. Environmental monitoring consists of two major activities: effluent monitoring and environmental surveillance.

environmental surveillance. The collection and analysis of samples or the direct measurement of air, water, soil, foodstuff, and biota in order to determine compliance with applicable standards and permit requirements.

erg. One-billionth (1E-09) of the energy released by a 100-watt bulb in one second. One dyne-cm.

evapotranspiration. The combined total precipitation returned to the air through direct evaporation and by transpiration of vegetation.

exposure. The subjection of a target (usually living tissue) to radiation.

F

fallout. The settling to earth of radioactive materials mixed into the earth's atmosphere.

finding. A Department of Energy compliance term. A finding is a statement of fact concerning a condition in the Environmental, Safety, and Health program that was investigated during an appraisal. Findings include best management practice findings, compliance findings, and noteworthy practices. A finding may be a simple statement of proficiency or a description of deficiency (i.e., a variance from procedures or criteria). (See also *self-assessment*.)

fission. The act or process of splitting into parts. A nuclear reaction in which an atomic nucleus splits into fragments (i.e., fission products, usually fragments of comparable mass) with the evolution of approximately 100 million to several hundred million electron volts of energy.

G

gamma isotopic (also *gamma scan*). An analytical method by which the quantity of several gamma ray-emitting radioactive isotopes may be determined simultaneously. Typical nuclear fuel cycle isotopes determined by this method include, but are not limited to, cobalt-60, zirconium-95, ruthenium-106, silver-110m, antimony-125, cesium-134, cesium-137, and europium-154. Naturally-occurring isotopes for which samples also often are analyzed are beryllium-7, potassium-40, radium-224, and radium-226.

gradient. Change in value of one variable with respect to another variable, such as a vertical change over a horizontal distance.

groundwater. Subsurface water in the pore spaces and fractures of soil and bedrock units.

H

half-life. The time in which half the atoms of a radionuclide disintegrate into another nuclear form. The half-life may vary from a fraction of a second to thousands of years.

hazardous waste. A waste or combination of wastes that because of quantity, concentration, or physical, chemical, or infectious characteristics may: a) cause or significantly contribute to an increase in mortality or an increase in serious irreversible or incapacitating reversible illness; or (b) pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported, disposed of, or otherwise managed.

high-level waste (HLW). The highly radioactive waste material that results from the reprocessing of spent nuclear fuel, including liquid waste produced directly in reprocessing and any solid waste derived from the liquid, that contains a combination of transuranic waste and fission products in concentrations sufficient to require permanent isolation. (See also *transuranic waste*.)

hydraulic conductivity. The ratio of flow velocity to driving force for viscous flow under saturated conditions of a specified liquid in a porous medium; the ratio describing the rate at which water can move through a permeable medium.

I

integrated safety management system (ISMS). The ISMS describes the programs, policies, and procedures used by WVNSCO and the DOE to ensure that WVNSCO establishes a safe workplace for the employees, the public, and the environment. The guiding principles of ISMS are line management responsibility for safety; clear roles and responsibilities; competence commensurate with responsibilities; balanced priorities; identification of safety standards and requirements; hazard controls; and operations authorization.

interim status. The status of any currently existing facility that becomes subject to the requirement to have a RCRA permit because of a new statutory or regulatory amendment to RCRA.

interstitial. The (annular) space between the inner and outer tank walls in a double-walled storage tank.

ion. An atom or group of atoms with an electric charge.

ion exchange. The reversible exchange of ions contained in solution with other ions that are part of the ion-exchange material.

isotope. Different forms of the same chemical element that are distinguished by having the same number of protons but a different number of neutrons in the nucleus. An element can have many isotopes. For example, the three isotopes of hydrogen are protium, deuterium, and tritium, with one, two, and three neutrons in the nucleus, respectively.

K

kame delta. A conical hill or short irregular ridge of gravel or sand deposited in contact with glacier ice.

L

lacustrine sediments. A sedimentary deposit consisting of material pertaining to, produced by, or formed in a lake or lakes.

land disposal restrictions (LDR). Regulations promulgated by the U.S. EPA (and by NYSDEC in New York State) governing the land disposal of hazardous wastes. The wastes must be treated using the best demonstrated available technology or must meet certain treatment standards before being disposed.

lower limit of detection (LLD). The lowest limit of a given parameter that an instrument is capable of detecting. A measurement of analytical sensitivity.

low-level waste (LLW). Radioactive waste not classified as high-level waste, transuranic waste, spent fuel, or uranium mill tailings. (See *Class A, B, and C low-level waste.*)

M

maximally exposed individual (MEI). On-site (occupational) or off-site (non-occupational) person that receives the highest dose from a release scenario.

maximally exposed off-site individual (MEOSI). Member of the general public receiving the highest dose from the effluent release.

mean. The average value of a series of measurements.

metric ton. (See *ton, metric.*)

millirem (mrem). A unit of radiation dose equivalent that is equal to one one-thousandth of a rem. An individual member of the public can receive up to 500 mrem per year according to DOE standards. This limit does not include radiation received for medical treatment or the roughly 360 mrem, on average, that people receive annually from background radiation.

minimum detectable concentration (MDC) or method detection limit (MDL). Depending on the sample medium, the smallest amount or concentration of a radioactive or nonradioactive analyte that can be reliably detected using a specific analytical method. Calculations of the minimum detectable concentrations are based on the lower limit of detection.

mixed waste (MW). A waste that is both radioactive and hazardous.

N

n-Dodecane/tributyl phosphate. An organic solution composed of 30% tributyl phosphate (TBP) dissolved in n-dodecane used to first separate the uranium and plutonium from the fission products in the dissolved fuel and then to separate the uranium from the plutonium.

neutron. An electrically neutral subatomic particle in the baryon family with a mass 1,839 times that of an electron, stable when bound in an atomic nucleus, and having a mean lifetime of approximately 16.6 minutes as a free particle.

notice of violation (NOV). A letter of notice from a regional water engineer in response to an instance of significant noncompliance with a SPDES permit. Generally, an official notification from a regulatory agency of noncompliance with permit requirements.

nucleus. The positively-charged central region of an atom, made up of protons and neutrons and containing almost all of the mass of the atom.

O

outfall. The discharge end of a drain or pipe that carries wastewater or other effluents into a ditch, pond, or river.

P

parameter. Any of a set of physical properties whose values determine the characteristics or behavior of something (e.g., temperature, pressure, density of air). In relation to environmental monitoring, a monitoring parameter is a constituent of interest. Statistically, the term “parameter” is a calculated quantity, such as a mean or variance, that describes a statistical population.

particulates. Solid particles and liquid droplets small enough to become airborne.

person-rem. The sum of the individual radiation dose equivalents received by members of a certain group or population. It may be calculated by multiplying the average dose per person by the number of persons exposed. For example, a thousand people each exposed to one millirem would have a collective dose of one person-rem.

plume. The distribution of a pollutant in air or water after being released from a source.

precision. The degree of reproducibility of a measurement under a given set of conditions. Precision in a data set is assessed by evaluating results from duplicate field or analytical samples.

proglacial lake. A lake occupying a basin in front of a glacier, generally in direct contact with the ice.

proton. A stable, positively-charged subatomic particle in the baryon family with a mass 1,836 times that of an electron.

pseudo-monitoring point. A theoretical monitoring location rather than an actual physical location; a calculation based on analytical test results of samples obtained from other associated, tributary, monitored locations. (Point 116 at the WVDP is classified as a “pseudo” monitoring point because samples are not physically collected at that location. Rather, using analytical results from samples collected from “real” upstream outfall locations, compliance with the total dissolved solids limit in the WVDP’s SPDES permit is calculated for this theoretical point.)

Q

quality factor (QF). The extent of tissue damage caused by different types of radiation of the same energy. The greater the damage, the higher the quality factor. More specifically, the factor by which absorbed doses are multiplied to obtain a quantity that indicates the degree of biological damage produced by ionizing radiation. See *radiation dose*.) The factor is dependent upon radiation type (alpha, beta, gamma, or x-ray) and exposure (internal or external).

R

rad. Radiation absorbed dose. One hundred ergs of energy absorbed per gram.

radiation. The process of emitting energy in the form of rays or particles that are thrown off by disintegrating atoms. The rays or particles emitted may consist of alpha, beta, or gamma radiation.

alpha radiation. The least penetrating type of radiation. Alpha radiation can be stopped by a sheet of paper or the outer dead layer of skin.

beta radiation. Electrons emitted from a nucleus during fission and nuclear decay. Beta radiation can be stopped by an inch of wood or a thin sheet of aluminum.

gamma radiation. A form of electromagnetic, high-energy radiation emitted from a nucleus. Gamma rays are essentially the same as x-rays and require heavy shielding such as lead, concrete, or steel to be stopped.

internal radiation. Radiation originating from a source within the body as a result of the inhalation, ingestion, or implantation of natural or man-made radionuclides in body tissues.

radiation dose:

absorbed dose. The amount of energy absorbed per unit mass in any kind of matter from any kind of ionizing radiation. Absorbed dose is measured in rads or grays.

collective dose equivalent. The sum of the dose equivalents for all the individuals comprising a defined population. The per capita dose equivalent is the quotient of the collective dose equivalent divided by the population. The unit of collective dose equivalent is person-rem or person-sievert.

collective effective dose equivalent. The sum of the effective dose equivalents for the individuals comprising a defined population. Units of measurement are person-rem or person-sievert. The per capita effective dose equivalent is obtained by dividing the collective dose equivalent by the population. Units of measurement are rem or sievert.

committed dose equivalent. A measure of internal radiation. The predicted total dose equivalent to a tissue or organ over a fifty-year period after a known intake of a radionuclide into the body. It does not include contributions from sources of external penetrating radiation. Committed dose equivalent is measured in rem or sievert.

committed effective dose equivalent. The sum of the committed dose equivalents to various tissues in the body, each multiplied by the appropriate weighting factor. Committed effective dose equivalent is measured in rem or sievert.

effective dose equivalent. The summation of the products of the dose equivalent received by specified tissues of the body and the appropriate weighting factors. It includes the dose from radiation sources internal and/or external to the body. The effective dose equivalent is expressed in units of rem or sievert.

radioactivity. A property possessed by some elements (such as uranium) whereby alpha, beta, or gamma rays are spontaneously emitted.

radioisotope. A radioactive isotope of a specified element. Carbon-14 is a radioisotope of carbon. Tritium is a radioisotope of hydrogen. (See *isotope*.)

radionuclide. A radioactive nuclide. Radionuclides are variations (isotopes) of elements. They have the same number of protons and electrons but different numbers of neutrons, resulting in different atomic masses. There are several hundred known nuclides, both manmade and naturally occurring.

reference man. A hypothetical aggregation of human physical and physiological characteristics arrived at by internal consensus. These characteristics may be used by researchers and public health workers to standardize results of experiments and to relate biological insult to a common base.

rem. An acronym for Roentgen Equivalent Man. A unit of radiation exposure that indicates the potential effect of radiation on human cells.

remote-handled waste. At the WVDP, waste that has an external surface dose rate that exceeds 100 millirem per hour or a high level of alpha and/or beta surface contamination and, therefore, must be handled in such a manner that a worker does not come into physical contact with it.

roentgen. A unit of exposure to ionizing radiation. It is that quantity of gamma or x-rays required to produce ions carrying one electrostatic unit of electrical charge in one cubic centimeter of dry air under standard conditions. The unit is named after Wilhelm Roentgen, German scientist who discovered x-rays in 1895.

S

self-assessment. Appraisals of work at the WVDP by individuals, groups, or organizations responsible for overseeing and/or performing the work. Self-assessments are intended to provide an internal review of performance to determine that specific functional areas are in programmatic and site-specific compliance with applicable DOE directives, WVDP procedures, and regulations.

finding. A direct and significant violation of applicable Department of Energy, regulatory, or other procedural or programmatic requirements. A finding requires documented corrective action.

observation. A condition that, while not a direct and significant violation of applicable Department of Energy, regulatory, or other procedural or programmatic requirements, could result in a finding if not corrected. An observation requires documented corrective action.

good practice. A statement of proficiency or confirmed excellence worthy of documenting.

sievert. A unit of dose equivalent from the International System of Units (Système Internationale). Equal to one joule per kilogram.

solid waste management unit (SWMU). Any discernible unit at which solid wastes have been placed at any time, irrespective of whether the unit was intended for the management of solid or hazardous waste. Such units include any area at a facility at which solid wastes have been routinely and systematically released. (See also *super solid waste management unit*.)

spent fuel. Nuclear fuel that has been used in a nuclear reactor; this fuel contains uranium, activation products, fission products, and plutonium.

spill. A spill or release is defined as “any spilling, leaking, pumping, pouring, emitting, emptying, discharging, injecting, escaping, leaching, dumping, or otherwise disposing of substances from the ordinary containers employed in the normal course of storage, transfer, processing, or use.”

stakeholder. A person or group that has an investment, share, or interest in something. At the WVDP stakeholders include Project management, scientists, other employees, politicians, regulatory agencies, local and national interest groups, and members of the general public.

standard deviation. An indication of the dispersion of a set of results around their average.

super solid waste management unit (SSWMU). Individual solid waste management units that have been grouped and ranked into larger units – super solid waste management units – because some individual units are contiguous or so close together as to make monitoring of separate units impractical. (See also *solid waste management unit*.)

surface water. Water that is exposed to the atmospheric conditions of temperature, pressure, and chemical composition at the surface of the earth.

surveillance. The act of monitoring or observing a process or activity to verify conformance with specified requirements.

T

thermoluminescent dosimeter (TLD). A device that luminesces upon heating after being exposed to radiation. The amount of light emitted is proportional to the amount of radiation to which the luminescent material has been exposed.

ton, metric (also *tonne*). A unit of mass equal to 1,000 kilograms.

ton (*short ton*). A unit of weight equal to 2,000 pounds or 907.1847 kilograms.

transuranic (TRU) waste. Waste containing transuranic elements, that is, those elements with an atomic number greater than 92, including neptunium, plutonium, americium, and curium.

U

universal wastes. Wastes subject to special management provisions that are intended to ease the management burden and facilitate recycling of such materials. Four types of waste are currently covered under the universal waste regulations: hazardous waste batteries, hazardous waste pesticides that are either recalled or collected in waste pesticide collection programs, hazardous waste thermostats, and hazardous waste lamps.

upgradient. Referring to the flow of water or air, “upgradient” is analogous to upstream. Upgradient is a point that is “before” an area of study that is used as a baseline for comparison with downstream or downgradient data. (See *gradient* and *downgradient*.)

W

watershed. The area contained within a drainage divide above a specified point on a stream or river.

water table. The upper surface in a body of groundwater; the surface in an unconfined aquifer or confining bed at which the pore water pressure is equal to atmospheric pressure.

X

x-ray. Penetrating electromagnetic radiations having wave lengths shorter than those of visible light. They are usually produced by bombarding a metallic target with fast electrons in a high vacuum. In nuclear reactions it is customary to refer to photons originating in the nucleus as gamma rays and those originating in the extranuclear part of the atom as x-rays. These rays are sometimes called roentgen rays after their discoverer, W.C. Roentgen.

This page intentionally left blank

ACRONYMS AND ABBREVIATIONS

A&PC	Analytical and Process Chemistry Laboratory
ACM	Asbestos-Containing Material
ACOE	(U.S.) Army Corps of Engineers
ALARA	As Low As Reasonably Achievable
ANSI	American National Standards Institute
ASER	Annual Site Environmental Report
ASME	American Society of Mechanical Engineers
ASQ	American Society for Quality (formerly American Society for Quality Control [ASQC])
AWQS	Ambient Water Quality Standard
BAT	Best Available Technology
BCG	Biota Concentration Guide
BEIR	Biological Effects of Ionizing Radiation
BOD₅	Biochemical Oxygen Demand (5-day)
BSW	Bulk Storage Warehouse
BTU	British Thermal Unit (also MBTU, MMBTU)
CAA	Clean Air Act
CCHD	Cattaraugus County Health Department
CD	Compact Disk
CDDL	Construction and Demolition Debris Landfill
CEDE	Committed Effective Dose Equivalent
CEMP	Code of Environmental Management Principles (for Federal Agencies)
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
CPC	Chemical Process Cell
CPC-WSA	Chemical Process Cell Waste Storage Area
CSPF	Container Sorting and Packaging Facility
CSRF	Contact Size-Reduction Facility

Acronyms and Abbreviations

CSS	Cement Solidification System
CWA	Clean Water Act
CX	Categorical Exclusion
CY	Calendar Year
D&D	Decontamination and Decommissioning
DBPs	Disinfection By-Products
DCDFMeth	Dichlorodifluoromethane
DCG	Derived Concentration Guide
DL	Detection Limit or Detection Level
DMR	Discharge Monitoring Report
DOE	(U.S.) Department of Energy
DOE-EM	Department of Energy, Office of Environmental Restoration and Waste Management
DOE-HQ	Department of Energy, Headquarters Office
DOE-OH	Department of Energy, Ohio Field Office
DOT	(U.S.) Department of Transportation
EA	Environmental Assessment
EDE	Effective Dose Equivalent
EHS	Extremely Hazardous Substance
EIS	Environmental Impact Statement
ELAB	(WVDP) Environmental Laboratory
EML	(DOE) Environmental Measurements Laboratory
EMS	Environmental Management System
EO	Executive Order
EPA	(U.S.) Environmental Protection Agency
EPCRA	Emergency Planning and Community Right-to-Know Act
ERA	Environmental Research Associates
ES&H	Environmental, Safety, and Health
ESR	(WVDP) Effluent Summary Report
FR	Federal Register
FRS	Fuel Receiving and Storage
FY	Fiscal Year
GEL	General Engineering Laboratory
HAA5	Haloacetic Acid-Five (5)
HEPA	High-Efficiency Particulate Air (filter)
HLW	High-Level (radioactive) Waste
HPIC	High-Pressure Ion Chamber
HTO	Hydrogen Tritium Oxide
HVAC	Heating, Ventilation, and Air Conditioning

IAEA	International Atomic Energy Agency
ICRP	International Commission on Radiological Protection
INEEL	Idaho National Engineering and Environmental Laboratory
IRTS	Integrated Radwaste Treatment System
ISCORS	Interagency Steering Committee on Radiation Standards
ISMS	Integrated Safety Management System
ISO	International Organization for Standardization
LAS	Linear Alkylate Sulfonate
LDR	Land Disposal Restriction
LIMS	Laboratory Information Management System
LLD	Lower Limit of Detection
LLW	Low-Level (radioactive) Waste
LLW2	Low-Level (liquid) Waste Treatment Facility (new)
LLWTF	Low-Level (liquid) Waste Treatment Facility (old)
LPS	Liquid Pretreatment System
LSA	Lag Storage Area
LTR	License Termination Rule
LWTS	Liquid Waste Treatment System
MAPEP	Mixed Analyte Performance Evaluation Program
MCL	Maximum Contaminant Level
MCLG	Maximum Contaminant Level Goal
MDC	Minimum Detectable Concentration
MDL	Method Detection Limit (also Minimum Detection Level)
MEI	Maximally Exposed Individual
MEOSI	Maximally Exposed Off-Site Individual
MGD	Million Gallons per Day
ML	Minimum Level
MMBTU	One million BTUs (a thousand thousand BTUs), also expressed as MBTU
MSDS	Material Safety Data Sheet
MTAR	Monthly Trend Analysis Report
MW	(Radioactive and Hazardous) Mixed Waste
NCRP	National Council on Radiation Protection and Measurements
NDA	Nuclear Regulatory Commission (NRC)-Licensed Disposal Area
NEPA	National Environmental Policy Act
NESHAP	National Emission Standards for Hazardous Air Pollutants
NFS	Nuclear Fuel Services, Inc.
NGVD	National Geodetic Vertical Datum
NH₃	Ammonia
NIST	National Institute of Standards and Technology
NOAA	National Oceanic and Atmospheric Administration

Acronyms and Abbreviations

NOI	Notice of Intent
NOV	Notice of Violation
NO_x	Nitrogen Oxides
NPDES	National Pollutant Discharge Elimination System
NPGRS	North Plateau Groundwater Recovery System
NPOC	Nonpurgeable Organic Carbon
NRC	(U.S.) Nuclear Regulatory Commission
NTS	Nevada Test Site
NTU	Nephelometric Turbidity Unit
NYCRR	New York Official Compilation of Codes, Rules, and Regulations
NYS	New York State
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
NYSDOH ELAP	(NYSDOH) Environmental Laboratory Approval Program
NYSDOL	New York State Department of Labor
NYSERDA	New York State Energy Research and Development Authority
NYSGS	New York State Geological Survey
OH/WVDP	Department of Energy, West Valley Demonstration Project
OSHA	Occupational Safety and Health Administration
OVE	Outdoor Ventilated Enclosure
P2	Pollution Prevention
PCB	Polychlorinated Biphenyl
PQL	Practical Quantitation Limit
PTW	Permeable Treatment Wall
PUREX	Plutonium Uranium Reduction Extraction
PVS	Permanent Ventilation System
PVU	Portable Ventilation Unit
QA	Quality Assurance
QAP	Quality Assessment Program (also Quality Assurance Program)
QC	Quality Control
QF	Quality Factor
RCRA	Resource Conservation and Recovery Act
REM	Roentgen Equivalent Man
RFI	RCRA Facility Investigation
RHWF	Remote-Handled Waste Facility
SAR	Safety Analysis Report
SARA	Superfund Amendments and Reauthorization Act
SD	Standard Deviation

SDA	(New York) State-Licensed Disposal Area
SDWA	Safe Drinking Water Act
SI	Système Internationale (International System of Units)
SO₂	Sulfur Dioxide
SPDES	(New York) State Pollutant Discharge Elimination System
SRM	Standard Reference Material
SSWMU	Super Solid Waste Management Unit
STL	Severn Trent Laboratories
STP	Site Treatment Plan
STS	Supernatant Treatment System
SVOC	Semivolatile Organic Compound
SWMU	Solid Waste Management Unit
TAGM	Technical and Administrative Guidance Memorandum
TBP	Tributyl Phosphate
TCE	Trichloroethylene
TDS	Total Dissolved Solids
THOREX	Thorium Reduction Extraction
TLD	Thermoluminescent Dosimeter
TOC	Total Organic Carbon
TOGS	Technical and Operational Guidance Series
TOX	Total Organic Halides
TRI	Toxic Release Inventory
TRU	Transuranic
TSCA	Toxic Substances Control Act
TSDF	Treatment, Storage, and Disposal Facility
TSS	Total Suspended Solids
TTHM	Total Trihalomethanes
U.S.	United States
URS	URS Group, Inc.
USC	United States Code
USGS	United States Geological Survey
VF	Vitrification Facility
VOC	Volatile Organic Compound
VPP	(U.S. DOE) Voluntary Protection Program
WNYNSC	Western New York Nuclear Service Center
WVDP	West Valley Demonstration Project
WVNS	West Valley Nuclear Services Company (now WVNSCO)
WVNSCO	West Valley Nuclear Services Company
WWTF	Wastewater Treatment Facility

This page intentionally left blank

Units of Measure

<u>Radioactivity</u>	<u>Symbol</u>	<u>Name</u>	<u>Volume</u>	<u>Symbol</u>	<u>Name</u>
	Ci	curie		cm ³	cubic centimeter
	mCi	millicurie (1E-03 Ci)		L	liter
	µCi	microcurie (1E-06 Ci)		mL	milliliter
	nCi	nanocurie (1E-09 Ci)		m ³	cubic meter
	pCi	picocurie (1E-12 Ci)		gal	gallon
	Bq	becquerel (27 pCi)		ft ³	cubic feet
	d/s	disintegrations per second			
<u>Dose</u>	<u>Symbol</u>	<u>Name</u>	<u>Area</u>	<u>Symbol</u>	<u>Name</u>
	Sv	sievert (100 rem)		ha	hectare (10,000 m ²)
	mSv	millisievert (1E-03 Sv)			
	Gy	gray (100 rad)			
	mrem	millirem (1E-03 rem)			
<u>Concentration</u>	<u>Symbol</u>	<u>Name</u>	<u>Length</u>	<u>Symbol</u>	<u>Name</u>
	µCi/mL	microcuries per milliliter		m	meter
	mL/L	milliliters per liter		km	kilometer (1E+03 m)
	µCi/g	microcuries per gram		cm	centimeter (1E-02 m)
	mg/L	milligrams per liter (ppm)		mm	millimeter (1E-03 m)
	mg/kg	milligrams per kilogram (ppm)		µm	micrometer (1E-06 m)
	µg/mL	micrograms per milliliter (ppm)			
	pCi/L	picocuries per liter	<u>Exposure</u>	<u>Symbol</u>	<u>Name</u>
	ng/L	nanograms per liter (ppt)		µR	microrentgen
	µg/L	micrograms per liter (ppb)		mR	milliroentgen
	µg/g	micrograms per gram (ppm)			
	Bq/L	becquerels per liter			
	ppm	parts per million			
	ppb	parts per billion			
	ppt	parts per trillion			
	NTU	nephelometric turbidity units			
	SU	standard units			
<u>Mass</u>	<u>Symbol</u>	<u>Name</u>	<u>Flow Rate or Speed</u>	<u>Symbol</u>	<u>Name</u>
	g	gram		mgd	million gallons per day
	kg	kilogram (1E+03 g)		cfm	cubic feet per minute
	mg	milligram (1E-03 g)		Lpm	liters per minute
	µg	microgram (1E-06 g)		gpd	gallons per day
	ng	nanogram (1E-09 g)		m/sec	meters per second
	t	metric ton (1E+06 g)			

Unit Prefixes

centi	$1/100 = 1 \times 10^{-2} = 0.01 = E-02$
milli	$1/1,000 = 1 \times 10^{-3} = 0.001 = E-03$
micro	$1/1,000,000 = 1 \times 10^{-6} = 0.000001 = E-06$
nano	$1/1,000,000,000 = 1 \times 10^{-9} = 0.000000001 = E-09$
pico	$1/1,000,000,000,000 = 1 \times 10^{-12} = 0.000000000001 = E-12$

Scientific Notation

Scientific notation may be used to express very large or very small numbers. A number smaller than 1 is expressed with a negative exponent (e.g., 1.3×10^{-6}). To convert this number to decimal form, the decimal point is moved left by the number of places equal to the exponent. Thus, 1.3×10^{-6} becomes 0.0000013.

A number larger than 10 is expressed with a positive exponent (e.g., 1.3×10^6). To convert this number to decimal form, the decimal point is moved right by the number of places equal to the exponent. Thus, 1.3×10^6 becomes 1,300,000.

The power of 10 also is expressed as E. For example, 1.3×10^{-6} also can be written as 1.3E-06. The chart below shows equivalent exponential and decimal values.

1.0×10^2	=	1E+02	=	100
1.0×10^1	=	1E+01	=	10
1.0×10^0	=	1E+00	=	1
1.0×10^{-1}	=	1E-01	=	0.1
1.0×10^{-2}	=	1E-02	=	0.01
1.0×10^{-3}	=	1E-03	=	0.001
1.0×10^{-4}	=	1E-04	=	0.0001
1.0×10^{-5}	=	1E-05	=	0.00001
1.0×10^{-6}	=	1E-06	=	0.000001
1.0×10^{-7}	=	1E-07	=	0.0000001
1.0×10^{-8}	=	1E-08	=	0.00000001

One millionth

Conversion Chart

Both traditional radiological units (curie, roentgen, rad, rem) and the Systeme Internationale (S.I.) units (becquerel, gray, sievert) are used in this report. Nonradiological measurements are presented in both English and metric units. Frequently-used radioactivity and dose conversions are bolded.

1 centimeter (cm)	=	0.3937 inches (in)
1 meter (m)	=	39.37 inches (in) = 3.28 feet (ft)
1 kilometer (km)	=	0.62 miles (mi)
1 milliliter (mL)	=	0.0338 ounces (oz)
	=	0.061 cubic inches (in ³)
	=	1 cubic centimeter (cm ³)
1 liter (L)	=	1.057 quarts (qt)
	=	61.02 cubic inches (in ³)
1 gram (g)	=	0.0353 ounces (oz)
	=	0.0022 pounds (lbs)
1 kilogram (kg)	=	2.2 pounds (lbs)
1 curie (Ci)	=	3.7E+10 disintegrations per second (d/s)
1 becquerel (Bq)	=	1 disintegration per second (d/s)
	=	27 picocuries (pCi)
1 roentgen (R)	=	2.58E-04 coulombs per kilogram of air (C/kg)
1 rad	=	0.01 gray (Gy)
1 rem	=	0.01 sievert (Sv)
1 millirem (mrem)	=	0.001 rem
1 sievert (Sv)	=	100 rem

Distribution

<u>Recipient</u>	<u>Federal Organization</u>	<u>Recipient</u>	<u>State Organization</u>
DOE Office of Scientific and Technical Information		J. Austin	Executive Chamber, State Capitol, Albany
R. Hardwick	DOE - HQ	E. Dassatti	NYSDEC - Albany
R. Natoli	DOE - HQ	R. Phaneuf	NYSDEC - Albany
G. Podonsky	DOE - HQ	T. Rice	NYSDEC - Albany
M. Rawlings	DOE - HQ	M. Wang	NYSDEC - Albany
J. Craig	DOE - OH	L. Winterberger	NYSDEC - Albany
R. Tormey	DOE - OH	B. Youngberg	NYSDEC - Albany
		B. Bartz	NYSDEC - Buffalo
C. Glenn	NRC - HQ	S. Doleski	NYSDEC - Buffalo
J. Greeves	NRC - HQ	J. Sciascia	NYSDEC - Buffalo
R. Prince	NRC - Region 1	P. Concannon	NYSDEC - Region 9
		M. Jackson	NYSDEC - Region 9
R. Chaput	U.S. EPA - Region II	J. Strickland	NYSDEC - Region 9
J. Eng	U.S. EPA - Region II		
P. Giardina	U.S. EPA - Region II	L. Sturman	NYSDOH - Albany
		G. Baker	NYSDOH - Buffalo
		B. Ignatz	NYSDOH - Buffalo
W. Kappel	USGS	A. Salame Alfie	NYSDOH - Troy
T. Reynolds	U.S. Congress, 26th Dist.	P. Piciulo	NYSERDA
B. Higgins	U.S. Congress, 27th Dist.	H. Brodie	NYSERDA - Albany
L. Slaughter	U.S. Congress, 28th Dist.		
R. Kuhl	U.S. Congress, 29th Dist.	R. Fakundiny	NYSGS
J. Quinn	U.S. Congress, 30th Dist.		
		D. Burling	New York Assembly, 147th Dist.
H. Clinton	U.S. Senate, New York	J. Giglio	New York Assembly, 149th Dist.
C. Schumer	U.S. Senate, New York	C. Young	New York Senate, 57th Dist.
		W. Stachowski	New York Senate, 58th Dist.
		D. Volker	New York Senate, 59th Dist.
<u>Recipient</u>	<u>Local Organization</u>	<u>Recipient</u>	<u>Local Organization</u>
E. Wohlers	Cattaraugus County Health Dept.		
G. Felton	Cattaraugus County Legislature	G. Eppolito	Mayor, Village of Springville
G. Fitzpatrick	Cattaraugus County Legislature	W. King	Supervisor, Town of Ashford
J. Burrell	Cattaraugus County Legislature	M. Steffan	Supervisor, Town of Concord
A. Billittier IV	Erie County Health Department		
B. Snyder, Jr.	President, Seneca Nation of Indians		
R. Ground	Seneca Nation of Indians Environmental Protection Department		

Distribution

Publication

Library

*Buffalo News, Buffalo, New York **

Town of Concord Hulbert Library, Springville, New York

*Salamanca Republican Press, Salamanca,
New York **

Seneca Nation of Indians Library, Cattaraugus Reservation,
Irving, New York

*Springville Journal, Springville, New York **

Seneca Nation of Indians Library, Allegheny Reservation,
Salamanca, New York

West Valley Demonstration Project, Public Reading Room,
West Valley, New York

** Notice of public availability*

Appendix A
Environmental Monitoring Program Maps

This page intentionally left blank

2004 Environmental Monitoring Program Sample Points

The following maps contain points sampled as part of the West Valley Demonstration Project (WVDP) routine environmental monitoring program for 2004. This program met or exceeded the requirements of U.S. Department of Energy (DOE) Order 450.1, DOE Order 5400.5, and DOE/EH-0173T. Specific methods and recommended monitoring program elements are found in DOE/EP-0096, "A Guide for Effluent Radiological Measurements at DOE Installations," and DOE/EP-0023, "A Guide for Environmental Radiological Surveillance at U.S. Department of Energy Installations," which were the bases for selecting most of the sampling locations. Additional monitoring was mandated by air and water discharge permits (40 CFR 61 and SPDES).

The index on pages A-iv through A-vii is a list of the codes used to identify the various sampling locations, which are shown on Figures A-2 through A-13. The sample location code describes the physical location where the sample is collected. The code consists of seven or eight characters: The first character identifies the sample medium as **A**ir, **W**ater, **S**oil/**S**ediment, **B**iological, or **D**irect Measurement. The second character specifies **o**N-site or **o**Ff-site. The remaining characters describe the specific location (e.g., **AFGRVAL** is **A**ir **o**Ff-site at **G**reat **V**Alley). Distances are measured in a straight line from the on-site main stack to the sampling location. Sampling points located inside buildings (e.g., on-site drinking water) or points that do not have a fixed location (e.g., outdoor ventilated enclosures) are not shown on these maps. Areas labeled as "wetlands" do not depict the WVDP's formally delineated wetlands inventory. As an aid to the reader, these polygons indicate relatively low-lying areas that almost always contain wet surface soils or standing water during years with typical precipitation totals.

List of Maps

A-1. West Valley Demonstration Project Base Map _____	A-1
A-2. On-Site Surface Water and Soil/Sediment Sampling Locations _____	A-2
A-3. Off-Site Surface Water and Soil/Sediment Sampling Locations _____	A-3
A-4. On-Site Air Monitoring and Sampling Locations _____	A-4
A-5. Off-Site Air and Fallout Sampling Locations _____	A-5
A-6. Active WVDP Groundwater Monitoring Locations _____	A-6
A-7. North Plateau On-Site Groundwater Monitoring Network _____	A-7
A-8. South Plateau On-Site Groundwater Monitoring Network _____	A-8
A-9. Near-Site Drinking Water and Biological Sampling Locations _____	A-9
A-10. Location of On-Site Thermoluminescent Dosimeters (TLDs) _____	A-10
A-11. Location of Off-Site Thermoluminescent Dosimeters (TLDs) Within 5 Kilometers of the WVDP _____	A-11
A-12. Environmental Sampling Locations Between 5 and 10 Kilometers From the WVDP _____	A-12
A-13. Environmental Sampling Locations More Than 10 Kilometers From the WVDP _____	A-13
A-14. Projected 2002 Population by Sector Within 80 Kilometers of the WVDP _____	A-14

List of Sampling Locations

On-Site Surface Water and Soil/Sediment Sampling Locations (Fig. A-2)

WNSP001	Lagoon 3 Weir Point
WNSP006	Facility Main Drainage
SNSP006	Soil at WNSP006
WNSP116	Pseudo Monitoring Point in Frank's Creek
WNSP007	Sanitary Waste Discharge
WNSWAMP	Northeast Swamp Drainage Point
SNSWAMP	Soil at WNSWAMP
WNSW74A	North Swamp Drainage Point
SNSW74A	Soil at WNSW74A
WNSDADR	SDA Runoff
WNSP008	French Drain LLWTF Area
WNSP005	South Facility Drainage
WNSCOOLW	Cooling Tower
WNSFRC67	Frank's Creek East
WNSERB53	Erdman Brook
WNSNDADR	Disposal Area Drainage
WNSDCELD	Drum Cell Drainage
WNSNDATR	NDA Trench Interceptor Project
WNSSTAW6	Standing Water

Off-Site Surface Water and Soil/Sediment Sampling Locations (Fig. A-3)

WNSBCBKG	Buttermilk Creek near Fox Valley, Background
WNSBCTCB	Buttermilk Creek at Thomas Corners
WNSBIGBR	Cattaraugus Creek at Bigelow Bridge, Background
WNSBISED	Cattaraugus Creek at Bigelow Bridge, Background Sediment
WNSFELBR	Cattaraugus Creek at Felton Bridge
WNSFTCORD	Soil at Thomas Corners Air Sampler
WNSFSDSED	Cattaraugus Creek at Springville Dam, Sediment
WNSFCCSED	Cattaraugus Creek at Felton Bridge, Sediment
WNSFTCSED	Buttermilk Creek at Thomas Corners, Sediment
WNSFBCSED	Buttermilk Creek at Fox Valley Road, Background Sediment
WNSFRSPRD	Soil at Rock Springs Road Air Sampler
WNSFRT240	Soil at Route 240 Air Sampler
WNSFBLKST	Soil at Bulk Storage Warehouse Air Sampler
WNSFFXVRD	Soil at Fox Valley Road Air Sampler
WNSFBOEHN	Soil at Dutch Hill Road Air Sampler
WNSSTAW4	Standing Water
WNSSTAW5	Standing Water
WNSSTAW9	Standing Water

List of Sampling Locations (continued)

On-Site Air Monitoring and Sampling Locations (Fig. A-4)

ANSTACK	Main Plant
ANSTSTK	Supernatant Treatment System
ANCSSTK	01-14 Building
ANCSRFK	Size-Reduction Facility
ANCSPFK	Container Sorting and Packaging Facility
ANVITSK	Vitrification Heating, Ventilation, and Air Conditioning
ANLAGAM	Lag Storage Area (ambient air)
ANNDAAM	NDA Area (ambient air)
ANSDAT9	SDA Trench 9 (ambient air)
ANRGFOP	Rain Gauge Fallout
ANRHWFK	Remote-Handled Waste Facility

Off-Site Air and Fallout Sampling Locations (Fig. A-5)

AFFXVRD	Fox Valley Sampler
AFFXFOP	Fox Valley Fallout
AFTCORD	Thomas Corners Sampler
AFTCFOP	Thomas Corners Fallout
AFRT240	Route 240 Sampler
AF24FOP	Route 240 Fallout
AFBOEHN	Dutch Hill Road Sampler
AFDHFOP	Dutch Hill Fallout
AFRSPRD	Rock Springs Road Sampler
AFBLKST	Bulk Storage Warehouse Sampler

List of Sampling Locations (continued)

Active WVDP Groundwater Monitoring Locations (Fig. A-6)

North Plateau On-Site Groundwater Monitoring Network (Fig. A-7)

South Plateau On-Site Groundwater Monitoring Network (Fig. A-8)

SSWMU #1	Low-Level Waste Treatment Facility Wells
SSWMU #2	Miscellaneous Small Units Wells
SSWMU #3	Liquid Waste Treatment System Wells
SSWMU #4	HLW Storage and Processing Tank Wells
SSWMU #5	Maintenance Shop Leach Field Wells
SSWMU #6	Low-Level Waste Storage Area Wells
SSWMU #7	CPC Waste Storage Area Wells
SSWMU #8	CDDL Wells
SSWMU #9	NDA Units Wells and NDATR
SSWMU #10	IRTS Drum Cell Wells
RHWF	Remote-Handled Waste Facility Wells
SSWMU #11	SDA Unit Wells
North Plateau Seeps	Northeastern Edge of North Plateau
Well Points	Downgradient of Main Plant
WNWNB1S	Former North Plateau Background Well

Near-Site Drinking Water and Biological Sampling Locations (Fig. A-9)

BFFCATC	Cattaraugus Creek Fish, Downstream
BFFCATD	Cattaraugus Creek Fish, Downstream of Springville Dam
BFMREED	North-Northwest Milk, Near-Site
BFMWIDR	Southeast Milk, Near-Site
BFMSCHT	South Milk, Near-Site
BFVNEAR	Produce, Near-Site
BFBNEAR	Beef, Near-Site
BFDNEAR	Venison, Near-Site
FWWEL Series	Private Wells

Location of On-Site Thermoluminescent Dosimeters (TLDs) (Fig. A-10)

DNTLD Series	On-Site Direct Radiation
--------------	--------------------------

Location of Off-Site Thermoluminescent Dosimeters (TLDs) Within 5 Kilometers of the WVDP (Fig. A-11)

DFTLD Series	Off-Site Direct Radiation
--------------	---------------------------

List of Sampling Locations (concluded)

Environmental Sampling Locations Between 5 and 10 Kilometers From the WVDP (Fig. A-12)

AFSPRVL	Springville Air Sampler
SFSPRVL	Soil at Springville Air Sampler
DFTL21	TLD at Springville Air Sampler
WFWEL10	Drinking Water at Springville Air Sampler
BFVNEAR	Produce, Near-site
DFTL22	TLD at West Valley Air Sampler
SFWEVAL	Soil at West Valley Air Sampler
AFWEVAL	West Valley Air Sampler

Environmental Sampling Locations More Than 10 Kilometers From the WVDP (Fig. A-13)

BFMCTLS	Milk, South, Background
BFVCTRL	Produce, Background
WNSTAWB	Standing Water, Background
BFFCTRL	Cattaraugus Creek Fish, Background
BFDCTRL	Venison, Background
AFGRVAL	Great Valley Air Sampler, Background
SFGRVAL	Soil at Great Valley Air Sampler, Background
DFTL23	TLD at Great Valley Air Sampler
WFWEL06	Drinking Water at Great Valley Air Sampler
BFBCTRL	Beef, Background

This page intentionally left blank




Figure A-1. West Valley Demonstration Project Base Map




Figure A-2. On-Site Surface Water and Soil/Sediment Sampling Locations




Figure A-3. Off-Site Surface Water and Soil/Sediment Sampling Locations




Figure A-4. On-Site Air Monitoring and Sampling Locations




Figure A-5. Off-Site Air and Fallout Sampling Locations




Figure A-6. Active WVDP Groundwater Monitoring Locations




Figure A-7. North Plateau On-Site Groundwater Monitoring Network (Includes Wells Used for Water-Level Measurements)




Figure A-8. South Plateau On-Site Groundwater Monitoring Network (Includes Wells Used for Water Level Measurements [WVDP] and SDA Wells [NYSERDA])




Figure A-9. Near-Site Drinking Water and Biological Sampling Locations




Figure A-10. Location of On-Site Thermoluminescent Dosimeters (TLDs)




Figure A-11. Location of Off-Site Thermoluminescent Dosimeters (TLDs) Within 5 Kilometers of the WVDP




Figure A-12. Environmental Sampling Locations Between 5 and 10 Kilometers From the WVDP

j:\gis\laser.apr fig A-13 regional points > 10km from site, r4 (03/24/05) - fjc




Figure A-13. Environmental Sampling Locations More Than 10 Kilometers From the WVDP




Figure A-14. Estimated 2002 Population by Sector Within 80 Kilometers of the WVDP

Appendix B
2004 Environmental Monitoring Program

This page intentionally left blank

2004 Environmental Monitoring Program

The following schedule represents the West Valley Demonstration Project (WVDP) routine environmental monitoring program for 2004. This schedule met or exceeded the requirements of DOE Order 450.1, DOE Order 5400.5, and DOE/EH-0173T. Specific methods and recommended monitoring program elements are found in DOE/EP-0096, *A Guide for Effluent Radiological Measurements at DOE Installations*, and DOE/EP-0023, *A Guide for Environmental Radiological Surveillance at U.S. Department of Energy Installations*, which were the bases for selecting most of the schedule specifics. Additional monitoring was mandated by air and water discharge permits (40 CFR 61 and SPDES), which also required formal reports. Specifics are identified in the schedule under Monitoring/Reporting Requirements.

A computerized environmental data-screening system identifies analytical data that exceed preset limits. All locations are checked monthly for trends or notable results in accordance with criteria established in *Documentation and Reporting of Environmental Monitoring Data* (West Valley Nuclear Services Co., March 26, 2003). Reportable results are then described in monthly trend analysis reports (MTARs) for indicator parameters and chemical and isotopic parameters together with possible causes and corrective actions, if indicated. WVDP Effluent Summary Reports (ESRs) are transmitted with the MTARs.

Schedule of Environmental Sampling

The index on pages B-vi through B-viii is a list of the codes used to identify the various sampling locations, which are shown on Figures A-2 through A-13 in Appendix A. The schedule of environmental sampling at the WVDP is found in this appendix. Table headings in the schedule are as follows:

- ***Sample Location Code.*** Describes the physical location where the sample is collected. The code consists of seven or eight characters: The first character identifies the sample medium as **A**ir, **W**ater, **S**oil/Sediment, **B**iological, or **D**irect Measurement. The second character specifies **oN**-site or **oFf**-site. The remaining characters describe the specific location (e.g., **AFGRVAL** is **A**ir **oFf**-site at **G**reat **V**ALley). Distances noted at sampling locations are as measured in a straight line from the main stack on site.
- ***Monitoring/Reporting Requirements.*** Notes the bases for monitoring the location, any additional references to permits, and the reports that are generated from the sample data. Routine reports cited in this appendix are the Effluent Summary Report (ESR), the monthly trend analysis reports (MTARs), the State Pollutant Discharge Elimination System Discharge Monitoring Report (SPDES DMR), the Air Emissions Report (NESHAP), and the Annual Site Environmental Report (ASER).
- ***Sampling Type/Medium.*** Describes the collection method and the physical characteristics of the medium.
- ***Collection Frequency.*** Indicates how often the samples are collected or retrieved.
- ***Total Annual Sample Collections.*** Specifies the number of discrete physical samples collected annually for each group of analytes.
- ***Analyses Performed/Composite Frequency.*** Notes the type of analyses of the samples taken at each collection, the frequency of composite, and the analytes determined for the composite samples.

Summary of Monitoring Program Changes in 2004

Location Code	Description of Changes
ANRHWFK	A new air sampling location (ANRHWFK) at the recently constructed remote-handled waste facility was brought on line in May 2004. Radiological operations began at this facility on June 14, 2004.
OVES/PVUs	These air samples were used in an expanded role in 2004 to monitor decontamination activities in the main plant.

Index of Environmental Monitoring Program Sample Points

Air Effluent and On-Site Ambient Air (Fig. A-4)

ANSTACK	Main Plant	B-1
ANSTSTK	Supernatant Treatment System	B-1
ANCSSTK	01-14 Building	B-1
ANCSRFK	Size-Reduction Facility	B-1
ANCSPFK	Container Sorting and Packaging Facility	B-1
ANVITSK	Vitrification Heating, Ventilation, and Air Conditioning	B-1
ANRHWFK	Remote-Handled Waste Facility	B-1
OVes/PVUs*	Outdoor Ventilated Enclosures/Portable Ventilation Units	B-3
ANLAGAM	Lag Storage Area (ambient air)	B-3
ANNDAAAM	NDA Area (ambient air)	B-3
ANSDAT9	SDA Trench 9 (ambient air)	B-3

Liquid Effluent and On-Site Water (Fig. A-2)

WNSP001	Lagoon 3 Weir Point	B-5
WNSP01B*	Internal Process Monitoring Point	B-7
WNSP116	Pseudo-Monitoring Point Outfall 116	B-7
WNSP006	Facility Main Drainage	B-9
WNURRAW*	Utility Room Raw Water	B-9
WNSP007	Sanitary Waste Discharge	B-11
WNSWAMP	Northeast Swamp Drainage Point	B-13
WNSW74A	North Swamp Drainage Point	B-13
WNSDADR	SDA Runoff	B-15
WNSP008	French Drain LLWTF Area	B-15
WNSP005	South Facility Drainage	B-15
WNCOOLW	Cooling Tower	B-15
WNFRC67	Frank's Creek East	B-17
WNERB53	Erdman Brook	B-17
WNNDADR	Disposal Area Drainage	B-17
WNDCELD	Drum Cell Drainage	B-17
WNNDATR	NDA Trench Interceptor Project	B-17
WNSTAW Series	Standing Water	B-19
WNDNK Series*	Site Potable Water	B-21

* Not detailed on map.

Index of Environmental Monitoring Program Sample Points (continued)

On-Site Groundwater and Seeps (Figs. A-6 through A-8)

SSWMU #1	Low-Level Waste Treatment Facility Wells	B-23
SSWMU #2	Miscellaneous Small Units Wells	B-23
SSWMU #3	Liquid Waste Treatment System Wells	B-23
SSWMU #4	HLW Storage and Processing Tank Wells	B-25
SSWMU #5	Maintenance Shop Leach Field Wells	B-25
SSWMU #6	Low-Level Waste Storage Area Wells	B-25
SSWMU #7	CPC Waste Storage Area Wells	B-25
SSWMU #8	CDDL Wells	B-27
SSWMU #9	NDA Units Wells and NDATR	B-27
SSWMU #10	IRTS Drum Cell Wells	B-27
RHWF	Remote-Handled Waste Facility Wells	B-27
SSWMU #11	SDA Unit Wells	B-29
North Plateau Seeps	Northeastern Edge of North Plateau	B-29
Well Points	Downgradient of Main Plant	B-29
WNWNB1S	Former North Plateau Background Well	B-29

Off-Site Surface Water (Fig. A-3)

WFBCBKG	Buttermilk Creek near Fox Valley (background)	B-31
WFBCTCB	Buttermilk Creek at Thomas Corners	B-31
WFBIGBR	Cattaraugus Creek at Bigelow Bridge (background)	B-33
WFFELBR	Cattaraugus Creek at Felton Bridge	B-33

Off-Site Drinking Water (Figs. A-9, A-12, and A-13)

FWWEL Series	Private Local Wells	B-35
--------------	---------------------	------

Off-Site Ambient Air (Figs. A-5, A-12, and A-13)

AFFXVRD	Fox Valley Sampler	B-37
AFTCORD	Thomas Corners Sampler	B-37
AFRT240	Route 240 Sampler	B-37
AFSPRVL	Springville Sampler	B-37
AFWEVAL	West Valley Sampler	B-37
AFBOEHN	Dutch Hill Road Sampler	B-37
AFRSPRD	Rock Springs Road Sampler	B-37
AFGRVAL	Great Valley Sampler (background)	B-37
AFBLKST	Bulk Storage Warehouse Sampler	B-37

Index of Environmental Monitoring Program Sample Points (concluded)

Fallout, Sediment, and Soil (Figs. A-2 through A-5, A-12, and A-13)

AFDHFOP	Dutch Hill Fallout	B-39
AFFXFOP	Fox Valley Fallout	B-39
AFTCFOP	Thomas Corners Fallout	B-39
AF24FOP	Route 240 Fallout	B-39
ANRGFOP	Rain Gauge Fallout	B-39
SF Soil Series	Air Sampler Area Soil	B-39
SFCCSED	Cattaraugus Creek at Felton Bridge, Sediment	B-39
SFSDSED	Cattaraugus Creek at Springville Dam, Sediment	B-39
SFBISED	Cattaraugus Creek at Bigelow Bridge, Background Sediment	B-39
SFTCSSED	Buttermilk Creek at Thomas Corners, Sediment	B-39
SFBCSED	Buttermilk Creek at Fox Valley Road, Background Sediment	B-39
SN Soil Series:	On-Site Soils/Sediments	B-39
SNSW74A		B-39
SNSWAMP		B-39
SNSP006		B-39

Off-Site Biological (Figs. A-9, A-12, and A-13)

BFFCATC	Cattaraugus Creek Fish, Downstream	B-41
BFFCATD	Cattaraugus Creek Fish, Downstream of Springville Dam	B-41
BFFCTRL	Cattaraugus Creek Fish, Background	B-41
BFMREED	North-Northwest Milk, Near-Site	B-41
BFMCTLS	Milk, South, Background	B-41
BFMWIDR	Southeast Milk, Near-Site	B-41
BFMSCHT	South Milk, Near-Site	B-41
BFVNEAR*	Produce, Near-Site	B-43
BFVCTRL*	Produce, Background	B-43
BFBNEAR	Beef, Near-Site	B-43
BFBCTRL	Beef, Background	B-43
BFDNEAR	Venison, Near-Site	B-43
BFDCTRL	Venison, Background	B-43

Direct Measurement Dosimetry (Figs. A-10 through A-13)

DFTLD Series	Off-Site Direct Radiation	B-45
DNTLD Series	On-Site Direct Radiation	B-47

* Near-site and background produce samples (corn, apples, and beans) are identified specifically as follows: corn = **BFVNEAC** and **BFVCTRC**; apples = **BFVNEAAF** and **BFVCTRA**; beans = **BFVNEAB** and **BFVCTRB**.

2004 Monitoring Program On-Site Effluent Monitoring

Air Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
ANSTACK <i>Main Plant Ventilation Exhaust Stack</i>	Airborne radioactive effluent points, including the LWTS <u>Required by:</u> <ul style="list-style-type: none"> • 40 CFR 61 <u>Reported in:</u> <ul style="list-style-type: none"> • ESR • MTARs • ASER • Air Emissions Annual Report (NESHAP) 	Continuous off-line air particulate monitors →	Continuous measurement of fixed filter; replaced weekly →	NA	→ Real-time alpha and beta monitoring
ANSTSTK <i>Supernatant Treatment System (STS) Ventilation Exhaust</i>		Continuous off-line air particulate filters →	Weekly →	52 each location	→ Gross alpha/beta, gamma isotopic* upon collection, flow
ANCSSTK <i>01-14 Building Ventilation Exhaust</i>		Weekly filters composited to 4 each location →			→ Quarterly composites for Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241, gamma isotopic, flow
ANCSRFK <i>Contact Size-Reduction Facility Exhaust</i>					
ANCSPFK <i>Container Sorting and Packaging Facility Exhaust</i>		Continuous off-line desiccant columns for water vapor collection →	Weekly →	52 at each of two locations	→ H-3 (ANSTACK and ANSTSTK only), flow
ANVITSK <i>Vitrification HVAC Exhaust</i>					
ANRHWFK <i>Remote-Handled Waste Facility Exhaust</i>		Continuous off-line charcoal cartridges →	Weekly →	Weekly cartridges composited to 4 each location	→ Quarterly composite for I-129

* Weekly gamma isotopic only if gross activity rises significantly.
NA - Not applicable.

Sampling Rationale

ANSTACK	DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3 Monitors and samples HEPA-filtered ventilation from most process areas, including cell ventilation, vessel off-gas, fuel receiving and storage (FRS), head end ventilation, and an analytical aisle. Requires continuous effluent monitoring per 40 CFR Subpart H, Section 61.93(b) because potential emissions may exceed the 0.1 mrem limit.
ANSTSTK	DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3 Monitors and samples HEPA-filtered ventilation (permanent ventilation system [PVS]) from building areas involved in treatment of high-level waste supernatant. Requires continuous effluent monitoring per 40 CFR Subpart H, Section 61.93(b) because potential emissions may exceed the 0.1 mrem limit.
ANCSSTK	DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3 Monitors and samples HEPA-filtered ventilation from the 01-14 building, which houses equipment used to treat the ceramic melter off-gas. Requires effluent monitoring per 40 CFR Subpart H, Section 61.93(b) to confirm that emissions are less than the 0.1 mrem limit.
ANCSRFK	DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3 Monitors and samples HEPA-filtered ventilation from a process area where radioactive tanks, pipes, and other equipment are cut up with a plasma torch to reduce volume.
ANCSPFK	DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3 Monitors and samples ventilation from lag storage area 4, the container sorting and packaging facility.
ANVITSK	DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3 Vitrification facility heating, ventilation, and air conditioning (HVAC) effluent exhaust stack. Monitors and samples HEPA-filtered ventilation from building areas involved in treatment of high-level waste supernatant. Sampler brought on-line in late 1995 when nonradioactive operations began. Radioactive operation began with the first high-level waste transfer in June 1996 and vitrification startup in July 1996. Vitrification was completed in 2002. Requires effluent monitoring per 40 CFR Subpart H, Section 61.93(b) because potential emissions may exceed the 0.1 mrem limit.
ANRHWFK	DOE/EH-0173T, 3.0; DOE-EP-0096, 3.3 Monitors and samples HEPA-filtered ventilation from the remote-handled waste facility (RHWF), where contaminated waste equipment (i.e., pumps, tanks, piping) are size reduced before being packaged for disposal. Construction of the RHWF was completed early in 2004 and radiological operations began in June 2004.

- Sampling locations are shown on Figure A-4.

**2004 Monitoring Program
On-Site Effluent Monitoring**

Air Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
OVES/PVUs <i>Outdoor Ventilated Enclosures/Portable Ventilation Units</i>	Airborne radioactive effluent points <u>Required by:</u> <ul style="list-style-type: none"> • 40 CFR 61 <u>Reported in:</u> <ul style="list-style-type: none"> • ESR • MTARs • ASER • Air Emissions Annual Report (NESHAP) 	Continuous off-line air particulate filter	→ As required	→ 1 each location	→ Filters for gross alpha/beta, gamma isotopic* upon collection, flow
				Collected filters** composited to 4	→ Quarterly composites for Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241, gamma isotopic, flow
ANLAGAM <i>Lag Storage Area Ambient Air</i> ANNDAAAM <i>NDA Ambient Air</i>	Ambient "diffuse source" air emissions <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Continuous air particulate filter	→ Weekly	→ 52 each location	→ Gross alpha/beta, flow
				Weekly filter composited to 4 each location	→ Quarterly composites for Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241, gamma isotopic, flow
ANSDAT9*** <i>SDA Trench 9 Ambient Air</i>	Ambient "diffuse source" air emissions <u>Reported in:</u> <ul style="list-style-type: none"> • ASER • Reported to NYSERDA 	Continuous air particulate filter	→ Weekly	→ 52	→ Gross alpha/beta, flow
		Continuous off-line desiccant columns for water vapor collection	→ Weekly	→ 52	→ Quarterly composite for gamma isotopic, flow
		Continuous off-line charcoal cartridges	→ Monthly	→ Monthly cartridges composited to 4	→ Quarterly composite for I-129, flow

* Gamma isotopic only if gross activity rises significantly.

** If gross determination of individual filter is significantly higher than background, the individual sample would be submitted immediately for isotopic analysis.

*** Sampling frequency and analytical parameters as directed by NYSERDA.

Sampling Rationale

OVes/PVUs DOE/EH-0173T, 3.0; DOE/EP-0096, 3.3

Outdoor ventilated enclosures; portable ventilation units used for handling radioactive materials or for decontamination in areas not having containment ventilation. Emissions are monitored to confirm that they are below the 0.1 mrem limit.

■ Sampling locations are not shown on figures.

ANLAGAM DOE/EH-0173T, 3.3.2

Monitors ambient air in the lag storage area, a possible diffuse source of air emissions.

ANNDAAAM DOE/EH-0173T, 3.3.2

Monitors ambient air in the NDA area, a possible diffuse source of air emissions.

ANSDAT9 DOE/EH-0173T, 3.3.2

Monitors potential diffuse sources of air emissions at the SDA and south plateau area. WVDP support of NYSERDA.

■ Sampling locations are shown on Figure A-4.

**2004 Monitoring Program
On-Site Effluent Monitoring**

Liquid Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency	
WNSP001 <i>Lagoon 3 Discharge Weir</i>	Primary point of liquid effluent batch release <u>Required by:</u> <ul style="list-style-type: none"> • SPDES permit <u>Reported in:</u> <ul style="list-style-type: none"> • Monthly SPDES DMR • ESR • MTARs • ASER 	Grab liquid	Daily, during lagoon 3 discharge*	24-56	Daily for gross beta, conductivity, flow	
					12-24	Near the start, middle, and end of each discharge, a sample is analyzed for gross alpha/beta, H-3, Sr-90, gamma isotopic
					Composite of daily samples for each discharge, 4-8	Weighted composite for gross alpha/beta, H-3, C-14, Sr-90, Tc-99, I-129, gamma isotopic, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, and Am-241 for each month of discharge
		Composite liquid	Twice during discharge, near start and near end	8-16	Two 24-hour composites for BOD ₅ , total suspended solids, SO ₄ , NO ₃ -N, NO ₂ -N, NH ₃ , total Al, Fe, Hg, and Mn, total recoverable Cd, Cr, Cu, Ni, Pb, and Zn, dissolved As and Cu, dissolved sulfide	
		Grab liquid	Twice during discharge, near start and near end	8-16	Settleable solids, total dissolved solids, pH, cyanide amenable to chlorination, oil & grease, surfactant (as LAS), total recoverable Co, Cr ⁺⁶ , Se, and V, 3,3-dichlorobenzidine, tributyl phosphate, hexachlorobenzene, alpha-BHC, heptachlor, xylene, 2-butanone	
		Composite liquid	Quarterly**	8	A 24-hour composite for bromide and boron	
		Composite liquid	Semiannual**	4	A 24-hour composite for titanium	
		Composite liquid	Annual**	2	A 24-hour composite for Ba and Sb	
		Grab liquid	Semiannual**	4	Bis(2-ethylhexyl) phthalate, 4-dodecene	
		Grab liquid	Annual**	2	Chloroform, dichlorodifluoromethane, trichlorofluoromethane	

* Lagoon 3 is discharged four to eight times per year, as necessary, averaging six to seven days per discharge.

** Two samples are collected, one near the start and one near the end of the discharge.

Sampling Rationale

WNSP001 DOE Order 5400.5; DOE/EH-0173T, 2.3.3; New York State SPDES Permit no. NY0000973

By DOE Order all liquid effluent streams from DOE facilities shall be evaluated and their potential for release of radionuclides addressed. These requirements for radiological parameters are met by daily grab sampling during periods of lagoon 3 discharge.

Sampling for chemical constituents is performed near the beginning and end of each discharge period to meet the site SPDES Permit. Both grab samples and 24-hour composite samples are collected.

For permit requirements, total Hg is analyzed by U.S. EPA Method 245.1. For mercury studies, samples are analyzed by EPA Method 1631.

- Sampling location is shown on Figure A-2.

**2004 Monitoring Program
On-Site Effluent Monitoring**

Liquid Effluents

<u>Sample Location Code</u>	<u>Monitoring/Reporting Requirements</u>	<u>Sampling Type/Medium</u>	<u>Collection Frequency</u>	<u>Total Annual Sample Collections</u>	<u>Analyses Performed/ Composite Frequency</u>
WNSP01B <i>Internal Process Monitoring Point</i>	Internal point for monitoring Hg at effluent of the Hg pretreatment process <u>Required by:</u> <ul style="list-style-type: none"> • SPDES Permit <u>Reported in:</u> <ul style="list-style-type: none"> • Monthly SPDES DMR 	Continuous	→ Weekly	→ NA	→ Flow
		Continuous	→ Monthly	→ NA	→ Flow time
		Composite liquid	→ Twice per month when operating	→ 24	→ Total Hg
WNSP116 <i>Pseudo-Monitoring Point Outfall 116</i>	Calculated concentration of dissolved solids at pseudo-monitoring point in Frank's Creek. Based upon TDS at WNSP001, WNSP006, and augmentation water. <u>Required by:</u> <ul style="list-style-type: none"> • SPDES Permit <u>Reported in:</u> <ul style="list-style-type: none"> • Monthly SPDES DMR 	Calculated	→ Twice per discharge event	→ 8-16	→ Total dissolved solids

NA - Not applicable

Sampling Rationale

WNSP01B New York State SPDES Permit no. NY0000973

This internal point is used to monitor mercury in effluent from the proposed mercury pretreatment process. Effluent from this point is subsequently released to lagoon 3, which is monitored at point WNSP001.

For permit requirements, total Hg is analyzed by U.S. EPA Method 245.1. For mercury studies, samples are analyzed by EPA Method 1631.

WNSP116 New York State SPDES Permit no. NY0000973

This “pseudo-monitoring point,” assumed to be in Frank’s Creek, is calculated from actual total dissolved solids (TDS) measurements and flow measurements from points WNSP001 and WNSP006 and from augmentation water.

- Sampling location WNSP116 is shown on Figure A-2. Sampling location WNSP01B is not shown on the figures.

2004 Monitoring Program On-Site Effluent Monitoring

Liquid Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency	
WNSP006 <i>Frank's Creek at the Security Fence</i>	Combined facility liquid discharge <u>Required by:</u> <ul style="list-style-type: none"> • SPDES Permit <u>Reported in:</u> <ul style="list-style-type: none"> • Monthly SPDES DMR • MTARs • ASER 	Timed continuous composite liquid	→ Weekly →	52	→ Gross alpha/beta, H-3	
					Weekly samples composited to 12	→ Monthly composite for gamma isotopic and Sr-90 (shared with NYSDOH)
					Weekly samples composited to 4	→ Quarterly composite for C-14, Tc-99, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
		Grab liquid	→ Four per discharge, before start, near start, near end, and after end →	16-32	→ TDS	
		Grab liquid	→ Monthly →	12	→ Hardness (Ca and Mg)	
		Grab liquid	→ Semiannual* →	2	→ Temperature (field), pH (field), dissolved oxygen (field), TOX, oil and grease	
		Grab liquid	→ Semiannual* →	2	→ TSS, NPOC, NH ₃ (as N), NO ₃ (as N), NO ₂ (as N), bromide, fluoride, chloride, sulfate, total sulfide, surfactant (as LAS), alpha-BHC, B, Ba, Co, Fe, Na, Mn, Sb, Ti, Tl, V, dissolved Al, As, Cd, Cr, Cu, Hg (method 1631), Ni, Pb, Se, Zn	
WNURRAW <i>Utility Room Raw Water</i>	Source water <u>Required by:</u> <ul style="list-style-type: none"> • SPDES Permit <u>Reported in:</u> <ul style="list-style-type: none"> • Monthly SPDES DMR 	Composite liquid	→ Weekly →	52	→ Total Fe	
		Grab liquid	→ Three per discharge, before start, near start, and near end →	12-24	→ TDS	
		Grab liquid	→ Monthly →	12	→ TOC, alkalinity	
		Grab liquid	→ Quarterly →	4	→ Giardia, cryptosporidium, heterotrophic bacteria	

* Semiannual samples collected when points WNSP001 and WNSP007 are discharging.

Sampling Rationale

WNSP006 DOE/EH-0173T, 5.10.1.1; New York State SPDES Permit no. NY0000973; 6 NYCRR, Parts 702–704

By DOE Order all liquid effluent streams from DOE facilities shall be evaluated and their potential for release of radionuclides addressed.

TDS is measured before the discharge begins, shortly after it begins, near the end, and after the end of each lagoon 3 discharge period to meet requirements of the site SPDES Permit. Measurements of TDS and flow are used to calculate TDS at pseudo-monitoring point outfall 116 in Frank's Creek.

Semiannual samples are collected when WNSP001 and WNSP007 are discharging.

WNURRAW New York State SPDES Permit no. NY0000973; 10 NYCRR, Part 5, Subpart 5-1

TDS is measured near the beginning and end of each lagoon 3 discharge. Results are used for outfall 116 calculations. (See **WNSP006** above.)

- Sampling location WNSP006 is shown on Figure A-2. Sampling location WNURRAW is not shown on the figures.

**2004 Monitoring Program
On-Site Effluent Monitoring**

Liquid Effluents

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
WNSP007 <i>Sanitary Waste Discharge</i>	Liquid effluent point for sanitary and utility plant combined discharge <u>Required by:</u> <ul style="list-style-type: none"> • SPDES Permit <u>Reported in:</u> <ul style="list-style-type: none"> • Monthly SPDES DMR • ESR • MTARs • ASER 	24-hour composite liquid	→ 3 each month →	36	→ Gross alpha/beta, H-3, pH, total suspended solids, NH ₃ , NO ₂ -N, BOD ₅ , total Fe, flow
				Monthly samples composited to 4	→ Quarterly composite for gamma isotopic and Sr-90
		Grab liquid	→ 3 each month →	36	→ Oil & grease
		Grab liquid	→ Weekly →	52	→ pH, settleable solids, total residual chlorine, temperature
		Grab liquid	→ Annual →	1	→ Chloroform
		Grab liquid	→ Monthly →	12	→ Flow, flow time

Sampling Rationale

WNSP007 DOE Order 5400.5; DOE/EH-0173T, 2.3.3; New York State SPDES Permit no. NY0000973

Monitoring of treated effluent from the sanitary and industrial wastewater treatment facility is performed in accordance with the New York State SPDES Permit no. NY0000973 and DOE Order 5400.5 criteria.

- Sampling location WNSP007 is shown on Figure A-2.

**2004 Monitoring Program
Environmental Surveillance**

On-Site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WNSWAMP Northeast Swamp Drainage	Site surface drainage <u>Reported in:</u> • ESR • MTARs • ASER	Timed continuous composite liquid	→ Weekly →	52 Weekly samples composited to 12 Weekly samples composited to 4	→ Gross alpha/beta, H-3, flow → Monthly composite for gamma isotopic and Sr-90 (shared with NYSDOH) → Quarterly composite for C-14, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
		Grab liquid	→ Semiannual* →	2	→ Temperature (field), pH (field), TOX, oil and grease
		24-hour timed continuous composite	→ Semiannual* →	2	→ TSS, TDS, NPOC, NH ₃ (as N), NO ₃ (as N), NO ₂ (as N), bromide, fluoride, sulfate, total sulfide, surfactant (as LAS), alpha-BHC, hardness (Ca and Mg), total Al, B, Cd, Co, Cr, Cu, Fe, Hg (method 1631), Mn, Ni, Pb, Sb, Se, Ti, Tl, V, Zn, dissolved As, Cu
WNSW74A North Swamp Drainage	Site surface drainage <u>Reported in:</u> • ESR • MTARs • ASER	Timed continuous composite liquid	→ Weekly →	52 Weekly samples composited to 12 Weekly samples composited to 4	→ Gross alpha/beta, H-3 → Monthly composite for gamma isotopic and Sr-90 → Quarterly composite for C-14, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
		Grab liquid	→ Semiannual* →	2	→ Temperature (field), pH (field), TOX, oil and grease
		24-hour timed continuous composite	→ Semiannual* →	2	→ TSS, TDS, NPOC, NH ₃ (as N), NO ₃ (as N), NO ₂ (as N), bromide, fluoride, sulfate, total sulfide, surfactant (as LAS), alpha-BHC, hardness (Ca and Mg), total Al, B, Cd, Co, Cr, Cu, Fe, Hg (method 1631), Mn, Ni, Pb, Sb, Se, Ti, Tl, V, Zn, dissolved As, Cu

* Sampled during ambient (i.e., non-wet weather) conditions.

Sampling Rationale

WNSWAMP DOE/EH-0173T, 5.10.1.1; 40 CFR, Part 122.26

Northeast site surface water drainage; provides for sampling of uncontrolled surface waters from this discrete drainage path just before they leave the site's controlled boundary. Waters represent surface and subsurface drainages from the construction and demolition debris landfill (CDDL), old hardstand areas, and other possible north plateau sources of radiological or nonradiological contamination on the north plateau.

Monitoring for nonradiological parameters is performed during ambient conditions to verify authorized non-storm water flows. Storm water monitoring is performed per WVDP-233, "Monitoring Plan for Storm Water Discharges at the West Valley Demonstration Project."

WNSW74A DOE/EH-0173T, 5.10.1.1; 40 CFR, Part 122.26

North site surface water drainage; provides for sampling of uncontrolled surface waters from this discrete drainage path just before they leave the site's controlled boundary. Waters represent surface and subsurface drainages from lag storage areas and other possible sources of radiological or nonradiological contamination on the north plateau.

Monitoring for nonradiological parameters is performed during ambient conditions to verify authorized non-storm water flows. Storm water monitoring is performed per WVDP-233.

- Sampling locations are shown on Figure A-2.

**2004 Monitoring Program
Environmental Surveillance**

On-Site Surface Water

<u>Sample Location Code</u>	<u>Monitoring/Reporting Requirements</u>	<u>Sampling Type/Medium</u>	<u>Collection Frequency</u>	<u>Total Annual Sample Collections</u>	<u>Analyses Performed/ Composite Frequency</u>
WNSDADR <i>SDA Run-Off</i>	Surface water run-off from south portion of SDA <u>Required by:</u> <ul style="list-style-type: none"> Interim Measures Compliance <u>Reported in:</u> <ul style="list-style-type: none"> ASER Reported to NYSERDA 	Grab liquid	→ Monthly	→ 12 maximum	→ pH, total suspended solids, oil & grease, flow, gross alpha/beta, H-3, gamma isotopic, precipitation
WNSP008* <i>French Drain</i>	Drains subsurface water from LLWTF lagoon area <u>Required by:</u> <ul style="list-style-type: none"> SPDES Permit <u>Reported in:</u> <ul style="list-style-type: none"> Monthly SPDES DMR ESR MTARs ASER 	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3
WNSP005 <i>Facility Yard Drainage</i>	Combined drainage from facility yard area <u>Reported in:</u> <ul style="list-style-type: none"> MTARs ASER 	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, pH
WNCoolW <i>Cooling Tower Basin</i>	Cools plant utility steam system water <u>Reported in:</u> <ul style="list-style-type: none"> MTARs ASER 	Grab liquid	→ Quarterly	→ 4	→ Gross alpha/beta, H-3, gamma isotopic, Sr-90, pH
				Monthly samples composited to 4	→ Quarterly composite for gamma isotopic and Sr-90

* Although WNSP008 is listed in the SPDES Permit, it was capped off in May 2001 and is no longer being sampled.

Sampling Rationale

WNSDADR NYSERDA interim measures compliance.

WNSP008 DOE/EH-0173T, 5.10.1.3; New York State SPDES Permit no. NY0000973

French drain of subsurface water from lagoon (LLWTF) area. The SPDES Permit also provides for sampling of uncontrolled subsurface water from this discrete drainage path before these waters flow into Erdman Brook. Waters represent subsurface drainages from downward infiltration around the LLWTF and lagoon systems. This point would also monitor any subsurface spillover from the overflowing of lagoons 2 and 3. Sampling is of significance for both radiological and nonradiological contamination. This point was capped off in May 2001 and is routinely checked to verify that there is no discharge.

WNSP005 Generally in accordance with DOE/EH-0173T, 5.10.1.1 (previously in accordance with SPDES permit no. NY0000973)

Provides for the sampling of uncontrolled surface waters from this discrete drainage path after outfall 007 discharge into the drainage and before these waters flow into Erdman Brook. Waters represent surface and subsurface drainages primarily from the main plant yard area. Historically, this point was used to monitor sludge pond and utility room discharges to the drainage. These two sources have been rerouted. Migration of residual site contamination around the main plant dictates surveillance of this point, primarily for radiological parameters.

WNCoolW Generally in accordance with DOE/EH-0173T, 5.10.1.1

Operational sampling carried out to confirm that radiological contamination is not migrating into the primary coolant loop of the high-level waste treatment facility and/or plant utility steam systems. Migration from either source might indicate radiological control failure.

■ Sampling locations are shown on Figure A-2.

2004 Monitoring Program Environmental Surveillance

On-Site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WNFRC67* <i>Frank's Creek East of the SDA</i>	Drains NYS Low-level Waste Disposal Area <u>Reported in:</u> • MTARs • ASER • Reported to NYSERDA	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, pH
				Monthly samples composited to 4	→ Quarterly composites for gamma isotopic and Sr-90
WNERB53* <i>Erdman Brook North of Disposal Areas</i>	Drains NYS and WVDP disposal areas <u>Reported in:</u> • MTARs • ASER • Reported to NYSERDA	Grab liquid	→ Weekly	→ 52	→ Gross alpha/beta, H-3, pH
				Weekly samples composited to 4	→ Quarterly composites for gamma isotopic and Sr-90
WNNDADR <i>Drainage Between NDA and SDA</i>	Drains WVDP disposal and storage area <u>Reported in:</u> • MTARs • ASER • Reported to NYSERDA	Timed continuous composite liquid	→ Weekly	→ 52	→ pH, H-3
				Weekly samples composited to 12	→ Monthly composite for gross alpha/beta, gamma isotopic, H-3
				Weekly samples composited to 4	→ Quarterly composite for Sr-90, I-129
WNDCELD <i>Drainage South of Drum Cell</i>	Drains WVDP storage area <u>Reported in:</u> • MTARs • ASER • Reported to NYSERDA	Grab liquid	→ Monthly	→ 52	→ NPOC, TOX
				Grab liquid	→ Monthly
WNNDATR** <i>NDA Trench Interceptor Project</i>	On-site groundwa- ter interception <u>Reported in:</u> • MTARs • ASER	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, gamma isotopic, NPOC, TOX
				Monthly samples composited to 4	→ Quarterly composite for I-129

* Monthly sample also collected by NYSDOH

** Coordinated with Main Plant Operations

Sampling Rationale

WNFRC67	DOE/EH-0173T, 5.10.1.1 Monitors the potential influence of both the SDA and drum cell drainage into Frank's Creek east of the SDA and upstream of its confluence with Erdman Brook.
WNERB53	DOE/EH-0173T, 5.10.1.1 Monitors the potential influence of the drainages from the SDA and the WVDP storage and disposal area into Erdman Brook upstream of its confluence with Frank's Creek.
WNNDADR	DOE/EH-0173T, 5.10.1.1 Monitors the potential influence of the drainages from the SDA and the WVDP storage and disposal area into Lagoon Road Creek upstream of the creek's confluence with Erdman Brook.
WNDCELD	DOE/EH-0173T, 5.10.1.1 Monitors the potential influence of drum cell drainage into Frank's Creek south of the SDA and upstream of WNFRC67 .
WNNDATR	Generally in accordance with DOE/EH-0173T, 5.10.1.1 Monitors groundwater in the vicinity of the NDA interceptor trench project. The grab sample is taken directly from the trench collection system.

- Sampling locations are shown on Figure A-2.

2004 Monitoring Program Environmental Surveillance

On-Site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
<p>WNSTAW Series <i>On-Site Standing Water Ponds Not Receiving Effluent</i></p> <p>WNSTAW4 <i>Border Pond Southwest of AFRT240</i></p> <p>WNSTAW5 <i>Border Pond Southwest of DFTLD13</i></p> <p>WNSTAW6 <i>Borrow Pit Northeast of Project Facilities</i></p> <p>WNSTAW9 <i>North Reservoir Near Intake</i></p> <p>WNSTAWB <i>Background Pond at Sprague Brook Maintenance Building</i></p>	<p>Water within vicinity of airborne or water effluent from the plant</p> <p><u>Reported in:</u></p> <ul style="list-style-type: none"> • MTARs • ASER 	<p>Grab liquid</p>	<p>→ Annual</p>	<p>→ 1 each location*</p>	<p>→ Gross alpha/beta, H-3, Sr-90, gamma isotopic, pH, conductivity, Cl, Fe, Mn, Na, NO₃+NO₂-N, SO₄</p>

* Sampling depends upon on-site ponding conditions during the year.

Sampling Rationale

WNSTAW Series DOE/EH-0173T, 5.10.1.1

Monitoring of on- and off-site standing waters at locations listed below. Although none receive effluent directly, the potential for contamination is present except at the background location. Former collecting sites 1,2,3,7, and 8 were deleted from the monitoring program because they were either built over or are now dry.

WNSTAW4 Border pond located south of **AFRT240**. Chosen as a location for showing potentially high concentrations, based on meteorological data. This perimeter location is next to a working farm. Drainage extends through private property and is accessible by the public.

WNSTAW5 Border pond located west of Project facilities near the perimeter fence and **DFTLD13**. Chosen as a location for showing potentially high concentrations, based on meteorological data. Location is next to a private residence and potentially accessible by the general public.

WNSTAW6 Borrow pit northeast of Project facilities just outside the inner security fence. Considered the closest standing water to the main plant and high-level waste facilities.

WNSTAW9 North reservoir near intake. Chosen to provide data in the event of potentially contaminated site potable water supply. Location is south of main plant facilities.

WNSTAWB Pond located near the Sprague Brook maintenance building. Considered a background location; approximately 14 kilometers north of the WVDP.

■ Sampling locations are shown on Figures A-2, A-3, and A-13.

2004 Monitoring Program Environmental Surveillance

On-Site Potable Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WNDNK Series <i>Site Potable Water</i>	Sources of potable water within site perimeter <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER • Also reported to Cattaraugus County 	Grab liquid →	Every third month (rotate sampling at WNDNKMS, WNDNKMP, WNDNKEL) →	4 each location	→ Gross alpha/beta, H-3, pH, conductivity
WNDNKMS <i>Maintenance Shop Drinking Water</i>					
WNDNKMP <i>Main Plant Drinking Water</i>		Grab liquid →	Quarterly (WNDNKEL only) →	4	→ Total haloacetic acids, total trihalomethanes, giardia, cryptosporidium, heterotrophic bacteria
WNDNKEL <i>Environmental Laboratory Drinking Water</i>					
WNDNKUR <i>Utility Room (EP-1) Potable Water Storage Tank</i>	Sources of potable water within site perimeter <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER • Also reported to Cattaraugus County 	Grab liquid →	Monthly →	12	→ Gross alpha/beta, H-3, pH, conductivity
		Grab liquid* →	Annual →	1	→ As, Ba, Be, Cd, Cr, Hg, Ni, Sb, Se, Tl, cyanide, fluoride

* Sample for NO₃ (as total nitrate) is collected by the Cattaraugus County Health Department. Pb and Cu also are sampled at this site based upon Cattaraugus County Health Department guidance.

Sampling Rationale

WNDNK Series	Site drinking water; generally according to DOE/EH-0173T, 5.10.1.2; 10 NYCRR, Part 5, Subpart 5-1 Potable water sampling to confirm no migration of radiological and/or nonradiological contamination into the site's drinking water supply.
WNDNKMS	Potable water sampled at the maintenance shop in order to monitor a point that is at an intermediate distance from the point of potable water generation and that is used heavily by site personnel.
WNDNKMP	Same rationale as WNDNKMS but sampled at the break room sink in the main plant.
WNDNKEL	Potable water sampled at the Environmental Laboratory. Disinfectant by-products are sampled at WNDNKEL , the furthest location from the entry point (WNDNKUR).
WNDNKUR	Sampled at the utility room potable water storage tank before the site drinking water distribution system. Sample location is entry point EP-1.

- Sampling locations are within the site facilities and are not detailed on figures.

**2004 Monitoring Program
Environmental Surveillance**

On-Site Groundwater

<u>Sample Location Code</u>	<u>Monitoring/Reporting Requirements</u>	<u>Sampling Type/Medium</u>	<u>Collection Frequency</u>	<u>Total Annual Sample Collections</u>	<u>Analyses Performed/ Composite Frequency</u>
Low-Level Waste Treatment Facility <i>(SSWMU #1)</i> 103 104 C 105 C 106 107 108 110 111 116 U 8604 C 8605	Groundwater monitoring points around site super solid waste management units (SSWMUs) <u>Reported in:</u> <ul style="list-style-type: none"> • ASER • Quarterly Ground-water Reports 	Grab liquid →	4 times per year (generally)* →	4 each well (generally)* →	Gross alpha, gross beta, H-3* →
Miscellaneous Small Units <i>(SSWMU #2)</i> 201 U 204 205 206 C 208 Liquid Waste Treatment System <i>(SSWMU #3)</i> 301 B 302 U		Direct field measurement of sampled water →	Each sampling event* →	Twice each sampling event →	Conductivity, pH →

NOTE: "U" designates upgradient, "B" designates background, and "C" designates crossgradient wells. The remainder are downgradient.

* Sampling frequency and analytes vary from point to point. See Appendix E^{ca} for a summary listing of all monitored analytes, a listing of analytes monitored at each location, and results from each location.

Sampling Rationale

On-Site Groundwater	<p>DOE/EH-0173T, 5.10.1.3; 40 CFR, Parts 264 and 265, Subpart F</p> <p>The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection was addressed in the "Groundwater Protection Management Program Plan," WVDP-091. Groundwater monitoring was detailed in the "Groundwater Monitoring Plan," WVDP-239.</p>
SSWMU #1	Low-level waste treatment facilities, including four active lagoons – lagoons 2, 3, 4, and 5 – and an inactive, filled-in lagoon – lagoon 1.
SSWMU #2	Miscellaneous small units, including the sludge pond, the solvent dike, the paper incinerator, the equalization basin, and the kerosene tank.
SSWMU #3	Liquid waste treatment system containing effluent from the supernatant treatment system.

- Sampling locations are shown on Figures A-6 and A-7.

2004 Monitoring Program Environmental Surveillance

On-Site Groundwater

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
HLW Storage and Processing Tank (SSWMU #4)					
401 B	Groundwater monitoring points around site super solid waste management units (SSWMUs)	Grab liquid	→ 4 times per year (generally)*	→ 4 each well (generally)*	→ Gross alpha, gross beta, H-3*
402 U					
403 U					
405 C					
406					
408					
409					
Maintenance Shop Leach Field (SSWMU #5)					
501 U	<u>Reported in:</u> <ul style="list-style-type: none">• ASER• Quarterly Ground-water Reports	Direct field measurement of sampled water	→ Each sampling event*	→ Twice each sampling event	→ Conductivity, pH
502					
Low-Level Waste Storage Area (SSWMU #6)					
602A					
604					
605					
8607 U					
8609 U					
Chemical Process Cell Waste Storage Area (SSWMU #7)					
704					
706 B					
707 C					

NOTE: "U" designates upgradient, "B" designates background, and "C" designates crossgradient wells. The remainder are downgradient.

* Sampling frequency and analytes vary from point to point. See Appendix E⁶³ for a summary listing of all monitored analytes, a listing of analytes monitored at each location, and results from each location.

Sampling Rationale

On-Site Groundwater	DOE/EH-0173T, 5.10.1.3; 40 CFR, Parts 264 and 265, Subpart F The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection was addressed in the "Groundwater Protection Management Program Plan," WVDP-091. Groundwater monitoring was detailed in the "Groundwater Monitoring Plan," WVDP-239.
SSWMU #4	High-level waste storage and processing area, including the high-level radioactive waste tanks, the supernatant treatment system, and the vitrification facility.
SSWMU #5	Maintenance shop sanitary leach field, formerly used by NFS and the WVDP to process domestic sewage generated by the maintenance shop.
SSWMU #6	Low-level waste storage area; includes metal and fabric structures housing low-level radioactive waste being stored for future disposal.
SSWMU #7	Chemical process cell (CPC) waste storage area, which contains packages of pipes, vessels, and debris from decontamination and cleanup of the chemical process cell in the former reprocessing plant.

- Sampling locations are shown on Figures A-6 and A-7.

**2004 Monitoring Program
Environmental Surveillance**

On-Site Groundwater

<u>Sample Location Code</u>	<u>Monitoring/Reporting Requirements</u>	<u>Sampling Type/Medium</u>	<u>Collection Frequency</u>	<u>Total Annual Sample Collections</u>	<u>Analyses Performed/ Composite Frequency</u>
Construction and Demolition Debris Landfill (CDDL) (SSWMU #8) 801 U 802 803 804 8603 U 8612	Groundwater monitoring points around site super solid waste management units (SSWMUs) <u>Reported in:</u> <ul style="list-style-type: none"> • ASER • Quarterly Ground-water Reports 	Grab liquid	→ 4 times per year (generally)*	→ 4 each well (generally)*	→ Gross alpha, gross beta, H-3*
NRC-Licensed Disposal Area (NDA) (SSWMU #9) 901 U 902 U 903 906 908 U 909 910 8610 8611 NDATR		Direct field measurement of sampled water	→ Each sampling event*	→ Twice each sampling event	→ Conductivity, pH
IRTS Drum Cell (SSWMU #10) 1005 U 1006 1007 1008b B 1008c B	Groundwater monitoring points around the new RHWF <u>Reported in:</u> <ul style="list-style-type: none"> • ASER • Quarterly Ground-water Reports 	Grab liquid	→ 4 times per year	→ 4 each well	→ Gross alpha, gross beta, H-3*
Remote-Handled Waste Facility (Not in a SSWMU) 1301 U 1302 U 1303 1304		Direct field measurement of sampled water	→ Each sampling event	→ Twice each sampling event	→ Conductivity, pH

NOTE: "U" designates upgradient, "B" designates background, and "C" designates crossgradient wells. The remainder are downgradient.

* Sampling frequency and analytes vary from point to point. See Appendix E⁶⁹ for a summary listing of all monitored analytes, a listing of analytes monitored at each location, and results from each location.

Sampling Rationale

On-Site Groundwater	DOE/EH-0173T, 5.10.1.3; 40 CFR, Parts 264 and 265, Subpart F The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection was addressed in the "Groundwater Protection Management Program Plan," WVDP-091. Groundwater monitoring was detailed in the "Groundwater Monitoring Plan," WVDP-239.
SSWMU #8	The construction and demolition debris landfill (CDDL); used by NFS and the WVDP to dispose of nonhazardous and nonradioactive materials.
SSWMU #9	The NRC-licensed disposal area (NDA); contains radioactive wastes generated by NFS and the WVDP. The NDA is bounded on its downgradient (northwest and northeast) perimeters by the interceptor trench, which is sampled at monitoring point NDATR.
SSWMU #10	The integrated radioactive waste system (IRTS) treatment drum cell; stores cement-stabilized low-level radioactive waste.
Remote-Handled Waste Facility	Establish pre-operational baseline groundwater conditions in the area of the newly constructed remote-handled waste facility (RHWF). Monitor groundwater in the vicinity of the RHWF.

- Sampling locations are shown on Figures A-6 through A-8.

2004 Monitoring Program Environmental Surveillance

On-Site Groundwater and Seeps

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/Composite Frequency
State-Licensed Disposal Area (SSWMU #11)*					
1101a U 1101b U 1101c U 1102a 1102b 1103a 1103b 1103c 1104a 1104b 1104c 1105a 1105b 1106a U 1106b U 1107a 1108a U 1109a U 1109b U 1110a 1111a	Groundwater monitoring points around site super solid waste management units (SSWMUs) <u>Reported in:</u> • ASER	Grab liquid →	Semiannual →	2 each well	→ Gross alpha/beta, H-3, pH, conductivity, turbidity
		Grab liquid →	Annual →	1 each well	→ Gamma scan, beta-emitters (C-14, Sr-90, Tc-99, I-129), VOCs
North Plateau Seeps (Not in an SSWMU)					
GSEEP SP04 SP06 SP11 SP12	Groundwater seepage points along the northeastern edge of the north plateau <u>Reported in:</u> • ASER • Quarterly Groundwater Reports	Grab liquid →	Semiannual (Quarterly at GSEEP) →	2 each seep (4 at GSEEP)	→ Gross alpha/beta, H-3, and (VOCs at GSEEP and SP12)
		Direct field measurement of sampled water →	Semiannual at SP12 (Quarterly at GSEEP) →	2 at SP12 (4 at GSEEP)	→ pH, conductivity
Miscellaneous Well Points (Not in an SSWMU)					
WP-A WP-C WP-H NB1S (Former Background Well)	Well points down-gradient of main plant and the former sand and gravel unit background well <u>Reported in:</u> • ASER • Quarterly Groundwater Reports	Grab liquid →	Annual (Quarterly at NB1S) →	1 each well (4 at NB1S)	→ Gross alpha/beta, H-3
		Direct field measurement of sampled water →	Annual (Quarterly at NB1S) →	1 each well (4 at NB1S)	→ pH, conductivity

NOTE: "U" designates upgradient, "B" designates background, and "C" designates crossgradient wells. The remainder are downgradient.

* SSWMU #11 is sampled by NYSERDA under a separate program.

Sampling Rationale

On-Site Groundwater	DOE/EH-0173T, 5.10.1.3; 40 CFR, Parts 264 and 265, Subpart F The on-site WVDP groundwater monitoring program provides for the determination of water quality, focusing on radiological and chemical surveillance of both active and inactive super solid waste management units (SSWMUs). In addition, using wells situated hydraulically upgradient (background) and downgradient of SSWMUs allows both detection of groundwater contamination and evaluation of the effects associated with the individual SSWMUs. Groundwater protection was addressed in the "Groundwater Protection Management Program Plan," WVDP-091. Groundwater monitoring was detailed in the "Groundwater Monitoring Plan," WVDP-239.
SSWMU #11	The New York State-licensed disposal area (SDA) was operated by NFS as a commercial low-level disposal facility; it also received wastes from NFS reprocessing operations.
North Plateau Seeps	Monitor groundwater emanating from the ground surface along the edge of the site's north plateau.
Well Points	Monitor groundwater of known subsurface contamination in the north plateau area. All well points are downgradient of the main plant.
WNWNB1S	Former background well on the north plateau.

- Sampling locations are shown on Figures A-6 through A-8.

2004 Monitoring Program Environmental Surveillance

Off-Site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WFBCBKG* <i>Buttermilk Creek Near Fox Valley (Background)</i>	Unrestricted surface water, background <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER • Reported to NYSERDA 	Timed continuous composite liquid	→ Weekly →	52 weekly samples composited to 12 Weekly samples composited to 4	→ Monthly composite for gross alpha/beta, H-3 → Quarterly composite for gamma isotopic, C-14, Sr-90, Tc-99, I-129, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
		Grab liquid	→ Monthly →	12	→ Hardness (Ca and Mg)
		Grab liquid	→ Semiannual** →	2	→ Temperature (field), pH (field), dissolved oxygen (field), TOX, oil and grease
		24-hour timed continuous composite	→ Semiannual** →	2	→ TSS, TDS, NPOC, NH ₃ (as N), NO ₃ (as N), NO ₂ (as N), bromide, fluoride, chloride, sulfate, total sulfide, surfactant (as LAS), alpha-BHC, B, Ba, Co, Fe, Na, Mn, Sb, Ti, Tl, V, dissolved Al, As, Cd, Cr, Cu, Hg (method 1631), Ni, Pb, Se, Zn
WFBCTCB* <i>Buttermilk Creek Upstream of Confluence With Cattaraugus Creek at Thomas Corners Road</i>	Restricted surface waters receiving plant effluents <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Timed continuous composite liquid	→ Weekly →	52 weekly samples composited to 12 Weekly samples composited to 4	→ Monthly composite for gross alpha/beta, H-3 → Quarterly composite for gamma isotopic, Sr-90, Tc-99
		Grab liquid	→ Monthly →	12	→ Hardness (Ca and Mg)
		Grab liquid	→ Semiannual** →	2	→ Temperature (field), pH (field), dissolved oxygen (field), TOX, oil and grease
		24-hour timed continuous composite	→ Semiannual** →	2	→ TSS, TDS, NPOC, NH ₃ (as N), NO ₃ (as N), NO ₂ (as N), bromide, fluoride, chloride, sulfate, total sulfide, surfactant (as LAS), alpha-BHC, B, Ba, Co, Fe, Na, Mn, Sb, Ti, Tl, V, dissolved Al, As, Cd, Cr, Cu, Hg (method 1631), Ni, Pb, Se, Zn

* Monthly composites are also sent to NYSDOH.

** Semiannual samples collected when points WNSP001 and WNSP007 are discharging.

Sampling Rationale

WFBCBKG DOE/EH-0173T, 5.10.1.1; 6 NYCRR, Part 702–704

Monitors background conditions of Buttermilk Creek upstream of the WVDP; allows for comparison to downstream conditions. Monitoring for nonradiological parameters performed during discharges from WNSP001 and WNSP007 for comparison with downstream conditions.

WFBCTCB DOE/EH-0173T, 5.10.1.1; 6 NYCRR, Part 702–704

Buttermilk Creek is the surface water that receives all WVDP effluents. **WFBCTCB** monitors the potential influence of WVDP drainage into Buttermilk Creek upstream of Buttermilk Creek's confluence with Cattaraugus Creek. Monitoring for nonradiological parameters performed during discharges from WNSP001 and WNSP007 for comparison with New York State ambient water quality standards (6 NYCRR, Part 702–704).

- Sampling locations are shown on Figure A-3.

2004 Monitoring Program Environmental Surveillance

Off-Site Surface Water

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
WFBIGBR <i>Cattaraugus Creek at Bigelow Bridge (Background)</i>	Unrestricted surface water, background <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Grab liquid	→ Monthly	→ 12	→ Gross alpha/beta, H-3, Sr-90, gamma isotopic, pH
WFFELBR* <i>Cattaraugus Creek at Felton Bridge</i>	Unrestricted surface waters receiving plant effluents <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Timed continuous composite liquid	→ Weekly	→ 52 Weekly samples composited to 12 Weekly samples composited to 4	→ Gross alpha/beta, H-3, pH, flow → Flow-weighted monthly composite for gross alpha/beta, H-3, Sr-90, and gamma isotopic → Quarterly composite for Tc-99

* Monthly composites are also sent to NYSDOH.

Sampling Rationale

WFBIGBR DOE/EH-0173T, 5.10.1.1

Monitors background conditions of Cattaraugus Creek at Bigelow Bridge, upstream of the WVDP; allows for comparison to downstream conditions.

WFFELBR DOE/EH-0173T, 5.10.1.1

Because Buttermilk Creek empties into Cattaraugus Creek, **WFFELBR** monitors the potential influence of WVDP drainage into Cattaraugus Creek directly downstream of the Cattaraugus Creek confluence with Buttermilk Creek.

■ Sampling locations are shown on Figure A-3.

**2004 Monitoring Program
Environmental Surveillance**

Off-Site Drinking Water

<u>Sample Location Code</u>	<u>Monitoring/Reporting Requirements</u>	<u>Sampling Type/Medium</u>	<u>Collection Frequency</u>	<u>Total Annual Sample Collections</u>	<u>Analyses Performed/Composite Frequency</u>
WFWEL Series: <i>Wells Outside the WYNSC Perimeter But Near the WVDP</i>					
WFWEL01 <i>3.0 km West-Northwest</i>					
WFWEL02 <i>1.5 km Northwest</i>					
WFWEL03 <i>3.5 km Northwest</i>					
WFWEL04 <i>3.0 km Northwest</i>	Drinking water supply; groundwater near facility*	Grab liquid →	Annual →	1 each location →	Gross alpha/beta, H-3, Sr-90, gamma isotopic, pH, conductivity
WFWEL05 <i>2.5 km Southwest</i>	<u>Reported in:</u>				
WFWEL06 <i>(Background)</i> <i>29 km South</i>	<ul style="list-style-type: none"> • MTARs • ASER 				
WFWEL07 <i>4.4 km North-Northeast</i>					
WFWEL08 <i>2.5 km East-Northeast</i>					
WFWEL09 <i>3.0 km Southeast</i>					
WFWEL10 <i>7.0 km North</i>					

* No drinking water wells are located in hydrogeological units affected by site activity.

Sampling Rationale

Off-Site DOE/EH-0173T, 5.10.1.2

Drinking Water

WFWEL Series Eight of the ten listed off-site private residential drinking water wells represent the nearest unrestricted uses of groundwater close to the WVDP. The ninth sample (**WFWEL10**) is taken from a public water supply from deep wells. The tenth drinking water well, **WFWEL06**, is located 29 kilometers south of the Project and is considered a background drinking water source.

- Sampling locations are shown on Figures A-9, A-12, and A-13.

2004 Monitoring Program Environmental Surveillance

Off-Site Air

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency	
AFEXVRD 3.0 km South-Southeast at Fox Valley	Air samples around WNYNSC perimeter and background <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Continuous → Weekly air particulate filter	→	52 each location →	→ Gross alpha/beta, flow	
AFTCORD 3.7 km North-Northwest at Thomas Corners Road						Weekly filters composited to 4 each location →
AFRT240* 2.0 km Northeast on Route 240						In addition, quarterly composite at
AFSPRVL 9.4 km North at Springville						AFRSPRD and
AFWEVAL 6.2 km South-Southeast at West Valley						AFGRVAL for U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
AFBOEHN 2.3 km Southwest on Dutch Hill Road			Continuous → Weekly desiccant column for water vapor collection at	→	52 each location →	H-3, flow
AFRSPRD 1.5 km Northwest on Rock Springs Road			AFRSPRD and AFGRVAL			
AFGRVAL 29 km South at Great Valley (Background)						
AFBLKST Bulk Storage Ware- house 2.2 km East- Southeast at Buttermilk Road		Continuous → Monthly charcoal cartridge at	→	12 composited to 4 each location →	Quarterly composite for I-129	
		AFRSPRD and AFGRVAL				

* Filter from duplicate sampler sent to NYSDOH.

Sampling Rationale

AFFXVRD	DOE/EH-0173T, 5.7.4
AFTCORD	
AFRT240	Air samplers put into service by NFS as part of the site's original monitoring program at perimeter locations chosen to obtain data from places most likely to provide highest concentrations. Choice of location based on meteorological data.
AFSPRVL	DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3
	Off-site (remote) sampler located on private property in a nearby community within 15 kilometers of the site (north).
AFWEVAL	DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3
	Off-site (remote) sampler located in a nearby community within 15 kilometers of the site (southeast).
AFBOEHN	DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3
	Perimeter location chosen to obtain data from the place most likely to provide the highest elevated release concentrations. AFBOEHN is located on NYSERDA property at the perimeter. Choice of location based on meteorological data.
AFRSPRD	DOE/EH-0173T, 5.7.4
	Perimeter location chosen to obtain data from the place most likely to provide the highest ground-level release concentrations. AFRSPRD is on WNYNSC property outside the main plant operations fenceline. H-3 and I-129 are sampled here because the sampling trains were easy to incorporate and the location was most likely to receive effluent releases. Choice of location based on meteorological data.
AFGRVAL	DOE/EH-0173T, 5.7.4; DOE/EP-0023, 4.2.3
	Off-site (remote) sampler considered representative of natural background radiation. Located on privately owned property 29 kilometers south of the site (typically upwind). H-3 and I-129 sampled here also.
AFBLKST	DOE/EH-0173T, 5.7.4
	Off-site monitoring of bulk storage warehouse, near the site perimeter.

- Sampling locations are shown on Figures A-5, A-12, and A-13.

2004 Monitoring Program Environmental Surveillance

Fallout, Sediment, and Soil

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
AFDHFOP 2.3 km Southwest AFFXFOP 3.0 km South-Southeast AFTCFOP 3.7 km North-Northwest AF24FOP 2.0 km Northeast ANRGFOP Rain Gauge On-Site	Collection of fallout particulates and precipitation around the WNYNSC perimeter <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Integrated precipitation	→ Monthly	→ 12 each location	→ Gross alpha/beta, H-3, pH, gamma isotopic, volume
SF Soil Series Surface Soil at Each of 9 Air Samplers	Long-term fallout accumulation <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Surface plug composite soil	→ Annual	→ 1 each location	→ Gross alpha/beta, gamma isotopic, Sr-90, Pu-238, Pu-239/240, Am-241 In addition at SFRSPRD , SFBOEHN , and SFGRVAL : U-232, U-233/234, U-235/236, U-238, and total U
SFCCSED Cattaraugus Creek at Felton Bridge SFSDSED Cattaraugus Creek at Springville Dam SFBISED Cattaraugus Creek at Bigelow Bridge (Background) SFTCED Buttermilk Creek at Thomas Corners Road SFBCSED Buttermilk Creek at Fox Valley Road (Background)	Deposition in sediment downstream of facility effluents <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Grab stream sediment	→ Annual (Split SFSDSED and SFBCSED with NYSDOH)	→ 1 each location	→ Gross alpha/beta, gamma isotopic, Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, Am-241
SN On-Site Soil Series: SNSW74A (Near WNSW74A) SNSWAMP (Near WNSWAMP) SNSP006 (Near WNSP006)	Surface soil corresponding to site drainage paths may be partially composed of sediments. <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Surface plug or grab	→ Annual	→ 1 each location	→ Gross alpha/beta, gamma isotopic, Sr-90, U-232, U-233/234, U-235/236, U-238, total U, Pu-238, Pu-239/240, and Am-241, Al, Sb, As, Ba, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Hg, Ni, K, Se, Ag, Na, Tl, V, Zn

Sampling Rationale

AFDHFOP	DOE/EP-0023, 4.7
AFFXFOP AFTCFOP AF24FOP	Collection of fallout particles and precipitation around the site perimeter at established air sampling locations: AFDHFOP (Dutch Hill at Boehn Road), AFFXFOP (Fox Valley Road), AFTCFOP (Thomas Corners), AF24FOP (Route 240). Indicates short-term effects.
ANRGFOP	Fallout particles and precipitation collected on-site by the Environmental Laboratory at the rain gauge. Indicates short-term effects.
SF Soil Series	DOE/EH-0173T, 5.9.1 Off-site soils collected at air sampling locations: SFWEVAL (West Valley), SFFXVRD (Fox Valley Road), SFSPRVL (Springville), SFTCORD (Thomas Corners), SFRT240 (Route 240), SFBOEHN (Boehn Road-Dutch Hill), SFGRVAL (Great Valley), SFRSPRD (Rock Springs Road), and SFBLKST (bulk storage warehouse): Collection of long-term fallout data at established air sampler locations via soil sampling.
SFCCSED	DOE/EH-0173T, 5.12.1 Sediment deposition in Cattaraugus Creek at Felton Bridge. Location is the first point of public access to Cattaraugus Creek downstream of its confluence with Buttermilk Creek.
SFSDSED	DOE/EH-0173T, 5.12.1 Sediment deposition in Cattaraugus Creek at Springville Dam. Reservoir provides ideal settling and collection location for sediments downstream of the Buttermilk Creek confluence with Cattaraugus Creek. Located downstream of SFCCSED .
SFBISED	DOE/EH-0173T, 5.12.1 Sediment deposition in Cattaraugus Creek at Bigelow Bridge. Location is upstream of the Buttermilk Creek confluence with Cattaraugus Creek and serves as the Cattaraugus Creek background location.
SFTCSED	DOE/EH-0173T, 5.12.1 Sediment deposition in Buttermilk Creek at Thomas Corners immediately downstream of all facility liquid effluents.
SFBCSED	DOE/EH-0173T, 5.12.1 Sediment deposition in Buttermilk Creek upsteam of facility effluents (background).
SN Soil Series	DOE/EH-0173T, 5.9.1. On-site soil. (Samples may be partially composed of sediments.) SNSW74A (surface soil near WNSW74A), SNSWAMP (surface soil near WNSWAMP), and SNSP006 (surface soil near WNSP006): Locations to be specifically defined by geographic coordinates. Correspond to site drainage pattern flows (i.e., most likely area of radiological deposition/accumulation).

■ Sampling locations are shown on Figures A-2 through A-5, A-12, and A-13.

2004 Monitoring Program Environmental Surveillance

Off-Site Biological

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
<p>BFFCATC <i>Fish From Cattaraugus Creek Downstream of Its Confluence With Buttermilk Creek</i></p> <p>BFFCATD <i>Fish From Cattaraugus Creek Downstream of the Springville Dam</i></p> <p>BFFCTRL <i>Control Fish Sample From Nearby Stream Not Affected by the WVDP (7 km or More Upstream of Site Effluent Point; Background)</i></p>	<p>Fish in waters up- and downstream of facility effluents</p> <p><u>Reported in:</u></p> <ul style="list-style-type: none"> • MTARs • ASER 	<p>Individual collection, biological</p>	<p>→ Annual (samples at BFFCATC and BFFCTRL shared with NYSDOH)</p>	<p>→ 10 fish each location</p>	<p>→ Gamma isotopic and Sr-90 in edible portions of each individual fish, % moisture</p>
<p>BFMREED <i>Dairy Farm 3.8 km North-Northwest</i></p> <p>BFMCTLS <i>Control Location 25 km South (Background)</i></p>	<p>Milk from animals foraging at locations near the facility perimeter and at background sites</p> <p><u>Reported in:</u></p> <ul style="list-style-type: none"> • MTARs • ASER 	<p>Grab biological</p>	<p>→ Monthly (samples at BFMREED shared with NYSDOH)</p>	<p>→ 12 monthly samples composited to 4 each location</p>	<p>→ Quarterly composite for gamma isotopic, H-3, Sr-90, and I-129</p>
<p>BFMWIDR <i>Dairy Farm 3.0 km Southeast</i></p> <p>BFMSCHT <i>Dairy Farm 4.8 km South</i></p>	<p>Milk from animals foraging near the site perimeter</p> <p><u>Reported in:</u></p> <ul style="list-style-type: none"> • MTARs • ASER 	<p>Grab biological</p>	<p>→ Annual</p>	<p>→ 1 each location</p>	<p>→ Gamma isotopic, H-3, Sr-90, and I-129</p>

Sampling Rationale

BFFCATC BFTCATD	DOE/EH-0173T, 5.11.1.1 Radioactivity may enter a food chain in which fish are a major component and are consumed by the local population.
BFFCTRL	Control fish sample; provides background data for comparison with data from fish caught downstream of facility effluents.
BFMREED BFMCTLS BFMWIDR BFMSCHT	DOE/EH-0173T, 5.8.2.1 Milk is consumed by all age groups and is frequently the most important food that could contribute to the radiation dose. Dairy animals pastured near the site allow adequate monitoring. Control milk samples are collected far from the site to provide background data for comparison with data from near-site milk samples.

- Sampling locations are shown on Figures A-9, A-12, and A-13.

2004 Monitoring Program Environmental Surveillance

Off-Site Biological

Sample Location Code	Monitoring/Reporting Requirements	Sampling Type/Medium	Collection Frequency	Total Annual Sample Collections	Analyses Performed/ Composite Frequency
BFVNEAR* <i>Nearby Locations</i> BFVCTRL* <i>Remote Locations (16 km or More From Facility; Background)</i>	Fruit and vegetables grown near facility perimeter, downwind if possible, and at background locations <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Grab biological (fruits and vegetables)	→ Annual (at harvest)	→ 3 each (split with NYSDOH)	→ Gamma isotopic and Sr-90 analysis of edible portions, H-3 in free moisture, % moisture
BFBNEAR <i>Beef Animal From Nearby Farm in Downwind Direction</i> BFBCTRL <i>Beef Animal From Control Location 16 km or More From Facility (Background)</i>	Meat (beef foraging near facility perimeter, downwind if possible, and a background location) <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Grab biological	→ Semiannual	→ 2 each location	→ Gamma isotopic and Sr-90 analysis of meat, H-3 in free moisture, % moisture
BFDNEAR <i>Deer in Vicinity of the Site</i> BFDCTRL <i>Control Deer 16 km or More From the Facility (Background)</i>	Venison (deer foraging near facility perimeter and at background locations) <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Individual collection, biological	→ Annual, during hunting season (BFDNEAR sample split with NYSDOH)	→ 3	→ Gamma isotopic and Sr-90 analysis of meat, H-3 in free moisture, % moisture
			During year as available (BFDCTRL sample split with NYSDOH)	→ 3	→ Gamma isotopic and Sr-90 analysis of meat, H-3 in free moisture, % moisture

* Near-site and control corn, apple, and bean samples are identified specifically as follows: corn = **BFVNEAC** and **BFVCTRC**; apples = **BFVNEAAF** and **BFVCTRA**; beans = **BFVNEAB** and **BFVCTRB**.

Sampling Rationale

- BFVNEAR** DOE/EH-0173T, 5.8.2.2
- Fruits and vegetables (corn, apples, and beans or leafy vegetables, if available) collected from areas near the site. These samples are collected, if possible, from areas near the site predicted to have worst-case downwind concentrations of radionuclides in air and soil. Sample analysis reflects steady state/chronic uptake or contamination of foodstuffs as a result of site activities. Possible pathway directly to humans or indirectly through animals.
- BFVCTRL** DOE/EH-0173T, 5.8.2.2
- Fruits and vegetables collected from an area remote from the site. Background fruits and vegetables collected for comparison with near-site samples. Collected in area(s) of no possible site effects.
- BFBNEAR** DOE/EH-0173T, 5.8.2.3
- Beef collected from animals raised near the site and foraging downwind of the site in areas of maximum probable effects. Following the rationale for vegetable matter collected near the site (**BFVNEAR**), edible flesh portion of beef animals is analyzed to determine possible radionuclide content passable directly to humans.
- BFBCTRL** DOE/EH-0173T, 5.8.2.3
- Beef collected from animals raised far from the site. Background beef collected for comparison with near-site samples. Collected in area(s) of no possible site effects.
- BFDNEAR** DOE/EH-0173T, 5.8.3
- Venison from near-site deer. Samples are taken from deer killed in collisions with vehicles. Sample rationale is similar to **BFBNEAR**.
- BFDCCTRL** DOE/EH-0173T, 5.8.3
- Venison from deer living far from the site. Background deer meat collected for comparison with near-site samples. Collected in area(s) of no possible site effects.

- Sampling locations are shown on Figures A-9, A-12, and A-13.

**2004 Monitoring Program
Environmental Surveillance**

Off-Site Direct Radiation

<u>Sample Location Code</u>	<u>Monitoring/Reporting Requirements</u>	<u>Sampling Type/Medium</u>	<u>Collection Frequency</u>	<u>Total Annual Sample Collections</u>	<u>Analyses Performed/ Composite Frequency</u>
DFTLD Series <i>Thermoluminescent Dosimetry (TLD)</i> <i>Off-Site:</i> #1-#16 <i>Each of 16 Compass Sectors at Nearest Accessible Perimeter Point</i> #20 <i>1,500 m Northwest (Downwind Receptor)</i> #21 <i>Springville 9.4 km North</i> #22 <i>West Valley 6.2 km South-Southeast</i> #23 <i>Great Valley 29 km South (Background)</i>	Direct radiation around facility <u>Reported in:</u> <ul style="list-style-type: none"> • MTARs • ASER 	Integrating TLD	→ Quarterly	→ TLD cards at each location collected 4 times per year	→ Quarterly gamma radiation exposure

Sampling Rationale

Direct Radiation DOE/EH-0173T, 5.5; DOE/EP-0023, 4.6.3

Off-Site

TLDs offer continuous integrated environmental gamma-ray monitoring and have been deployed systematically about the site. Off-site TLDs are used to verify that site activities have not adversely affected the surrounding environs.

An annual high-pressure ion chamber (HPIC) gamma radiation measurement was completed at all locations in order to confirm TLD measurements.

- Sampling locations are shown on Figures A-11 through A-13.

**2004 Monitoring Program
Environmental Surveillance**

On-Site Direct Radiation

<u>Sample Location Code</u>	<u>Monitoring/Reporting Requirements</u>	<u>Sampling Type/Medium</u>	<u>Collection Frequency</u>	<u>Total Annual Sample Collections</u>	<u>Analyses Performed/ Composite Frequency</u>
<p>DNTLD Series Thermoluminescent Dosimetry (TLD) On-Site:</p> <p>#18, #19, #33 At Three Corners of the SDA</p> <p>#24, #26-#32, #34 9 TLDS at the Security Fence Around the Site</p> <p>#35, #36, #38-#40 5 TLDS On-Site Near Operational Areas</p> <p>#25 Rock Springs Road 500 m North-Northwest of the Plant</p> <p>#42 SDA T-1 Building</p> <p>#43 SDA west Perimeter Fence</p>	<p>Direct radiation around facility</p> <p><u>Reported in:</u></p> <ul style="list-style-type: none"> • MTARs • ASER 	Integrating TLD	→ Quarterly	→ TLD cards at each location collected 4 times per year	→ Quarterly gamma radiation exposure

Sampling Rationale

Direct Radiation DOE/EH-0173T, 5.4 and 5.5

On-Site

On-site TLDs monitor waste management units and verify that the potential dose rate to the general public (i.e., at Rock Springs Road) is below 100 mrem/year (1 mSv/year) from site activities.

An annual high-pressure ion chamber (HPIC) gamma radiation measurement is completed at all locations in order to confirm TLD measurements.

Potential TLD sampling locations are continually evaluated with respect to site activities.

- Sampling locations are shown on Figure A-10.

This page intentionally left blank

Appendix C-1
Summary of Water Limits, Guidelines, and Standards

This page intentionally left blank

Table C-1A
West Valley Demonstration Project State Pollutant Discharge Elimination
System (SPDES) Sampling Program

Outfall	Parameter	Daily Maximum Limit*	Sample Frequency
001 (Process and Storm Wastewater)	Flow	Monitor	2 per discharge
	Aluminum, total	14.0 mg/L	2 per discharge
	Ammonia (NH ₃)	Monitor	2 per discharge
	Arsenic, dissolved	0.15 mg/L	2 per discharge
	BOD ₅	10.0 mg/L	2 per discharge
	Iron, total	Monitor	2 per discharge
	Zinc, total recoverable	0.48 mg/L	2 per discharge
	Suspended solids	45.0 mg/L	2 per discharge
	Cyanide, amenable to chlorination	0.022 mg/L	2 per discharge
	Settleable solids	0.30 mL/L	2 per discharge
	pH (range)	6.5–8.5	2 per discharge
	Oil and grease	15.0 mg/L	2 per discharge
	Sulfate (as S)	Monitor	2 per discharge
	Sulfide, dissolved	0.4 mg/L	2 per discharge
	Manganese, total	2.0 mg/L	2 per discharge
	Nitrate (as N)	Monitor	2 per discharge
	Nitrite (as N)	0.1 mg/L	2 per discharge
	Chromium, total recoverable	0.3 mg/L	2 per discharge
	Chromium, hexavalent, total recoverable	0.011 mg/L	2 per discharge
	Cadmium, total recoverable	0.002 mg/L	2 per discharge
	Copper, total recoverable	0.030 mg/L	2 per discharge
	Copper, dissolved	Monitor	2 per discharge
	Lead, total recoverable	0.006 mg/L	2 per discharge
	Nickel, total recoverable	0.14 mg/L	2 per discharge
	Dichlorodifluoromethane	0.01 mg/L	annual
	Trichlorofluoromethane	0.01 mg/L	annual
	3,3-dichlorobenzidine	0.01 mg/L	2 per discharge
	Tributyl phosphate	32 mg/L	2 per discharge
	Vanadium, total recoverable	0.014 mg/L	2 per discharge
	Cobalt, total recoverable	0.005 mg/L	2 per discharge
	Selenium, total recoverable	0.004 mg/L	2 per discharge
	Hexachlorobenzene	0.02 mg/L	2 per discharge
	Alpha - BHC	0.00001 mg/L	2 per discharge
	Heptachlor	0.00001 mg/L	2 per discharge
	Surfactants (as LAS)	0.4 mg/L	2 per discharge
	Xylene	0.05 mg/L	2 per discharge
	2-butanone	0.5 mg/L	2 per discharge
	Total dissolved solids	Monitor	2 per discharge
	Mercury, total	0.0002 mg/L	2 per discharge

* Daily average limitations are also identified in the permit but require only monitoring for all parameters except total aluminum (daily average limit - 7.0 mg/L); suspended solids (daily average limit - 30.0 mg/L); BOD₅ for the sum of outfalls 001, 007, and 008 (daily average limit - 5.0 mg/L); and ammonia for the sum of outfalls 001 and 007 (daily average limit - 1.49 mg/L).

Table C-1A (concluded)
West Valley Demonstration Project State Pollutant Discharge Elimination
System (SPDES) Sampling Program

Outfall	Parameter	Daily Maximum Limit*	Sample Frequency
001 (concluded)	Barium	0.5 mg/L	annual
	Antimony	1.0 mg/L	annual
	Chloroform	0.3 mg/L	annual
	Bis(2-ethylhexyl)phthalate	1.6 mg/L	semiannual
	4-Dodecene	0.6 mg/L	semiannual
	Titanium	0.65 mg/L	semiannual
	Bromide	5.0 mg/L	quarterly
	Boron	2.0 mg/L	quarterly
01B (Internal Process Monitoring Point)	Flow	Monitor	weekly
	Mercury, total	10.0 µg/L	2 per month
007 (Sanitary and Utility Wastewater)	Flow	Monitor	3 per month
	Ammonia (as NH ₃)	Monitor	3 per month
	BOD ₅	10 mg/L	3 per month
	Iron, total	Monitor	3 per month
	Solids, suspended	45.0 mg/L	3 per month
	Solids, settleable	0.3 mL/L	weekly
	pH (range)	6.5–8.5	weekly
	Nitrite (as N)	0.1 mg/L	3 per month
	Oil and grease	15 mg/L	3 per month
	Chlorine, total residual	0.1 mg/L	weekly
	Chloroform	0.20 mg/L	annual
008 (French Drain Wastewater)	Flow	Monitor	3 per month
	BOD ₅	5.0 mg/L	3 per month
	Iron, total	Monitor	3 per month
	pH (range)	6.5–8.5	3 per month
	Cadmium, total recoverable	0.002 mg/L	3 per month
	Lead, total recoverable	0.006 mg/L	3 per month
	Silver, total	0.008 mg/L	annual
	Zinc, total	0.100 mg/L	annual
	Arsenic	0.17 mg/L	annual
	Chromium	0.13 mg/L	annual
Sum of Outfalls 001, 007, and 008	Iron, total	0.30 mg/L	3 per month
	BOD ₅	Monitor	3 per month
Sum of Outfalls 001 and 007	Ammonia (as NH ₃)	2.1 mg/L	3 per month
Pseudo-monitoring point (116)	Solids, total dissolved	500 mg/L	2 per discharge

* Daily average limitations are also identified in the permit but require only monitoring for all parameters except total aluminum (daily average limit - 7.0 mg/L); suspended solids (daily average limit - 30.0 mg/L); BOD₅ for the sum of outfalls 001, 007, and 008 (daily average limit - 5.0 mg/L); and ammonia for the sum of outfalls 001 and 007 (daily average limit - 1.49 mg/L).

Table C-1B
New York Water Quality Standards and Guidelines^a

Parameter	Units	Class A	Class B	Class C	Class D	Class GA
Gross Alpha ^b	pCi/L (μCi/mL)	15 (1.5E-08)	--	--	--	15 (1.5E-08)
Gross Beta ^c	pCi/L (μCi/mL)	1,000 (1E-06)	--	--	--	1,000 (1E-06)
Tritium (H-3)	pCi/L (μCi/mL)	20,000 (2E-05)	--	--	--	--
Strontium-90	pCi/L (μCi/mL)	8 (8E-09)	--	--	--	--
Alpha BHC	mg/L	0.000002	0.000002	0.000002	0.000002	0.00001
Aluminum, Dissolved	mg/L	0.10	0.10	0.10	--	--
Aluminum, Total	mg/L	--	--	--	--	--
Ammonia, Total as N	mg/L	0.09-2.1	0.09-2.1	0.09-2.1	0.67-29	2.0
Antimony, Total	mg/L	0.003	--	--	--	0.003
Arsenic, Dissolved	mg/L	0.050	0.150	0.150	0.340	--
Arsenic, Total	mg/L	0.050	--	--	--	0.025
Barium, Total	mg/L	1.00	--	--	--	1.00
Beryllium, Total	mg/L	0.003	^d	^d	--	0.003
Bicarbonate Alkalinity (as CaCO ₃)	mg/L	--	--	--	--	--
Boron, Total	mg/L	10.0	10.0	10.0	--	1.00
Bromide	mg/L	2.00	--	--	--	2.00
Cadmium, Dissolved ^e	mg/L	--	--	--	--	--
Cadmium, Total	mg/L	0.005	--	--	--	0.005
Calcium, Total	mg/L	--	--	--	--	--
Carbonate Alkalinity (as CaCO ₃)	mg/L	--	--	--	--	--
Chloride	mg/L	250	--	--	--	250
Chromium, Dissolved ^e	mg/L	--	--	--	--	--
Chromium, Total	mg/L	0.05	--	--	--	0.05
Cobalt, Total ^h	mg/L	0.005	0.005	0.005	0.110	--
Conductivity	μmhos/cm@25°C	--	--	--	--	--
Copper, Dissolved ^e	mg/L	--	--	--	--	--
Copper, Total	mg/L	0.20	--	--	--	0.20
Cyanide	mg/L	0.0052	0.0052	0.0052	0.22	0.200
Dissolved Oxygen (minimum)	mg/L	4.0	4.0	4.0	3.0	--
Fluoride ^e	mg/L	--	--	--	--	1.5
Hardness	mg/L	--	--	--	--	--
Iron and Manganese (sum)	mg/L	--	--	--	--	0.500

-- No applicable guideline or reference standard available

Note: All water quality and metals standards are presented in mg/L (ppm) to provide consistency in comparisons.

^a Source: 6 NYCRR Parts 701–704; The most stringent applicable pathway (e.g., wildlife, aquatic, human health) values are reported.

^b Gross alpha standard includes radium-226, but excludes radon and uranium; however WVDP results include these isotopes.

^c Gross beta standard excludes strontium-90 and alpha emitters, however WVDP results include these isotopes.

^d Beryllium standard for classes “B” and “C” are based on stream hardness values.

^e Standards for these constituents vary according to stream location hardness values.

^f pH shall not be lower than 6.5 or the pH of natural groundwater, whichever is lower, nor shall pH be greater than 8.5 or the pH of the natural groundwater, whichever is greater.

^g Applies to the sum of those organic substances which have individual human health water source standards listed at 0.100 mg/L or less in 6 NYCRR Part 703.5

^h Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-1B (concluded)
New York Water Quality Standards and Guidelines^a

Parameter	Units	Class A	Class B	Class C	Class D	Class GA
Iron, Total	mg/L	0.30	0.30	0.30	0.30	0.30
Lead, Dissolved ^c	mg/L	--	--	--	--	--
Lead, Total	mg/L	0.050	--	--	--	0.025
Magnesium, Total	mg/L	35.0	--	--	--	35.0
Manganese, Total	mg/L	0.30	--	--	--	0.30
Mercury, Dissolved	mg/L	0.0000007	0.0000007	0.0000007	0.0000007	--
Mercury, Total	mg/L	0.0007	--	--	--	0.0007
Nickel, Dissolved ^c	mg/L	--	--	--	--	--
Nickel, Total	mg/L	0.10	--	--	--	0.10
Nitrate-N	mg/L	10.0	--	--	--	10.0
Nitrate + Nitrite	mg/L	10.0	10.0	10.0	10.0	10.0
Nitrite-N	mg/L	0.10	0.10	0.10	--	1.00
NPOC ^g	mg/L	0.10	--	--	--	--
Oil & Grease	mg/L	--	--	--	--	--
pH	SU	6.5–8.5 ^f	6.5–8.5 ^f	6.5–8.5 ^f	6.0–9.5	6.5–8.5 ^f
Potassium, Total	mg/L	--	--	--	--	--
Selenium, Dissolved	mg/L	0.0046	0.0046	0.0046	--	--
Selenium, Total	mg/L	0.01	--	--	--	0.01
Silver, Total	mg/L	0.05	--	--	--	0.05
Sodium, Total	mg/L	--	--	--	--	20.0
Solids, Settleable	mg/L	--	--	--	--	--
Solids, Total Dissolved	mg/L	500	500	500	--	500
Solids, Total Suspended	mg/L	--	--	--	--	--
Sulfate	mg/L	250	--	--	--	250
Sulfide (undissociated form)	mg/L	0.002	0.002	0.002	--	0.050 (as HS)
Surfactants (as LAS)	mg/L	0.04	0.04	0.04	--	--
Thallium, Total ^h	mg/L	0.0005	0.008	0.008	0.020	0.0005
Titanium, Total	mg/L	--	--	--	--	--
TOX (total organic halides) ^g	mg/L	0.10	--	--	--	--
Vanadium, Total ^h	mg/L	0.014	0.014	0.014	0.190	--
Zinc, Dissolved ^c	mg/L	--	--	--	--	--
Zinc, Total	mg/L	2.00	--	--	--	2.00

-- No applicable guideline or reference standard available

Note: All water quality and metals standards are presented in mg/L (ppm) to provide consistency in comparisons.

HS - Hydrogen sulfide

^a Source: 6 NYCRR Parts 701–704; The most stringent applicable pathway (e.g., wildlife, aquatic, human health) values are reported.

^b Gross alpha standard includes radium-226, but excludes radon and uranium; however WVDP results include these isotopes.

^c Gross beta standard excludes strontium-90 and alpha emitters, however WVDP results include these isotopes.

^d Beryllium standard for classes “B” and “C” are based on stream hardness.

^e Standards for these constituents vary according to stream location hardness values.

^f pH shall not be lower than 6.5 or the pH of natural groundwater, whichever is lower, nor shall pH be greater than 8.5 or the pH of the natural groundwater, whichever is greater.

^g Applies to the sum of those organic substances which have individual human health water source standards listed at 0.100 mg/L or less in 6 NYCRR Part 703.5

^h Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-1C
New York State Department of Health/U.S. Environmental Protection Agency
MCLs, MCLGs, and Raw Water Standards

Parameter	Units	NYSDOH or EPA MCL ^a	EPA MCLG ^b	NYSDOH Raw Water Standards ^c
Gross Alpha	pCi/L (μCi/mL)	15 (1.5E-08) ^d	0	--
Gross Beta	pCi/L (μCi/mL)	50 (5E-08) ^e	0	1,000 (1E-06)
Tritium (H-3)	pCi/L (μCi/mL)	20,000 (2E-05)	--	--
Strontium-90	pCi/L (μCi/mL)	8 (8E-09)	--	10 (1E-08)
Antimony, Total	mg/L	0.006	0.006	--
Arsenic, Total	mg/L	0.05	--	0.05
Barium, Total	mg/L	2.00	2.00	1
Beryllium, Total	mg/L	0.004	0.004	--
Cadmium, Total	mg/L	0.005	0.005	0.01
Chromium, Total	mg/L	0.10	0.10	--
Conductivity	μmhos/cm@25°C	--	--	--
Cyanide	mg/L	0.2	0.2	<0.1
E. Coli	NA	one positive sample	0	--
Fluoride	mg/L	2.2	--	1.5
Free Residual Chlorine	mg/L	0.02 (min) 4.0 (max)	--	--
Haloacetic Acids -Five (5)	mg/L	0.060	--	--
Iron, Total	mg/L	0.3	--	--
Mercury, Total	mg/L	0.002	0.002	0.005
Nickel, Total	mg/L	--	--	--
Nitrate-N	mg/L	10	10	--
pH	SU	--	--	6.5–8.5
POC ^f	mg/L	--	0.0005	--
Selenium, Total	mg/L	0.05	0.05	0.01
Solids, Total Dissolved	mg/L	--	--	500
Thallium, Total	mg/L	0.002	0.0005	--
Total Coliform	NA	2 or more positive samples	zero	--
Total Trihalomethanes	mg/L	0.080	--	--
Turbidity	NTU	1 (max)	--	--

-- No applicable guideline or reference standard available

Note: All water quality and metals standards are presented in mg/L (ppm) to provide consistency in comparisons.

NA - Not applicable

^a MCL - Listed is NYSDOH or EPA Maximum Contaminant Level. Sources: 40 CFR 141 and/or 5 NYCRR 5-1.52, whichever is more stringent.

^b MCLG - Maximum Contaminant Level Goal (non-enforceable) as listed in 40 CFR Part 141

^c Source: 10 NYCRR Part 170.4

^d Alpha guideline includes radium-226, but excludes uranium; however, WVDP results include these isotopes.

^e Average annual concentration assumed to produce a total body organ dose of 4 mrem/year

^f POC - Principle Organic Contaminant

Table C-1D
U.S. Department of Energy Derived Concentration Guides (DCGs)^a

Radionuclide	Units	Concentration in Ingested Water
Gross Alpha (as Am-241) ^b	μCi/mL	3E-08
Gross Beta (as Sr-90) ^b	μCi/mL	1E-06
Tritium (H-3)	μCi/mL	2E-03
Carbon-14 (C-14)	μCi/mL	7E-05
Potassium-40 (K-40)	μCi/mL	7E-06
Cobalt-60 (Co-60)	μCi/mL	5E-06
Strontium-90 (Sr-90)	μCi/mL	1E-06
Technetium-99 (Tc-99)	μCi/mL	1E-04
Iodine-129 (I-129)	μCi/mL	5E-07
Cesium-137 (Cs-137)	μCi/mL	3E-06
Europium-154 (Eu-154)	μCi/mL	2E-05
Uranium-232 (U-232)	μCi/mL	1E-07
Uranium-233 (U-233)	μCi/mL	5E-07
Uranium-234 (U-234)	μCi/mL	5E-07
Uranium-235 (U-235)	μCi/mL	6E-07
Uranium-236 (U-236)	μCi/mL	5E-07
Uranium-238 (U-238)	μCi/mL	6E-07
Plutonium-238 (Pu-238)	μCi/mL	4E-08
Plutonium-239 (Pu-239)	μCi/mL	3E-08
Plutonium-240 (Pu-240)	μCi/mL	3E-08
Americium-241 (Am-241)	μCi/mL	3E-08

^a DCGs are established in DOE Order 5400.5 and are defined as the concentration of a radionuclide that, under conditions of continuous exposure for one year by one exposure mode, would result in an effective dose equivalent of 100 mrem (1mSv).

^b Because there are no DCGs for gross alpha and gross beta concentrations, the DCGs for the most restrictive alpha and beta emitters at the WVDP, americium-241 and strontium-90 (3E-08 and 1E-06 μCi/mL, respectively) are used as a conservative basis for comparison at locations for which there are no radionuclide-specific data, in which case a more appropriate DCG may be applied.

Appendix C-2

Process Effluent Data

Table C-2A contains a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Key to bolding convention:

Results for each constituent constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered nondetectable. Chemical results preceded by “less than” (<) are considered nondetectable.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

Table C-2A
Total Radioactivity (curies) of Liquid Effluents Released From Lagoon 3
(WNSP001) in 2004

Isotope	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	Annual Total
Gross Alpha	4.10±0.54E-04	1.82±0.40E-04	1.69±0.30E-04	1.14±0.32E-04	8.76±0.80E-04
Gross Beta	4.35±0.13E-03	3.60±0.10E-03	2.57±0.07E-03	1.18±0.07E-03	1.17±0.02E-02
H-3	2.52±0.13E-02	2.02±0.11E-02	2.14±0.11E-02	1.59±0.10E-02	8.27±0.22E-02
C-14	0.99±3.97E-04	-2.32±2.84E-04	1.84±0.66E-04	0.06±1.68E-04	0.58±5.20E-04
K-40	6.12±8.23E-04	-5.17±5.72E-04	0.95±4.59E-04	3.79±4.59E-04	0.57±1.19E-03
Co-60	-0.64±4.63E-05	-1.21±2.18E-05	-2.11±3.23E-05	0.41±1.74E-05	-3.54±6.30E-05
Sr-90	1.58±0.07E-03	1.39±0.05E-03	9.24±0.52E-04	5.37±0.44E-04	4.43±0.11E-03
Tc-99	2.80±0.28E-04	3.32±0.28E-04	6.11±0.35E-04	2.35±0.27E-04	1.46±0.06E-03
I-129	0.83±1.59E-05	1.30±1.56E-05	3.06±1.20E-05	4.46±1.98E-05	9.65±3.22E-05
Cs-137	1.44±0.11E-03	8.86±0.57E-04	5.35±0.67E-04	2.42±0.41E-04	3.11±0.14E-03
U-232	1.73±0.08E-04	1.05±0.06E-04	9.88±0.73E-05	7.94±0.67E-05	4.56±0.14E-04
U-233/234	1.09±0.06E-04	7.20±0.51E-05	6.19±0.55E-05	5.52±0.56E-05	2.99±0.11E-04
U-235/236	6.61±1.53E-06	5.55±1.44E-06	3.33±1.37E-06	3.34±1.42E-06	1.88±0.29E-05
U-238	8.77±0.55E-05	5.72±0.45E-05	4.40±0.47E-05	3.91±0.47E-05	2.28±0.10E-04
Total U (g)	2.79±0.12E+02	1.78±0.04E+02	1.35±0.03E+02	1.05±0.03E+02	6.98±0.13E+02
Pu-238	2.74±0.94E-06	9.56±5.11E-07	8.54±6.34E-07	3.00±0.92E-06	7.55±1.55E-06
Pu-239/240	1.70±0.75E-06	9.80±5.02E-07	7.81±5.84E-07	2.68±0.88E-06	6.14±1.39E-06
Am-241	2.38±0.93E-06	1.16±0.45E-06	7.84±5.37E-07	4.11±1.04E-06	8.44±1.56E-06

Note: Bolding convention applied to these data. See page C-10.

Table C-2B
Comparison of 2004 Lagoon 3 (WNSP001) Liquid Effluent Radioactivity Concentrations With U.S. Department of Energy Guidelines

Isotope ^a	Discharge Activity ^b (Ci)	Radioactivity ^c (Becquerels)	Concentration (μ Ci/mL)	DCG (μ Ci/mL)	% of DCG
Gross Alpha	8.76 \pm 0.80E-04	3.24 \pm 0.30E+07	1.55 \pm 0.14E-08	NA ^d	NA
Gross Beta	1.17 \pm 0.02E-02	4.33 \pm 0.07E+08	2.07 \pm 0.03E-07	NA ^d	NA
H-3	8.27 \pm 0.22E-02	3.06 \pm 0.08E+09	1.46 \pm 0.04E-06	2E-03	0.07
C-14	0.58 \pm 5.20E-04	0.21 \pm 1.92E+07	1.02 \pm 9.19E-09	7E-05	<0.01
K-40	0.57 \pm 1.19E-03	2.11 \pm 4.42E+07	1.01 \pm 2.11E-08	NA ^e	NA
Co-60	-3.54 \pm 6.30E-05	-1.31 \pm 2.33E+06	-0.63 \pm 1.11E-09	5E-06	<0.02
Sr-90	4.43 \pm 0.11E-03	1.64 \pm 0.04E+08	7.83 \pm 0.19E-08	1E-06	7.83
Tc-99	1.46 \pm 0.06E-03	5.39 \pm 0.22E+07	2.58 \pm 0.11E-08	1E-04	0.03
I-129	9.65 \pm 3.22E-05	3.57 \pm 1.19E+06	1.70 \pm 0.57E-09	5E-07	0.34
Cs-137	3.11 \pm 0.14E-03	1.15 \pm 0.05E+08	5.49 \pm 0.26E-08	3E-06	1.83
U-232^f	4.56 \pm 0.14E-04	1.69 \pm 0.05E+07	8.06 \pm 0.25E-09	1E-07	8.06
U-233/234^f	2.99 \pm 0.11E-04	1.10 \pm 0.04E+07	5.27 \pm 0.20E-09	5E-07	1.05
U-235/236^f	1.88 \pm 0.29E-05	6.97 \pm 1.06E+05	3.33 \pm 0.51E-10	5E-07 ^g	0.07
U-238^f	2.28 \pm 0.10E-04	8.44 \pm 0.36E+06	4.03 \pm 0.17E-09	6E-07	0.67
Pu-238	7.55 \pm 1.55E-06	2.79 \pm 0.57E+05	1.33 \pm 0.27E-10	4E-08	0.33
Pu-239/240	6.14 \pm 1.39E-06	2.27 \pm 0.51E+05	1.08 \pm 0.25E-10	3E-08	0.36
Am-241	8.44 \pm 1.56E-06	3.12 \pm 0.58E+05	1.49 \pm 0.28E-10	3E-08	0.50
Total % of DCGs					21.18

NA - Not applicable

^a Half-lives are listed in Table K-1^(b)

^b Total volume released: 5.66E+10 mL (1.50E+07 gal)

^c 1 curie (Ci) = 3.7E+10 becquerels (Bq); 1Bq = 2.7E-11 Ci

^d DOE-derived concentration guides (DCGs) do not exist for indicator parameters gross alpha and gross beta.

^e Potassium-40 activity is not applicable because of its natural origin.

^f Total U (g) = 6.98 \pm 0.13E+02; Average U (μ g/mL) = 1.23 \pm 0.02E-02

^g DCG for U-236 is used for this comparison.

Table C-2C
2004 SPDES Results for Outfall 001 (WNSP001):
Water Quality

	Ammonia (mg/L)		BOD ₅ day (mg/L)		Cyanide (amenable to chlorination) (mg/L)		Discharge Rate (MGD)	
Permit limit	Monitor		10.0 mg/L daily maximum		0.022 mg/L daily maximum		Monitor	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
January	0.24	0.33	<2.4	2.8	<0.010	<0.010	0.317	0.349
February ^a	--	--	--	--	--	--	--	--
March	0.14	0.15	<2.0	<2.0	<0.010	<0.010	0.341	0.379
April	<0.05	<0.05	<2.0	<2.0	<0.010	<0.010	0.193	0.274
May	0.061	0.091	<1.3	2.1	<0.003	<0.003	0.176	0.288
June	0.12	0.17	<0.57	<0.57	<0.0030	<0.0030	0.262	0.335
July ^a	--	--	--	--	--	--	--	--
August	0.028	0.034	<2.0	<2.0	<0.003	<0.003	0.271	0.327
September	<0.019	0.025	<2.2	2.3	<0.003	<0.003	0.232	0.307
October ^a	--	--	--	--	--	--	--	--
November ^a	--	--	--	--	--	--	--	--
December	0.075	0.090	<2.0	<2.0	<0.003	<0.003	0.249	0.277

	Nitrate (as N) (mg/L)		Nitrite (as N) (mg/L)		Oil & Grease (mg/L)	
Permit limit	Monitor		0.1 mg/L daily maximum		15.0 mg/L daily maximum	
Month	Avg	Max	Avg	Max	Avg	Max
January	0.92	1.0	<0.05	<0.05	<5.0	<5.0
February ^a	--	--	--	--	--	--
March	1.2	1.2	<0.05	<0.05	<5.0	<5.0
April	1.4	1.5	<0.05	<0.05	<5.0	<5.0
May	0.8	1.0	<0.05	0.06	<1.9	<1.9
June	0.46	0.49	<0.05	<0.05	<1.9	<1.9
July ^a	--	--	--	--	--	--
August	<0.036	<0.036	<0.05	<0.05	<1.9	<1.9
September	<0.036	<0.036	<0.05	<0.05	<1.9	1.9
October ^a	--	--	--	--	--	--
November ^a	--	--	--	--	--	--
December	0.10	0.10	<0.05	<0.05	<2.7	<2.7

Note: No results exceeded the permit limits.

^a No discharge this month

Table C-2C (concluded)
2004 SPDES Results for Outfall 001 (WNSP001):
Water Quality

	pH (standard units)		Solids Settleable (mL/L)		Solids Total Dissolved (mg/L)		Solids Total Suspended (mg/L)	
Permit limit	6.5–8.5		0.30 mL/L daily maximum		Monitor		45.0 mg/L daily maximum; 30.0 daily average	
Month	Min	Max	Avg	Max	Avg	Max	Avg	Max
January	7.1	7.7	<0.1	<0.1	740	746	<3.0	4.0
February ^a	--	--	--	--	--	--	--	--
March	7.3	7.3	<0.1	<0.1	728	740	<2.0	<2.0
April	7.6	8.2	<0.1	<0.1	768	789	<2.0	<2.0
May	7.4	8.1	<0.1	<0.1	713	733	43.8 ^b	78.5 ^b
June	7.5	7.8	<0.1	<0.1	698	717	<1.0	<1.0
July ^a	--	--	--	--	--	--	--	--
August	7.6	7.8	<0.1	<0.1	759	775	<6.5	9.0
September	7.8	8.0	<0.1	<0.1	738	741	10.5	14.0
October ^a	--	--	--	--	--	--	--	--
November ^a	--	--	--	--	--	--	--	--
December	7.5	7.7	<0.1	<0.1	758	762	<4.0	<4.0

	Sulfate (as S) (mg/L)		Sulfide (as S) Dissolved (mg/L)		Surfactants as LAS (mg/L)	
Permit limit	Monitor		0.4 mg/L daily maximum		0.4 mg/L daily maximum	
Month	Avg	Max	Avg	Max	Avg	Max
January	40	57	<0.2	<0.2	<0.1	0.1
February ^a	--	--	--	--	--	--
March	34	34	<0.2	<0.2	<0.1	<0.1
April	36	36	<0.2	<0.2	<0.1	<0.1
May	28	30	0.08	0.1	<0.03	0.04
June	39	43	0.1	0.1	0.04	0.04
July ^a	--	--	--	--	--	--
August	58	63	<0.04	<0.04	0.07	0.08
September	57	58	<0.04	<0.04	0.04	0.05
October ^a	--	--	--	--	--	--
November ^a	--	--	--	--	--	--
December	66	69	<0.04	0.04	0.06	0.07

^a No discharge this month

^b Exceedance of the permit limits for TSS in May 2004

Table C-2D
2004 SPDES Results for Outfall 001 (WNSP001):
Metals

	Aluminum Total (mg/L)		Arsenic Dissolved (mg/L)		Cadmium Total Recoverable (mg/L)		Cobalt Total Recoverable (mg/L)	
Permit limit	14.0 mg/L daily maximum; 7.0 mg/L daily average		0.15 mg/L daily maximum		0.002 mg/L daily maximum		0.005 mg/L daily maximum	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
January	<0.275	0.349	0.0020	0.0022	<0.001	<0.001	<0.004	<0.004
February ^a	--	--	--	--	--	--	--	--
March	0.302	0.314	0.0014	0.0015	<0.001	<0.001	<0.004	<0.004
April	<0.200	<0.200	0.0018	0.0018	<0.001	<0.001	<0.004	<0.004
May	2.3	4.2	0.0018	0.0018	<0.0006	<0.0006	<0.003	0.004
June	0.22	0.259	0.0021	0.0021	<0.0006	<0.0006	<0.002	<0.002
July ^a	--	--	--	--	--	--	--	--
August	0.112	0.139	0.0022	0.0022	<0.001	<0.001	<0.002	<0.002
September	0.174	0.199	0.002	0.002	<0.0006	<0.0006	<0.002	<0.002
October ^a	--	--	--	--	--	--	--	--
November ^a	--	--	--	--	--	--	--	--
December	0.253	0.294	0.0025	0.0026	<0.0006	<0.0006	<0.002	<0.002

	Chromium Total Recoverable (mg/L)		Chromium VI Total Recoverable (mg/L)		Copper Dissolved (mg/L)		Copper Total Recoverable (mg/L)	
Permit limit	0.3 mg/L daily maximum		0.011 mg/L daily maximum		Monitor		0.030 mg/L daily maximum	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
January	<0.002	<0.002	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
February ^a	--	--	--	--	--	--	--	--
March	<0.002	<0.002	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
April	<0.002	<0.002	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
May	<0.003	0.004	<0.009	<0.010	<0.0024	<0.0024	0.0035	0.0045
June	<0.0009	<0.0009	<0.008	<0.008	<0.0024	<0.0024	<0.0024	<0.0024
July ^a	--	--	--	--	--	--	--	--
August	<0.0009	<0.0009	<0.008	<0.008	0.0028	0.0028	0.0036	0.0040
September	<0.0009	<0.0009	<0.008	<0.008	0.0050	0.0068	<0.0036	0.0047
October ^a	--	--	--	--	--	--	--	--
November ^a	--	--	--	--	--	--	--	--
December	<0.001	0.001	<0.009	<0.010	<0.0043	<0.0043	0.0037	0.004

Note: No results exceeded the permit limits.

^a No discharge this month

Table C-2D (concluded)
2004 SPDES Results for Outfall 001 (WNSP001):
Metals

	Iron Total (mg/L)		Lead Total Recoverable (mg/L)		Manganese Total (mg/L)		Mercury, Total (per EPA Method 245.1) (mg/L)		Mercury, Total (per EPA Method 1631) (µg/L)	
Permit limit	Monitor		0.006 mg/L daily maximum		2.0 mg/L daily maximum		0.0002 mg/L daily maximum		Monitor	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max
January	0.138	0.164	<0.0005	0.0006	0.127	0.206	<0.0002	<0.0002	0.0374	0.0439
February ^a	--	--	--	--	--	--	--	--	--	--
March	0.263	0.264	<0.0005	<0.0005	0.029	0.030	<0.0002	<0.0002	0.0191	0.0203
April	0.118	0.143	<0.0005	<0.0005	0.013	0.017	<0.0002	<0.0002	0.00895	0.00961
May	2.43	4.61	<0.001	0.002	0.074	0.11	<0.0002	<0.0002	0.01045	0.0114
June	0.268	0.324	0.0004	0.0004	0.14	0.15	<0.0002	<0.0002	0.00576	0.00648
July ^a	--	--	--	--	--	--	--	--	--	--
August	0.116	0.141	<0.0003	0.0004	0.040	0.043	<0.0002	<0.0002	0.00470	0.00558
September	0.168	0.178	0.0005	0.0005	0.10	0.13	<0.0002	<0.0002	0.00571	0.00634
October ^a	--	--	--	--	--	--	--	--	--	--
November ^a	--	--	--	--	--	--	--	--	--	--
December	0.325	0.389	0.0008	0.0008	0.017	0.017	<0.0002	<0.0002	0.0152	0.0170

	Nickel Total Recoverable (mg/L)		Selenium Total Recoverable (mg/L)		Vanadium Total Recoverable (mg/L)		Zinc Total Recoverable (mg/L)	
Permit limit	0.14 mg/L daily maximum		0.004 mg/L daily maximum		0.014 mg/L daily maximum		0.48 mg/L daily maximum	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
January	<0.010	<0.010	<0.001	0.001	<0.010	<0.010	<0.010	<0.010
February ^a	--	--	--	--	--	--	--	--
March	<0.010	<0.010	<0.001	<0.001	<0.010	<0.010	<0.010	<0.010
April	<0.010	<0.010	<0.001	<0.001	<0.010	<0.010	<0.010	<0.010
May	<0.0037	0.0058	<0.0004	<0.0004	0.006	0.011	0.012	0.018
June	<0.0016	<0.0016	<0.0004	<0.0004	<0.00098	<0.00098	<0.0069	0.0081
July ^a	--	--	--	--	--	--	--	--
August	0.002	0.002	<0.0004	<0.0004	<0.0011	<0.0011	<0.0064	0.0071
September	0.0024	0.0027	<0.0004	<0.0004	<0.0011	<0.0011	<0.0056	<0.0056
October ^a	--	--	--	--	--	--	--	--
November ^a	--	--	--	--	--	--	--	--
December	0.0026	0.0026	<0.0004	<0.0004	<0.0011	<0.0011	0.0071	0.0071

Note: No results exceeded the permit limits.

^a No discharge this month

Table C-2E
2004 SPDES Results for Outfall 001 (WNSP001):
Organics

SEMIVOLATILES

	3,3-Dichlorobenzidine (mg/L)		Hexachlorobenzene (mg/L)		Heptachlor (mg/L)		Tributyl Phosphate (mg/L)	
Permit limit	0.01 mg/L daily maximum		0.02 mg/L daily maximum		0.00001 mg/L daily maximum		32 mg/L daily maximum	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max
January	<0.0099	<0.0099	<0.01	<0.01	<0.000009	<0.000009	<0.010	<0.010
February ^a	--	--	--	--	--	--	--	--
March	<0.0099	<0.0099	<0.01	<0.01	<0.000009	<0.000009	<0.010	<0.010
April	<0.0099	<0.0099	<0.01	<0.01	<0.000006	<0.000009	<0.010	<0.010
May	<0.007	<0.007	<0.007	<0.007	<0.000003	0.000003	<0.0014	<0.0014
June	<0.007	<0.007	<0.007	<0.007	<0.0000007	<0.0000008	<0.0014	<0.0014
July ^a	--	--	--	--	--	--	--	--
August	<0.007	<0.007	<0.007	<0.007	<0.0000008	<0.0000008	<0.0014	<0.0014
September	<0.007	<0.007	<0.007	<0.007	<0.000001	<0.000001	<0.0014	<0.0014
October ^a	--	--	--	--	--	--	--	--
November ^a	--	--	--	--	--	--	--	--
December	<0.007	<0.007	<0.007	<0.007	<0.0000008	<0.0000008	<0.0013	<0.0013

VOLATILES

	2-Butanone (mg/L)		Xylene (mg/L)		Alpha-BHC (mg/L)	
Permit limit	0.5 mg/L daily maximum		0.05 mg/L daily maximum		0.00001 mg/L daily maximum	
Month	Avg	Max	Avg	Max	Avg	Max
January	<0.01	<0.01	<0.01	<0.01	<0.000009	<0.000009
February ^a	--	--	--	--	--	--
March	<0.01	<0.01	<0.01	<0.01	<0.000009	<0.000009
April	<0.01	<0.01	<0.01	<0.01	<0.000009	<0.000009
May	<0.005	<0.005	<0.007	<0.007	<0.000002	<0.000002
June	<0.005	<0.005	<0.007	<0.007	<0.000001	<0.000001
July ^a	--	--	--	--	--	--
August	<0.005	<0.005	<0.007	<0.007	<0.000001	<0.000001
September	<0.005	<0.005	<0.007	<0.007	<0.000002	<0.000002
October ^a	--	--	--	--	--	--
November ^a	--	--	--	--	--	--
December	<0.005	<0.005	<0.007	<0.007	<0.000001	<0.000001

Note: No results exceeded the permit limits.

^a No discharge this month

Table C-2F
2004 SPDES Results for Outfall 007 (WNSP007):
Water Quality and Iron

	Ammonia (as NH₃) (mg/L)		BOD₅ (mg/L)		Chlorine Total Residual (mg/L)		Discharge Rate (MGD)		Iron Total (mg/L)	
Permit limit	Monitor		10 mg/L daily maximum		0.1 mg/L daily maximum		Monitor		Monitor	
Month	Avg	Max	Avg	Max	Avg	Max	Avg	Max	Avg	Max
January	<0.62	1.0	2.8	3.8	0.02	0.04	0.046	0.075	<0.189	0.317
February	<0.11	0.22	2.2	2.6	0.02	0.02	0.043	0.068	0.085	0.100
March	<0.050	<0.050	<2.0	<2.0	0.01	0.02	0.036	0.064	0.073	0.080
April	<0.050	<0.050	<2.0	<2.0	0.02	0.05	0.023	0.033	0.0997	0.118
May	<0.015	0.024	<1.6	2.3	0.01	0.02	0.018	0.028	0.163	0.216
June	<0.010	<0.010	<1.9	2.9	0.02	0.02	0.017	0.028	0.085	0.105
July	0.041	0.051	<2.8	4.3	0.02	0.02	0.016	0.025	<0.026	0.0332
August	0.044	0.061	<2.9	3.6	0.01	0.01	0.013	0.019	0.0579	0.0959
September	<0.025	0.032	<2.4	3.2	0.02	0.03	0.019	0.023	0.0732	0.0933
October	<0.025	0.032	<2.4	3.2	0.02	0.03	0.018	0.030	0.0581	0.110
November	0.075	0.16	<2.1	2.4	0.02	0.03	0.020	0.026	0.0750	0.0912
December	0.043	0.099	<2.0	<2.0	0.02	0.03	0.024	0.035	0.184	0.419

	Nitrite (as N) (mg/L)		Oil & Grease (mg/L)		pH (standard units)		Solids Settleable (mL/L)		Solids Total Suspended (mg/L)	
Permit limit	0.1 mg/L daily maximum		15 mg/L daily maximum		6.5 to 8.5		0.3 mL/L daily maximum		45.0 mg/L daily maximum; 30.0 daily average	
Month	Avg	Max	Avg	Max	Min	Max	Avg	Max	Avg	Max
January	<0.05	<0.05	<5.0	<5.0	7.3	8.0	<0.1	<0.1	<2.7	3.0
February	<0.08	0.1	<5.0	<5.0	7.0	7.5	<0.2	<0.3	<4.0	8.0
March	<0.05	<0.05	<5.0	<5.0	7.7	8.0	<0.2	<0.3	<2.0	<2.0
April	<0.05	<0.05	<5.0	<5.0	7.4	7.7	<0.1	<0.1	<2.0	<2.0
May	<0.05	<0.05	<1.9	<1.9	7.2	7.5	<0.1	<0.1	<1.3	2.0
June	<0.05	<0.05	<1.9	<1.9	7.4	7.7	<0.1	<0.1	<1.0	<1.0
July	<0.05	<0.05	<1.9	<1.9	7.6	7.9	<0.1	<0.1	<2.3	5.0
August	<0.05	<0.05	<1.9	<1.9	7.5	7.9	<0.1	<0.1	<4.0	<4.0
September	<0.05	<0.05	<1.9	<1.9	7.2	7.7	<0.1	<0.1	<7.0	12.0
October	<0.05	<0.05	<1.9	<1.9	7.7	7.9	<0.1	<0.1	<4.0	<4.0
November	<0.05	<0.05	<3.4	4.9	7.1	7.8	<0.1	<0.1	<4.0	<4.0
December	<0.05	<0.05	<2.7	<2.7	7.3	7.9	<0.1	<0.1	<4.0	<4.0

Note: No results exceeded the permit limits.

Table C-2G
2004 SPDES Results for Outfall 008 (WNSP008):
Water Quality

**NO DISCHARGE FROM THE
FRENCH DRAIN (WNSP008) SINCE MAY 2001**

Table C-2H
2004 SPDES Results for Sums of Outfalls 001, 007, 008, and 116:
Water Quality

2004 Results for Sums of Outfalls 001, 007 and 008

	Ammonia^a		BOD₅ day		Iron
	Flow-Weighted Average		(mg/L)		Flow-Weighted Average
	(mg/L)		(mg/L)		(mg/L)
Permit limit	2.1 daily maximum; 1.49 daily average		5.0 daily average		0.30 daily average
Month	Avg	Max	Avg	Max	Avg
January	<0.44	0.80	<2.3	2.9	0.04
February ^b	<0.11	0.22	2.2	2.6	0.00
March	<0.102	<0.14	<2.0	<2.0	0.00
April	<0.05	<0.05	<2.0	<2.0	0.00
May	<0.040	<0.080	<1.5	<1.9	0.00
June	<0.074	<0.15	<1.4	2.9	0.00
July ^b	0.041	0.051	<2.8	4.3	0.00
August	0.032	0.038	<2.4	3.1	0.00
September	<0.017	0.025	<2.5	3.2	0.00
October ^b	<0.025	0.032	<2.4	3.2	0.00
November ^b	0.075	0.16	<2.1	2.4	0.00
December	0.054	0.091	<2.0	<2.0	0.00

2004 Results for Outfall 116

	Total Dissolved Solids	
	(mg/L)	
Permit limit	500 mg/L daily maximum	
Month	Avg	Max
January	350	360
February ^b	--	--
March	281	320
April	288	297
May	253	347
June	343	372
July ^b	--	--
August	381	381
September	356	381
October ^b	--	--
November ^b	--	--
December	279	316

Note: No results exceeded the permit limits.

^a Sum of Outfalls 001 and 007 only

^b No discharge this month

Table C-2I
2004 Quarterly/Semiannual/Annual SPDES Results for Outfall 001
(WNSP001): Water Quality, Metals, and Organics

	Action Level	Monitoring Frequency	Collection Date	Maximum Measured
Boron, Total (mg/L)	2.0 mg/L daily maximum	Quarterly	March 2004 May 2004 August 2004 December 2004	0.035 0.040 0.049 0.038
Bromide, Total (mg/L)	5.0 mg/L daily maximum	Quarterly	March 2004 May 2004 August 2004 December 2004	1.4 1.8 2.0 1.9
Titanium, Total (mg/L)	0.65 mg/L daily maximum	Semiannual	March 2004 August 2004	0.0068 0.0037
Bis(2-ethylhexyl)phthalate (mg/L)	1.6 mg/L daily maximum	Semiannual	March 2004 August 2004	<0.010 <0.0051
4-dodecene (mg/L)	0.6 mg/L daily maximum	Semiannual	March 2004 August 2004	<0.06 <0.010
Chloroform (mg/L)	0.3 mg/L daily maximum	Annual	March 2004	<0.005
Antimony, Total (mg/L)	1.0 mg/L daily maximum	Annual	March 2004	<0.020
Barium, Total (mg/L)	0.5 mg/L daily maximum	Annual	March 2004	0.03
Dichlorodifluoromethane (mg/L)	0.01 mg/L daily maximum	Annual	March 2004	<0.005
Trichlorofluoromethane (mg/L)	0.01 mg/L daily maximum	Annual	March 2004	<0.005

Note: No results exceeded the permit limits.

Table C-2J
2004 Annual SPDES Results for Outfall 007 (WNSP007):
Water Quality

	Action Level	Monitoring Frequency	Collection Date	Maximum Measured
Chloroform (mg/L)	0.20 mg/L daily maximum	Annual	February 2004	<0.005

Table C-2K
2004 Annual SPDES Results for Outfall 008 (WNSP008):
Water Quality

**NO DISCHARGE FROM THE
FRENCH DRAIN (WNSP008) SINCE MAY 2001**

Table C-2L
2004 Annual SPDES Results for Outfall 01B (WNSP01B):
Water Quality

**NO FLOW THROUGH INTERNAL MONITORING SYSTEM
DURING 2004**

Table C-2M
2004 Radioactivity for Sewage Treatment Outfall (WNSP007)

Analyte	Units	N	WNSP007 Concentrations			Guideline ^a
			Minimum	Average	Maximum	
Gross Alpha	μCi/mL	36	<1.55E-09	-0.30±2.97E-09	2.99E-09	3E-08 ^b
Gross Beta	μCi/mL	36	3.51E-09	1.35±0.47E-08	2.48E-08	1E-06 ^c
Tritium	μCi/mL	36	<6.01E-08	1.96±8.06E-08	1.96E-07	2E-03
Sr-90	μCi/mL	4	2.33E-09	3.17±1.61E-09	4.47E-09	1E-06
Cs-137	μCi/mL	4	<1.96E-09	0.97±2.98E-09	1.99E-09	3E-06

N - Number of samples

^a DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results.

^b Alpha as Am-241

^c Beta as Sr-90

Appendix C-3
***Site Surface Drainage, Subsurface Drainage,
and Contained Water***

This page intentionally left blank

Table C-3A
2004 Radioactivity and pH in Surface Water at Facility Yard Drainage
(WNSP005)

Analyte	Units	N	WNSP005 Concentrations			Guideline ^a or Standard ^b
			Minimum	Average	Maximum	
Gross Alpha	μCi/mL	12	<1.66E-09	0.22±2.85E-09	<4.28E-09	3E-08 ^c
Gross Beta	μCi/mL	12	4.06E-08	1.88±0.09E-07	4.42E-07	1E-06 ^d
Tritium	μCi/mL	12	<7.88E-08	5.62±8.19E-08	1.66E-07	2E-03
Sr-90	μCi/mL	4	3.82E-08	8.82±0.56E-08	1.50E-07	1E-06
Cs-137	μCi/mL	4	<1.89E-09	0.79±1.99E-09	<2.08E-09	3E-06
pH	SU	12	6.85	7.42	7.99	6.0–9.5

N - Number of samples

^a DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results.

^b New York State Water Quality Standards for Class "D" as a comparative reference for nonradiological results

^c Alpha as Am-241

^d Beta as Sr-90

Table C-3B
2004 Radioactivity in Surface Water at French Drain (WNSP008)

**NO DISCHARGE FROM THE
FRENCH DRAIN SINCE MAY 2001**

Table C-3C
2004 Water Quality of Surface Water at the North Swamp (WNSW74A)

RADIOACTIVITY CONCENTRATIONS

Analyte	Units	N	WNSW74A		N	Reference Values	
			Concentrations			Background Range WFBCBK ^a	Guideline ^b
			Average	Maximum			
Gross Alpha	μCi/mL	53	-0.21±3.44E-09	7.89E-09	12	<4.53E-10–2.55E-09	3E-08 ^c
Gross Beta	μCi/mL	53	1.25±0.43E-08	2.15E-08	12	<1.16E-09–3.64E-09	1E-06 ^d
Tritium	μCi/mL	53	-0.45±7.75E-08	1.16E-07	12	<7.48E-08–1.35E-07	2E-03
C-14	μCi/mL	4	-0.42±2.40E-08	<2.95E-08	4	<5.38E-09–<3.03E-08	7E-05
Sr-90	μCi/mL	12	6.23±1.94E-09	8.39E-09	4	<1.13E-09–<1.30E-09	1E-06
I-129	μCi/mL	4	1.28±8.57E-10	<1.12E-09	4	<6.26E-10–1.21E-09	5E-07
Cs-137	μCi/mL	12	1.72±7.35E-09	<1.08E-08	4	<1.94E-09–<2.34E-09	3E-06
U-232	μCi/mL	4	-0.04±4.80E-11	<5.98E-11	4	<3.46E-11–<1.00E-10	1E-07
U-233/234	μCi/mL	4	2.28±1.12E-10	3.01E-10	4	8.19E-11–1.81E-10	5E-07
U-235/236	μCi/mL	4	3.49±5.67E-11	6.64E-11	4	<4.14E-11–5.25E-11	5E-07 ^e
U-238	μCi/mL	4	1.01±0.76E-10	1.56E-10	4	<4.68E-11–8.50E-11	6E-07
Total U	μg/mL	4	3.13±0.09E-04	4.27E-04	4	3.32E-05–6.00E-04	--
Pu-238	μCi/mL	4	0.23±2.92E-11	<3.53E-11	4	<1.24E-11–<3.38E-11	4E-08
Pu-239/240	μCi/mL	4	0.84±2.43E-11	<2.90E-11	4	<1.25E-11–<3.85E-11	3E-08
Am-241	μCi/mL	4	0.66±2.88E-11	3.13E-11	4	<2.21E-11–<4.85E-11	3E-08

N - Number of samples

-- No guideline or standard available for these analytes

^a Background location

^b DOE ingestion-based DCGs for 100 mrem/yr dose limits are provided as a guideline for radiological results.

^c Alpha as Am-241

^d Beta as Sr-90

^e DCG for U-236 is used for this comparison.

Table C-3C (continued)
2004 Water Quality of Surface Water at the North Swamp (WNSW74A)

CHEMICAL CONSTITUENTS

Analyte	Units	N	WNSW74A		N	Reference Values	
			Concentrations			Background Range WFBCBKG ^a	Standard ^b
			Average	Maximum			
Alpha-BHC	mg/L	2	<0.000009	<0.000009	2	<0.000009-<0.000009	0.000002
Aluminum, Total	mg/L	2	<0.10	<0.10	0	NA	--
Ammonia-N	mg/L	2	<0.05	<0.05	2	<0.05-0.07	0.67-29
Antimony, Total	mg/L	2	<0.003	<0.003	2	<0.003-<0.003	--
Arsenic, Dissolved	mg/L	2	<0.005	<0.005	2	<0.005-<0.005	0.340
Boron, Total	mg/L	2	0.03	0.04	2	0.01-0.02	--
Bromide	mg/L	2	<0.72	0.94	2	<0.50-<0.50	--
Cadmium, Total	mg/L	2	<0.001	<0.001	0	NA	--
Calcium, Total	mg/L	2	89.3	96	12	23.1-46.9	--
Chromium, Total	mg/L	2	<0.01	<0.01	0	NA	--
Cobalt, Total	mg/L	2	<0.005	<0.005	2	<0.005-<0.005	0.110 ^c
Copper, Dissolved	mg/L	2	<0.005	<0.005	2	<0.005-<0.005	0.037 ^d
Copper, Total	mg/L	2	<0.005	<0.005	0	NA	--
Fluoride	mg/L	2	0.15	0.16	2	<0.10-<0.10	27.8 ^d
Hardness	mg/L	2	271	290	12	73-144	--
Iron, Total	mg/L	2	0.14	0.2	2	0.51-2.16	0.30
Lead, Total	mg/L	2	<0.0005	<0.0005	0	NA	--
Magnesium, Total	mg/L	2	11.68	12.15	12	3.57-6.59	--
Manganese, Total	mg/L	2	0.08	0.09	2	0.04-0.04	--
Mercury, Total, Method 1631	mg/L	1	0.00000110	0.00000110	0	NA	--
Nickel, Total	mg/L	2	<0.04	<0.04	0	NA	--
Nitrate-N	mg/L	2	0.54	0.56	2	<0.05-0.61	--
Nitrite-N	mg/L	2	<0.05	<0.05	2	<0.05-<0.05	--
NPOC	mg/L	2	4.4	4.6	2	2.0-2.4	--
Oil & Grease	mg/L	2	<5	<5	2	<5-<5	--
pH	SU	2	7.58	7.83	2	7.68-7.97	6.0-9.5
Selenium, Total	mg/L	2	<0.001	<0.001	0	NA	--
Solids, Total Dissolved	mg/L	2	744	890	2	117-188	--
Solids, Total Suspended	mg/L	2	<4	<5	2	<4-39	--

N - Number of samples

NA - No data available

-- No guideline or standard available for these analytes

^a Background location

^b New York State Water Quality Standards, Class "D" as a comparative reference for nonradiological results at WNSW74A

^c Standards for cobalt, thallium, and vanadium are acid-soluble.

^d Calculated from maximum measurement of hardness of surface water drainage at WNSW74A

Table C-3C (concluded)
2004 Water Quality of Surface Water at the North Swamp (WNSW74A)

CHEMICAL CONSTITUENTS (concluded)

Analyte	Units	N	WNSW74A		N	Reference Values	
			Concentrations			Background Range WFBCBKG ^a	Standard ^b
			Average	Maximum			
Sulfate	mg/L	2	45.9	50.3	2	14.4-20.7	--
Sulfide	mg/L	2	<0.07	0.1	2	<0.04-0.08	--
Surfactants	mg/L	2	<0.10	<0.10	2	<0.03-<0.10	--
Thallium, Total	mg/L	2	<0.008	<0.008	2	<0.008-<0.008	0.020 ^c
Titanium, Total	mg/L	2	<0.05	<0.05	2	<0.05-<0.05	--
TOX	mg/L	2	<0.03	<0.04	2	<0.005-<0.030	--
Vanadium, Total	mg/L	2	<0.01	<0.01	2	<0.01-<0.01	0.190 ^c
Zinc, Total	mg/L	2	<0.02	<0.02	0	NA	--

N - Number of samples

NA - No data available

-- No guideline or standard available for these analytes

^a Background location

^b New York State Water Quality Standards, Class "D" as a comparative reference for nonradiological results at WNSW74A

^c Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-3D
2004 Water Quality of Surface Water at the Northeast Swamp (WNSWAMP)

RADIOACTIVITY CONCENTRATIONS

Analyte	Units	N	WNSWAMP Concentrations		N	Reference Values	
			Average	Maximum		WFBCBKG ^a	Guideline ^b
						Background Range	
Gross Alpha	μCi/mL	53	0.33±2.27E-09	3.91E-09	12	<4.53E-10–2.55E-09	3E-08 ^c
Gross Beta	μCi/mL	53	2.51±0.03E-06	6.68E-06	12	<1.16E-09–3.64E-09	1E-06 ^d
Tritium	μCi/mL	53	7.75±7.99E-08	1.96E-07	12	<7.48E-08–1.35E-07	2E-03
C-14	μCi/mL	4	0.03±2.09E-08	<2.78E-08	4	<5.38E-09–<3.03E-08	7E-05
Sr-90	μCi/mL	12	1.31±0.03E-06	2.48E-06	4	<1.13E-09–<1.30E-09	1E-06
I-129	μCi/mL	4	4.90±8.94E-10	<1.09E-09	4	<6.26E-10–1.21E-09	5E-07
Cs-137	μCi/mL	12	1.34±2.03E-09	2.56E-09	4	<1.94E-09–<2.34E-09	3E-06
U-232	μCi/mL	4	-0.82±4.37E-11	<5.87E-11	4	<3.46E-11–<1.00E-10	1E-07
U-233/234	μCi/mL	4	1.53±0.90E-10	2.18E-10	4	8.19E-11–1.81E-10	5E-07
U-235/236	μCi/mL	4	2.18±4.13E-11	<5.60E-11	4	<4.14E-11–5.25E-11	5E-07 ^e
U-238	μCi/mL	4	1.38±0.83E-10	1.59E-10	4	<4.68E-11–8.50E-11	6E-07
Total U	μg/mL	4	4.51±1.09E-04	6.23E-04	4	3.32E-05–6.00E-04	--
Pu-238	μCi/mL	4	0.48±3.35E-11	<4.68E-11	4	<1.24E-11–<3.38E-11	4E-08
Pu-239/240	μCi/mL	4	0.73±2.82E-11	<4.00E-11	4	<1.25E-11–<3.85E-11	3E-08
Am-241	μCi/mL	4	1.04±4.09E-11	<5.04E-11	4	<2.21E-11–<4.85E-11	3E-08

N - Number of samples

-- No guideline or standard available for these analytes

^a Background location

^b DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results.

^c Alpha as Am-241

^d Beta as Sr-90

^e DCG for U-236 is used for this comparison

Table C-3D (continued)
2004 Water Quality of Surface Water at the Northeast Swamp (WNSWAMP)

CHEMICAL CONSTITUENTS

Analyte	Units	N	WNSWAMP Concentrations		N	Reference Values	
			Average	Maximum		WFBCBK ^a Background Range	Standard ^b
Aluminum, Total	mg/L	2	0.05	0.06	0	NA	--
Ammonia-N	mg/L	2	<0.10	<0.10	2	<0.05–0.07	0.67–29
Antimony, Total	mg/L	2	<0.003	<0.003	2	<0.003–<0.003	--
Arsenic, Dissolved	mg/L	2	<0.004	0.004	2	<0.005–<0.005	0.340
Boron, Total	mg/L	2	0.04	0.05	2	0.01–0.02	--
Bromide	mg/L	2	0.79	1	2	<0.50–<0.50	--
Cadmium, Total	mg/L	2	<0.0004	<0.0004	0	NA	--
Calcium, Total	mg/L	2	113.5	119	12	23.1–46.9	--
Chromium, Total	mg/L	2	<0.0012	<0.0012	0	NA	--
Cobalt, Total	mg/L	2	<0.001	<0.001	2	<0.005–<0.005	0.110 ^c
Copper, Dissolved	mg/L	2	0.003	0.003	2	<0.005–<0.005	0.045 ^d
Copper, Total	mg/L	2	0.002	0.003	0	NA	--
Fluoride	mg/L	2	<0.10	<0.10	2	<0.10–<0.10	34.1 ^d
Hardness	mg/L	2	344	363	12	73–144	--
Iron, Total	mg/L	2	<0.05	0.06	2	0.51–2.16	0.30
Lead, Total	mg/L	2	<0.0031	<0.0031	0	NA	--
Magnesium, Total	mg/L	2	14.80	16	12	3.57–6.59	--
Manganese, Total	mg/L	2	0.10	0.12	2	0.04–0.04	--
Mercury, Total, Method 1631	mg/L	2	0.00000159	0.00000194	0	NA	--
Nickel, Total	mg/L	2	<0.0012	<0.0012	0	NA	--
Nitrate-N	mg/L	2	0.10	0.11	2	<0.05–0.61	--
Nitrite-N	mg/L	2	<0.03	0.03	2	<0.05–<0.05	--
NPOC	mg/L	2	5.1	5.6	2	2.0–2.4	--
Oil & Grease	mg/L	2	<1	<1	2	<5–<5	--
pH	SU	2	7.12	7.56	2	7.68–7.97	6.0–9.5

N - Number of samples

NA - No data available

-- No guideline or standard available for these analytes

^a Background location

^b New York State Water Quality Standards, Class "D" as a comparative reference for nonradiological results at WNSWAMP

^c Standards for cobalt, thallium, and vanadium are acid-soluble.

^d Calculated from maximum measurement of hardness of surface water drainage at WNSWAMP

Table C-3D (concluded)
2004 Water Quality of Surface Water at the Northeast Swamp (WNSWAMP)

CHEMICAL CONSTITUENTS (concluded)

Analyte	Units	N	WNSWAMP		N	Reference Values	
			Concentrations			WFBCBK ^a	Standard ^b
			Average	Maximum			
Selenium, Total	mg/L	2	<0.004	<0.004	0	NA	--
Solids, Total Dissolved	mg/L	2	742	776	2	117-188	--
Solids, Total Suspended	mg/L	2	<5	<5	2	<4-39	--
Sulfate	mg/L	2	21.6	22.4	2	14.4-20.7	--
Sulfide	mg/L	2	<1.00	<1.00	2	<0.04-0.08	--
Surfactants	mg/L	2	<0.10	<0.10	2	<0.03-<0.10	--
Thallium, Total	mg/L	2	<0.007	<0.007	2	<0.008-<0.008	0.020 ^c
Titanium, Total	mg/L	2	<0.0004	<0.0004	2	<0.05-<0.05	--
TOX	mg/L	2	0.03	0.04	2	<0.005-<0.030	--
Vanadium, Total	mg/L	2	<0.0010	<0.0010	2	<0.01-<0.01	0.190 ^c
Zinc, Total	mg/L	2	0.01	0.02	0	NA	--

N - Number of samples

NA - No data available

-- No guideline or standard available for these analytes

^a Background location

^b New York State Water Quality Standards, Class "D" as a comparative reference for nonradiological results at WNSWAMP

^c Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-3E
2004 Indicator Results at Storage and Disposal Area Drainage (WNNADR)

Analyte	Units	N	WNNADR Concentrations			Standard ^a
			Minimum	Average	Maximum	
Gross Alpha	µCi/mL	12	<9.65E-10	0.59±1.31E-09	2.11E-09	--
Gross Beta	µCi/mL	12	1.49E-07	1.97±0.06E-07	2.58E-07	--
Tritium	µCi/mL	12	4.04E-07	8.11±0.92E-07	1.30E-06	--
Sr-90	µCi/mL	4	8.49E-08	9.73±0.53E-08	1.05E-07	--
I-129	µCi/mL	4	<8.18E-10	-1.46±9.22E-10	<1.03E-09	--
Cs-137	µCi/mL	12	<1.90E-09	1.52±7.34E-09	<1.23E-08	--
NPOC	mg/L	53	1.1	5.7	11.8	--
pH	SU	53	6.54	7.39	8.08	6.0–9.5
TOX	mg/L	53	<0.005	<0.03	0.225	--

N - Number of samples

-- No applicable reference standard available

^a New York State Water Quality Standards, Class "D" as a comparative reference for nonradiological results at WNNADR

Table C-3F
2004 Indicator Results in Subsurface Water at the NDA Interceptor Trench (WNNATR)

Analyte	Units	N	WNNATR Concentrations		
			Minimum	Average	Maximum
Gross Alpha	µCi/mL	12	<1.50E-09	1.26±2.40E-09	4.51E-09
Gross Beta	µCi/mL	12	1.29E-07	1.76±0.07E-07	2.01E-07
Tritium	µCi/mL	12	2.49E-07	3.75±0.17E-06	6.36E-06
I-129	µCi/mL	4	<8.00E-10	0.55±1.33E-09	<1.78E-09
Cs-137	µCi/mL	12	<4.33E-09	1.59±6.50E-09	7.08E-09
NPOC	mg/L	12	2.3	4.3	6.4
TOX	mg/L	12	<0.006	<0.018	0.033

Note: No standards applicable for this location. These waters are pumped and treated at the LLWTF prior to discharge at outfall WNSP001.

N - Number of samples

Table C-3G
2004 Indicator Results at SDA Drainage (WNSDADR)

Analyte	Units	N	WNSDADR Concentrations			Guideline or Standard ^a
			Minimum	Average	Maximum	
Gross Alpha	µCi/mL	12	<3.06E-10	7.58±6.72E-10	1.73E-09	--
Gross Beta	µCi/mL	12	1.71E-09	5.59±0.95E-09	2.18E-08	--
Tritium	µCi/mL	12	1.63E-07	5.23±0.83E-07	1.74E-06	--
Cs-137	µCi/mL	12	<4.91E-09	0.28±7.32E-09	<1.08E-08	--
pH	SU	12	6.61	7.22	7.9	6.5–8.5

N - Number of samples

-- No applicable reference standard available

^a New York State Water Quality Standards, Class "C" as a comparative reference for nonradiological results at WNSDADR

Table C-3H
2004 Indicator Results in Surface Water at Cooling Tower Basin (WNCOOLW)

Analyte	Units	N	WNCOOLW Concentrations		
			Minimum	Average	Maximum
Gross Alpha	µCi/mL	4	<1.06E-09	0.17±1.39E-09	<1.91E-09
Gross Beta	µCi/mL	4	<2.45E-09	2.20±2.98E-09	3.69E-09
Tritium	µCi/mL	4	<5.61E-08	1.00±6.94E-08	8.47E-08
Sr-90	µCi/mL	4	<1.36E-09	1.07±1.36E-09	2.21E-09
Cs-137	µCi/mL	4	<3.99E-09	-2.39±7.40E-09	<1.05E-08
pH	SU	4	7.79	8.07	8.56

Note: No standards are applicable for this location. These waters are pumped and treated at the LLWTF prior to discharge at outfall WNSP001.

N - Number of samples

This page intentionally left blank

Appendix C-4
Ambient Surface Water Data

This page intentionally left blank

Table C-4A
2004 Radioactivity and pH in Surface Water Downstream of the WVDP in
Cattaraugus Creek at Felton Bridge (WFFELBR)

Analyte	Units	N	WFFELBR		N	Reference Values	
			Concentrations			WFBIGBR ^a	Guideline ^b
			Average	Maximum			
Gross Alpha	μCi/mL	12	0.95±1.34E-09	3.51E-09	12	<8.71E-10–2.10E-09	3E-08 ^d
Gross Beta	μCi/mL	12	3.61±1.69E-09	7.69E-09	12	<9.03E-10–4.16E-09	1E-06 ^c
Tritium	μCi/mL	12	-2.10±8.10E-08	<8.94E-08	12	<5.52E-08–8.98E-08	2E-03
Sr-90	μCi/mL	12	1.81±1.46E-09	2.74E-09	12	<1.12E-09–2.24E-09	1E-06
Tc-99	μCi/mL	4	-1.94±2.22E-09	<2.61E-09	0	NA	1E-04
Cs-137	μCi/mL	12	0.75±2.35E-09	2.33E-09	12	<1.87E-09–1.97E-09	3E-06
pH	SU	53	7.01	8.28	12	7.30–8.34	6.5–8.5

N - Number of samples

NA - Data not available

^a Background location

^b DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results in the absence of water quality standards.

^c New York State Water Quality Standards, Class “B” as a comparative reference for nonradiological results

^d Alpha as Am-241

^e Beta as Sr-90

Table C-4B
2004 Water Quality of Surface Water Downstream of the WVDP in Buttermilk
Creek at Thomas Corners Bridge (WFBCTCB)

RADIOACTIVITY CONCENTRATIONS

Analyte	Units	N	WFBCTCB		N	Reference Values	
			Concentrations			WFBCKG ^a	Guideline ^b
			Average	Maximum			
Gross Alpha	μCi/mL	12	6.90±9.30E-10	2.11E-09	12	<4.53E-10–2.55E-09	3E-08 ^c
Gross Beta	μCi/mL	12	7.88±1.49E-09	1.18E-08	12	<1.16E-09–3.64E-09	1E-06 ^d
Tritium	μCi/mL	12	1.49±8.09E-08	1.76E-07	12	<7.48E-08–1.35E-07	2E-03
Sr-90	μCi/mL	4	3.67±1.64E-09	4.89E-09	4	<1.13E-09–<1.30E-09	1E-06
Tc-99	μCi/mL	4	-2.10±2.08E-09	<2.39E-09	4	<1.44E-09–<2.27E-09	1E-04
Cs-137	μCi/mL	4	2.46±2.82E-09	4.23E-09	4	<1.94E-09–<2.34E-09	3E-06

N - Number of samples

^a Background location

^b DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results in the absence of water quality standards.

^c Alpha as Am-241

^d Beta as Sr-90

Table C-4B (continued)
2004 Water Quality of Surface Water Downstream of the WVDP in Buttermilk Creek at Thomas Corners Bridge (WFBCTCB)

CHEMICAL CONSTITUENTS

Analyte	Units	N	WFBCTCB Concentrations		N	Reference Values	
			Average	Maximum		WFBCBKG ^a Background Range	Standard ^b
Aluminum, Dissolved	mg/L	2	0.686	1.26	2	<0.100-0.328	0.10
Ammonia-N	mg/L	2	<0.16	0.28	2	<0.05-0.07	0.09-2.1
Antimony, Total	mg/L	2	<0.003	<0.003	2	<0.003-<0.003	--
Arsenic, Dissolved	mg/L	2	<0.005	<0.005	2	<0.005-<0.005	0.150
Barium, Total	mg/L	2	<0.06	0.07	2	0.06-0.10	--
Boron, Total	mg/L	2	0.02	0.03	2	0.01-0.02	10.0
Bromide	mg/L	2	<0.50	<0.50	2	<0.50-<0.50	--
Cadmium, Dissolved	mg/L	2	<0.001	<0.001	2	<0.001-<0.001	0.003 ^c
Calcium, Total	mg/L	12	38.1	54.4	12	23.1-46.9	--
Chloride	mg/L	2	20	23	2	12-13	--
Chromium, Dissolved	mg/L	2	<0.01	<0.01	2	<0.01-<0.01	0.114 ^c
Cobalt, Total	mg/L	2	<0.005	<0.005	2	<0.005-<0.005	0.005 ^d
Copper, Dissolved	mg/L	2	<0.005	<0.005	2	<0.005-<0.005	0.014 ^c
Dissolved, Oxygen	mg/L	2	10.9	12.3	2	10.5-11.9	4.0 (min)
Fluoride	mg/L	2	<0.10	<0.10	2	<0.10-<0.10	3.43 ^c
Hardness	mg/L	12	120	170	12	73-144	--
Iron, Total	mg/L	2	1.66	2.52	2	0.51-2.16	0.30
Lead, Dissolved	mg/L	2	<0.0005	<0.0005	2	<0.0005-<0.0005	0.007 ^c
Magnesium, Total	mg/L	12	5.99	8.22	12	3.57-6.59	--
Manganese, Total	mg/L	2	0.03	0.04	2	0.04-0.04	--
Mercury, Dissolved, Method 1631	mg/L	2	<0.00000815	0.00000113	2	<0.00000500-0.00000113	--
Nickel, Dissolved	mg/L	2	<0.04	<0.04	2	<0.04-<0.04	0.081 ^c
Nitrate-N	mg/L	2	0.58	0.62	2	<0.05-0.61	--
Nitrite-N	mg/L	2	<0.05	<0.05	2	<0.05-<0.05	0.10
NPOC	mg/L	2	2.4	2.4	2	2.0-2.4	--

N - Number of samples

-- No reference standard available for this analyte

^a Background location

^b New York State Water Quality Standards, Class "C" as a comparative reference for nonradiological results

^c Calculated from maximum measurement of hardness of surface water stream at WFBCTCB

^d Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-4B (concluded)
2004 Water Quality of Surface Water Downstream of the WVDP
in Buttermilk Creek at Thomas Corners Bridge (WFBCTCB)

CHEMICAL CONSTITUENTS (concluded)

Analyte	Units	N	WFBCTCB		N	Reference Values	
			Concentrations			WFBCKG ^a Background Range	Standard ^b
			Average	Maximum			
Oil & Grease	mg/L	2	<5	<5	2	<5-<5	--
pH	SU	2	7.85	7.89	2	7.68-7.97	6.5-8.5
Selenium, Dissolved	mg/L	2	<0.001	<0.001	2	<0.001-<0.001	0.0046
Sodium, Total	mg/L	2	13	16.1	2	7.7-9.0	--
Solids, Total Dissolved	mg/L	2	178	229	2	117-188	500
Solids, Total Suspended	mg/L	2	<4	<4	2	<4-39	--
Sulfate	mg/L	2	20.2	24.7	2	14.4-20.7	--
Sulfide	mg/L	2	0.06	0.08	2	<0.04-0.08	0.002
Surfactants	mg/L	2	<0.10	<0.10	2	<0.03-<0.10	0.04
Thallium, Total	mg/L	2	<0.008	<0.008	2	<0.008-<0.008	0.008 ^d
Titanium, Total	mg/L	2	<0.05	0.05	2	<0.05-<0.05	--
TOX	mg/L	2	<0.02	<0.03	2	<0.00-<0.03	--
Vanadium, Total	mg/L	2	<0.01	<0.01	2	<0.01-<0.01	0.014 ^d
Zinc, Dissolved	mg/L	2	<0.02	<0.02	2	<0.02-<0.02	0.130 ^c

N - Number of samples

-- No reference standard available for this analyte

^a Background location

^b New York State Water Quality Standards, Class "C" as a comparative reference for nonradiological results

^c Calculated from maximum measurement of hardness of surface water stream at WFBCTCB

^d Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-4C
2004 Water Quality of Surface Water Downstream of the WVDP at
Frank's Creek (WNSP006)

RADIOACTIVITY CONCENTRATIONS

Analyte	Units	N	WNSP006		N	Reference Values	
			Concentrations			WFBCBKG ^a	Guideline ^b
			Average	Maximum			
Gross Alpha	μCi/mL	53	0.62±1.72E-09	6.91E-09	12	<4.53E-10–2.55E-09	3E-08 ^c
Gross Beta	μCi/mL	53	4.31±0.40E-08	8.28E-08	12	<1.16E-09–3.64E-09	1E-06 ^d
Tritium	μCi/mL	53	7.53±8.00E-08	5.81E-07	12	<7.48E-08–1.35E-07	2E-03
C-14	μCi/mL	4	-0.32±2.36E-08	<2.86E-08	4	<5.38E-09–<3.03E-08	7E-05
Sr-90	μCi/mL	12	2.12±0.31E-08	3.52E-08	4	<1.13E-09–<1.30E-09	1E-06
Tc-99	μCi/mL	4	1.04±2.25E-09	3.55E-09	4	<1.44E-09–<2.27E-09	1E-04
I-129	μCi/mL	4	4.82±7.93E-10	1.05E-09	4	<6.26E-10–1.21E-09	5E-07
Cs-137	μCi/mL	12	2.41±7.57E-09	1.14E-08	4	<1.94E-09–<2.34E-09	3E-06
U-232	μCi/mL	4	2.92±1.35E-10	3.87E-10	4	<3.46E-11–<1.00E-10	1E-07
U-233/234	μCi/mL	4	3.90±1.46E-10	5.36E-10	4	8.19E-11–1.81E-10	5E-07
U-235/236	μCi/mL	4	6.40±6.00E-11	9.57E-11	4	<4.14E-11–5.25E-11	5E-07 ^e
U-238	μCi/mL	4	4.18±1.47E-10	5.49E-10	4	<4.68E-11–8.50E-11	6E-07
Total U	μg/mL	4	9.60±0.19E-04	1.38E-03	4	3.32E-05–6.00E-04	--
Pu-238	μCi/mL	4	1.09±3.24E-11	3.28E-11	4	<1.24E-11–<3.38E-11	4E-08
Pu-239/240	μCi/mL	4	2.07±3.55E-11	6.62E-11	4	<1.25E-11–<3.85E-11	3E-08
Am-241	μCi/mL	4	2.32±3.47E-11	<4.68E-11	4	<2.21E-11–<4.85E-11	3E-08

N - Number of samples

-- No guideline or standard available for these analytes

^a Background location

^b DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results.

^c Alpha as Am-241

^d Beta as Sr-90

^e DCG for U-236 is used for this comparison.

Table C-4C (continued)
2004 Water Quality of Surface Water Downstream of the WVDP at
Frank's Creek (WNSP006)

CHEMICAL CONSTITUENTS

Analyte	Units	N	WNSP006		N	Reference Values	
			Concentrations			WFBCBKG ^a	Standard ^b
			Average	Maximum			
Alpha-BHC	mg/L	2	<0.000009	<0.000009	2	<0.000009–<0.000009	0.000002
Aluminum, Dissolved	mg/L	2	0.508	0.598	2	<0.100–0.328	0.10
Ammonia-N	mg/L	2	<0.05	<0.05	2	<0.05–0.07	0.09–2.1
Antimony, Total	mg/L	2	<0.003	<0.003	2	<0.003–<0.003	--
Arsenic, Dissolved	mg/L	2	<0.005	<0.005	2	<0.005–<0.005	0.150
Barium, Total	mg/L	2	0.07	0.09	2	0.06–0.10	--
Boron, Total	mg/L	2	0.03	0.03	2	0.01–0.02	10.0
Bromide	mg/L	2	<0.63	0.76	2	<0.50–<0.50	--
Cadmium, Dissolved	mg/L	2	<0.001	<0.001	2	<0.001–<0.001	0.004 ^c
Calcium, Total	mg/L	12	52.2	76.6	12	23.1–46.9	--
Chloride	mg/L	2	110	125	2	12–13	--
Chromium, Dissolved	mg/L	2	<0.01	<0.01	2	<0.01–<0.01	0.153 ^c
Cobalt, Total	mg/L	2	<0.005	<0.005	2	<0.005–<0.005	0.005 ^d
Conductivity	µmhos/cm@25°C	3	554	614	0	NA	--
Copper, Dissolved	mg/L	2	<0.005	<0.005	2	<0.005–<0.005	0.019 ^c
Dissolved Oxygen	mg/L	2	10.8	12.7	2	10.5–11.9	4.0 (min)
Fluoride	mg/L	2	<0.10	<0.10	2	<0.10–<0.10	4.72 ^c
Hardness	mg/L	12	167	242	12	73–144	--
Iron, Total	mg/L	2	5.96	8.79	2	0.51–2.16	0.30
Lead, Dissolved	mg/L	2	<0.0005	<0.0005	2	<0.0005–<0.0005	0.010 ^c
Magnesium, Total	mg/L	12	8.93	12.1	12	3.57–6.59	--
Manganese, Total	mg/L	2	0.17	0.26	2	0.04–0.04	--
Mercury, Dissolved, Method 1631	mg/L	2	<0.00000228	0.00000405	2	<0.000000500–0.00000405	--
Nickel, Dissolved	mg/L	2	<0.04	<0.04	2	<0.04–<0.04	0.11 ^c
Nitrate-N	mg/L	2	0.58	0.58	2	<0.05–0.61	--
Nitrite-N	mg/L	2	<0.06	0.06	2	<0.05–<0.05	0.10
NPOC	mg/L	2	2.9	3.5	2	2.0–2.4	--
Oil & Grease	mg/L	2	<5	<5	2	<5–<5	--
pH	SU	2	6.88	7.83	2	7.68–7.97	6.5–8.5

N - Number of samples

NA - No data available

-- No guideline or standard available for these analytes

^a Background location

^b New York Water Quality Standards for Class "C" surface waters as a comparative reference for nonradiological results.

^c Calculated from maximum measured hardness of surface water stream at WNSP006.

^d Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-4C (concluded)
2004 Water Quality of Surface Water Downstream of the WVDP at
Frank's Creek (WNSP006)

CHEMICAL CONSTITUENTS (concluded)

Analyte	Units	N	WNSP006		N	Reference Values	
			Concentrations			WFBCBK ^a	Standard ^b
			Average	Maximum			
Selenium, Dissolved	mg/L	2	<0.001	<0.001	2	<0.001–<0.001	0.0046
Sodium, Total	mg/L	2	87.4	93.1	2	7.7–9.0	--
Solids, Total Dissolved	mg/L	40	314	489	2	117–188	500
Solids, Total Suspended	mg/L	2	86	113	2	<4–39	--
Sulfate	mg/L	2	46.0	57.8	2	14.4–20.7	--
Sulfide	mg/L	2	<0.04	<0.04	2	<0.04–0.08	0.002
Surfactants	mg/L	2	<0.06	<0.10	2	<0.03–<0.10	0.40
Thallium, Total	mg/L	2	<0.008	<0.008	2	<0.008–<0.008	0.008 ^d
Titanium, Total	mg/L	2	0.06	0.07	2	<0.05–<0.05	--
TOX	mg/L	2	0.01	0.01	2	<0.00–<0.03	--
Vanadium, Total	mg/L	2	<0.01	0.01	2	<0.01–<0.01	0.014 ^d
Zinc, Dissolved	mg/L	2	<0.02	<0.02	2	<0.02–<0.02	0.18 ^c

N - Number of samples

-- No guideline or standard available for these analytes

^a Background location

^b New York Water Quality Standards for Class "C" surface waters as a comparative reference for nonradiological results.

^c Calculated from maximum measured hardness of surface water stream at WNSP006.

^d Standards for cobalt, thallium, and vanadium are acid-soluble.

Table C-4D
2004 Total Dissolved Solids From Outfall WNSP116

Month	Units	N	Total Dissolved Solids		Daily Maximum Limit
			Average	Maximum	
January	mg/L	2	350	360	500
February ^a	mg/L	0	--	--	500
March	mg/L	2	281	320	500
April	mg/L	2	288	297	500
May	mg/L	2	253	347	500
June	mg/L	2	343	372	500
July ^a	mg/L	0	--	--	500
August	mg/L	2	381	381	500
September	mg/L	2	356	381	500
October ^a	mg/L	0	--	--	500
November ^a	mg/L	0	--	--	500
December	mg/L	2	279	316	500

N - Number of samples

^a No discharge this month

Table C-4E
2004 Indicator Results in Surface Water at Erdman Brook (WNERB53)

Analyte	Units	N	WNERB53 Concentrations			Reference
			Minimum	Average	Maximum	Guideline ^a or Standard ^b
Gross Alpha	μCi/mL	53	<9.33E-10	-0.13±1.89E-09	2.44E-09	3E-08 ^c
Gross Beta	μCi/mL	53	1.00E-08	1.78±0.27E-08	3.32E-08	1E-06 ^d
Tritium	μCi/mL	53	<5.54E-08	4.75±7.71E-08	1.77E-07	2E-03
Sr-90	μCi/mL	4	7.20E-09	7.96±2.03E-09	8.79E-09	1E-06
Cs-137	μCi/mL	4	<2.05E-09	0.44±5.63E-09	2.41E-09	3E-06
pH	SU	53	6.52	7.52	8.08	6.0–9.5

N - Number of samples

^a DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results.

^b New York State Water Quality Standards, Class "D" for surface waters as a standard for nonradiological results

^c Alpha as Am-241

^d Beta as Sr-90

Table C-4F
2004 Indicator Results in Surface Water at Frank's Creek East of the SDA
(WNFRC67)

Analyte	Units	N	WNFRC67 Concentrations			Reference
			Minimum	Average	Maximum	Guideline ^a or Standard ^b
Gross Alpha	μCi/mL	12	<4.90E-10	-0.35±8.03E-10	<1.43E-09	3E-08 ^c
Gross Beta	μCi/mL	12	<1.08E-09	1.90±1.19E-09	3.86E-09	1E-06 ^d
Tritium	μCi/mL	12	<5.64E-08	4.84±8.35E-08	1.82E-07	2E-03
Sr-90	μCi/mL	4	<8.49E-10	0.62±1.19E-09	<1.47E-09	1E-06
Cs-137	μCi/mL	4	<1.98E-09	1.02±2.83E-09	<3.54E-09	3E-06
pH	SU	12	7.34	7.59	8.06	6.5–8.5

N - Number of samples

^a DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results in the absence of water quality standards.

^b New York State Water Quality Standards for Class "C" surface waters as a comparative reference for nonradiological results.

^c Alpha as Am-241

^d Beta as Sr-90

Table C-4G
2004 Indicator Results in Surface Water at Drum Cell Drainage (WNDCELD)

Analyte	Units	N	WNDCELD Concentrations			Reference
			Minimum	Average	Maximum	Guideline ^a or Standard ^b
Gross Alpha	μCi/mL	12	<4.84E-10	-0.94±8.74E-10	1.28E-09	3E-08 ^c
Gross Beta	μCi/mL	12	<1.08E-09	1.89±1.21E-09	2.82E-09	1E-06 ^d
Tritium	μCi/mL	4	<7.86E-08	5.50±8.21E-08	9.79E-08	2E-03
Sr-90	μCi/mL	4	<1.20E-09	1.76±1.63E-09	4.66E-09	1E-06
I-129	μCi/mL	4	<4.98E-10	2.15±8.41E-10	9.56E-10	5E-07
Cs-137	μCi/mL	4	4.54E-09	1.18±5.80E-09	4.54E-09	3E-06
pH	SU	12	6.94	7.48	7.85	6.5–8.5

N - Number of samples

^a DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results in the absence of water quality standards.

^b New York State Water Quality Standards for Class "C" surface waters as a comparative reference for nonradiological results.

^c Alpha as Am-241

^d Beta as Sr-90

Table C-4H
2004 Water Quality of Surface Water at the Standing Water (WNSTAW-Series)
Locations

Analyte	Units	N	WNSTAW4	WNSTAW5	Reference Values	
					WNSTAWB ^a Background Location	Guideline ^b or Standard ^c
Gross Alpha	μCi/mL	1	-5.48±3.88E-10	-6.63±2.72E-10	0.57±8.09E-10	3E-08 ^d
Gross Beta	μCi/mL	1	4.16±0.88E-09	1.92±0.64E-09	2.17±0.93E-09	1E-06 ^e
Tritium	μCi/mL	1	-1.85±8.27E-08	1.76±5.77E-08	6.11±8.07E-08	2E-03
Sr-90	μCi/mL	1	1.93±1.55E-09	0.85±1.08E-09	1.72±0.97E-09	1E-06
Cs-137	μCi/mL	1	0.46±8.38E-09	1.15±6.79E-09	-0.01±1.21E-08	3E-06
Chloride	mg/L	1	6	<1	22	--
Conductivity	μmhos/cm@25°C	1	95	47	321	--
Iron, Total	mg/L	1	0.63	0.68	0.2	0.3
Manganese, Total	mg/L	1	0.04	0.08	0.1	--
Nitrate+Nitrite	mg/L	1	<0.05	<0.05	<0.05	--
pH	SU	1	7.88	8.19	7.97	6.0-9.5
Sodium, Total	mg/L	1	4.5	<1.0	13	--
Sulfate	mg/L	1	5.4	5.8	11	--

Analyte	Units	N	WNSTAW6	Reference Values	
				WNSTAWB ^a Background Location	Guideline ^b or Standard ^c
Gross Alpha	μCi/mL	1	-7.53±6.85E-10	0.57±8.09E-10	3E-08 ^d
Gross Beta	μCi/mL	1	3.15±1.00E-09	2.17±0.93E-09	1E-06 ^e
Tritium	μCi/mL	1	-5.51±7.93E-08	6.11±8.07E-08	2E-03
Sr-90	μCi/mL	1	0.10±1.52E-09	1.72±0.97E-09	1E-06
Cs-137	μCi/mL	1	4.36±5.05E-09	-0.01±1.21E-08	3E-06
Chloride	mg/L	1	3	22	--
Conductivity	μmhos/cm@25°C	1	200	321	--
Iron, Total	mg/L	1	<0.10	0.2	0.3
Manganese, Total	mg/L	1	<0.02	0.1	--
Nitrate+Nitrite	mg/L	1	<0.05	<0.05	--
pH	SU	1	8.26	7.97	6.0-9.5
Sodium, Total	mg/L	1	1.4	13	--
Sulfate	mg/L	1	6.6	11	--

N - Number of samples

-- No guideline or standard available for these analytes

^a Background location

^b DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results.

^c New York State Water Quality Standards Class "D" surface waters as a comparative standard for nonradiological results

^d Alpha as Am-241

^e Beta as Sr-90

Table C-4H (concluded)
2004 Water Quality of Surface Water at the Standing Water (WNSTAW-Series)
Locations

Analyte	Units	N	WNSTAW9	Reference Values	
				WNSTAWB ^a Background Location	Guideline ^b or Standard ^c
Gross Alpha	μCi/mL	1	-0.38±5.36E-10	0.57±8.09E-10	3E-08 ^d
Gross Beta	μCi/mL	1	2.20±0.90E-09	2.17±0.93E-09	1E-06 ^e
Tritium	μCi/mL	1	-5.20±8.07E-08	6.11±8.07E-08	2E-03
Sr-90	μCi/mL	1	0.41±1.21E-09	1.72±0.97E-09	1E-06
Cs-137	μCi/mL	1	6.38±6.30E-09	-0.01±1.21E-08	3E-06
Chloride	mg/L	1	6	22	--
Conductivity	μmhos/cm@25°C	1	185	321	--
Iron, Total	mg/L	1	0.48	0.2	0.3
Manganese, Total	mg/L	1	0.29	0.1	--
Nitrate+Nitrite	mg/L	1	<0.05	<0.05	--
pH	SU	1	7.86	7.97	6.5–8.5
Sodium, Total	mg/L	1	4.8	13	--
Sulfate	mg/L	1	13.2	11	--

N - Number of samples

-- No guideline or standard available for these analytes

^a Background location

^b DOE ingestion-based DCGs for 100 mrem/yr dose limit are provided as a guideline for radiological results.

^c New York State Water Quality Standards Class "C" surface waters as a comparative standard for nonradiological results at WNSTAW9

^d Alpha as Am-241

^e Beta as Sr-90

Appendix C-5
Potable Water (Drinking Water) Data

This page intentionally left blank

Table C-5A
2004 Indicator Results in Potable Well Water Around the WVDP

Analyte	Units	N	Annual Concentrations at Potable Wells			Reference Values	
			WFWEL01	WFWEL02	WFWEL03	Background ^a WFWEL06	Standard ^{b,c}
Gross Alpha	μCi/mL	1	0.22±1.06E-09	-0.36±1.39E-09	0.92±1.09E-09	-2.26±7.02E-10	1.5E-08 ^d
Gross Beta	μCi/mL	1	4.24±1.31E-09	1.82±1.47E-09	1.22±1.41E-09	1.77±8.44E-10	1E-06 ^e
Tritium	μCi/mL	1	5.46±8.37E-08	-2.54±7.72E-08	-2.76±7.74E-08	-8.11±7.99E-08	--
Sr-90	μCi/mL	1	1.59±1.52E-09	0.20±1.56E-09	0.28±1.38E-09	0.58±1.25E-09	--
Cs-137	μCi/mL	1	2.66±5.70E-09	0.32±1.28E-08	-0.10±6.66E-09	-3.34±6.39E-09	--
Conductivity	μmhos/cm@25°C	1	406	404	206	270	--
pH	SU	1	7.89	7.55	7.97	8.14	6.5–8.5

Analyte	Units	N	Annual Concentrations at Potable Wells			Reference Values	
			WFWEL04	WFWEL05	WFWEL07	Background ^a WFWEL06	Standard ^{b,c}
Gross Alpha	μCi/mL	1	7.76±4.25E-09	1.09±8.96E-10	-3.64±8.05E-10	-2.26±7.02E-10	1.5E-08 ^d
Gross Beta	μCi/mL	1	2.46±3.33E-09	2.35±0.97E-09	1.22±0.88E-09	1.77±8.44E-10	1E-06 ^e
Tritium	μCi/mL	1	6.65±8.36E-08	2.87±5.53E-08	-4.22±8.13E-08	-8.11±7.99E-08	--
Sr-90	μCi/mL	1	1.30±1.39E-09	2.77±1.31E-09	-1.69±8.35E-10	0.58±1.25E-09	--
Cs-137	μCi/mL	1	-1.97±6.23E-09	0.99±1.76E-08	4.39±7.60E-09	-3.34±6.39E-09	--
Conductivity	μmhos/cm@25°C	1	1,580	262	288	270	--
pH	SU	1	8.12	6.56	7.55	8.14	6.5–8.5

Analyte	Units	N	Annual Concentrations at Potable Wells			Reference Values	
			WFWEL08	WFWEL09	WFWEL10	Background ^a WFWEL06	Standard ^{b,c}
Gross Alpha	μCi/mL	1	1.92±1.38E-09	2.10±1.70E-09	-3.14±1.95E-09	-2.26±7.02E-10	1.5E-08 ^d
Gross Beta	μCi/mL	1	2.23±1.50E-09	2.45±1.51E-09	2.42±1.54E-09	1.77±8.44E-10	1E-06 ^e
Tritium	μCi/mL	1	-1.20±0.74E-07	-2.96±7.70E-08	4.35±8.11E-08	-8.11±7.99E-08	--
Sr-90	μCi/mL	1	1.15±1.53E-09	3.06±1.60E-09	1.30±1.39E-09	0.58±1.25E-09	--
Cs-137	μCi/mL	1	-3.82±4.19E-09	1.23±7.04E-09	-0.79±1.00E-08	-3.34±6.39E-09	--
Conductivity	μmhos/cm@25°C	1	429	501	724	270	--
pH	SU	1	7.05	8.14	7.38	8.14	6.5–8.5

N - Number of samples

-- No guideline or standard available for these analytes

^a Background location

^b New York State Water Quality Standard for Class "GA" for fresh groundwater

^c NYSDOH raw water supply standards (10 NYCRR Part 170.4)

^d Alpha standard excludes radon and uranium, however, the WVDP results include these isotopes.

^e Beta standard excludes strontium and alpha emitters. The WVDP results include strontium and other beta emitters.

Table C-5B
2004 Indicator Results in Main Plant Potable Water (WNDNKMP)

Analyte	Units	N	Annual Concentration			Standard ^a
			Minimum	Average	Maximum	
Gross Alpha	µCi/mL	4	<3.50E-10	1.06±5.83E-10	<8.74E-10	1.5E-08
Gross Beta	µCi/mL	4	9.51E-10	1.64±0.75E-09	2.55E-09	5E-08
Tritium	µCi/mL	4	<8.12E-08	3.25±8.15E-08	<8.22E-08	2E-05
Conductivity	µmhos/cm@25°C	4	153	184	207	--
pH	SU	4	7.65	7.99	8.5	--

2004 Indicator Results in Environmental Laboratory Potable Water (WNDNKEL)

Analyte	Units	N	Annual Concentration			Standard ^a
			Minimum	Average	Maximum	
Gross Alpha	µCi/mL	4	<4.05E-10	-1.95±5.29E-10	<6.94E-10	1.5E-08
Gross Beta	µCi/mL	4	1.07E-09	1.29±0.74E-09	1.57E-09	5E-08
Tritium	µCi/mL	4	<5.43E-08	3.09±7.57E-08	1.01E-07	2E-05
Conductivity	µmhos/cm@25°C	4	161	200	259	--
Haloacetic Acids-Five (5)	mg/L	3	<0.013	<0.021	<0.033	0.06
pH	SU	4	7.87	7.99	8.12	--
Total Trihalomethanes	mg/L	3	<0.011	<0.026	<0.053	0.08

2004 Indicator Results in Maintenance Shop Potable Water (WNDNKMS)

Analyte	Units	N	Annual Concentration			Standard ^a
			Minimum	Average	Maximum	
Gross Alpha	µCi/mL	4	<3.96E-10	-1.13±5.41E-10	7.27E-10	1.5E-08
Gross Beta	µCi/mL	4	1.44E-09	1.82±0.76E-09	2.30E-09	5E-08
Tritium	µCi/mL	4	<5.55E-08	4.01±8.43E-08	1.08E-07	2E-05
Conductivity	µmhos/cm@25°C	4	198	209	225	--
pH	SU	4	7.87	8.05	8.19	--

N - Number of samples

-- No guideline or standard available for these analytes

^aNew York State Department of Health MCLs for drinking water used as a comparative reference

Table C-5C
2004 Water Quality Results in Utility Room Potable Water (WNDNKUR)

Analyte	Units	N	WNDNKUR Concentrations			Standard or Guideline ^a
			Minimum	Average	Maximum	
Gross Alpha	µCi/mL	12	<3.16E-10	-0.72±5.30E-10	<8.96E-10	1.5E-08
Gross Beta	µCi/mL	12	1.09E-09	1.49±0.74E-09	1.96E-09	5E-08
Tritium	µCi/mL	12	<5.88E-08	3.27±7.85E-08	1.23E-07	2E-05
Antimony, Total	mg/L	1	NA	NA	<0.001	0.006
Arsenic, Total	mg/L	1	NA	NA	<0.025	0.05
Barium, Total	mg/L	1	NA	NA	<0.20	2.00
Beryllium, Total	mg/L	1	NA	NA	<0.0003	0.004
Cadmium, Total	mg/L	1	NA	NA	<0.002	0.005
Chromium, Total	mg/L	1	NA	NA	<0.01	0.10
Conductivity	µmhos/cm@25°C	12	144	194	263	--
Cyanide, Total	mg/L	1	NA	NA	<0.01	0.2
Fluoride	mg/L	1	NA	NA	<0.20	2.2
Free Residual Chlorine	mg/L	1,097	0.43	NA	2.95	0.2–4.0
Mercury, Total	mg/L	1	NA	NA	<0.0004	0.002
Nickel, Total	mg/L	1	NA	NA	<0.005	--
pH	SU	12	7.89	8.04	8.32	--
Selenium, Total	mg/L	1	NA	NA	<0.002	0.05
Thallium, Total	mg/L	1	NA	NA	<0.001	0.002
Turbidity	NTU	2,194	<0.1	NA	1.6	1.0 ^b

N - Number of samples

NA - Not available, constituents sampled annually

-- No guideline or standard available for these analytes

^a New York State Department of Health MCLs for drinking water or EPA MCLGs, whichever is more stringent

^b A treatment standard of 0.3 NTU applies to the 95th percentile on a monthly basis.

Table C-5D
2004 Water Quality Results in Utility Room Raw (Untreated) Water
(WNURRAW)

Analyte	Units	N	WNURRAW Concentrations		
			Minimum	Average	Maximum
Iron, Total	mg/L	52	0.13	1.28	30.4
Solids, Total Dissolved	mg/L	24	61	110	148

N - Number of samples

Table C-5E
2004 Biological and Chlorine Results From Various Site Tap Water Locations
(Analyzed by Cattaraugus County Department of Health)

Analyte	Units	N	Various Site Tap Water Locations Results	Standard ^a
E. coli	NA	12	Negative	one positive sample
Free Residual Chlorine	mg/L	11	Range: 0.08–1.78	4.0 (max)
Total Coliform	NA	12	Negative	two or more positive samples

N - Number of samples

NA - Not applicable

^a New York State Department of Health MCLs for drinking water or EPA MCLGs, whichever is more stringent

Table C-5F
2004 Tap Water Nitrate Results From WVDP Restroom Sink
(Analyzed by Cattaraugus County Department of Health)

Analyte	Units	N	Date Collected	Annual Concentration	Standard ^a
Nitrate-N	mg/L	1	3/17/04	0.700	10

N - Number of samples

^a New York State Department of Health MCLs for drinking water or EPA MCLGs, whichever is more stringent

Appendix D
Summary of Air Monitoring Data

This page intentionally left blank

Table D-1
2004 Effluent Airborne Radioactivity at Main Stack (ANSTACK)

Isotope ^a	N	Total Activity Released ^b (Ci)	Average Concentration (μ Ci/mL)	Maximum Concentration (μ Ci/mL)	DCG ^c (μ Ci/mL)	Average % DCG
Gross Alpha	53	3.93 \pm 0.17E-06	5.19 \pm 0.22E-15	2.48E-14	--	--
Gross Beta	53	1.30 \pm 0.01E-04	1.71 \pm 0.01E-13	9.31E-13	--	--
H-3	53	5.57 \pm 0.11E-03	7.34 \pm 0.15E-12	3.24E-11	1E-07	0.01
Co-60	4	6.00 \pm 6.58E-08	7.91 \pm 8.68E-17	2.82E-16	8E-11	<0.01
Sr-90	4	3.15 \pm 0.03E-05	4.15 \pm 0.04E-14	7.56E-14	9E-12	0.46
I-129	4	2.78 \pm 0.22E-05	3.67 \pm 0.29E-14	5.64E-14	7E-11	0.05
Cs-137	4	5.47 \pm 0.16E-05	7.21 \pm 0.21E-14	1.23E-13	4E-10	0.02
Eu-154	4	0.57 \pm 1.69E-07	0.75 \pm 2.23E-16	<4.71E-16	5E-11	<0.01
U-232 ^d	4	2.31 \pm 0.68E-08	3.05 \pm 0.90E-17	4.90E-17	2E-14	0.15
U-233/234 ^d	4	4.25 \pm 0.92E-08	5.60 \pm 1.21E-17	9.65E-17	9E-14	0.06
U-235/236 ^d	4	1.11 \pm 0.59E-08	1.47 \pm 0.77E-17	1.67E-17	1E-13	0.01
U-238 ^d	4	3.80 \pm 0.80E-08	5.01 \pm 1.06E-17	6.99E-17	1E-13	0.05
Pu-238	4	7.61 \pm 0.36E-07	1.00 \pm 0.05E-15	1.86E-15	3E-14	3.35
Pu-239/240	4	8.03 \pm 0.37E-07	1.06 \pm 0.05E-15	2.01E-15	2E-14	5.30
Am-241	4	2.08 \pm 0.06E-06	2.75 \pm 0.08E-15	5.38E-15	2E-14	13.73
Total % of DCGs						23.19

N - Number of samples

-- DCGs are not specified for gross alpha and beta activity.

^a Half-lives are listed in Table K-1 .

^b Total volume released at 50,000 cfm = 7.58E+14 mL/year

^c Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^d Total Uranium: 9.25 \pm 0.09E-02 g; average = 1.22E \pm 0.01E-10 μ g/mL

Table D-2
2004 Effluent Airborne Radioactivity at Vitrification System HVAC
(ANVITSK)

Isotope	N	Total Activity Released (Ci)	Average Concentration ($\mu\text{Ci/mL}$)	Maximum Concentration ($\mu\text{Ci/mL}$)	DCG ^a ($\mu\text{Ci/mL}$)
Gross Alpha	53	-0.90±2.95E-08	-2.37±7.78E-17	5.80E-16	--
Gross Beta	53	2.88±6.34E-08	0.76±1.67E-16	1.50E-15	--
Co-60	4	0.93±3.13E-08	2.45±8.25E-17	<2.34E-16	8E-11
Sr-90	4	1.70±2.42E-08	4.48±6.38E-17	1.77E-16	9E-12
I-129	4	3.20±0.94E-07	8.44±2.48E-16	1.67E-15	7E-11
Cs-137	4	1.03±2.40E-08	2.72±6.33E-17	<1.61E-16	4E-10
Eu-154	4	1.04±9.09E-08	0.27±2.40E-16	<7.63E-16	5E-11
U-232 ^b	4	2.09±2.74E-09	5.51±7.23E-18	1.77E-17	2E-14
U-233/234 ^b	4	1.60±0.38E-08	4.22±1.00E-17	5.99E-17	9E-14
U-235/236 ^b	4	6.04±2.39E-09	1.59±0.63E-17	3.20E-17	1E-13
U-238 ^b	4	1.41±0.35E-08	2.73±9.23E-17	4.15E-17	1E-13
Pu-238	4	-0.01±1.62E-09	-0.03±4.27E-18	<1.29E-17	3E-14
Pu-239/240	4	0.57±1.61E-09	1.50±4.25E-18	<8.65E-18	2E-14
Am-241	4	4.91±3.05E-09	1.29±0.80E-17	2.95E-17	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and beta activity.

^a Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^b Total Uranium: 4.16±0.04E-02 g; average = 1.10±0.01E-10 $\mu\text{g/mL}$

Table D-3
2004 Effluent Airborne Radioactivity at 01-14 Building (ANCSSTK)

Isotope	N	Total Activity Released (Ci)	Average Concentration ($\mu\text{Ci}/\text{mL}$)	Maximum Concentration ($\mu\text{Ci}/\text{mL}$)	DCG ^a ($\mu\text{Ci}/\text{mL}$)
Gross Alpha	53	0.79±1.22E-08	5.37±8.29E-17	1.13E-15	--
Gross Beta	53	3.44±2.57E-08	2.34±1.75E-16	1.78E-15	--
Co-60	4	0.05±1.19E-08	0.34±8.09E-17	<1.85E-16	8E-11
Sr-90	4	2.22±9.02E-09	1.51±6.13E-17	<1.38E-16	9E-12
I-129	4	3.46±2.47E-08	2.35±1.68E-16	6.66E-16	7E-11
Cs-137	4	1.29±1.16E-08	8.77±7.88E-17	1.61E-16	4E-10
Eu-154	4	4.59±3.53E-08	3.12±2.40E-16	<5.44E-16	5E-11
U-232 ^b	4	0.31±1.10E-09	2.11±7.48E-18	<1.90E-17	2E-14
U-233/234 ^b	4	7.73±1.75E-09	5.25±1.19E-17	6.87E-17	9E-14
U-235/236 ^b	4	1.42±0.93E-09	9.65±6.32E-18	9.17E-18	1E-13
U-238 ^b	4	7.95±1.69E-09	5.40±1.15E-17	6.72E-17	1E-13
Pu-238	4	-2.93±7.42E-10	-1.99±5.04E-18	<1.55E-17	3E-14
Pu-239/240	4	-0.47±8.26E-10	-0.32±5.61E-18	<1.36E-17	2E-14
Am-241	4	1.26±1.01E-09	8.56±6.86E-18	9.99E-18	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and beta activity.

^a Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^b Total Uranium: 3.60±0.03E-02 g; average = 2.45±0.02E-10 $\mu\text{g}/\text{mL}$

Table D-4
2004 Airborne Radioactivity at Contact Size-Reduction Facility (ANCSRFK)

VENTILATION OFF DURING CY 2004

Table D-5
2004 Effluent Airborne Radioactivity at Supernatant Treatment System
(ANSTSTK)

Isotope	N	Total Activity Released (Ci)	Average Concentration ($\mu\text{Ci/mL}$)	Maximum Concentration ($\mu\text{Ci/mL}$)	DCG ^a ($\mu\text{Ci/mL}$)
Gross Alpha	53	0.09±6.41E-09	0.13±9.39E-17	8.45E-16	--
Gross Beta	53	1.23±1.37E-08	1.80±2.01E-16	1.38E-15	--
H-3	53	3.15±0.48E-05	4.61±0.70E-13	1.94E-12	1E-07
Co-60	4	1.14±0.70E-08	1.67±1.03E-16	3.19E-16	8E-11
Sr-90	4	2.84±5.01E-09	4.16±7.34E-17	<1.44E-16	9E-12
I-129	4	1.38±0.09E-05	2.02±0.13E-13	3.25E-13	7E-11
Cs-137	4	9.40±6.11E-09	1.38±0.90E-16	1.69E-16	4E-10
Eu-154	4	-0.09±1.47E-08	-0.13±2.15E-16	<4.61E-16	5E-11
U-232 ^b	4	5.82±5.60E-10	8.53±8.20E-18	1.84E-17	2E-14
U-233/234 ^b	4	4.25±0.93E-09	6.23±1.36E-17	6.23E-17	9E-14
U-235/236 ^b	4	1.13±0.48E-09	1.66±0.70E-17	2.57E-17	1E-13
U-238 ^b	4	3.92±0.85E-09	4.28±1.25E-17	6.19E-17	1E-13
Pu-238	4	1.08±3.96E-10	1.58±5.80E-18	<1.45E-17	3E-14
Pu-239/240	4	1.82±3.97E-10	2.67±5.82E-18	<1.42E-17	2E-14
Am-241	4	1.16±0.58E-09	1.70±0.85E-17	1.85E-17	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and beta activity.

^a Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^b Total Uranium: 9.08±0.09E-03 g; average = 1.33±0.01E-10 $\mu\text{g/mL}$

Table D-6
2004 Effluent Airborne Radioactivity at Container Sorting and Packaging Facility (ANCSPFK)

Isotope	N	Total Activity Released (Ci)	Average Concentration ($\mu\text{Ci}/\text{mL}$)	Maximum Concentration ($\mu\text{Ci}/\text{mL}$)	DCG ^a ($\mu\text{Ci}/\text{mL}$)
Gross Alpha	53	3.90±1.60E-09	2.20±0.90E-16	1.21E-15	--
Gross Beta	53	4.16±3.09E-09	2.35±1.74E-16	3.63E-15	--
Co-60	4	1.60±1.38E-09	9.02±7.78E-17	<1.86E-16	8E-11
Sr-90	4	0.43±1.09E-09	2.42±6.15E-17	1.40E-16	9E-12
I-129	4	1.78±0.14E-07	1.00±0.08E-14	1.54E-14	7E-11
Cs-137	4	-0.29±1.23E-09	-1.63±6.93E-17	<1.69E-16	4E-10
Eu-154	4	0.83±3.49E-09	0.47±1.97E-16	<4.65E-16	5E-11
U-232^b	4	1.38±1.31E-10	7.78±7.39E-18	2.08E-17	2E-14
U-233/234^b	4	1.10±0.21E-09	6.20±1.18E-17	8.25E-17	9E-14
U-235/236^b	4	1.78±1.18E-10	1.00±0.66E-17	3.55E-17	1E-13
U-238^b	4	1.22±0.21E-09	6.88±1.18E-17	9.28E-17	1E-13
Pu-238	4	0.26±1.33E-10	1.47±7.50E-18	<2.18E-17	3E-14
Pu-239/240	4	0.45±9.20E-11	0.25±5.19E-18	<1.18E-17	2E-14
Am-241	4	0.89±1.19E-10	5.02±6.71E-18	1.89E-17	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^b Total Uranium: 3.06±0.03E-03 g; average = 1.73±0.02E-10 $\mu\text{g}/\text{mL}$

Table D-7
**2004 Effluent Airborne Radioactivity at Outdoor Ventilation Enclosures/
 Portable Ventilation Units (OVEs/PVUs)**

Isotope	N	Total Activity Released (Ci)	Average Concentration ($\mu\text{Ci/mL}$)	Maximum Concentration ($\mu\text{Ci/mL}$)	DCG ^a ($\mu\text{Ci/mL}$)
Gross Alpha	82	3.70 \pm 0.52E-08	6.55 \pm 0.92E-16	1.36E-14	--
Gross Beta	82	5.06 \pm 0.89E-08	8.96 \pm 1.58E-16	1.64E-14	--
Co-60	6	4.10 \pm 4.61E-09	7.26 \pm 8.17E-17	3.71E-16	8E-11
Sr-90	6	3.89 \pm 3.88E-09	6.89 \pm 6.87E-17	2.08E-16	9E-12
Cs-137	6	2.35 \pm 0.63E-08	4.16 \pm 1.11E-16	9.81E-16	4E-10
Eu-154	6	0.48 \pm 1.53E-08	0.86 \pm 2.72E-16	<4.95E-15	5E-11
U-232 ^b	6	2.31 \pm 5.56E-10	4.09 \pm 9.85E-18	<1.63E-15	2E-14
U-233/234 ^b	6	4.40 \pm 0.69E-09	7.79 \pm 1.22E-17	1.63E-16	9E-14
U-235/236 ^b	6	1.28 \pm 0.42E-09	2.26 \pm 0.74E-17	7.48E-17	1E-13
U-238 ^b	6	3.59 \pm 0.61E-09	6.36 \pm 1.07E-17	1.37E-16	1E-13
Pu-238	6	8.36 \pm 1.00E-09	1.48 \pm 0.18E-16	4.04E-16	3E-14
Pu-239/240	6	9.85 \pm 1.05E-09	1.74 \pm 0.19E-16	4.56E-16	2E-14
Am-241	6	2.91 \pm 0.14E-08	5.16 \pm 0.25E-16	1.23E-15	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^b Total Uranium: 1.00 \pm 0.01E-02 g; average = 1.78 \pm 0.01E-10 $\mu\text{g/mL}$

Table D-8
2004 Effluent Airborne Radioactivity at Remote-Handled Waste Facility Stack
(ANRHWFK)

Isotope	N	Total Activity Released (Ci)	Average Concentration ($\mu\text{Ci/mL}$)	Maximum Concentration ($\mu\text{Ci/mL}$)	DCG ^a ($\mu\text{Ci/mL}$)
Gross Alpha	34	-0.23±1.11E-08	-0.35±1.66E-16	7.90E-16	--
Gross Beta	34	1.99±2.43E-08	2.99±3.66E-16	1.55E-15	--
Co-60	3	0.20±1.19E-08	0.31±1.78E-16	<4.48E-16	8E-11
Sr-90	3	-3.36±9.40E-09	-0.51±1.41E-16	<3.08E-16	9E-12
I-129	3	4.80±2.64E-08	7.22±3.97E-16	9.30E-16	7E-11
Cs-137	3	0.18±1.08E-08	0.27±1.63E-16	<2.87E-16	4E-10
Eu-154	3	0.49±2.36E-08	0.73±3.55E-16	8.56E-16	5E-11
U-232 ^b	3	0.55±1.23E-09	0.83±1.84E-17	<4.87E-17	2E-14
U-233/234 ^b	3	5.25±1.55E-09	7.90±2.34E-17	5.45E-17	9E-14
U-235/236 ^b	3	2.22±1.22E-09	3.34±1.52E-17	3.20E-17	1E-13
U-238 ^b	3	6.55±1.63E-09	9.85±2.46E-17	7.72E-17	1E-13
Pu-238	3	1.85±6.44E-10	2.79±9.69E-18	2.45E-17	3E-14
Pu-239/240	3	4.32±7.73E-10	0.65±1.16E-17	<2.53E-17	2E-14
Am-241	3	1.81±1.24E-09	2.72±1.87E-17	1.81E-17	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Derived concentration guides (DCGs) are listed for reference only. They are applicable to average concentrations at the site boundary but not to stack concentrations, as might be inferred from their inclusion in this table.

^b Total Uranium: 1.78±0.02E-02 g; average = 2.68±0.03E-10 $\mu\text{g/mL}$

Table D-9
2004 Ambient Airborne Radioactivity at Lag Storage (ANLAGAM)

Isotope	N	ANLAGAM μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	7.15±7.68E-16	1.45E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.75±0.24E-14	3.26E-14	53	8.58E-15–3.06E-14	--
K-40	4	2.93±2.84E-15	5.57E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	0.59±1.86E-16	2.21E-16	4	<2.09E-16–3.27E-16	8E-11
Sr-90	4	0.43±1.40E-16	<1.85E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	-0.22±1.42E-16	<1.96E-16	4	<1.92E-16–2.56E-16	4E-10
Eu-154	4	0.35±4.97E-16	<7.04E-16	4	<5.37E-16–7.92E-16	5E-11
U-232 ^c	4	-0.05±1.39E-17	<1.81E-17	4	<8.81E-18–4.96E-17	2E-14
U-233/234 ^c	4	4.62±2.15E-17	5.83E-17	4	5.51E-17–1.27E-16	9E-14
U-235/236 ^c	4	1.35±1.35E-17	3.88E-17	4	1.25E-17–2.65E-17	1E-13
U-238 ^c	4	6.72±2.40E-17	1.40E-16	4	4.68E-17–6.64E-17	1E-13
Pu-238	4	1.01±9.05E-18	<1.50E-17	4	<8.43E-18–2.25E-17	3E-14
Pu-239/240	4	3.38±1.71E-17	1.31E-16	4	<1.31E-17–1.53E-17	2E-14
Am-241	4	1.75±1.71E-17	3.24E-17	4	<1.70E-17–2.30E-17	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

^c Total Uranium: ANLAGAM average = 1.79±0.07E-10 μg/mL; AFGRVAL average = 1.66±0.03E-10 μg/mL

Table D-10
2004 Ambient Airborne Radioactivity at the NDA (ANNDAAAM)

Isotope	N	ANNDAAAM μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	8.60±8.13E-16	2.03E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.71±0.24E-14	2.90E-14	53	8.58E-15–3.06E-14	--
K-40	4	2.60±2.07E-15	3.38E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	0.43±1.63E-16	<1.86E-16	4	<2.09E-16–3.27E-16	8E-11
Sr-90	4	0.45±1.16E-16	<1.50E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	0.41±2.08E-16	<3.52E-16	4	<1.92E-16–2.56E-16	4E-10
Eu-154	4	0.95±4.16E-16	<4.29E-16	4	<5.37E-16–7.92E-16	5E-11
U-232 ^c	4	1.10±1.88E-17	<2.82E-17	4	<8.81E-18–4.96E-17	2E-14
U-233/234 ^c	4	5.28±2.40E-17	6.04E-17	4	5.51E-17–1.27E-16	9E-14
U-235/236 ^c	4	1.25±1.47E-17	3.21E-17	4	1.25E-17–2.65E-17	1E-13
U-238 ^c	4	3.32±1.87E-17	4.50E-17	4	4.68E-17–6.64E-17	1E-13
Pu-238	4	0.44±1.27E-17	<1.84E-17	4	<8.43E-18–2.25E-17	3E-14
Pu-239/240	4	0.23±1.08E-17	<1.33E-17	4	<1.31E-17–1.53E-17	2E-14
Am-241	4	0.46±1.21E-17	1.57E-17	4	<1.70E-17–2.30E-17	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

^c Total Uranium: ANNDAAAM average = 9.81±0.17E-11 μg/mL; AFGRVAL average = 1.66±0.03E-10 μg/mL

Table D-11
2004 Ambient Airborne Radioactivity at SDA Trench 9 (ANSDAT9)

Isotope	N	ANSDAT9 μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	52	0.60±1.09E-15	2.44E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	52	1.63±0.32E-14	3.69E-14	53	8.58E-15–3.06E-14	--
Tritium	52	9.40±6.10E-13	5.51E-12	53	5.76E-14–1.05E-12	1E-07
K-40	4	3.51±4.09E-15	4.43E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	0.23±2.41E-16	<3.32E-16	4	<2.09E-16–3.27E-16	8E-11
I-129	4	0.26±2.52E-16	<3.23E-16	4	3.02E-16–3.89E-16	7E-11
Cs-137	4	0.15±2.35E-16	<3.47E-16	4	<1.92E-16–2.56E-16	4E-10

N - Number of samples

Note: Samples taken on July 6, 2004 were rejected for gross alpha, gross beta, and tritium.

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-12
2004 Ambient Airborne Radioactivity at Rock Springs Road (AFRSPRD)

Isotope	N	AFRSPRD μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	0.66±1.04E-15	2.03E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.66±0.31E-14	3.46E-14	53	8.58E-15–3.06E-14	--
Tritium	53	-0.21±6.66E-13	1.17E-12	53	5.76E-14–1.05E-12	1E-07
K-40	4	2.17±3.53E-15	<4.98E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	0.05±2.45E-16	<3.61E-16	4	<2.09E-16–3.27E-16	8E-11
Sr-90	4	-0.39±1.96E-16	<2.88E-16	4	<1.41E-16–2.05E-16	9E-12
I-129	4	-0.11±3.92E-16	<4.53E-16	4	3.02E-16–3.89E-16	7E-11
Cs-137	4	-0.01±1.76E-16	<1.95E-16	4	<1.92E-16–2.56E-16	4E-10
Eu-154	4	0.13±7.40E-16	<1.10E-15	4	<5.37E-16–7.92E-16	5E-11
U-232 ^c	4	-0.36±2.18E-17	<2.53E-17	4	<8.81E-18–4.96E-17	2E-14
U-233/234 ^c	4	8.74±3.82E-17	1.22E-16	4	5.51E-17–1.27E-16	9E-14
U-235/236 ^c	4	2.65±2.43E-17	5.02E-17	4	1.25E-17–2.65E-17	1E-13
U-238 ^c	4	6.42±3.47E-17	9.12E-17	4	4.68E-17–6.64E-17	1E-13
Pu-238	4	-0.21±1.71E-17	<2.28E-17	4	<8.43E-18–2.25E-17	3E-14
Pu-239/240	4	0.70±1.92E-17	1.89E-17	4	<1.31E-17–1.53E-17	2E-14
Am-241	4	1.41±2.15E-17	3.42E-17	4	<1.70E-17–2.30E-17	2E-14

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

^c Total Uranium: AFRSPRD average = 1.48±0.03E-10 μg/mL; AFGRVAL average = 1.66±0.03E-10 μg/mL

Table D-13
2004 Ambient Airborne Radioactivity at Dutch Hill Road (AFBOEHN)

Isotope	N	AFBOEHN μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	0.82±1.09E-15	2.97E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.79±0.32E-14	3.05E-14	53	8.58E-15–3.06E-14	--
K-40	4	1.76±3.81E-15	3.91E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	1.14±2.89E-16	3.49E-16	4	<2.09E-16–3.27E-16	8E-11
Sr-90	4	0.66±1.90E-16	<2.55E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	-0.47±2.28E-16	<3.38E-16	4	<1.92E-16–2.56E-16	4E-10

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-14
2004 Ambient Airborne Radioactivity at Fox Valley Road (AFFXVRD)

Isotope	N	AFFXVRD μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	0.78±1.10E-15	2.08E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.65±0.31E-14	3.05E-14	53	8.58E-15–3.06E-14	--
K-40	4	2.89±3.82E-15	2.69E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	-0.75±2.75E-16	<4.26E-16	4	<2.09E-16–3.27E-16	8E-11
Sr-90	4	0.91±1.98E-16	2.13E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	1.15±2.26E-16	3.74E-16	4	<1.92E-16–2.56E-16	4E-10

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-15
2004 Ambient Airborne Radioactivity at the Bulk Storage Warehouse
(AFBLKST)

Isotope	N	AFBLKST μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	0.70±1.06E-15	2.12E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.63±0.31E-14	2.82E-14	53	8.58E-15–3.06E-14	--
K-40	4	2.09±5.46E-15	<7.47E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	-0.16±2.20E-16	<3.21E-16	4	<2.09E-16–3.27E-16	8E-11
Sr-90	4	0.47±1.71E-16	<2.49E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	1.18±2.12E-16	1.57E-16	4	<1.92E-16–2.56E-16	4E-10

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-16
2004 Ambient Airborne Radioactivity at Route 240 (AFRT240)

Isotope	N	AFRT240 μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	0.59±1.05E-15	1.93E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.70±0.32E-14	2.68E-14	53	8.58E-15–3.06E-14	--
K-40	4	3.20±3.12E-15	5.97E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	0.13±2.14E-16	1.48E-16	4	<2.09E-16–3.27E-16	8E-11
Sr-90	4	0.33±1.73E-16	2.50E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	0.33±2.00E-16	<3.02E-16	4	<1.92E-16–2.56E-16	4E-10

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-17
2004 Ambient Airborne Radioactivity at Thomas Corners Road (AFTCORD)

Isotope	N	AFTCORD μCi/mL		N	AFGRVAL ^a	DCG ^b
		Average	Maximum		μCi/mL Background Range	
Gross Alpha	53	0.85±1.11E-15	2.68E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.70±0.31E-14	3.13E-14	53	8.58E-15–3.06E-14	--
K-40	4	1.73±3.51E-15	4.84E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	-0.35±2.21E-16	<2.65E-16	4	<2.09E-16–<3.27E-16	8E-11
Sr-90	4	0.13±1.82E-16	<2.32E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	1.52±1.84E-16	<2.37E-16	4	<1.92E-16–<2.56E-16	4E-10

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-18
2004 Ambient Airborne Radioactivity at West Valley (AFWEVAL)

Isotope	N	AFWEVAL μCi/mL		N	AFGRVAL ^a	DCG ^b
		Average	Maximum		μCi/mL Background Range	
Gross Alpha	53	0.83±1.11E-15	3.04E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.76±0.32E-14	3.14E-14	53	8.58E-15–3.06E-14	--
K-40	4	4.43±4.98E-15	6.91E-15	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	0.02±2.54E-16	<3.04E-16	4	<2.09E-16–<3.27E-16	8E-11
Sr-90	4	0.44±1.68E-16	<2.06E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	-0.55±2.43E-16	<3.06E-16	4	<1.92E-16–<2.56E-16	4E-10

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-19
2004 Ambient Airborne Radioactivity at Springville (AFSPRVL)

Isotope	N	AFSPRVL μCi/mL		N	AFGRVAL ^a μCi/mL	DCG ^b
		Average	Maximum		Background Range	
Gross Alpha	53	0.74±1.07E-15	3.25E-15	53	<5.59E-16–2.16E-15	--
Gross Beta	53	1.70±0.31E-14	3.13E-14	53	8.58E-15–3.06E-14	--
K-40	4	4.57±4.48E-15	1.28E-14	4	<3.71E-15–6.07E-15	9E-10
Co-60	4	0.92±2.45E-16	<2.84E-16	4	<2.09E-16–<3.27E-16	8E-11
Sr-90	4	1.03±1.82E-16	1.83E-16	4	<1.41E-16–2.05E-16	9E-12
Cs-137	4	0.54±1.96E-16	1.92E-16	4	<1.92E-16–<2.56E-16	4E-10

N - Number of samples

-- DCGs are not specified for gross alpha and gross beta activity.

^a Background air sampling location

^b Derived concentration guides (DCGs) are applicable to average concentrations at the site boundary.

Table D-20
2004 Radioactivity in Fallout: Dutch Hill (AFDHFOP)

Analyte	Units	N	Minimum	Average	Maximum
Gross Alpha	nCi/m ²	12	1.13E-02	2.80±1.18E-02	6.34E-02
Gross Beta	nCi/m ²	12	1.69E-01	4.84±0.41E-01	1.17E+00
H-3	µCi/mL	12	<5.46E-08	-1.82±7.80E-08	9.50E-08
K-40	nCi/m ²	12	<8.59E-01	0.18±6.79E+00	2.82E+00
Cs-137	nCi/m ²	12	<8.55E-02	2.57±5.09E-01	1.46E+00

N - Number of samples

Table D-21
2004 Radioactivity in Fallout: Rain Gauge (ANRGFOP)

Analyte	Units	N	Minimum	Average	Maximum
Gross Alpha	nCi/m ²	12	1.44E-02	4.07±1.62E-02	1.02E-01
Gross Beta	nCi/m ²	12	2.14E-01	5.13±0.51E-01	1.05E+00
H-3	µCi/mL	12	<7.66E-08	-0.48±8.09E-08	1.03E-07
K-40	nCi/m ²	12	<2.57E+00	0.59±9.80E+00	4.83E+00
Cs-137	nCi/m ²	12	<1.57E-01	0.45±7.50E-01	1.73E+00

N - Number of samples

Table D-22
2004 Radioactivity in Fallout: Route 240 (AF24FOP)

Analyte	Units	N	Minimum	Average	Maximum
Gross Alpha	nCi/m ²	12	1.35E-02	3.26±1.41E-02	1.01E-01
Gross Beta	nCi/m ²	12	2.21E-01	5.26±0.47E-01	1.00E+00
H-3	µCi/mL	12	<7.61E-08	0.20±8.14E-08	1.32E-07
K-40	nCi/m ²	12	<9.84E-01	-3.43±7.68E+00	3.40E+00
Cs-137	nCi/m ²	12	<8.07E-02	0.11±5.87E-01	<1.38E+00

N - Number of samples

Table D-23
2004 Radioactivity in Fallout: Thomas Corners (AFTCFOP)

Analyte	Units	N	Minimum	Average	Maximum
Gross Alpha	nCi/m ²	12	1.93E-02	3.46±1.50E-02	5.65E-02
Gross Beta	nCi/m ²	12	2.86E-01	6.19±0.54E-01	1.13E+00
H-3	µCi/mL	12	<7.67E-08	0.09±8.12E-08	8.54E-08
K-40	nCi/m ²	12	<1.32E+00	-2.97±8.66E+00	5.69E+00
Cs-137	nCi/m ²	12	<1.05E-01	0.15±5.74E-01	<1.17E+00

N - Number of samples

Table D-24
2004 Radioactivity in Fallout: Fox Valley Road (AFFXFOP)

Analyte	Units	N	Minimum	Average	Maximum
Gross Alpha	nCi/m ²	12	1.65E-02	4.78±1.71E-02	1.06E-01
Gross Beta	nCi/m ²	12	2.52E-01	5.59±0.52E-01	1.13E+00
Tritium	µCi/mL	12	7.04E-08	0.80±8.02E-08	7.04E-08
K-40	nCi/m ²	12	<1.41E+00	0.58±8.47E+00	1.00E+01
Cs-137	nCi/m ²	12	<1.21E-01	0.55±6.05E-01	1.25E-01

N - Number of samples

Appendix E
Summary of Groundwater Monitoring Data

Groundwater Sampling Methodology

Groundwater samples are collected from monitoring wells using either dedicated Teflon® well bailers or bladder pumps. Bailers are used in low-yield wells; bladder pumps are used in wells with good water-yielding characteristics. This sampling equipment is dedicated to an individual well to reduce the likelihood of sample contamination from external materials or cross contamination.

To ensure that only representative groundwater is sampled, three well volumes are removed (purged) from the well before the actual samples are collected. In low-yield wells, pumping or bailing to dryness provides sufficient purging. Conductivity and pH are measured before and after sampling to confirm the geochemical stability of the groundwater during sampling.

The bailer, a tube with a check valve at the bottom, is lowered slowly into the well to minimize agitation of the water column. The bailer containing the groundwater is then withdrawn from the well and emptied into a sample container. Bladder pumps use compressed air that is pumped from the surface to gently squeeze a Teflon® bladder encased in a stainless-steel tube near the bottom of the well. Groundwater flowing into the bladder is pumped into a sample container, allowing additional groundwater to enter the bladder with a minimum of agitation and mixing. A check valve ensures that the water flows in only one direction.

Groundwater samples are cooled and preserved, with chemicals if required, to minimize chemical and/or biological changes after sample collection. A strict chain-of-custody protocol is followed for all samples collected by the WVDP.

Key to bolding convention:

Tables E-2 through E-11^{CD} contain a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Results for each analyte constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered nondetectable. Chemical results preceded by “less than” (<) are considered nondetectable. The bolding convention is not applied to data series consisting of less than three values.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

2004 Groundwater Sampling and Analysis Agenda

<i>Analyte Group</i>	<i>Description of Parameters¹</i>
Contamination Indicator Parameters (I)	pH, specific conductance (field measurements)
Radiological Indicator Parameters (RI)	Gross alpha, gross beta, tritium
Volatile Organic Compounds (V)	6 NYCRR Appendix 33 Volatile Organic Compounds (VOCs) (See Table E-12 ⁶⁰ .)
Semivolatile Organic Compounds (SV)	6 NYCRR Appendix 33 Semivolatile Organic Compounds (SVOCs) and tributyl phosphate (TBP) (See Table E-12 ⁶⁰ .)
6 NYCRR Appendix 33 Metals (M)	Antimony, arsenic, barium, beryllium, cadmium, chromium, cobalt, copper, lead, mercury, nickel, selenium, silver, thallium, tin, vanadium, zinc
Special Monitoring Parameters for Early Warning Wells (SM)	Aluminum, iron, manganese
Radioisotopic Analyses: alpha-, beta-, and gamma-emitters (R)	Carbon-14, strontium-90, technetium-99, iodine-129, cesium-137, radium-226, radium-228, uranium-232, uranium-233/234, uranium-235/236, uranium-238, total uranium
Strontium-90 (S)	Strontium-90

2004 Quarterly Monitoring Schedule:

1st Qtr - December 1, 2003 to February 28, 2004

2nd Qtr - March 1, 2004 to May 31, 2004

3rd Qtr - June 1, 2004 to August 31, 2004

4th Qtr - September 1, 2004 to November 30, 2004

¹*Analysis performed for selected active monitoring locations only. See Table E-1⁶⁰ for the analytes assigned to each monitoring location.*

Table E-1
Groundwater Monitoring Network: Super Solid Waste Management Units

Sand and Gravel Wells

Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹	Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹
103*	1, 3	D	I, RI, V	802	8	D	I, RI, V
104	1	C	I, RI, SV, V	803	8	D	I, RI, SV, V
105	1	C	I, RI, V	804*	8	D	I, RI, V
106	1	D	I, RI, V	1302 ²	NA	D	I, RI, M, R, SV, V
111*	1	D	I, RI, M, S, SV, V	1304 ²	NA	U	I, RI, M, R, SV, V
116*	1, 8	C, U	I, RI, S, V	8603	8	U	I, RI, SV, V
201	2	U	I, RI, V	8604	1	C	I, RI, V
205	2, 3	D	I, RI	8605*	1, 2	D	I, RI, M, R, SV, V
301*	3	B	I, RI	8607*	6, 4	U, D	I, RI, V
401*	4, 3	B	I, RI, R	8609*	3, 4, 6	D, D, U	I, RI, S, V
403	4	U	I, RI, V	8612*	8	D	I, RI, SV, V
406*	4, 6	D, U	I, RI, R, V	NB-1S ³	NA	B	I, RI
408*	4, 3	D	I, RI, R, V	WP-A ⁴	NA	D	I, RI
501*	5	U	I, RI, S, V	WP-C ⁴	NA	D	I, RI
502*	5	D	I, RI, S, SM, V	WP-H ⁴	NA	D	I, RI
602A	6	D	I, RI, S	SP04 ⁵	NA	D	RI
604	6	D	I, RI	SP06 ⁵	NA	D	RI
605	6	D	I, RI, S	SP11 ⁵	NA	D	RI
706*	7	B	I, RI, M, R, SV, V	SP12 ⁵	NA	D	I, RI, V
801*	8, 6	U, D	I, RI, S, V	GSEEP ⁵	NA	D	I, RI, V

Legend: Gradient Positions
B (background)
C (crossgradient)
D (downgradient)
U (upgradient)

NA - Not applicable

¹ *See p. E-3 for a description of codes and analytes.*

² *Monitor upgradient and downgradient of remote-handled waste facility*

³ *Former background well*

⁴ *Monitor locations north and east of main plant*

⁵ *Monitor groundwater emanating from seeps along the edge of the north plateau*

* *Monitoring for certain parameters is required by the RCRA §3008(h) Order on Consent.*

Table E-1 (continued)
Groundwater Monitoring Network: Super Solid Waste Management Units

Lavery Till Sand Wells

Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹
204*	2, 3	D	I, RI
206	2	C	I, RI
208	2	D	I, RI, V
302	3	U	I, RI
402	4	B	I, RI

Weathered Lavery Till Wells

Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹	Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹
906*	9	D	I, RI	1005*	9, 10	C, U	I, RI
908*	9	B	I, RI	1006*	9, 10	C, D	I, RI
909*	9	D	I, RI, M, R, SV, V	1007	10	D	I, RI
NDATR*	9	D	I, RI, M, R, SV, V	1008C*	9, 10	U	I, RI

Unweathered Lavery Till Wells

Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹	Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹
107	1	D	I, RI, V	409	4	D	I, RI
108	1	D	I, RI, V	704	7	D	I, RI, V
110*	1	D	I, RI, V	910*	9	D	I, RI
405	4	B	I, RI, M, R, SV, V	1301 ²	NA	D	I, RI, M, R, SV, V
407	4	D	I, RI	1303 ²	NA	U	I, RI, M, R, SV, V

Legend: Gradient Positions
B (background)
C (crossgradient)
D (downgradient)
U (upgradient)

NA - Not applicable

¹ See p. E-3 for a description of codes and analytes.

² Monitor upgradient and downgradient of remote-handled waste facility

* Monitoring for certain parameters is required by the RCRA §3008(h) Order on Consent.

Table E-1 (concluded)
Groundwater Monitoring Network: Super Solid Waste Management Units

Kent Recessional Sequence Wells

Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹	Well ID	SSWMU	Gradient Position	Analytical Parameters in 2004 ¹
901*	4	B	I, RI	1008B	10	U	I, RI
902*	9	U	I, RI	8610*	9	D	I, RI
903*	9	D	I, RI	8611*	9	D	I, RI

State-Licensed Disposal Area (SDA) Wells

(Note: The SDA wells are sampled by NYSERDA under an independent monitoring program)

Well ID	Geologic Unit	Gradient Position	Well ID	Geologic Unit	Gradient Position
1101A	W	U	1105A	W	D
1101B	U	U	1105B	U	D
1101C	K	U	1106A	W	U
1102A	W	D	1106B	U	U
1102B	U	D	1107A	W	D
1103A	W	D	1108A	W	U
1103B	U	D	1109A	W	U
1103C	K	D	1109B	U	U
1104A	W	D	1110A	W	D
1104B	U	D	1111A	W	D
1104C	K	D			

Legend:

Gradient Positions

B (background)
C (crossgradient)
D (downgradient)
U (upgradient)

Geologic Unit

K (Kent recessional sequence)
U (unweathered Lavery till)
W (weathered Lavery till)

¹ See p. E-3 for a description of codes and analytes.

Note: Additional monitoring wells used for measurement of water elevations only are illustrated on Figures A-6 and A-7.

* Monitoring for certain parameters is required by the RCRA §3008(h) Order on Consent.

Table E-2
2004 Indicator Results From the Sand and Gravel Unit

Location Code	Hydraulic Position	pH (SU)	Conductivity (µmhos/cm@25°C)	Gross Alpha (µCi/mL)	Gross Beta (µCi/mL)	Tritium (µCi/mL)
301	UP(1)	6.56	898	1.90±1.95E-09	8.04±3.68E-09	0.17±5.64E-08
301	UP(2)	6.43	2,220	0.00±3.97E-09	1.72±0.47E-08	1.11±0.78E-07
301	UP(3)	6.40	975	1.30±2.87E-09	1.02±0.37E-08	5.82±8.13E-08
301	UP(4)	6.58	1,765	-2.61±5.11E-09	9.07±3.84E-09	5.46±5.45E-08
401	UP(1)	6.44	4,003	-0.12±9.23E-09	3.51±7.77E-09	1.17±0.83E-07
401	UP(2)	6.62	4,393	-1.99±7.89E-09	7.20±7.97E-09	4.08±7.79E-08
401	UP(3)	6.58	4,162	8.62±7.95E-09	5.23±7.54E-09	1.32±0.83E-07
401	UP(4)	6.50	2,795	-8.59±7.34E-09	7.34±6.74E-09	8.06±7.74E-08
403	UP(1)	6.79	562	-3.25±9.24E-10	9.45±2.69E-09	9.98±7.99E-08
403	UP(2)	6.82	2,292	-1.87±3.81E-09	8.61±4.93E-09	4.41±7.66E-08
403	UP(3)	6.69	1,228	-0.35±2.10E-09	8.38±2.59E-09	6.72±8.14E-08
403	UP(4)	6.84	1,222	1.21±3.49E-09	8.75±2.71E-09	7.96±7.75E-08
706	UP(1)	6.65	794	-1.76±1.91E-09	8.78±2.33E-09	7.81±8.01E-08
706	UP(2)	6.63	803	0.12±1.34E-09	8.34±2.09E-09	2.32±7.90E-08
706	UP(3)	6.78	672	0.44±2.19E-09	1.17±0.25E-08	6.34±8.07E-08
706	UP(4)	6.53	1,298	-1.70±2.40E-09	1.42±0.24E-08	1.68±0.79E-07
1304	UP(1)	7.45	1,926	-1.60±3.12E-09	3.54±3.47E-09	8.68±8.25E-08
1304	UP(2)	6.91	4,018	-2.15±5.77E-09	1.33±0.78E-08	-5.10±5.80E-08
1304	UP(3)	6.88	3,826	-0.33±1.04E-08	8.71±8.12E-09	3.18±8.14E-08
1304	UP(4)	7.10	1,992	-7.29±6.22E-09	5.23±6.48E-09	3.55±7.93E-08
NB1S	UP(1)	6.43	458	-0.37±1.29E-09	1.18±1.84E-09	7.76±8.24E-08
NB1S	UP(2)	6.48	592	-0.19±1.04E-09	2.31±1.72E-09	-4.63±7.83E-08
NB1S	UP(3)	6.59	719	-0.68±1.36E-09	2.38±1.36E-09	-0.95±8.40E-08
NB1S	UP(4)	6.52	778	0.47±1.88E-09	3.77±1.73E-09	3.32±8.22E-08
201	DOWN(1)	6.47	2,275	0.41±3.81E-09	4.64±0.69E-08	1.34±0.81E-07
201	DOWN(2)	6.37	2,856	0.41±5.19E-09	5.25±0.74E-08	8.64±7.77E-08
201	DOWN(3)	6.36	3,164	3.81±4.45E-09	5.90±0.65E-08	1.03±8.39E-08
201	DOWN(4)	6.45	3,449	-2.10±4.90E-09	5.16±0.51E-08	0.75±7.85E-08
305	DOWN(1)	7.01	2,242	1.46±4.16E-09	1.19±0.49E-08	-3.36±8.53E-08
307	DOWN(1)	6.80	2,217	-0.92±5.40E-09	1.44±0.46E-08	8.42±8.06E-08
1302	DOWN(1)	7.10	1,399	0.83±1.67E-09	2.91±2.31E-09	1.15±0.83E-07
1302	DOWN(2)	6.85	2,035	0.28±3.21E-09	-0.23±3.43E-09	-6.55±8.16E-08
1302	DOWN(3)	7.23	2,044	3.16±6.04E-09	5.62±4.21E-09	1.15±0.82E-07
1302	DOWN(4)	7.69	2,654	1.27±2.90E-09	0.01±2.67E-09	-3.89±7.81E-08
103	DOWN(1)	8.22	2,577	2.98±3.93E-09	4.26±0.63E-08	1.56±8.01E-08
103	DOWN(2)	8.02	7,232	-0.94±7.15E-09	2.57±0.16E-07	9.34±8.05E-08
103	DOWN(3)	7.90	6,035	4.97±8.74E-09	1.92±0.16E-07	-1.18±0.82E-07
103	DOWN(4)	7.99	3,712	6.37±7.49E-09	6.99±1.01E-08	-1.70±7.55E-08

Note: Bolding convention applied to these data. (See p. E-2²⁰)

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-2 (continued)
2004 Indicator Results From the Sand and Gravel Unit

Location Code	Hydraulic Position	pH (SU)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
104	DOWN(1)	6.88	1,717	1.45±2.59E-09	6.54±0.01E-05	3.79±0.88E-07
104	DOWN(2)	6.88	1,616	0.04±1.86E-09	5.57±0.01E-05	2.81±0.81E-07
104	DOWN(3)	6.91	1,883	0.91±3.16E-09	7.16±0.01E-05	2.42±0.75E-07
104	DOWN(4)	6.96	1,870	4.10±3.14E-09	6.45±0.01E-05	2.54±0.80E-07
111	DOWN(1)	6.58	788	2.64±2.37E-09	6.05±0.05E-06	2.77±0.61E-07
111	DOWN(2)	6.33	563	2.67±1.81E-09	2.21±0.03E-06	7.07±7.96E-08
111	DOWN(3)	6.42	626	3.15±2.74E-09	5.03±0.05E-06	2.36±0.86E-07
111	DOWN(4)	6.39	1,323	7.51±3.96E-09	1.18±0.01E-05	1.91±0.79E-07
205	DOWN(1)	7.08	1,628	0.00±3.62E-09	5.52±6.68E-09	5.26±7.95E-08
205	DOWN(2)	6.95	3,372	-4.04±6.49E-09	1.89±0.82E-08	1.22±7.65E-08
205	DOWN(3)	6.95	2,262	2.47±4.20E-09	9.34±6.94E-09	-5.21±8.29E-08
205	DOWN(4)	6.73	3,910	7.99±8.07E-09	8.71±7.80E-09	1.35±0.78E-07
406	DOWN(1)	6.74	1,084	-1.26±2.68E-09	5.46±3.90E-09	1.66±0.58E-07
406	DOWN(2)	6.64	1,746	-1.82±2.93E-09	6.96±3.99E-09	1.38±0.78E-07
406	DOWN(3)	7.22	1,010	1.50±2.88E-09	8.97±4.06E-09	1.33±8.39E-08
406	DOWN(4)	6.68	1,213	-0.86±3.38E-09	8.57±3.71E-09	1.49±6.79E-08
408	DOWN(1)	6.59	1,691	0.23±1.71E-09	1.98±0.01E-04	5.64±2.45E-07
408	DOWN(2)	6.72	1,657	2.62±2.24E-09	2.62±0.01E-04	2.24±1.05E-07
408	DOWN(3)	6.62	2,013	3.04±7.16E-09	2.92±0.01E-04	2.79±1.18E-07
408	DOWN(4)	6.71	1,568	3.13±9.60E-10	2.24±0.01E-04	1.66±1.11E-07
501	DOWN(1)	6.90	1,409	0.18±2.86E-09	1.31±0.01E-04	1.05±0.84E-07
501	DOWN(2)	7.09	1,370	1.29±2.46E-09	1.22±0.01E-04	1.53±0.56E-07
501	DOWN(3)	6.74	1,708	-0.52±4.34E-09	1.61±0.01E-04	1.19±0.60E-07
501	DOWN(4)	7.05	1,416	4.04±3.49E-09	1.22±0.01E-04	3.49±7.93E-08
502	DOWN(1)	6.94	1,588	2.39±3.40E-09	1.35±0.01E-04	1.41±0.85E-07
502	DOWN(2)	7.05	1,474	1.13±2.54E-09	1.17±0.01E-04	1.33±0.56E-07
502	DOWN(3)	6.87	1,697	-0.53±4.39E-09	1.38±0.01E-04	9.27±8.48E-08
502	DOWN(4)	6.99	1,558	1.14±3.56E-09	1.19±0.01E-04	6.97±8.08E-08
602A	DOWN(1)	6.97	543	-1.36±1.37E-09	1.07±0.24E-08	2.15±0.82E-07
602A	DOWN(2)	6.98	551	-0.50±1.02E-09	1.18±0.22E-08	2.03±0.79E-07
602A	DOWN(3)	6.71	575	0.23±1.31E-09	1.01±0.16E-08	2.34±0.61E-07
602A	DOWN(4)	6.98	581	-0.87±1.18E-09	1.21±0.15E-08	3.14±0.81E-07
604	DOWN(1)	6.25	1,070	2.09±2.32E-09	8.58±4.34E-09	0.29±8.25E-08
604	DOWN(2)	6.33	938	-0.45±1.77E-09	3.57±2.54E-09	2.10±8.25E-08
604	DOWN(3)	6.32	1,121	2.72±3.35E-09	4.82±2.64E-09	-9.65±8.27E-08
604	DOWN(4)	6.24	1,367	0.19±3.08E-09	8.06±2.64E-09	5.34±7.87E-08

Note: Bolding convention applied to these data. (See p. E-2²⁰)

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-2 (continued)
2004 Indicator Results From the Sand and Gravel Unit

Location Code	Hydraulic Position	pH (SU)	Conductivity (µmhos/cm@25°C)	Gross Alpha (µCi/mL)	Gross Beta (µCi/mL)	Tritium (µCi/mL)
8605	DOWN(1)	6.56	1,584	6.78±2.90E-09	1.11±0.01E-05	4.68±0.90E-07
8605	DOWN(2)	6.43	1,444	8.02±3.80E-09	1.15±0.01E-05	4.18±0.59E-07
8605	DOWN(3)	6.63	1,852	1.39±0.64E-08	9.96±0.07E-06	3.02±0.62E-07
8605	DOWN(4)	6.71	1,542	2.08±0.58E-08	1.23±0.01E-05	1.26±0.80E-07
8607	DOWN(1)	6.41	646	0.94±8.82E-10	1.23±0.28E-08	2.04±0.83E-07
8607	DOWN(2)	6.30	1,766	-1.34±2.63E-09	3.42±0.51E-08	-0.74±8.08E-08
8607	DOWN(3)	6.47	914	-0.27±1.38E-09	3.01±0.36E-08	0.44±8.46E-08
8607	DOWN(4)	6.41	1,059	-2.94±2.51E-09	2.69±0.35E-08	-2.31±7.88E-08
8609	DOWN(1)	6.70	1,962	-1.74±4.32E-09	1.90±0.03E-06	4.18±0.89E-07
8609	DOWN(2)	6.97	1,810	0.66±3.51E-09	1.58±0.03E-06	3.46±0.84E-07
8609	DOWN(3)	6.72	2,195	0.36±6.12E-09	1.51±0.03E-06	2.54±0.87E-07
8609	DOWN(4)	6.95	2,445	-0.13±3.27E-09	2.14±0.02E-06	2.79±0.82E-07
105	DOWN(1)	6.61	2,005	0.98±4.05E-09	4.98±0.02E-05	3.42±0.88E-07
105	DOWN(2)	6.56	1,877	4.46±3.82E-09	4.94±0.01E-05	3.10±0.82E-07
105	DOWN(3)	6.54	1,834	0.62±3.58E-09	4.57±0.01E-05	1.86±0.86E-07
105	DOWN(4)	6.29	1,896	4.60±4.58E-09	5.51±0.02E-05	3.31±0.80E-07
106	DOWN(1)	6.64	1,609	1.28±3.20E-09	1.66±0.45E-08	1.10±0.07E-06
106	DOWN(2)	6.79	1,571	1.44±2.23E-09	2.40±0.32E-08	8.29±0.61E-07
106	DOWN(3)	6.64	1,401	-0.85±2.36E-09	3.50±0.36E-08	6.84±0.88E-07
106	DOWN(4)	6.65	1,581	6.61±4.32E-09	4.29±0.57E-08	1.20±0.07E-06
116	DOWN(1)	7.08	1,508	0.00±3.14E-09	1.46±0.02E-06	1.58±0.60E-07
116	DOWN(2)	6.62	4,090	2.55±4.54E-09	1.93±0.04E-06	1.09±0.80E-07
116	DOWN(3)	6.61	1,217	-2.50±3.92E-09	1.16±0.03E-06	8.52±8.40E-08
116	DOWN(4)	6.74	1,464	3.70±4.69E-09	1.33±0.03E-06	8.06±7.90E-08
605	DOWN(1)	6.84	474	-0.67±1.26E-09	3.69±0.33E-08	8.65±5.66E-08
605	DOWN(2)	7.07	910	-0.66±1.08E-09	4.83±0.26E-08	0.33±7.64E-08
605	DOWN(3)	6.68	792	1.98±2.14E-09	3.18±0.33E-08	-0.17±8.17E-08
605	DOWN(4)	6.70	706	-1.51±1.74E-09	4.00±0.33E-08	1.34±0.78E-07
801	DOWN(1)	6.93	1,032	0.15±2.34E-09	4.12±0.04E-06	2.00±0.86E-07
801	DOWN(2)	6.59	2,110	5.45±4.21E-09	7.04±0.06E-06	1.22±0.78E-07
801	DOWN(3)	6.53	1,824	0.27±4.58E-09	5.90±0.05E-06	1.09±0.85E-07
801	DOWN(4)	6.62	1,696	2.49±3.91E-09	5.14±0.05E-06	1.85±0.81E-07
802	DOWN(1)	6.34	502	-0.60±1.47E-09	2.06±0.32E-08	8.78±8.03E-08
802	DOWN(2)	6.25	135	0.00±1.02E-09	5.80±3.32E-09	7.19±5.65E-08
802	DOWN(3)	6.83	190	0.73±1.23E-09	1.10±0.36E-08	6.82±8.53E-08
802	DOWN(4)	6.72	1,268	-2.13±3.68E-09	9.10±0.70E-08	1.28±0.78E-07

Note: Bolding convention applied to these data. (See p. E-2^{□□})

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-2 (concluded)
2004 Indicator Results From the Sand and Gravel Unit

Location Code	Hydraulic Position	pH (SU)	Conductivity ($\mu\text{mhos/cm}@25^{\circ}\text{C}$)	Gross Alpha ($\mu\text{Ci/mL}$)	Gross Beta ($\mu\text{Ci/mL}$)	Tritium ($\mu\text{Ci/mL}$)
803	DOWN(1)	6.79	1,250	3.53±3.14E-09	1.72±0.44E-08	2.06±0.82E-07
803	DOWN(2)	6.86	1,198	1.20±2.87E-09	1.46±0.41E-08	7.23±8.30E-08
803	DOWN(3)	7.06	1,095	3.17±3.13E-09	1.78±0.42E-08	1.46±0.58E-07
803	DOWN(4)	6.75	1,296	-2.41±2.89E-09	1.40±0.28E-08	1.58±0.78E-07
804	DOWN(1)	6.67	1,020	-0.84±1.60E-09	1.40±0.05E-07	2.05±0.81E-07
804	DOWN(2)	6.92	1,360	0.88±3.05E-09	5.93±0.14E-07	7.05±8.16E-08
804	DOWN(3)	6.77	1,096	1.21±2.36E-09	2.19±0.08E-07	1.12±0.85E-07
804	DOWN(4)	6.53	1,064	-1.92±2.67E-09	1.95±0.08E-07	1.21±0.78E-07
8603	DOWN(1)	7.12	1,936	-0.75±3.80E-09	6.58±0.02E-05	3.33±0.88E-07
8603	DOWN(2)	6.57	1,829	-1.14±2.74E-09	5.89±0.02E-05	1.80±0.80E-07
8603	DOWN(3)	7.18	1,851	-0.29±4.89E-09	6.03±0.02E-05	2.39±0.87E-07
8603	DOWN(4)	7.30	1,822	4.39±4.62E-09	6.16±0.02E-05	2.22±0.81E-07
8604	DOWN(1)	7.07	1,768	-0.22±3.41E-09	4.89±0.01E-05	3.45±0.88E-07
8604	DOWN(2)	6.69	1,630	0.96±2.66E-09	4.59±0.01E-05	2.50±0.82E-07
8604	DOWN(3)	6.79	1,778	-2.43±4.26E-09	5.26±0.02E-05	2.56±0.87E-07
8604	DOWN(4)	7.26	1,718	3.74±4.17E-09	5.32±0.02E-05	2.84±0.57E-07
8612	DOWN(1)	7.23	1,250	-4.42±3.27E-09	-2.09±3.52E-09	5.37±0.87E-07
8612	DOWN(2)	6.99	1,338	-0.73±2.58E-09	3.50±3.45E-09	3.70±0.84E-07
8612	DOWN(3)	7.01	1,250	2.34±4.04E-09	1.25±3.53E-09	3.56±0.87E-07
8612	DOWN(4)	7.06	1,438	0.07±3.92E-09	1.26±3.51E-09	4.16±0.82E-07
GSEEP	DOWN(1)	6.52	849	-0.60±1.75E-09	1.31±1.73E-09	6.12±0.87E-07
GSEEP	DOWN(2)	6.12	839	-0.29±1.56E-09	4.62±2.41E-09	2.65±0.81E-07
GSEEP	DOWN(3)	6.60	854	-1.40±2.09E-09	1.94±2.42E-09	3.72±0.85E-07
GSEEP	DOWN(4)	6.51	1,087	-2.93±2.68E-09	7.11±2.57E-09	4.14±0.82E-07
SP04	DOWN(1)	NS	NS	1.70±2.58E-09	1.63±2.52E-09	3.64±0.86E-07
SP04	DOWN(3)	NS	NS	0.21±3.41E-09	8.18±3.90E-09	2.71±0.84E-07
SP06	DOWN(1)	NS	NS	0.12±1.48E-09	0.87±1.30E-09	1.61±0.83E-07
SP06	DOWN(3)	NS	NS	-0.25±2.03E-09	1.52±1.89E-09	6.79±8.45E-08
SP11	DOWN(1)	NS	NS	-2.05±1.96E-09	3.88±0.32E-08	2.35±0.83E-07
SP11	DOWN(3)	NS	NS	-0.25±2.98E-09	7.13±0.53E-08	1.04±0.84E-07
SP12	DOWN(1)	6.45	833	-1.13±2.40E-09	2.62±2.58E-09	3.66±0.84E-07
SP12	DOWN(3)	7.58	750	1.74±2.73E-09	4.51±2.59E-09	3.06±0.86E-07
WP-A	DOWN(4)	7.21	123	0.26±3.99E-10	1.81±0.13E-08	1.26±0.04E-05
WP-C	DOWN(4)	6.46	204	-0.91±4.57E-10	5.03±0.21E-08	5.35±0.16E-05
WP-H	DOWN(1)	6.63	1,007	2.26±2.47E-09	6.97±0.05E-06	2.12±0.12E-06
WP-H	DOWN(4)	5.94	1,443	1.59±0.29E-08	5.78±0.04E-06	1.49±0.08E-06

Note: Bolding convention applied to these data. (See p. E-2)

NS - Not sampled

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-3
2004 Indicator Results From the Lavery Till-Sand Unit

Location Code	Hydraulic Position	pH (SU)	Conductivity (µmhos/cm@25°C)	Gross Alpha (µCi/mL)	Gross Beta (µCi/mL)	Tritium (µCi/mL)
302	UP(1)	6.81	3,207	0.00±5.51E-09	0.00±6.84E-09	1.93±8.02E-08
302	UP(2)	6.89	3,024	-7.57±5.93E-09	-5.04±6.89E-09	9.26±7.74E-08
302	UP(3)	6.88	3,084	-5.15±9.77E-09	-2.04±7.42E-09	9.79±8.15E-08
302	UP(4)	6.71	3,908	-0.07±1.11E-08	9.50±7.30E-09	7.45±7.72E-08
402	UP(1)	6.96	2,552	4.84±4.24E-09	2.18±4.91E-09	-4.55±8.03E-08
402	UP(2)	7.12	2,376	0.45±5.62E-09	0.44±6.94E-09	-0.95±8.21E-08
402	UP(3)	7.20	2,053	3.38±9.50E-09	2.68±7.36E-09	1.13±0.84E-07
402	UP(4)	6.95	2,734	-2.80±7.44E-09	6.00±6.64E-09	6.90±7.76E-08
204	DOWN(1)	7.54	1,150	2.66±2.37E-09	1.94±3.33E-09	0.33±8.50E-08
204	DOWN(2)	7.42	1,067	0.63±2.69E-09	-0.11±3.45E-09	2.19±7.99E-08
204	DOWN(3)	7.53	949	0.92±1.81E-09	2.22±3.31E-09	8.45±5.78E-08
204	DOWN(4)	7.55	1,157	-1.17±3.09E-09	5.08±3.43E-09	0.32±7.88E-08
206	DOWN(1)	7.60	1,188	0.81±2.63E-09	1.50±3.55E-09	7.87±8.01E-08
206	DOWN(2)	7.41	1,257	0.00±2.33E-09	0.77±3.33E-09	-0.17±7.78E-08
206	DOWN(3)	7.33	1,168	1.20±2.78E-09	2.72±3.40E-09	-2.40±8.43E-08
206	DOWN(4)	7.31	1,226	4.54±3.34E-09	-0.89±3.49E-09	1.27±0.78E-07
208	DOWN(1)	7.77	254	5.15±5.54E-10	0.38±5.70E-10	6.28±7.93E-08
208	DOWN(2)	7.78	253	5.29±8.05E-10	0.73±1.19E-09	1.45±0.79E-07
208	DOWN(3)	7.80	231	1.18±0.81E-09	0.87±1.09E-09	1.91±8.38E-08
208	DOWN(4)	7.80	264	0.18±1.00E-09	2.18±1.16E-09	-1.16±0.77E-07

Note: Bolding convention applied to these data. (See p. E-2[□])

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-4
2004 Indicator Results From the Weathered Lavery Till Unit

Location Code	Hydraulic Position	pH (SU)	Conductivity ($\mu\text{mhos/cm}@25^{\circ}\text{C}$)	Gross Alpha ($\mu\text{Ci/mL}$)	Gross Beta ($\mu\text{Ci/mL}$)	Tritium ($\mu\text{Ci/mL}$)
908	UP(1)	6.80	2,680	1.57±3.20E-09	9.52±6.90E-09	3.11±5.73E-08
908	UP(3)	6.61	2,501	1.09±0.62E-08	1.35±0.57E-08	1.01±0.82E-07
1005	UP(1)	6.98	839	4.69±2.78E-09	-1.08±1.62E-09	1.83±0.82E-07
1005	UP(3)	7.05	715	3.09±2.85E-09	2.19±2.43E-09	-1.02±0.83E-07
1008C	UP(1)	7.42	592	-0.46±1.36E-09	-0.04±1.24E-09	1.33±0.82E-07
1008C	UP(3)	7.43	520	1.12±1.76E-09	0.65±1.84E-09	0.95±8.38E-08
906	DOWN(1)	7.31	596	0.00±2.06E-09	1.93±1.95E-09	1.22±0.81E-07
906	DOWN(3)	7.13	536	1.69±2.15E-09	9.00±2.28E-09	8.90±8.42E-08
1006	DOWN(1)	6.63	1,786	-0.30±3.73E-09	0.80±3.34E-09	7.18±8.11E-08
1006	DOWN(3)	6.86	1,590	6.23±5.49E-09	2.62±4.83E-09	-3.80±8.45E-08
1007	DOWN(1)	6.89	1,338	4.36±3.46E-09	4.77±3.76E-09	1.55±0.81E-07
1007	DOWN(3)	6.69	1,224	2.46±3.27E-09	4.26±3.75E-09	4.94±5.90E-08
NDATR	DOWN(1)	7.41	836	1.27±1.36E-09	1.81±0.05E-07	4.68±0.19E-06
NDATR	DOWN(2)	7.59	1,150	1.58±2.76E-09	1.91±0.08E-07	4.57±0.19E-06
NDATR	DOWN(3)	7.78	779	2.49±1.97E-09	1.74±0.07E-07	3.81±0.17E-06
NDATR	DOWN(4)	7.63	827	1.98±2.00E-09	1.97±0.08E-07	2.81±0.14E-06
909	DOWN(1)	6.61	1,295	-0.53±3.20E-09	2.70±0.11E-07	9.26±0.96E-07
909	DOWN(3)	6.89	1,209	1.93±3.28E-09	3.29±0.14E-07	6.86±0.92E-07

Note: Bolding convention applied to these data. (See p. E-2²⁰)

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-5
2004 Indicator Results From the Unweathered Lavery Till Unit

Location Code	Hydraulic Position	pH (SU)	Conductivity ($\mu\text{mhos/cm@25}^\circ\text{C}$)	Gross Alpha ($\mu\text{Ci/mL}$)	Gross Beta ($\mu\text{Ci/mL}$)	Tritium ($\mu\text{Ci/mL}$)
405	UP(1)	7.28	1,194	-0.95 \pm 3.30E-09	0.75 \pm 4.76E-09	1.88 \pm 7.90E-08
405	UP(2)	7.16	2,507	-1.04 \pm 3.78E-09	1.37\pm0.53E-08	6.07\pm5.42E-08
405	UP(3)	7.07	1,638	5.12\pm4.75E-09	1.26 \pm 0.51E-08	-1.07 \pm 0.87E-07
405	UP(4)	7.10	1,800	-3.76 \pm 4.75E-09	8.41 \pm 4.69E-09	-8.48 \pm 5.53E-08
1303	UP(1)	7.77	292	2.24\pm1.03E-09	9.38\pm1.53E-09	0.98 \pm 8.25E-08
1303	UP(2)	7.25	351	7.94 \pm 8.20E-10	3.70 \pm 1.32E-09	-1.29 \pm 0.81E-07
1303	UP(3)	7.31	358	1.72 \pm 1.30E-09	2.95 \pm 1.30E-09	-5.81 \pm 8.30E-08
1303	UP(4)	7.76	367	3.14 \pm 8.32E-10	2.10\pm1.30E-09	-2.97 \pm 7.89E-08
110	DOWN(1)	7.32	502	0.56 \pm 1.13E-09	2.49 \pm 1.70E-09	1.43\pm0.10E-06
110	DOWN(2)	7.27	515	0.83 \pm 1.05E-09	0.42 \pm 1.26E-09	1.27 \pm 0.10E-06
110	DOWN(3)	7.43	430	1.82\pm1.58E-09	2.33 \pm 1.67E-09	1.17 \pm 0.10E-06
110	DOWN(4)	7.20	537	0.22 \pm 1.73E-09	2.90\pm1.66E-09	1.06\pm0.09E-06
704	DOWN(1)	6.46	782	-0.14 \pm 1.68E-09	2.59\pm1.78E-09	-0.48 \pm 8.01E-08
704	DOWN(2)	6.41	690	-0.14 \pm 1.53E-09	4.34 \pm 2.37E-09	6.30 \pm 7.75E-08
704	DOWN(3)	6.52	712	1.38 \pm 2.39E-09	7.88 \pm 2.90E-09	-6.87 \pm 8.32E-08
704	DOWN(4)	6.57	886	0.62 \pm 2.52E-09	9.78\pm2.67E-09	-6.75 \pm 7.86E-08
707	DOWN(1)	6.53	366	-0.56 \pm 1.06E-09	4.71 \pm 1.67E-09	2.81 \pm 8.40E-08
707	DOWN(2)	6.46	354	1.41 \pm 8.93E-10	3.73 \pm 1.58E-09	0.03 \pm 5.62E-08
707	DOWN(3)	6.37	548	-0.78 \pm 1.70E-09	2.10\pm1.58E-09	-2.28 \pm 0.90E-07
707	DOWN(4)	6.56	534	-0.10 \pm 1.51E-09	5.52\pm1.54E-09	-1.83 \pm 7.87E-08
107	DOWN(1)	7.27	660	0.97 \pm 1.47E-09	6.94\pm2.63E-09	3.84\pm0.84E-07
107	DOWN(2)	7.29	674	0.65 \pm 1.56E-09	8.01 \pm 2.58E-09	2.32 \pm 0.79E-07
107	DOWN(3)	7.19	710	-0.33 \pm 1.99E-09	1.17 \pm 0.27E-08	2.17 \pm 0.83E-07
107	DOWN(4)	7.12	791	-0.32 \pm 2.39E-09	1.31\pm0.28E-08	1.58\pm0.57E-07
108	DOWN(1)	7.82	488	1.57\pm1.19E-09	2.05\pm1.35E-09	2.04\pm0.81E-07
108	DOWN(2)	7.65	503	1.06 \pm 1.23E-09	2.64 \pm 1.74E-09	1.94 \pm 0.79E-07
108	DOWN(3)	7.50	460	1.01 \pm 1.40E-09	3.60 \pm 1.75E-09	1.82 \pm 0.83E-07
108	DOWN(4)	7.68	534	-0.50 \pm 1.49E-09	4.52\pm1.75E-09	1.81 \pm 7.88E-08
409	DOWN(1)	7.94	345	0.28 \pm 1.02E-09	2.05\pm1.31E-09	-3.33 \pm 5.76E-08
409	DOWN(2)	7.91	325	6.33 \pm 8.04E-10	3.11\pm1.24E-09	4.99 \pm 7.68E-08
409	DOWN(3)	7.95	300	0.36 \pm 1.00E-09	2.72 \pm 1.28E-09	-8.56 \pm 5.83E-08
409	DOWN(4)	7.41	351	0.87 \pm 1.21E-09	2.72 \pm 1.20E-09	1.07\pm0.78E-07
910	DOWN(1)	6.91	1,254	3.25 \pm 2.73E-09	9.45 \pm 3.88E-09	-0.43 \pm 8.27E-08
910	DOWN(3)	7.22	1,118	3.12 \pm 1.88E-09	1.23 \pm 0.27E-08	3.69 \pm 8.43E-08

Note: Bolding convention applied to these data. (See p. E-2²⁰)

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-6
2004 Indicator Results From the Kent Recessional Sequence

Location Code	Hydraulic Position	pH (SU)	Conductivity (μmhos/cm@25°C)	Gross Alpha (μCi/mL)	Gross Beta (μCi/mL)	Tritium (μCi/mL)
901	UP(1)	7.77	354	5.31±6.76E-10	1.41±0.64E-09	4.38±8.06E-08
901	UP(3)	7.61	347	1.56±1.16E-09	3.66±1.41E-09	1.09±8.06E-08
902	UP(1)	7.83	425	1.77±1.29E-09	1.18±1.06E-09	1.12±0.82E-07
902	UP(3)	7.45	378	0.76±1.31E-09	2.54±1.60E-09	-1.36±0.82E-07
1008B	UP(1)	7.82	365	0.77±1.06E-09	2.26±8.41E-10	3.02±8.06E-08
1008B	UP(3)	7.68	412	1.02±1.26E-09	2.67±1.32E-09	-7.31±8.33E-08
903	DOWN(1)	7.46	902	4.29±2.37E-09	4.12±2.62E-09	1.01±0.82E-07
903	DOWN(3)	7.31	806	0.62±1.86E-09	-0.08±2.36E-09	-1.88±0.83E-07
8610	DOWN(1)	7.78	1,040	1.43±1.73E-09	3.55±2.47E-09	2.58±8.01E-08
8610	DOWN(3)	7.50	989	1.32±2.52E-09	2.83±2.50E-09	8.32±8.43E-08
8611	DOWN(1)	7.25	893	3.03±2.08E-09	2.38±2.37E-09	-1.50±7.94E-08
8611	DOWN(3)	7.34	779	1.19±2.27E-09	2.71±2.46E-09	-2.91±8.32E-08

Note: Bolding convention is not applicable to these data.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-7
2004 Volatile Organic Compound Results
at Selected Groundwater Monitoring Locations

Location Code	Sampling Quarter	1,1-DCA (µg/L)	DCDFMeth (µg/L)	1,1-DCE (µg/L)	1,2-DCE(total) (µg/L)	1,2-DCE(trans) (µg/L)	1,1,1-TCA (µg/L)
SP12	1	<5.0	<1.0	<5.0	NS	<1.0	<5.0
	3	<5.0	<1.0	<5.0	NS	<1.0	<5.0
803	1	<5.0	<1.0	<5.0	NS	<1.0	<5.0
	2	<5.0	<1.0	<5.0	NS	<1.0	<5.0
	3	<5.0	<1.0	<5.0	NS	<1.0	<5.0
	4	<5.0	<1.0	<5.0	NS	<1.0	<5.0
8609	1	<5.0	<5.0	<5.0	NS	<5.0	<5.0
8612	1	11.0	<5.0*	<5.0*	26.0	<5.0	<5.0*
	2	8.9	<5.0*	<5.0*	23.0	<5.0*	<5.0*
	3	9.9	<5.0*	<5.0*	24.0	<5.0	<5.0*
	4	9.1	<5.0	<5.0*	24.3	<5.0*	<5.0*

See Table E-12⁶ for compound definition.

Note: Bolding convention applied to these data. (See p. E-2⁶)

NS - Not sampled.

* Compound was reported at an estimated concentration less than the practical quantitation limit.

Table E-8
2004 Tributyl Phosphate Results
at Selected Groundwater Monitoring Locations

Location Code	Sampling Quarter	Tributyl Phosphate (TBP) (µg/L)
111	1	<10.0*
	3	12.0
8605	1	410
	3	400

Practical quantitation limit is 10 µg/L.

Note: Bolding convention not applicable to these data.

* Compound was reported at an estimated concentration less than the practical quantitation limit.

Table E-9
2004 Results for Metals in Groundwater (µg/L)
Title 6 NYCRR Appendix 33 List

Location Code	Hydraulic Position	Antimony	Arsenic	Barium	Beryllium	Cadmium	Chromium	Cobalt	Copper
Sand and Gravel									
706	UP(1)	<10	<10	156	<1	<5	51	<50	<25
706	UP(2)	<10	<10	153	<1	<5	40	<50	<25
706	UP(3)	<10	<10	202	<1	<5	43	<50	<25
706	UP(4)	<10	<10	236	<1	<5	272	<50	<25
1304	UP(1)	<10	34	420	2	<5	65	<50	74
1304	UP(2)	<10	14	321	1	<5	31	<50	32
1304	UP(3)	<10	20	327	1	<5	39	<50	45
1304	UP(4)	<10	<10	134	<1	<5	12	<50	<25
1302	DOWN(1)	<10	21	356	2	<5	39	<50	57
1302	DOWN(2)	<10	<10	212	<1	<5	15	<50	<25
1302	DOWN(3)	<10	<10	290	<1	<5	18	<50	25
1302	DOWN(4)	<10	<10	290	<1	<5	14	<50	<25
111	DOWN(1)	<3	<3	96	0.1	1	3	2	4
502	DOWN(1)	NS	4	330	NS	<0.3	838	2	8
502	DOWN(3)	NS	<4	370	NS	<0.4	888	2	6
8605	DOWN(1)	<3	6	148	0.17	<0.3	2	2	3
Weathered Till									
NDATR	DOWN(1)	<10	<10	48	<1	<5	<5	<50	<25
NDATR	DOWN(2)	<10	<10	66	<1	<5	<5	<50	<25
NDATR	DOWN(3)	<10	<10	48	<1	<5	<5	<50	<25
NDATR	DOWN(4)	<10	<10	54	<1	<5	<5	<50	<25
909	DOWN(1)	<10	12	191	<1	<5	10	<50	<25
Unweathered Till									
405	UP(1)	<10	<10	137	<1	<5	138	<50	<25
405	UP(2)	<10	<10	132	<1	<5	702	<50	<25
405	UP(3)	<10	<10	140	<1	<5	18	<50	<25
405	UP(4)	<10	<10	169	<1	<5	173	<50	<25
1303	UP(1)	<10	23	371	2	<5	60	<50	59
1303	UP(2)	<10	24	419	2	<5	60	<50	53
1303	UP(3)	<10	64	756	5	<5	139	95	138
1303	UP(4)	<10	15	272	1	<5	29	<50	26

Note: Bolding convention applied to these data. (See p. E-2^{ca})
NS - Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-9 (concluded)
2004 Results for Metals in Groundwater (µg/L)
Title 6 NYCRR Appendix 33 List

Location Code	Hydraulic Position	Lead	Mercury	Nickel	Selenium	Silver	Thallium	Tin	Vanadium	Zinc
Sand and Gravel										
706	UP(1)	3	<0.2	<40	<5	<10	<10	<3,000	<50	<20
706	UP(2)	<3	<0.2	<40	<5	<10	<10	<3,000	<50	<20
706	UP(3)	<3	<0.2	288	<5	<10	<10	<3,000	<50	<20
706	UP(4)	<3	<0.2	532	<5	<10	<10	<3,000	<50	36
1304	UP(1)	44	<0.2	63	<5	<10	<10	<3,000	63	226
1304	UP(2)	19	<0.2	<40	<5	<10	<10	<3,000	<50	95
1304	UP(3)	27	<0.2	<40	<25	<10	<10	<3,000	<50	130
1304	UP(4)	10	<0.2	<40	<5	<10	<10	<3,000	<50	44
1302	DOWN(1)	34	<0.2	45	<5	<10	<10	<3,000	50	173
1302	DOWN(2)	14	<0.2	<40	<5	<10	<10	<3,000	<50	68
1302	DOWN(3)	16	<0.2	<40	<5	<10	<10	<3,000	<50	76
1302	DOWN(4)	13	<0.2	<40	<5	<10	<10	<3,000	<50	49
111	DOWN(1)	<3	<0.1	5	<3	<1	<6	<6	1	26
502	DOWN(1)	<3	<0.1	56	<3	<1	NS	NS	3	9
502	DOWN(3)	<3	<0.1	38	<4	<1	NS	NS	2	<0.5
8605	DOWN(1)	<3	<0.1	3	<3	<1	<6	<6	1	<0.5
Weathered Till										
NDATR	DOWN(1)	<3	<0.2	<40	<5	<10	<10	<3,000	<50	<20
NDATR	DOWN(2)	<3	<0.2	<40	<5	<10	<10	<3,000	<50	24
NDATR	DOWN(3)	<3	<0.2	<40	<5	<10	<10	<3,000	<50	<20
NDATR	DOWN(4)	<3	<0.2	<40	<5	<10	<10	<3,000	<50	<20
909	DOWN(1)	5	<0.2	<40	<5	<10	<10	<3,000	<50	30
Unweathered Till										
405	UP(1)	5	<0.2	668	<5	<10	<10	<3,000	<50	<20
405	UP(2)	<3	<0.2	1,210	<5	<10	<10	<3,000	<50	<20
405	UP(3)	<3	<0.2	2,280	<5	<10	<10	<3,000	<50	<20
405	UP(4)	<3	<0.2	1,710	<5	<10	<10	<3,000	<50	<20
1303	UP(1)	27	<0.2	89	<5	<10	<10	<3,000	71	179
1303	UP(2)	27	<0.2	89	<5	<10	<10	<3,000	72	221
1303	UP(3)	81	<0.2	218	<25	<10	<10	<3,000	161	471
1303	UP(4)	9	<0.2	44	<5	<10	<10	<3,000	<50	89

Note: Bolding convention applied to these data. (See p. E-2[□])
NS - Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-10
2004 Metals Indicator Results for Early Warning Monitoring Wells ($\mu\text{g/L}$)

Location Code	Sample Quarter	Aluminum Total	Iron Total	Manganese Total
502	(1)	168	5,310	11.3
	(3)	213	4,800	11.3

Note: Bolding convention is not applicable to these data.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-11
2004 Radioactivity ($\mu\text{Ci/mL}$) in Groundwater From Selected
Monitoring Locations

Location Code	Hydraulic Position	C-14	Sr-90	Tc-99
Sand and Gravel				
401	UP(1)	-0.97 \pm 3.12E-08	4.02 \pm 1.36E-09	-1.84 \pm 1.55E-09
706	UP(1)	0.41 \pm 3.13E-08	4.77 \pm 1.74E-09	-4.80 \pm 2.74E-09
706	UP(2)	1.22 \pm 3.00E-08	2.72\pm1.42E-09	0.03 \pm 2.23E-09
706	UP(3)	-2.96 \pm 2.65E-08	4.37 \pm 1.61E-09	0.00 \pm 1.87E-09
706	UP(4)	2.86 \pm 4.62E-09	5.39\pm2.19E-09	1.53 \pm 2.28E-09
1304	UP(1)	-0.55 \pm 3.11E-08	1.23 \pm 1.55E-09	-2.64 \pm 2.10E-09
1304	UP(2)	3.69\pm2.65E-08	4.67\pm1.63E-09	-1.49 \pm 2.02E-09
1304	UP(3)	-1.52 \pm 2.64E-08	2.44 \pm 1.43E-09	0.47 \pm 1.84E-09
1304	UP(4)	0.00 \pm 4.44E-09	1.76 \pm 1.20E-09	-1.28 \pm 2.26E-09
1302	DOWN(1)	-1.81 \pm 3.09E-08	-1.50 \pm 1.19E-09	-2.88 \pm 1.98E-09
1302	DOWN(2)	0.14 \pm 2.62E-08	0.17 \pm 1.10E-09	-2.45 \pm 2.14E-09
1302	DOWN(3)	0.49 \pm 2.71E-08	0.40 \pm 1.40E-09	1.44 \pm 1.90E-09
1302	DOWN(4)	2.17 \pm 4.72E-09	0.44 \pm 1.10E-09	-1.63 \pm 2.25E-09
111	DOWN(1)	NS	3.00 \pm 0.05E-06	NS
406	DOWN(1)	-1.80 \pm 3.07E-08	2.34 \pm 1.48E-09	0.97 \pm 1.49E-09
408	DOWN(1)	-0.69 \pm 3.11E-08	1.25 \pm 0.01E-04	1.96 \pm 0.29E-08
501	DOWN(1)	NS	6.51 \pm 0.02E-05	NS
502	DOWN(1)	NS	6.85 \pm 0.02E-05	NS
602A	DOWN(1)	NS	6.32 \pm 1.83E-09	NS
602A	DOWN(3)	NS	4.84 \pm 1.66E-09	NS
8605	DOWN(1)	NS	5.69 \pm 0.06E-06	NS
8609	DOWN(1)	NS	9.94 \pm 0.18E-07	NS
8609	DOWN(3)	NS	8.01 \pm 0.31E-07	NS
116	DOWN(1)	NS	6.96 \pm 0.17E-07	NS
116	DOWN(3)	NS	5.91 \pm 0.21E-07	NS
605	DOWN(1)	NS	1.86 \pm 0.28E-08	NS
605	DOWN(3)	NS	1.79 \pm 0.25E-08	NS

Note: Bolding convention applied to these data. (See p. E-2²⁰)

NS - Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-11 (continued)
2004 Radioactivity ($\mu\text{Ci/mL}$) in Groundwater From Selected
Monitoring Locations

Location Code	Hydraulic Position	C-14	Sr-90	Tc-99
Sand and Gravel (concluded)				
801	DOWN(1)	NS	2.00±0.04E-06	NS
801	DOWN(2)	NS	3.64±0.04E-06	NS
801	DOWN(3)	NS	3.19±0.05E-06	NS
801	DOWN(4)	NS	2.71±0.04E-06	NS
8603	DOWN(1)	NS	3.23±0.02E-05	NS
8603	DOWN(3)	NS	3.14±0.02E-05	NS
Weathered Till				
NDATR	DOWN(1)	-0.14±3.11E-08	7.57±0.51E-08	2.17±2.18E-09
NDATR	DOWN(3)	-1.25±2.68E-08	8.50±0.52E-08	0.27±1.88E-09
909	DOWN(1)	-1.66±3.07E-08	1.90±0.06E-07	0.62±1.86E-09
Unweathered Till				
405	UP(1)	0.70±3.16E-08	2.63±1.48E-09	-2.28±1.36E-09
405	UP(2)	1.52±3.00E-08	7.38±1.53E-09	-0.57±2.03E-09
405	UP(3)	-0.64±2.70E-08	3.85±1.50E-09	-0.56±1.79E-09
405	UP(4)	7.43±5.08E-09	3.90±1.21E-09	-1.18±2.19E-09
1303	UP(1)	-0.41±3.08E-08	0.95±1.60E-09	-1.48±2.05E-09
1303	UP(2)	-0.41±2.55E-08	1.33±1.26E-09	-1.75±2.43E-09
1303	UP(3)	0.90±2.69E-08	0.95±1.26E-09	1.29±2.08E-09
1303	UP(4)	1.91±4.53E-09	-0.26±1.30E-09	-1.24±2.25E-09

Note: Bolding convention applied to these data. (See p. E-2⁹⁹)

NS - Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-11 (continued)
2004 Radioactivity ($\mu\text{Ci}/\text{mL}$) in Groundwater From Selected
Monitoring Locations

Location Code	Hydraulic Position	I-129	Cs-137	Ra-226	Ra-228	U-232
Sand and Gravel						
401	UP(1)	0.05±1.31E-09	-0.32±9.63E-09	4.50±2.37E-10	1.66±0.49E-09	2.44±3.28E-11
706	UP(1)	1.01±1.07E-09	-1.48±6.96E-09	3.55±1.98E-10	6.89±4.71E-10	1.01±8.68E-11
706	UP(2)	7.19±9.72E-10	1.51±5.36E-09	3.87±2.40E-10	4.24±4.39E-10	1.21±3.38E-11
706	UP(3)	-0.28±8.58E-10	-0.10±1.14E-08	3.44±2.26E-10	0.14±4.75E-10	-0.06±6.64E-11
706	UP(4)	1.58±1.09E-09	4.16±5.74E-09	4.10±3.01E-10	1.32±0.54E-09	0.77±1.19E-10
1304	UP(1)	2.83±2.48E-09	-0.88±6.83E-09	3.86±2.53E-10	1.01±0.53E-09	-3.06±4.01E-11
1304	UP(2)	0.10±1.92E-09	-1.65±5.94E-09	5.46±2.53E-10	1.24±0.53E-09	3.30±3.87E-11
1304	UP(3)	3.65±8.43E-10	-1.53±6.64E-09	6.67±3.18E-10	-4.81±3.55E-10	-0.69±5.19E-11
1304	UP(4)	0.91±2.06E-09	-1.09±7.08E-09	5.10±3.52E-10	0.56±4.03E-10	-0.68±5.46E-11
1302	DOWN(1)	0.95±1.00E-09	2.34±8.31E-09	2.89±2.88E-10	4.15±4.21E-10	7.04±7.58E-11
1302	DOWN(2)	-3.69±7.24E-10	3.99±6.95E-09	1.39±1.52E-10	8.83±4.35E-10	1.25±4.54E-11
1302	DOWN(3)	0.98±1.31E-09	-2.94±6.94E-09	5.10±2.12E-10	0.59±5.69E-10	-0.68±4.14E-11
1302	DOWN(4)	-0.46±1.12E-09	1.93±6.69E-09	6.39±3.90E-10	-1.22±4.94E-10	1.76±6.79E-11
406	DOWN(1)	1.34±4.01E-10	-3.76±5.32E-09	4.55±2.16E-10	4.71±4.30E-10	-0.77±6.59E-11
408	DOWN(1)	1.53±3.36E-10	-2.93±3.82E-09	3.87±2.26E-10	4.48±5.04E-10	-0.27±4.55E-11
8605	DOWN(1)	NS	1.56±9.90E-09	NS	NS	NS
Weathered Till						
NDATR	DOWN(1)	0.50±1.04E-09	2.84±6.70E-09	1.33±0.56E-09	1.35±0.49E-09	3.50±6.47E-11
NDATR	DOWN(3)	6.22±9.72E-10	-0.49±6.27E-09	1.74±1.60E-10	3.10±4.13E-10	7.58±8.60E-11
909	DOWN(1)	5.16±3.18E-09	-1.27±6.04E-09	7.26±4.04E-10	6.13±4.52E-10	-0.40±5.18E-11
Unweathered Till						
405	UP(1)	-5.13±6.78E-10	1.78±6.76E-09	3.23±1.62E-10	1.49±0.49E-09	7.76±6.88E-11
405	UP(2)	0.95±7.57E-10	-0.52±7.38E-09	5.26±2.92E-10	6.90±4.85E-10	5.43±4.84E-11
405	UP(3)	0.27±9.45E-10	0.65±6.44E-09	3.88±2.43E-10	7.15±5.04E-10	1.75±6.86E-11
405	UP(4)	-1.79±8.20E-10	-4.65±5.53E-09	3.23±2.73E-10	1.07±0.63E-09	0.48±1.25E-10
1303	UP(1)	0.60±1.27E-09	-2.90±6.90E-09	2.70±2.12E-10	1.07±0.48E-09	0.15±4.23E-11
1303	UP(2)	1.34±1.11E-09	3.52±6.54E-09	2.77±1.81E-10	5.81±4.49E-10	1.65±6.21E-11
1303	UP(3)	-0.44±8.58E-10	3.15±6.49E-09	3.88±2.09E-10	1.22±3.43E-10	-1.68±6.40E-11
1303	UP(4)	-0.28±8.22E-10	1.94±6.44E-09	1.35±2.64E-10	9.55±3.95E-10	2.76±6.45E-11
Well Points						
WP-H	DOWN(1)	NS	-0.27±3.96E-09	NS	NS	NS

Note: Bolding convention applied to these data. (See p. E-2²⁰)

NS - Not sampled.

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-11 (concluded)
2004 Radioactivity ($\mu\text{Ci}/\text{mL}$) in Groundwater From Selected
Monitoring Locations

Location Code	Hydraulic Position	U-233/234	U-235/236	U-238	Total U ($\mu\text{g}/\text{mL}$)
Sand and Gravel					
401	UP(1)	7.84 \pm 4.86E-11	0.54 \pm 3.03E-11	4.57 \pm 4.12E-11	1.02 \pm 0.05E-04
706	UP(1)	1.52\pm0.98E-10	1.40 \pm 5.41E-11	6.28\pm5.37E-11	1.11 \pm 0.12E-04
706	UP(2)	1.41 \pm 1.08E-10	2.33 \pm 5.26E-11	1.14 \pm 0.95E-10	0.00 \pm 1.98E-04
706	UP(3)	1.30\pm1.04E-10	2.03 \pm 6.21E-11	2.06\pm1.09E-10	0.00 \pm 2.55E-04
706	UP(4)	1.42 \pm 0.90E-10	6.29\pm5.61E-11	1.14 \pm 0.76E-10	2.18\pm0.09E-04
1304	UP(1)	4.57\pm1.21E-10	1.25 \pm 4.40E-11	3.65\pm1.03E-10	8.11 \pm 0.17E-04
1304	UP(2)	1.85\pm1.18E-10	5.23 \pm 6.94E-11	1.90 \pm 1.18E-10	1.42\pm0.06E-03
1304	UP(3)	3.54 \pm 1.39E-10	1.19 \pm 3.74E-11	1.80\pm0.91E-10	6.93\pm0.52E-04
1304	UP(4)	3.72 \pm 1.57E-10	6.92 \pm 7.68E-11	2.10 \pm 1.22E-10	5.45 \pm 0.09E-04
1302	DOWN(1)	5.87\pm1.74E-10	0.48 \pm 6.00E-11	5.31\pm1.68E-10	1.28\pm0.03E-03
1302	DOWN(2)	1.86 \pm 1.13E-10	0.89 \pm 4.76E-11	1.70 \pm 1.03E-10	5.10\pm3.13E-04
1302	DOWN(3)	3.96 \pm 1.37E-10	5.75 \pm 5.77E-11	1.67 \pm 0.88E-10	5.99 \pm 0.37E-04
1302	DOWN(4)	1.48\pm1.14E-10	1.15\pm0.92E-10	1.29\pm0.99E-10	6.31 \pm 0.17E-04
406	DOWN(1)	6.86 \pm 5.37E-11	3.18 \pm 3.28E-11	7.39 \pm 5.47E-11	0.00 \pm 1.98E-04
408	DOWN(1)	9.72 \pm 2.37E-10	3.34 \pm 5.12E-11	3.58 \pm 1.43E-10	8.00 \pm 0.18E-04
Weathered Till					
NDATR	DOWN(1)	1.92 \pm 0.25E-09	3.04 \pm 1.04E-10	1.27 \pm 0.20E-09	3.61 \pm 0.07E-03
NDATR	DOWN(3)	1.71 \pm 0.29E-09	1.04 \pm 0.79E-10	1.17 \pm 0.25E-09	4.06 \pm 0.17E-03
909	DOWN(1)	4.75 \pm 1.29E-10	7.99 \pm 5.86E-11	3.14 \pm 1.03E-10	5.86 \pm 0.31E-04
Unweathered Till					
405	UP(1)	4.74 \pm 0.94E-10	1.90 \pm 2.28E-11	3.61 \pm 0.83E-10	9.62\pm0.23E-04
405	UP(2)	5.27 \pm 1.74E-10	9.48 \pm 7.92E-11	3.05 \pm 1.36E-10	7.30 \pm 1.67E-04
405	UP(3)	3.23\pm1.32E-10	1.04\pm0.79E-10	2.44\pm1.11E-10	0.00 \pm 2.55E-04
405	UP(4)	6.53\pm2.59E-10	3.39 \pm 7.65E-11	3.83\pm2.01E-10	8.58 \pm 0.11E-04
1303	UP(1)	1.20\pm0.18E-09	7.16 \pm 4.80E-11	1.03\pm0.17E-09	2.12 \pm 0.04E-03
1303	UP(2)	1.31 \pm 0.30E-09	8.72\pm8.47E-11	6.82 \pm 2.14E-10	2.69\pm0.11E-03
1303	UP(3)	6.57\pm1.74E-10	6.16 \pm 7.25E-11	6.01 \pm 1.64E-10	1.48\pm0.07E-03
1303	UP(4)	6.36 \pm 2.19E-10	7.56 \pm 7.40E-11	2.73\pm1.43E-10	1.58 \pm 0.03E-03

Note: Bolding convention applied to these data. (See p. E-2[□])

Sample collection quarter is noted in parentheses next to hydraulic position. Hydraulic position is relative to other wells within the same hydrogeologic unit.

Table E-12
Practical Quantitation Limits (PQLs)

COMPOUND	PQL (µg/L)	COMPOUND	PQL (µg/L)
<i>6 NYCRR Appendix 33 Volatiles</i>		<i>6 NYCRR Appendix 33 Volatiles</i>	
Acetone	10	Isobutyl alcohol	100
Acetonitrile	100	Methacrylonitrile	5
Acrolein	11	Methyl ethyl ketone	10
Acrylonitrile	5	Methyl iodide	5
Allyl chloride	5	Methyl methacrylate	5
Benzene	5	4-Methyl-2-pentanone	10
Bromodichloromethane	5	Methylene bromide	10
Bromoform	5	Methylene chloride	5
Bromomethane	10	Pentachloroethane	5
Carbon disulfide	10	Propionitrile	50
Carbon tetrachloride	5	Styrene	5
Chlorobenzene	5	1,1,1,2-Tetrachloroethane	5
Chloroethane	10	1,1,2,2-Tetrachloroethane	5
Chloroform	5	Tetrachloroethylene	5
Chloromethane	10	Toluene	5
Chloroprene	5	1,1,1-Trichloroethane (1,1,1-TCA)	5
1,2-Dibromo-3-chloropropane	5	1,1,2-Trichloroethane	5
Dibromochloromethane	5	1,2,3-Trichloropropane	5
1,2-Dibromoethane	5	Vinyl acetate	10
Dichlorodifluoromethane (DCDFMeth)	5	Vinyl chloride	10
1,1-Dichloroethane (1,1-DCA)	5	Xylene (total)	5
1,2-Dichloroethane (1,2-DCA)	5	cis-1,3-Dichloropropene	5
1,1-Dichloroethylene (1,1-DCE)	5	trans-1,2-Dichloroethylene (1,2-DCE[trans])	5
1,2-Dichloropropane	5	trans-1,3-Dichloropropene	5
Ethyl benzene	5	trans-1,4-Dichloro-2-butene	5
Ethyl methacrylate	5	Trichloroethylene (TCE)	5
2-Hexanone	10	Trichlorofluoromethane	5
<i>6 NYCRR Appendix 33 Metals</i>		<i>6 NYCRR Appendix 33 Metals</i>	
*Aluminum	200	Lead	3
Antimony	10	*Manganese	15
Arsenic	10	Mercury	0.2
Barium	200	Nickel	40
Beryllium	1	Selenium	5
Cadmium	5	Silver	10
Chromium	10	Thallium	10
Cobalt	50	Tin	3,000
Copper	25	Vanadium	50
*Iron	100	Zinc	20

Note: Specific quantitation limits are highly matrix dependent and may not always be achievable.

** Not a 6 NYCRR Appendix 33 parameter; sampled for the north plateau early warning program.*

Table E-12 (continued)
Practical Quantitation Limits (PQLs)

COMPOUND	PQL (µg/L)	COMPOUND	PQL (µg/L)
<i>NYCRR Appendix 33 Semivolatiles</i>		<i>NYCRR Appendix 33 Semivolatiles</i>	
Acenaphthene	10	2,4-Dinitrotoluene	10
Acenaphthylene	10	2,6-Dinitrotoluene	10
Acetophenone	10	Diphenylamine	10
2-Acetylaminofluorene	10	Ethyl methanesulfonate	10
4-Aminobiphenyl	10	Famphur	10
Aniline	10	Fluoranthene	10
Anthracene	10	Fluorene	10
Aramite	10	Hexachlorobenzene	10
Benzo[a]anthracene	10	Hexachlorobutadiene	10
Benzo[a]pyrene	10	Hexachlorocyclopentadiene	25
Benzo[b]fluoranthene	10	Hexachloroethane	10
Benzo[ghi]perylene	10	Hexachlorophene	330
Benzo[k]fluoranthene	10	Hexachloropropene	10
Benzyl alcohol	10	Indeno(1,2,3,-cd)pyrene	10
Bis(2-chlorethyl)ether	10	Isodrin	10
Bis(2-chloroethoxy)methane	10	Isophorone	10
Bis(2-chloroisopropyl)ether	10	Isosafrole	10
Bis(2-ethylhexyl)phthalate	10	Kepone	50
4-Bromophenyl phenyl ether	10	Methapyrilene	40
Butyl benzyl phthalate	10	Methyl methanesulfonate	10
Chlorobenzilate	10	3-Methylcholanthrene	10
2-Chloronaphthalene	10	2-Methylnaphthalene	10
2-Chlorophenol	10	1,4-Naphthoquinone	10
4-Chlorophenyl phenyl ether	10	1-Naphthylamine	10
Chrysene	10	2-Naphthylamine	10
Di-n-butyl phthalate	10	Nitrobenzene	10
Di-n-octyl phthalate	10	5-Nitro-o-toluidine	10
Diallate	10	4-Nitroquinoline 1-oxide	40
Dibenz[a,h]anthracene	10	N-Nitrosodi-n-butylamine	10
Dibenzofuran	10	N-Nitrosodiethylamine	10
3,3-Dichlorobenzidine	10	N-Nitrosodimethylamine	10
2,4-Dichlorophenol	10	N-Nitrosodipropylamine	10
2,6-Dichlorophenol	10	N-Nitrosodiphenylamine	10
Diethyl phthalate	10	N-Nitrosomethylethylamine	10
Dimethoate	10	N-Nitrosomorpholine	10
7, 12-Dimethylbenz[a]anthracene	10	N-Nitrosopiperidine	10
3,3-Dimethylbenzidine	21	N-Nitrosopyrrolidine	10
2,4-Dimethylphenol	10	Naphthalene	10
Dimethyl phthalate	10	0,0,0-Triethyl phosphorothioate	10
4,6-Dinitro-o-cresol	25	0,0-Diethyl 0-2-pyrazinyl- phosphorothioate	10
2,4-Dinitrophenol	25		

Note: Specific quantitation limits are highly matrix dependent and may not always be achievable.

Table E-12 (concluded)
Practical Quantitation Limits (PQLs)

COMPOUND	PQL ($\mu\text{g/L}$)	COMPOUND	PQL ($\mu\text{g/L}$)
<i>NYCRR Appendix 33 Semivolatiles</i>		<i>NYCRR Appendix 33 Semivolatiles</i>	
p-(Dimethylamino)azobenzene	10	2,3,4,6-Tetrachlorophenol	10
p-Chloroaniline	10	Tetraethyl dithiopyrophosphate	10
p-Chloro-m-cresol	10	1,2,4-Trichlorobenzene	10
p-Cresol	10	2,4,5-Trichlorophenol	25
p-Dichlorobenzene	10	2,4,6-Trichlorophenol	10
p-Nitroaniline	25	alpha,alpha-Dimethylphenethylamine	50
p-Nitrophenol	25	m-Cresol	10
p-Phenylenediamine	100	m-Dichlorobenzene	10
Parathion	10	m-Dinitrobenzene	10
Pentachlorobenzene	10	m-Nitroaniline	25
Pentachloronitrobenzene	10	o-Cresol	10
Pentachlorophenol	25	o-Dichlorobenzene	10
Phenacetin	10	o-Nitroaniline	25
Phenanthrene	10	o-Nitrophenol	10
Phenol	10	o-Toluidine	10
Pronamide	10	sym-Trinitrobenzene	10
Pyrene	10	2-Picoline	10
Safrole	10	Pyridine	10
1,2,4,5-Tetrachlorobenzene	10	1,4-Dioxane	10
<i>Other Organic Compounds</i>			
1,2-Dichloroethelyne (Total)	5		
Tributyl phosphate	10		

Note: Specific quantitation limits are highly matrix dependent and may not always be achievable.

This page intentionally left blank

Appendix F
Summary of Biological Data

The following tables contain a bolding convention devised to help the reader, when viewing the data, to quickly see the range of detectable measurements within a data series. A data series is a set of chemical or radionuclide measurements (e.g., gross alpha, gross beta, tritium) from a single location or from similar locations. Note that some tables contain data that should not be technically evaluated under this convention.

Key to bolding convention:

Results for each constituent constitute a single data series. If a radiological result is larger than the uncertainty term, the measurement is considered positive. Otherwise, a result is considered nondetectable.

If all results in a data series are positive, the lowest and highest values are bolded.

If a data series contains some positive results, the highest value is bolded.

If all values in a data series are nondetectable, no values are bolded.

Table F-1
2004 Radioactivity Concentrations ($\mu\text{Ci/mL}$) in Milk

Location	H-3	K-40	Sr-90	I-129	Cs-137
BFMCTLS					
(Control)					
<i>1st Quarter</i>	0.98±1.10E-07	1.45±0.15E-06	9.43±3.87E-10	-1.31±5.29E-10	0.56±2.60E-09
<i>2nd Quarter</i>	0.60±1.10E-07	1.44±0.15E-06	3.94±5.41E-10	-1.34±3.44E-10	1.43±2.07E-09
<i>3rd Quarter</i>	0.97±1.21E-07	1.37±0.17E-06	-1.25±5.72E-10	4.66±3.24E-10	-0.34±2.91E-09
<i>4th Quarter</i>	0.00±1.21E-07	1.23±0.10E-06	1.51±0.67E-09	-0.44±3.93E-10	1.31±1.43E-09
BFMREED					
(NNW Farm)					
<i>1st Quarter</i>	0.65±1.07E-07	1.42±0.16E-06	6.98±3.52E-10	-0.60±4.86E-10	-1.30±2.17E-09
<i>2nd Quarter</i>	0.59±1.08E-07	1.55±0.15E-06	1.09±0.69E-09	-1.60±2.81E-10	0.89±2.33E-09
<i>3rd Quarter</i>	1.09±1.19E-07	1.44±0.18E-06	4.38±5.12E-10	-0.70±4.08E-10	2.40±3.18E-09
<i>4th Quarter</i>	-1.12±1.25E-07	1.30±0.08E-06	-2.23±0.64E-09	0.56±3.50E-10	2.27±2.23E-09
BFMSCHT					
(S Farm)					
<i>Annual</i>	-0.02±1.08E-07	1.20±0.14E-06	1.41±0.82E-09	1.40±2.97E-10	-2.75±3.18E-09
BFMWIDR					
(SE Farm)					
<i>Annual</i>	0.71±1.03E-07	1.16±0.09E-06	9.52±4.73E-10	-2.06±4.43E-10	0.54±1.23E-09

Note: Bolding convention applied to these data. See page F-2

Table F-2
2004 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Meat

2004 Radioactivity Concentrations in Beef

Location	% Moisture	H-3 ($\mu\text{Ci/mL}$)	K-40	Sr-90	Cs-137
Beef Flesh Background (BFBCTRL 06/04)	75.0	-0.82 \pm 1.21E-07	1.39 \pm 0.12E-05	3.23 \pm 2.21E-09	1.15 \pm 1.55E-08
Beef Flesh Background (BFBCTRL 11/04)	76.4	-0.17 \pm 1.15E-07	1.15 \pm 0.07E-05	-0.10 \pm 1.38E-09	2.08 \pm 1.89E-08
Beef Flesh Near-Site (BFBNEAR 03/04)	69.8	-1.24 \pm 1.17E-07	7.63 \pm 0.81E-06	2.82 \pm 2.83E-09	1.58 \pm 1.57E-08
Beef Flesh Near-Site (BFBNEAR 09/04)	72.5	0.00 \pm 1.16E-07	1.07 \pm 0.07E-05	-1.23 \pm 1.44E-09	2.09 \pm 1.68E-08

2004 Radioactivity Concentrations in Venison

Location	% Moisture	H-3 ($\mu\text{Ci/mL}$)	K-40	Sr-90	Cs-137
Deer Flesh Background (BFDCTRL 12/04)	73.8	-0.64 \pm 1.12E-07	1.16 \pm 0.10E-05	-3.40 \pm 1.74E-09	6.08 \pm 2.73E-08
Deer Flesh Background (BFDCTRL 12/04)	73.3	-0.58 \pm 1.14E-07	1.14\pm0.10E-05	-1.01 \pm 2.32E-09	0.00 \pm 2.30E-08
Deer Flesh Background (BFDCTRL 12/04)	73.3	-0.07 \pm 1.15E-07	1.34\pm0.14E-05	-1.97 \pm 1.79E-09	6.15\pm3.99E-08
Deer Flesh Near-Site (BFDNEAR 10/04)	74.7	0.52 \pm 1.17E-07	1.13\pm0.11E-05	1.78 \pm 1.86E-09	3.68\pm0.48E-07
Deer Flesh Near-Site (BFDNEAR 10/04)	75.9	-0.18 \pm 1.03E-07	1.43\pm0.11E-05	1.85 \pm 2.42E-09	6.13 \pm 2.47E-08
Deer Flesh Near-Site (BFDNEAR 11/04)	73.0	-0.13 \pm 1.16E-07	1.23 \pm 0.10E-05	-1.06 \pm 1.33E-09	1.59\pm1.57E-08

Note: Bolding convention applied to venison data. See page F-2⁶⁰

Table F-3
2004 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Food Crops

Location	% Moisture	H-3 ($\mu\text{Ci/mL}$)	K-40	Co-60	Sr-90	Cs-137
<u>CORN</u>						
Background						
(BFVCTRC)	80.7	1.64 \pm 1.03E-07	1.37 \pm 0.11E-05	0.73 \pm 1.49E-08	0.25 \pm 2.64E-09	-0.82 \pm 1.27E-08
Near-Site						
(BFVNEAC)	80.6	1.45 \pm 0.88E-07	2.08 \pm 0.27E-05	-0.94 \pm 7.52E-08	-1.96 \pm 1.78E-09	1.72 \pm 8.40E-08
<u>BEANS</u>						
Background						
(BFVCTRB)	91.9	1.74 \pm 1.02E-07	3.14 \pm 0.31E-05	4.62 \pm 5.65E-08	1.13 \pm 0.10E-07	0.03 \pm 4.51E-08
Near-Site						
(BFVNEAB)	73.8	1.32 \pm 1.01E-07	1.38 \pm 0.13E-05	1.47 \pm 1.76E-08	7.86 \pm 0.75E-08	2.44 \pm 2.80E-08
<u>APPLES</u>						
Background						
(BFVCTRA)	86.0	1.41 \pm 1.22E-07	7.65 \pm 0.92E-06	1.62 \pm 5.59E-08	0.60 \pm 1.47E-09	-0.32 \pm 1.79E-08
Near-Site						
(BFVNEAAF)	81.4	2.18 \pm 1.43E-07	9.08 \pm 0.90E-06	-0.52 \pm 1.46E-08	-1.93 \pm 1.58E-09	-0.51 \pm 1.29E-08

Note: Bolding convention not applicable to these data.

Table F-4
2004 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Fish Flesh
From Cattaraugus Creek

Cattaraugus Creek above the Springville Dam (BFFCATC)

Annual 2004

Species	% Moisture	Sr-90	Cs-137
Hog-nosed Sucker	75.4	4.22±0.78E-08	3.25±3.72E-08
Hog-nosed Sucker	72.0	6.36±0.61E-08	3.79±6.41E-08
Hog-nosed Sucker	74.8	6.83±0.72E-08	2.16±4.03E-08
Hog-nosed Sucker	75.1	3.83±0.57E-08	1.06±4.18E-08
Hog-nosed Sucker	74.7	5.26±0.86E-08	1.34±4.34E-08
Bullhead	79.1	1.02±0.77E-08	6.31±5.00E-08
Hog-nosed Sucker	74.6	4.90±0.47E-08	-1.38±4.59E-08
Hog-nosed Sucker	76.5	2.33±0.54E-08	-1.12±4.52E-08
Hog-nosed Sucker	73.3	2.04±0.21E-08	2.03±2.59E-08
Hog-nosed Sucker	76.8	2.51±0.24E-08	0.00±8.45E-08
Average % Moisture	75.2		
Median		4.02E-08	<4.43E-08
Maximum		6.83E-08	6.31E-08
Minimum		1.02E-08	<2.59E-08

Cattaraugus Creek below the Springville Dam (BFFCATD)

Annual 2004

Species	% Moisture	Sr-90	Cs-137
Steelhead Trout	72.2	2.74±2.51E-09	1.55±2.83E-08
Steelhead Trout	75.1	5.20±2.38E-09	1.39±2.16E-08
Steelhead Trout	70.7	1.72±2.08E-09	0.00±3.60E-08
Steelhead Trout	71.6	6.16±2.46E-09	0.29±2.25E-08
Steelhead Trout	70.7	-1.45±1.32E-09	1.68±2.82E-08
Steelhead Trout	73.9	1.47±1.48E-09	0.10±1.04E-07
Steelhead Trout	72.5	1.75±1.37E-09	3.22±4.51E-08
Steelhead Trout	72.6	2.15±2.90E-09	3.43±2.46E-08
Steelhead Trout	70.5	-0.59±2.40E-09	0.58±2.81E-08
Chinook Salmon	78.3	-0.76±2.02E-09	0.00±2.43E-08
Average % Moisture	72.8		
Median		<2.24E-09	<2.82E-08
Maximum		6.16E-09	3.43E-08
Minimum		<1.32E-09	<2.16E-08

Note: Bolding convention applied to these data. See page F-2

Table F-4 (concluded)
2004 Radioactivity Concentrations ($\mu\text{Ci/g}$ - dry) in Fish Flesh
From Cattaraugus Creek

Cattaraugus Creek Background (BFFCTRL)

Annual 2004

Species	% Moisture	Sr-90	Cs-137
White Sucker	77.1	6.83±4.45E-09	1.58±5.61E-08
White Sucker	76.4	2.15±1.86E-09	0.00±1.46E-07
White Sucker	77.0	7.43±4.25E-09	-0.60±4.10E-08
White Sucker	75.4	2.55±2.03E-09	0.41±3.34E-08
White Sucker	78.2	8.27±3.53E-09	-0.96±4.42E-08
Hog-nosed Sucker	74.5	4.87±7.32E-09	-2.83±5.38E-08
Brown Trout	73.1	3.12±3.90E-09	5.57±9.57E-08
Brown Trout	71.2	0.86±3.82E-09	3.80±4.76E-08
Brown Trout	75.1	-0.22±4.41E-09	1.01±4.64E-08
Brown Trout	72.9	1.92±4.31E-09	1.55±4.11E-08
Average % Moisture	75.1		
Median		4.36E-09	<4.70E-08
Maximum		8.27E-09	<1.46E-07
Minimum		2.15E-09	<3.34E-08

Note: Bolding convention applied to these data. See page F-2

This page intentionally left blank

Appendix G-1
Summary of Soil and Aquatic Sediment
Guidelines and Standards

This page intentionally left blank

Table G-1A
Eastern U.S.A. Background Concentrations for Elements in Soils^a

Analyte	Units	Eastern U.S.A Background Concentrations for Soil
Aluminum	mg/kg (ppm)	33,000
Antimony	mg/kg (ppm)	--
Arsenic	mg/kg (ppm)	3–12 ^b
Barium	mg/kg (ppm)	15–600
Beryllium	mg/kg (ppm)	0–1.75
Cadmium	mg/kg (ppm)	0.1–1
Calcium	mg/kg (ppm)	130–35,000
Chromium	mg/kg (ppm)	1.5–40 ^b
Cobalt	mg/kg (ppm)	2.5–60 ^b
Copper	mg/kg (ppm)	1–50
Iron	mg/kg (ppm)	2,000–550,000
Lead	mg/kg (ppm)	4–61 ^c
Magnesium	mg/kg (ppm)	100–5,000
Manganese	mg/kg (ppm)	50–5,000
Mercury	mg/kg (ppm)	0.001–0.2
Nickel	mg/kg (ppm)	0.5–25
Potassium	mg/kg (ppm)	8,500–43,000 ^b
Selenium	mg/kg (ppm)	0.1–3.9
Silver	mg/kg (ppm)	--
Sodium	mg/kg (ppm)	6,000–8,000
Thallium	mg/kg (ppm)	--
Vanadium	mg/kg (ppm)	1–300
Zinc	mg/kg (ppm)	9–50

-- No reference level available for these analytes

^a Source: New York State Department of Environmental Conservation “Technical and Administrative Guidance Memorandum (TAGM) #4046”

^b New York State background

^c Background levels for lead vary widely. Average levels in undeveloped, rural areas may range from 4–61 ppm. Average background levels in metropolitan or suburban areas or near highways are much higher and typically range from 200–500 ppm.

Table G-1B
Screening Concentrations for Elements in Contaminated Sediments^a

Analyte	Units	Lowest Effect Level ^b	Severe Effect Level ^c
Aluminum	mg/kg (ppm)	--	--
Antimony	mg/kg (ppm)	2.0 (L)	25.0 (L)
Arsenic	mg/kg (ppm)	6.0 (P)	33.0 (P)
Barium	mg/kg (ppm)	--	--
Beryllium	mg/kg (ppm)	--	--
Cadmium	mg/kg (ppm)	0.6 (P)	9.0 (L)
Calcium	mg/kg (ppm)	--	--
Chromium	mg/kg (ppm)	26.0 (P)	110.0 (P)
Cobalt	mg/kg (ppm)	--	--
Copper	mg/kg (ppm)	16.0 (P)	110.0 (P)
Iron	%	2.0 (P)	4.0 (P)
Lead	mg/kg (ppm)	31.0 (P)	110.0 (L)
Magnesium	mg/kg (ppm)	--	--
Manganese	mg/kg (ppm)	460.0 (P)	1,100.0 (L)
Mercury	mg/kg (ppm)	0.15 (L)	1.3 (L)
Nickel	mg/kg (ppm)	16.0 (P)	50.0 (L)
Potassium	mg/kg (ppm)	--	--
Selenium	mg/kg (ppm)	--	--
Silver	mg/kg (ppm)	1.0 (L)	2.2 (L)
Sodium	mg/kg (ppm)	--	--
Thallium	mg/kg (ppm)	--	--
Vanadium	mg/kg (ppm)	--	--
Zinc	mg/kg (ppm)	120.0 (P/L)	270.0 (L)

-- No reference value available for these analytes

^a Source: New York State Department of Environmental Conservation "Technical Guidance for Screening Contaminated Sediments," January 1999

^b The Lowest Effect Level for each metal is the lowest of the either the Persaud et al. (1992) Lowest Effect Level or the Long and Morgan (1990) Effect Range-Low

^c The Severe Effect Level for each metal is the lowest of either the Persaud et al. (1992) Severe Effect Level or the Long and Morgan (1990) Effect Range-Moderate

L - An "L" following a criterion indicates that it was taken from Long and Morgan (1990).

P - A "P" following a criterion indicates that it was taken from Persaud et al. (1992).

Table G-1C
Elemental Screening Thresholds for In-Water and Riparian Management of Sediment and Dredge Material^a

Analyte	Units	No Appreciable Contamination Level
Arsenic	mg/kg (ppm)	14
Cadmium	mg/kg (ppm)	<1.2
Copper	mg/kg (ppm)	<33
Lead	mg/kg (ppm)	<33
Mercury	mg/kg (ppm)	0.17

^a Source: Draft New York State Department of Environmental Conservation Technical and Operational Guidance Series (TOGs) #5.1.9, "In-Water and Riparian Management of Sediment and Dredge Material"

Appendix G-2
Soil and Sediment Data

This page intentionally left blank

Table G-2A
2004 Contaminants in On-Site Soils Downstream of the WVDP at
Frank's Creek (SNSP006)

Analyte	Units	N	SNSP006	Guidance Values		
				Lowest Effect Level ^a	Severe Effect Level ^a	No Appreciable Contamination Level ^b
Gross Alpha	μCi/g	1	7.21±1.90E-06	--	--	--
Gross Beta	μCi/g	1	2.40±0.28E-05	--	--	--
K-40	μCi/g	1	1.55±0.13E-05	--	--	--
Co-60	μCi/g	1	0.28±1.42E-08	--	--	--
Sr-90	μCi/g	1	3.52±0.29E-07	--	--	--
Cs-137	μCi/g	1	5.22±0.49E-06	--	--	--
U-232	μCi/g	1	0.92±4.07E-08	--	--	--
U-233/234	μCi/g	1	5.53±1.48E-07	--	--	--
U-235/236	μCi/g	1	1.04±0.64E-07	--	--	--
U-238	μCi/g	1	5.56±1.46E-07	--	--	--
Total U	μg/g	1	2.29±0.03E+00	--	--	--
Pu-238	μCi/g	1	2.94±1.83E-08	--	--	--
Pu-239/240	μCi/g	1	5.64±7.67E-09	--	--	--
Am-241	μCi/g	1	3.20±2.94E-08	--	--	--
Aluminum	mg/kg	1	4,950	--	--	--
Antimony	mg/kg	1	<0.25	2.0	25.0	--
Arsenic	mg/kg	1	5.1	6.0	33.0	14
Barium	mg/kg	1	52.8	--	--	--
Beryllium	mg/kg	1	0.25	--	--	--
Cadmium	mg/kg	1	0.08	0.6	9.0	<1.2
Calcium	mg/kg	1	14,200	--	--	--
Chromium	mg/kg	1	7.0	26.0	110.0	--
Cobalt	mg/kg	1	7.6	--	--	--
Copper	mg/kg	1	12.0	16.0	110.0	<33
Iron	%	1	0.001	2.0	4.0	--
Lead	mg/kg	1	9.4	31.0	110.0	<33
Magnesium	mg/kg	1	5,425	--	--	--
Manganese	mg/kg	1	507	460.0	1,100.0	--
Mercury	mg/kg	1	<0.02	0.15	1.3	0.17
Nickel	mg/kg	1	15.0	16.0	50.0	--
Potassium	mg/kg	1	608	--	--	--
Selenium	mg/kg	1	<0.32	--	--	--
Silver	mg/kg	1	<0.06	1.0	2.2	--
Sodium	mg/kg	1	57.6	--	--	--
Thallium	mg/kg	1	<0.37	--	--	--
Vanadium	mg/kg	1	9	--	--	--
Zinc	mg/kg	1	42.6	120.0	270.0	--

Note: Effects of radiological soils and sediments are addressed with the evaluation of radiological dose to biota in Chapter 2.

N - Number of samples

-- No reference standard available

^a Screening guidelines for chemical constituents obtained from NYSDEC "Technical Guidance for Screening Contaminated Sediments"

^b NYSDEC: Draft Technical and Operational Guidance Series 5.1.9, "In-Water and Riparian Management of Sediment and Dredge Material," January 2003.

Table G-2B
2004 Contaminants in On-Site Soils From North Swamp (SNSW74A)

Analyte	Units	N	SNSW74A	Reference Value ^a
Gross Alpha	μCi/g	1	1.26±0.17E-05	--
Gross Beta	μCi/g	1	1.82±0.18E-05	--
K-40	μCi/g	1	1.43±0.12E-05	--
Co-60	μCi/g	1	1.18±1.73E-08	--
Sr-90	μCi/g	1	1.16±0.21E-07	--
Cs-137	μCi/g	1	1.05±0.12E-06	--
U-232	μCi/g	1	-0.88±1.39E-08	--
U-233/234	μCi/g	1	5.30±1.35E-07	--
U-235/236	μCi/g	1	8.91±5.68E-08	--
U-238	μCi/g	1	7.86±1.62E-07	--
Total U	μg/g	1	2.59±0.04E+00	--
Pu-238	μCi/g	1	-0.01±1.17E-08	--
Pu-239/240	μCi/g	1	1.94±1.38E-08	--
Am-241	μCi/g	1	2.22±1.27E-08	--
Aluminum	mg/kg	1	7,250	33,000
Antimony	mg/kg	1	<0.31	--
Arsenic	mg/kg	1	10.7	3–12 ^b
Barium	mg/kg	1	69.5	15–600
Beryllium	mg/kg	1	0.34	0–1.75
Cadmium	mg/kg	1	0.37	0.1–1
Calcium	mg/kg	1	45,300	130–35,000
Chromium	mg/kg	1	14.7	1.5–40 ^b
Cobalt	mg/kg	1	7.2	2.5–60 ^b
Copper	mg/kg	1	29.1	1–50
Iron	mg/kg	1	22,000	2,000–550,000
Lead	mg/kg	1	19.6	4–61 ^c
Magnesium	mg/kg	1	15,500	100–5,000
Manganese	mg/kg	1	917	50–5,000
Mercury	mg/kg	1	<0.02	0.001–0.2
Nickel	mg/kg	1	21.6	0.5–25
Potassium	mg/kg	1	916	8,500–43,000 ^b
Selenium	mg/kg	1	<0.39	0.1–3.9
Silver	mg/kg	1	<0.07	--
Sodium	mg/kg	1	184.0	6,000–8,000
Thallium	mg/kg	1	<0.46	--
Vanadium	mg/kg	1	13.7	1–300
Zinc	mg/kg	1	150.0	9–50

Note: Effects of radiological soils and sediments are addressed with the evaluation of radiological dose to biota in Chapter 2.

N - Number of samples

-- No reference standard available for these analytes

^a NYSDEC: Technical and Administrative Guidance Memorandum (TAGM) #4046.

^b New York State background

^c Background levels vary widely. Average levels in undeveloped rural areas may range from 4–61 ppm (reported here). Average background levels in metropolitan or suburban areas, or near highways are much higher and typically range from 200–500 ppm.

Table G-2C
2004 Contaminants in On-Site Soils From Northeast Swamp (SNSWAMP)

Analyte	Units	N	SNSWAMP	Reference Value ^a
Gross Alpha	μCi/g	1	1.32±0.17E-05	--
Gross Beta	μCi/g	1	5.43±0.25E-05	--
K-40	μCi/g	1	1.69±0.14E-05	--
Co-60	μCi/g	1	1.00±1.68E-08	--
Sr-90	μCi/g	1	2.82±0.12E-06	--
Cs-137	μCi/g	1	1.38±0.12E-05	--
U-232	μCi/g	1	-2.65±1.79E-08	--
U-233/234	μCi/g	1	8.85±1.58E-07	--
U-235/236	μCi/g	1	5.44±4.04E-08	--
U-238	μCi/g	1	8.92±1.57E-07	--
Total U	μg/g	1	4.26±0.10E+00	--
Pu-238	μCi/g	1	3.47±0.55E-07	--
Pu-239/240	μCi/g	1	4.68±0.63E-07	--
Am-241	μCi/g	1	9.90±1.69E-07	--
Aluminum	mg/kg	1	10,700	33,000
Antimony	mg/kg	1	0.26	--
Arsenic	mg/kg	1	10.6	3–12 ^b
Barium	mg/kg	1	73.9	15–600
Beryllium	mg/kg	1	0.51	0–1.75
Cadmium	mg/kg	1	0.11	0.1–1
Calcium	mg/kg	1	4,490	130–35,000
Chromium	mg/kg	1	14	1.5–40 ^b
Cobalt	mg/kg	1	9.2	2.5–60 ^b
Copper	mg/kg	1	23.7	1–50
Iron	mg/kg	1	24,300	2,000–550,000
Lead	mg/kg	1	21.9	4–61 ^c
Magnesium	mg/kg	1	4,460	100–5,000
Manganese	mg/kg	1	563	50–5,000
Mercury	mg/kg	1	0.04	0.001–0.2
Nickel	mg/kg	1	22.8	0.5–25
Potassium	mg/kg	1	1,230	8,500–43,000 ^b
Selenium	mg/kg	1	0.29	0.1–3.9
Silver	mg/kg	1	<0.05	--
Sodium	mg/kg	1	50.5	6,000–8,000
Thallium	mg/kg	1	<0.33	--
Vanadium	mg/kg	1	16.3	1–300
Zinc	mg/kg	1	92.4	9–50

Note: Effects of radiological soils and sediments are addressed with the evaluation of radiological dose to biota in Chapter 2.

N - Number of samples

-- No reference standard available for these analytes

^a NYSDEC: Technical and Administrative Guidance Memorandum (TAGM) #4046.

^b New York State background

^c Background levels vary widely. Average levels in undeveloped rural areas may range from 4–61 ppm (reported here). Average background levels in metropolitan or suburban areas, or near highways are much higher and typically range from 200–500 ppm.

Table G-2D
2004 Radioactivity in Surface Soils Collected at Air Stations Around the
WVDP

Analyte	Units	N	SFBOEHN	SFRSPRD	Background Location SFGRVAL
Gross Alpha	μCi/g	1	9.40±2.58E-06	9.86±2.75E-06	1.09±0.29E-05
Gross Beta	μCi/g	1	1.59±0.20E-05	1.54±0.19E-05	1.61±0.19E-05
K-40	μCi/g	1	1.52±0.10E-05	1.22±0.11E-05	1.17±0.10E-05
Co-60	μCi/g	1	0.02±1.66E-08	-0.28±1.96E-08	-0.53±1.63E-08
Sr-90	μCi/g	1	2.90±2.40E-08	8.47±2.30E-08	1.03±0.23E-07
Cs-137	μCi/g	1	3.86±0.39E-07	8.29±1.13E-07	6.21±0.70E-07
U-232	μCi/g	1	-0.52±2.16E-08	0.08±2.81E-08	0.58±2.24E-08
U-233/234	μCi/g	1	8.96±1.54E-07	8.56±1.58E-07	7.92±1.39E-07
U-235/236	μCi/g	1	6.98±4.57E-08	7.48±4.63E-08	8.35±4.64E-08
U-238	μCi/g	1	8.37±1.47E-07	8.69±1.58E-07	7.21±1.32E-07
Total U	μg/g	1	3.35±0.19E+00	3.71±0.21E+00	3.40±0.19E+00
Pu-238	μCi/g	1	0.37±1.17E-08	0.57±1.12E-08	2.82±2.61E-08
Pu-239/240	μCi/g	1	1.36±1.97E-08	0.43±1.15E-08	4.59±3.29E-08
Am-241	μCi/g	1	0.02±1.10E-08	1.33±2.61E-08	0.74±1.68E-08

Analyte	Units	N	SFFXVRD	SFRT240	Background Location SFGRVAL
Gross Alpha	μCi/g	1	1.29±0.30E-05	9.22±2.47E-06	1.09±0.29E-05
Gross Beta	μCi/g	1	1.61±0.21E-05	1.43±0.19E-05	1.61±0.19E-05
K-40	μCi/g	1	1.04±0.06E-05	1.20±0.09E-05	1.17±0.10E-05
Co-60	μCi/g	1	0.14±1.40E-08	0.22±1.47E-08	-0.53±1.63E-08
Sr-90	μCi/g	1	6.82±2.23E-08	7.37±2.46E-08	1.03±0.23E-07
Cs-137	μCi/g	1	5.22±0.35E-07	4.17±0.56E-07	6.21±0.70E-07
Pu-238	μCi/g	1	-0.42±1.23E-08	-0.42±1.23E-08	2.82±2.61E-08
Pu-239/240	μCi/g	1	0.88±1.66E-08	2.31±2.26E-08	4.59±3.29E-08
Am-241	μCi/g	1	4.43±3.41E-08	2.06±2.51E-08	0.74±1.68E-08

N - Number of samples

Table G-2D (concluded)
2004 Radioactivity in Surface Soils Collected at Air Stations Around the
WVDP

Analyte	Units	N	SFSPRVL	SFTCORD	Background Location SFGRVAL
Gross Alpha	μCi/g	1	1.57±0.31E-05	1.11±0.33E-05	1.09±0.29E-05
Gross Beta	μCi/g	1	1.75±0.20E-05	2.60±0.24E-05	1.61±0.19E-05
K-40	μCi/g	1	1.26±0.05E-05	2.11±0.16E-05	1.17±0.10E-05
Co-60	μCi/g	1	0.44±1.22E-08	-0.50±1.54E-08	-0.53±1.63E-08
Sr-90	μCi/g	1	8.91±2.48E-08	1.31±0.25E-07	1.03±0.23E-07
Cs-137	μCi/g	1	3.90±0.26E-07	2.96±0.35E-07	6.21±0.70E-07
Pu-238	μCi/g	1	-0.13±1.10E-08	-0.30±1.29E-08	2.82±2.61E-08
Pu-239/240	μCi/g	1	0.96±1.54E-08	2.05±2.50E-08	4.59±3.29E-08
Am-241	μCi/g	1	2.02±2.51E-08	3.02±2.08E-08	0.74±1.68E-08
Analyte	Units	N	SFBLKST	SFWEVAL	Background Location SFGRVAL
Gross Alpha	μCi/g	1	1.50±0.34E-05	1.19±0.29E-05	1.09±0.29E-05
Gross Beta	μCi/g	1	1.86±0.22E-05	1.37±0.19E-05	1.61±0.19E-05
K-40	μCi/g	1	1.92±0.08E-05	1.32±0.11E-05	1.17±0.10E-05
Co-60	μCi/g	1	0.19±1.84E-08	-0.12±1.52E-08	-0.53±1.63E-08
Sr-90	μCi/g	1	1.88±2.27E-08	1.88±0.68E-07	1.03±0.23E-07
Cs-137	μCi/g	1	1.44±0.33E-07	2.66±0.38E-07	6.21±0.70E-07
Pu-238	μCi/g	1	0.44±1.18E-08	-0.57±1.29E-08	2.82±2.61E-08
Pu-239/240	μCi/g	1	0.44±1.18E-08	1.64±2.03E-08	4.59±3.29E-08
Am-241	μCi/g	1	0.73±1.07E-08	-0.36±1.57E-08	0.74±1.68E-08

N - Number of samples

Table G-2E
2004 Radioactivity in Stream Sediments Around the WVDP

Analyte	Units	N	SFCCSED	SFSDSED	Background Location SFBISED
Gross Alpha	μCi/g	1	6.87±2.94E-06	1.36±0.34E-05	9.37±2.66E-06
Gross Beta	μCi/g	1	1.37±0.21E-05	1.98±0.24E-05	1.31±0.20E-05
K-40	μCi/g	1	1.18±0.09E-05	1.67±0.13E-05	1.23±0.09E-05
Co-60	μCi/g	1	0.28±1.56E-08	0.29±1.60E-08	0.35±6.22E-09
Sr-90	μCi/g	1	1.88±3.08E-08	4.07±4.19E-08	3.10±4.21E-08
Cs-137	μCi/g	1	1.14±0.27E-07	5.09±2.24E-08	2.47±1.05E-08
U-232	μCi/g	1	-0.20±3.00E-08	-0.57±2.71E-08	1.24±3.55E-08
U-233/234	μCi/g	1	5.48±1.30E-07	7.64±1.57E-07	6.06±1.32E-07
U-235/236	μCi/g	1	7.65±4.81E-08	6.48±4.65E-08	6.07±4.65E-08
U-238	μCi/g	1	5.40±1.29E-07	7.74±1.57E-07	6.34±1.34E-07
Total U	μg/g	1	1.62±0.02E+00	2.63±0.04E+00	1.27±0.01E+00
Pu-238	μCi/g	1	-0.16±1.12E-08	0.19±1.41E-08	-3.08±4.27E-09
Pu-239/240	μCi/g	1	0.22±1.12E-08	-0.16±1.34E-08	0.64±1.26E-08
Am-241	μCi/g	1	0.08±1.74E-08	-0.20±1.35E-08	-1.09±1.68E-08

Analyte	Units	N	SFTCSSED	--	Background Location SFBCSSED
Gross Alpha	μCi/g	1	7.98±3.24E-06	--	7.99±2.88E-06
Gross Beta	μCi/g	1	2.04±0.24E-05	--	1.51±0.20E-05
K-40	μCi/g	1	1.17±0.06E-05	--	1.25±0.11E-05
Co-60	μCi/g	1	-0.42±1.48E-08	--	1.84±9.37E-09
Sr-90	μCi/g	1	8.26±4.48E-08	--	4.76±2.45E-08
Cs-137	μCi/g	1	6.48±0.37E-07	--	3.13±1.49E-08
U-232	μCi/g	1	-1.70±2.07E-08	--	-3.18±4.87E-09
U-233/234	μCi/g	1	6.49±1.35E-07	--	7.59±1.45E-07
U-235/236	μCi/g	1	4.48±4.03E-08	--	9.29±5.05E-08
U-238	μCi/g	1	7.69±1.47E-07	--	8.53±1.53E-07
Total U	μg/g	1	2.07±0.03E+00	--	2.11±0.02E+00
Pu-238	μCi/g	1	-0.15±1.27E-08	--	1.39±2.23E-08
Pu-239/240	μCi/g	1	-0.30±1.30E-08	--	-0.19±1.59E-08
Am-241	μCi/g	1	2.08±2.16E-08	--	0.47±1.19E-08

N - Number of samples

-- Not applicable; no additional sampling location

Table G-2F
2004 Contaminants in Rail Bed Soil Material

Analyte	Units	N	Maximum	Allowable Soil Concentration Reference Value ^a	Soil Cleanup Objectives to Protect Groundwater Quality Reference Value ^a
Am-241	µCi/g	9	<6.85E-08	--	--
Cs-137	µCi/g	9	8.52±2.59E-08	--	--
2,3,7,8-TCDD Dioxin	mg/kg	9	<0.000026	0.0006	0.06
2,4,5-T	mg/kg	9	<0.0043	0.019	1.9
2,4-D	mg/kg	9	<0.0046	0.005	0.5
alpha BHC	mg/kg	9	<0.000460	0.002	0.2
Anthracene	mg/kg	9	<0.160	7.0	700.0
Benzene	mg/kg	9	<0.001	0.0006	0.06
beta BHC	mg/kg	9	<0.00023	0.002	0.2
delta BHC	mg/kg	9	<0.00046	0.003	0.3
Ethyl benzene	mg/kg	9	<0.0008	0.055	5.5
gamma BHC (Lindane)	mg/kg	9	<0.000460	0.0006	0.06
Heptachlor	mg/kg	9	<0.000250	0.0010	0.1
Heptachlor epoxide	mg/kg	9	<0.000200	0.0002	0.02
Lead, total	mg/kg	9	18.8	4-61 ^b	4-61 ^b
Naphthalene	mg/kg	9	<0.130	0.130	13.0
o-Cresol (2-methylphenol)	mg/kg	9	<0.100	0.001	0.1
PCB-1016	mg/kg	9	<2.0	0.1	10
PCB-1221	mg/kg	9	<2.0	0.1	10
PCB-1232	mg/kg	9	<2.0	0.1	10
PCB-1242	mg/kg	9	<2.0	0.1	10
PCB-1248	mg/kg	9	<2.0	0.1	10
PCB-1254	mg/kg	9	<2.0	0.1	10
PCB-1260	mg/kg	9	<2.0	0.1	10
Total TCDD	mg/kg	9	<0.000026	0.0006	0.06
p-Cresol (4-methylphenol)	mg/kg	9	<0.130	0.009	0.9
Pentachlorophenol (8151)	mg/kg	9	<0.0045	0.01	1.0
Pentachlorophenol (8270)	mg/kg	9	<0.800	0.01	1.0
Silvex (2,4,5-TP)	mg/kg	9	<0.0540	0.007	0.7
Toluene	mg/kg	9	0.02	0.015	1.5
Xylene (Total)	mg/kg	9	<0.004	0.012	1.2

N - Number of samples

-- No reference standard available

^a NYSDEC: Technical Administrative Guidance Memorandum (TAGM) 4046

^b Background levels vary widely. Average levels in undeveloped, rural areas may range from 4–61 ppm (reported here). Average background levels in metropolitan or suburban areas, or near highways are much higher and typically range from 200–500 ppm.

This page intentionally left blank

Appendix H

Summary of Direct Radiation Monitoring Data

This page intentionally left blank

Table H-1
Summary of 2004 Quarterly Averages of Off-Site TLD Measurements
(mR±2 SD/quarter)

Location Number*	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	Location Average
DFTLD01	17±4	20±4	15±4	17±4	17±4
DFTLD02	17±4	22±5	15±4	18±4	18±4
DFTLD03	15±3	17±4	12±3	16±4	15±4
DFTLD04	16±4	19±4	14±4	19±4	17±4
DFTLD05	17±4	19±4	14±4	17±4	17±4
DFTLD06	16±4	19±4	13±4	16±4	16±4
DFTLD07	14±3	17±4	11±3	12±3	13±3
DFTLD08	16±4	21±5	15±4	18±4	17±4
DFTLD09	16±4	20±4	14±4	16±4	16±4
DFTLD10	15±3	18±4	14±4	17±4	16±4
DFTLD11	15±3	18±4	12±3	14±4	15±4
DFTLD12	17±4	20±4	14±4	17±4	17±4
DFTLD13	17±4	21±5	16±4	17±4	18±4
DFTLD14	17±4	20±4	14±4	16±4	17±4
DFTLD15	15±3	NA	14±4	16±4	15±3
DFTLD16	16±4	19±4	14±4	16±4	16±4
DFTLD20	14±3	18±4	10±3	13±3	14±3
DFTLD21	18±4	21±4	14±4	17±4	17±4
DFTLD22	17±4	21±5	15±4	18±4	18±4
DFTLD23	17±4	19±4	14±4	19±4	17±4

NA - Not available; TLD card missing second quarter of 2004.

* Off-site locations are shown on Figures A-11, A-12, and A-13.

Conversion factor: Milliroentgen (mR) units are used to report exposure rates in air. To convert mR to mrem (dose to humans), a conversion factor of 1.03 must be applied. For example, a reported exposure rate of 18.1 mR/quarter would be equivalent to 18.6 mrem/quarter (based upon dose-equivalent phantom calibration using cesium-137).

Table H-2
Summary of 2004 Quarterly Averages of On-Site TLD Measurements
(mR±2SD/quarter)

Location Number*	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	Location Average
DNTLD18	26±5	30±6	24±5	27±6	27±6
DNTLD19	18±4	22±5	17±4	19±4	19±4
DNTLD24	471±92	473±93	484±95	472±93	475±93
DNTLD25	20±4	24±5	21±5	23±5	22±5
DNTLD26	19±4	25±5	19±4	20±5	21±5
DNTLD27	17±4	20±4	14±4	19±4	18±4
DNTLD28	18±4	22±5	17±4	20±5	20±4
DNTLD29	19±4	24±5	18±4	22±5	20±4
DNTLD30	20±4	24±5	19±5	23±5	21±5
DNTLD31	17±4	21±4	15±4	17±4	17±4
DNTLD32	27±5	21±5	24±5	26±6	24±5
DNTLD33	27±5	31±6	25±5	28±6	28±6
DNTLD34	45±9	49±10	42±9	47±9	46±9
DNTLD35	65±13	71±14	58±12	53±11	62±12
DNTLD36	33±7	22±5	29±6	45±9	32±7
DNTLD38	30±6	35±7	29±6	55±11	37±8
DNTLD39	41±8	50±10	49±10	50±10	48±10
DNTLD40	105±21	117±23	115±23	112±22	112±22
DNTLD42	75±15	73±14	68±14	68±14	71±14
DNTLD43	26±5	30±6	23±5	26±6	26±5

* On-site locations are shown on Figure A-10.

Conversion factor: Milliroentgen (mR) units are used to report exposure rates in air. To convert mR to mrem (dose to humans), a conversion factor of 1.03 must be applied. For example, a reported exposure rate of 18.1 mR/quarter would be equivalent to 18.6 mrem/quarter (based upon dose-equivalent phantom calibration using cesium-137).

Table H-3
Third-Quarter 2004 TLD Results and Instantaneous Exposure Rate Readings
($\mu\text{R/hr}$) With a High-Pressure Ion Chamber (HPIC) at Each Monitoring
Location

Off-Site Location Number	3rd-Quarter TLD Result	3rd-Quarter HPIC Result	On-Site Location Number	3rd-Quarter TLD Result	3rd-Quarter HPIC Result
DFTLD01	6.8	9.5	DNTLD18	11.0	13.7
DFTLD02	7.1	9.5	DNTLD19	7.9	9.5
DFTLD03	5.3	8.3	DNTLD24	221.6	303.9
DFTLD04	6.4	8.1	DNTLD25	9.8	11.3
DFTLD05	6.5	8.9	DNTLD26	8.6	10.7
DFTLD06	5.9	9.1	DNTLD27	6.6	8.6
DFTLD07	4.9	8.9	DNTLD28	7.8	9.1
DFTLD08	6.7	8.6	DNTLD29	8.0	9.6
DFTLD09	6.3	9.0	DNTLD30	8.8	11.6
DFTLD10	6.3	8.8	DNTLD31	6.7	8.0
DFTLD11	5.3	8.7	DNTLD32	10.9	14.9
DFTLD12	6.2	8.9	DNTLD33	11.3	13.3
DFTLD13	7.4	8.7	DNTLD34	19.1	23.0
DFTLD14	6.6	8.7	DNTLD35	26.6	36.9
DFTLD15	6.3	8.6	DNTLD36	13.0	17.8
DFTLD16	6.3	8.6	DNTLD38	13.2	16.9
DFTLD20	4.7	8.9	DNTLD39	22.6	24.9
DFTLD21	6.6	9.1	DNTLD40	52.7	54.5
DFTLD22	6.8	9.3	DNTLD42	31.2	26.2
DFTLD23	6.4	8.9	DNTLD43	10.3	11.9




Figure H-1. 2004 Average Yearly Gamma Exposure Rates Around the WVDP





Figure H-2. 2004 Average Yearly Gamma Exposure Rates on the WVDP

Appendix I

Summary of Meteorological Data

This page intentionally left blank




NUMBERS INDICATE SECTOR MEAN WIND SPEED
SECTORS ARE DIRECTIONS FROM WHICH THE WIND IS BLOWING


WIND SPEED RANGE (M/SEC)

- 0.5 - 3.0
- ▨ 3.0 - 6.0
- ▧ 6.0 - 9.0
- ▩ 9.0 - 15.0
- ▤ > 15.0

WEST VALLEY NUCLEAR SERVICES
REGIONAL MONITORING STATION
WEST VALLEY, NEW YORK

FIGURE I-1
10.0-METER WIND FREQUENCY ROSE
JANUARY 1, 2004 - DECEMBER 31, 2004








Figure I-4. Calendar Year 2004 Weekly Precipitation




Figure I-5. Calendar Year 2004 Cumulative Precipitation

Table I-1
2004 Site Precipitation Collection Data

Week Ending:	Weekly		Cumulative		Week Ending:	Weekly		Cumulative	
	(cm)	(inches)	(cm)	(inches)		(cm)	(inches)	(cm)	(inches)
Jan 02	0.51	0.20	0.51	0.20	Jul 02	0.61	0.24	48.31	19.02
Jan 09	1.98	0.78	2.49	0.98	Jul 09	4.52	1.78	52.83	20.80
Jan 16	1.65	0.65	4.14	1.63	Jul 16	6.96	2.74	59.79	23.54
Jan 23	1.45	0.57	5.59	2.20	Jul 23	1.93	0.76	61.72	24.30
Jan 30	1.19	0.47	6.78	2.67	Jul 30	1.19	0.47	62.92	24.77
Feb 06	1.07	0.42	7.85	3.09	Aug 06	1.32	0.52	64.24	25.29
Feb 13	0.53	0.21	8.38	3.30	Aug 13	1.24	0.49	65.48	25.78
Feb 20	0.46	0.18	8.84	3.48	Aug 20	0.94	0.37	66.42	26.15
Feb 27	1.45	0.57	10.29	4.05	Aug 27	0.74	0.29	67.16	26.44
Mar 05	1.09	0.43	11.38	4.48	Sep 03	2.95	1.16	70.10	27.60
Mar 12	1.35	0.53	12.73	5.01	Sep 10	10.03	3.95	80.14	31.55
Mar 19	0.94	0.37	13.67	5.38	Sep 17	6.45	2.54	86.59	34.09
Mar 26	2.95	1.16	16.61	6.54	Sep 24	0.00	0.00	86.59	34.09
Apr 02	3.15	1.24	19.76	7.78	Oct 01	0.00	0.00	86.59	34.09
Apr 09	1.09	0.43	20.85	8.21	Oct 08	0.36	0.14	86.94	34.23
Apr 16	3.84	1.51	24.69	9.72	Oct 15	0.15	0.06	87.10	34.29
Apr 23	1.35	0.53	26.04	10.25	Oct 22	4.37	1.72	91.47	36.01
Apr 30	0.66	0.26	26.70	10.51	Oct 29	0.61	0.24	92.08	36.25
May 07	1.91	0.75	28.60	11.26	Nov 05	3.35	1.32	95.43	37.57
May 14	3.38	1.33	31.98	12.59	Nov 12	0.03	0.01	95.45	37.58
May 21	2.44	0.96	34.42	13.55	Nov 19	0.20	0.08	95.66	37.66
May 28	8.69	3.42	43.10	16.97	Nov 26	1.78	0.70	97.43	38.36
Jun 04	0.97	0.38	44.07	17.35	Dec 03	4.34	1.71	101.78	40.07
Jun 11	0.10	0.04	44.17	17.39	Dec 10	0.99	0.39	102.77	40.46
Jun 18	2.18	0.86	46.36	18.25	Dec 17	2.67	1.05	105.44	41.51
Jun 25	1.35	0.53	47.70	18.78	Dec 24	3.58	1.41	109.02	42.92
					Dec 31	0.74	0.29	109.75	43.21

This page intentionally left blank

Appendix J
Summary of Quality Assurance Crosscheck Analyses

This page intentionally left blank

Table J-1
Crosscheck Sample Comparisons From the DOE Environmental
Measurements Laboratory (EML) Quality Assessment Program (QAP) 60;
QAP 0403; June 2004

Analyte	Matrix	Units	Actual	Reported	Ratio	Accept?	Analyzed by:
Co-60	Air filter	Bq/filter	35.4	36.3	1.025	Yes	ELAB
Co-60	Air filter	Bq/filter	35.4	36.4	1.028	Yes	ELAB
Cs-137	Air filter	Bq/filter	26.4	27.8	1.053	Yes	ELAB
Cs-137	Air filter	Bq/filter	26.4	27.7	1.049	Yes	ELAB
Gross Alpha	Air filter	Bq/filter	1.2	1.16	0.967	Yes	ELAB
Gross Beta	Air filter	Bq/filter	2.85	2.92	1.025	Yes	ELAB
Am-241	Air filter	Bq/filter	0.1045	0.093	0.890	Yes	GEL
Co-60	Air filter	Bq/filter	35.4	35.754	1.010	Yes	GEL
Cs-137	Air filter	Bq/filter	26.4	26.369	0.999	Yes	GEL
Gross Alpha	Air filter	Bq/filter	1.2	1.181	0.984	Yes	GEL
Gross Beta	Air filter	Bq/filter	2.85	2.326	0.816	Yes	GEL
Pu-238	Air filter	Bq/filter	0.0405	0.038	0.938	Pass	GEL
Pu-239	Air filter	Bq/filter	0.1644	0.157	0.955	Yes	GEL
Sr-90	Air filter	Bq/filter	1.76	1.72	0.977	Yes	GEL
U-234	Air filter	Bq/filter	0.0858	0.079	0.921	Yes	GEL
U-238	Air filter	Bq/filter	0.085	0.075	0.882	Pass	GEL
U (total)	Air filter	µg/filter	6.873	6.7	0.975	Yes	GEL
Am-241	Soil	Bq/kg	13.0	12.925	0.994	Yes	GEL
Cs-137	Soil	Bq/kg	1,323.0	1,411.797	1.067	Yes	GEL
K-40	Soil	Bq/kg	539.0	616.667	1.144	Yes	GEL
Pu-238	Soil	Bq/kg	0.82	0.772	0.941	Yes	GEL
Pu-239	Soil	Bq/kg	22.82	22.336	0.979	Yes	GEL
Sr-90	Soil	Bq/kg	51.0	49.765	0.976	Yes	GEL
Th-234	Soil	Bq/kg	84.0	97.446	1.160	Yes	GEL
U-234	Soil	Bq/kg	87.22	77.33	0.887	Yes	GEL
U-238	Soil	Bq/kg	89.73	86.58	0.965	Yes	GEL
U (total)	Soil	µg/g	7.25	6.763	0.933	Yes	GEL

ELAB - Environmental Laboratory

GEL - General Engineering Laboratory

Note: This report has been excerpted to include only those matrix/analyte combinations performed in support of the analyses of samples collected at the WVDP and which are presented in this Annual Site Environmental Report.

Acceptance is based on the reported-to-actual ratio, assigned statistically on a case-by-case basis. Yes indicates a ratio within warning limits. Pass indicates a ratio within control limits but outside warning limits. No indicates a ratio outside control limits.

Table J-1 (concluded)
Crosscheck Sample Comparisons From the DOE Environmental
Measurements Laboratory (EML) Quality Assessment Program (QAP) 60;
QAP 0403; June 2004

Analyte	Matrix	Units	Actual	Reported	Ratio	Accept?	Analyzed by:
Am-241	Veg	Bq/kg	4.93	4.415	0.896	Yes	GEL
Co-60	Veg	Bq/kg	14.47	15.873	1.097	Yes	GEL
Cs-137	Veg	Bq/kg	584.67	649.967	1.112	Yes	GEL
K-40	Veg	Bq/kg	720.0	830.033	1.153	Yes	GEL
Pu-238	Veg	Bq/kg	0.455	0.545	1.198	Yes	GEL
Pu-239	Veg	Bq/kg	6.81	6.475	0.951	Yes	GEL
Sr-90	Veg	Bq/kg	734.0	852.702	1.162	Pass	GEL
Co-60	Water	Bq/L	163.2	158.0	0.968	Yes	ELAB
Cs-137	Water	Bq/L	51.95	52.4	1.009	Yes	ELAB
Gross Alpha	Water	Bq/L	326.0	299.0	0.917	Yes	ELAB
Gross Beta	Water	Bq/L	1,170.0	1,242.0	1.062	Yes	ELAB
H-3	Water	Bq/L	186.6	230.0	1.233	Yes	ELAB
Sr-90	Water	Bq/L	4.76	5.06	1.063	Yes	ELAB
Am-241	Water	Bq/L	1.31	1.127	0.860	Pass	GEL
Co-60	Water	Bq/L	163.2	157.867	0.967	Yes	GEL
Cs-137	Water	Bq/L	51.95	50.69	0.976	Yes	GEL
Gross Alpha	Water	Bq/L	326.0	336.763	1.033	Yes	GEL
Gross Beta	Water	Bq/L	1,170.0	1,157.069	0.989	Yes	GEL
H-3	Water	Bq/L	186.6	202.991	1.088	Yes	GEL
Pu-238	Water	Bq/L	1.1	1.023	0.930	Yes	GEL
Pu-239	Water	Bq/L	3.08	2.884	0.936	Yes	GEL
Sr-90	Water	Bq/L	4.76	5.144	1.081	Yes	GEL
U-234	Water	Bq/L	2.28	2.199	0.964	Yes	GEL
U-238	Water	Bq/L	2.25	2.188	0.972	Yes	GEL
U (total)	Water	µg/mL	0.182	0.1927	1.059	Yes	GEL

ELAB - Environmental Laboratory

GEL - General Engineering Laboratory

Note: This report has been excerpted to include only those matrix/analyte combinations performed in support of the analyses of samples collected at the WVDP and which are presented in this Annual Site Environmental Report.

Acceptance is based on the reported-to-actual ratio, assigned statistically on a case-by-case basis. Yes indicates a ratio within warning limits. Pass indicates a ratio within control limits but outside warning limits. No indicates a ratio outside control limits

Table J-2
Crosscheck Sample Comparisons From the DOE Mixed Analyte Performance
Evaluation Program (MAPEP)^a; May 2004

Analyte	Matrix	Units	Actual	Reported	Acceptance Range	Accept?	Analyzed by:
MAPEP - 03 - W11							
Antimony	Water	mg/L	0.1296	0.121	0.09–0.17	Yes	LVLI
Arsenic	Water	mg/L	0.0537	0.0456	0.04–0.07	Yes	LVLI
Barium	Water	mg/L	0.541	0.523	0.38–0.70	Yes	LVLI
Beryllium	Water	mg/L	0.0985	0.0914	0.07–0.13	Yes	LVLI
Cadmium	Water	mg/L	0.0799	0.0749	0.06–0.10	Yes	LVLI
Copper	Water	mg/L	0.803	0.751	0.56–1.04	Yes	LVLI
Lead	Water	mg/L	0.894	0.844	0.63–1.16	Yes	LVLI
Nickel	Water	mg/L	0.495	0.467	0.35–0.64	Yes	LVLI
Selenium	Water	mg/L	0.06981	0.0654	0.05–0.09	Yes	LVLI
Silver	Water	mg/L	--	0.00084	--	Yes ^b	LVLI
Thallium	Water	mg/L	2.088	1.98	1.46–2.71	Yes	LVLI
Vanadium	Water	mg/L	1.2	1.13	0.84–1.56	Yes	LVLI
Zinc	Water	mg/L	1.037	0.965	0.73–1.35	Yes	LVLI
1,3-Dichlorobenzene	Water	µg/L	39.6	43	14.00–65.16	Yes	LVLI
1,2-Dichlorobenzene	Water	µg/L	22.7	25	9.45–36.03	Yes	LVLI
2,4-Dimethylphenol	Water	µg/L	79.2	79	40.94–117.57	Yes	LVLI
2,4-Dichlorophenol	Water	µg/L	73.1	74	30.38–115.76	Yes	LVLI
1,2,4-Trichlorobenzene	Water	µg/L	41.4	49	0.53–82.22	Yes	LVLI
Napthalene	Water	µg/L	48.2	53	11.02–85.43	Yes	LVLI
4-Chloro-3-methylphenol	Water	µg/L	30.5	33	14.05–46.97	Yes	LVLI
2-Methylphenol	Water	µg/L	45.4	51	15.37–75.49	Yes	LVLI
2,6-Dichlorophenol	Water	µg/L	55.7	60	18.03–93.29	Yes	LVLI
2,6-Dinitrotoluene	Water	µg/L	74.1	69	44.30–103.91	Yes	LVLI
2,4-Dinitrotoluene	Water	µg/L	91.8	110	46.77–136.82	Yes	LVLI
Fluorene	Water	µg/L	28.9	37	QL–85.38	Yes	LVLI
Diethylphthalate	Water	µg/L	61.9	60	26.41–97.43	Yes	LVLI
Phenanthrene	Water	µg/L	23.2	27	QL–49.06	Yes	LVLI
Anthracene	Water	µg/L	35.4	39	QL–78.28	Yes	LVLI
Pyrene	Water	µg/L	35	49	QL–110.01	Yes	LVLI
Benzo(a)anthracene	Water	µg/L	62.1	66	4.91–119.29	Yes	LVLI
Chrysene	Water	µg/L	41.1	46	QL–84.03	Yes	LVLI

LVLI - Lionville Laboratories, Inc.

QL - Quantitation limit

^a MAPEP monitors performance and requests corrective action as required.

^b Although no actual values or acceptable range was provided, the results were assessed by MAPEP as acceptable.

Note: This report has been excerpted to include only those matrix/analyte combinations performed in support of the analyses of samples collected at the WVDP and which are presented in this Annual Site Environmental Report.

Table J-2 (concluded)
Crosscheck Sample Comparisons From the DOE Mixed Analyte Performance
Evaluation Program (MAPEP)^a; May 2004

Analyte	Matrix	Units	Actual	Reported	Acceptance Range	Accept?	Analyzed by:
MAPEP - 03 - W11							
Am-241	Water	Bq/L	--	0.008	--	Yes ^b	GEL
Cs-137	Water	Bq/L	124	118.6	86.80–161.20	Yes	GEL
Co-60	Water	Bq/L	121.8	122.3	85.26–158.34	Yes	GEL
H-3	Water	Bq/L	379	389.7	265.30–492.70	Yes	GEL
Pu-238	Water	Bq/L	1.49	1.364	1.04–1.94	Yes	GEL
Pu-239/240	Water	Bq/L	2.39	2.232	1.67–3.11	Yes	GEL
Sr-90	Water	Bq/L	17.7	17.132	12.39–23.01	Yes	GEL
Tc-99	Water	Bq/L	28.8	23.96	20.16–37.44	Yes	GEL
U-233/234	Water	Bq/L	2.35	2.305	1.64–3.05	Yes	GEL
U-238	Water	Bq/L	2.43	2.184	1.70–3.16	Yes	GEL

GEL - General Engineering Laboratories

^a MAPEP monitors performance and requests corrective action as required.

^b Although no actual values or acceptable range was provided, the results were assessed by MAPEP as acceptable.

Note: This report has been excerpted to include only those matrix/analyte combinations performed in support of the analyses of samples collected at the WVDP and which are presented in this Annual Site Environmental Report.

Table J-3
Crosscheck Sample Comparisons From the DOE Mixed Analyte Performance
Evaluation Program (MAPEP)^a; November 2004

Analyte	Matrix	Units	Actual	Reported	Acceptance Range	Accept?	Analyzed by:
MAPEP - 04 - GrF12 Gross Alpha/Beta Air Filter							
Gross Alpha	Air Filter	Bq/filter	0.37	0.123	>0.0-0.8	Yes	ELAB
Gross Beta	Air Filter	Bq/filter	1.21	1.25	0.6-1.8	Yes	ELAB
MAPEP - 04 - GrW12 Gross Alpha/Beta Water Standard							
Gross Alpha	Water	Bq/L	1.24	0.699	0.0-2.5	Yes	ELAB
Gross Beta	Water	Bq/L	4.07	4.01	2.0-6.2	Yes	ELAB
Gross Alpha	Water	Bq/L	1.24	0.949	0.0-2.5	Yes	GEL
Gross Beta	Water	Bq/L	4.07	4.172	2.0-6.2	Yes	GEL
MAPEP - 04 - MaS12 Soil Standard							
Antimony	Soil	mg/kg	47.1	25.9	33.00-61.20	No	LVLI
Arsenic	Soil	mg/kg	63	60.3	44.10-81.90	Yes	LVLI
Barium	Soil	mg/kg	559.7	557	391.79-727.61	Yes	LVLI
Beryllium	Soil	mg/kg	18.83	17.9	13.18-24.48	Yes	LVLI
Cadmium	Soil	mg/kg	10.03	9.4	7.02-13.04	Yes	LVLI
Chromium	Soil	mg/kg	67	77.0	46.90-87.10	Yes	LVLI
Lead	Soil	mg/kg	62.4	59.8	43.68-81.12	Yes	LVLI
Nickel	Soil	mg/kg	113	111	79.10-146.90	Yes	LVLI
Selenium	Soil	mg/kg	9.09	8.4	6.36-11.82	Yes	LVLI
Silver	Soil	mg/kg	19.8	19.3	13.86-25.74	Yes	LVLI
Thallium	Soil	mg/kg	88.6	84.2	62.02-115.18	Yes	LVLI
Vanadium	Soil	mg/kg	60.8	63.8	42.56-79.04	Yes	LVLI
Zinc	Soil	mg/kg	146	151	102.20-189.80	Yes	LVLI
Am-241	Soil	Bq/kg	67	67.35	46.88-87.06	Yes	GEL
Cs-137	Soil	Bq/kg	836	774.040	585.34-1,087.06	Yes	GEL
Co-60	Soil	Bq/kg	518	510.353	362.60-673.40	Yes	GEL
Pu-238	Soil	Bq/kg	35.4	32.8	24.78-46.02	Yes	GEL
Pu-239/240	Soil	Bq/kg	41.8	3.067	29.27-54.35	No	GEL
K-40	Soil	Bq/kg	604	640.717	422.80-785.20	Yes	GEL
Sr-90	Soil	Bq/kg	^b	1.21	--	No ^c	GEL
U-233/234	Soil	Bq/kg	37	24.691	25.90-48.10	No	GEL
U-238	Soil	Bq/kg	38.9	30.759	27.19-50.50	Yes ^d	GEL

ELAB - Environmental Laboratory

GEL - General Engineering Laboratories

LVLI - Lionville Laboratories, Inc.

^a MAPEP monitors performance and requests corrective action as required.

^b False positive

^c Although no actual values or acceptable range was provided, the results were assessed by MAPEP as not acceptable.

^d Result acceptable with warning 20% < bias <= 30%

Note: This report has been excerpted to include only those matrix/analyte combinations performed in support of the analyses of samples collected at the WVDP and which are presented in this Annual Site Environmental Report.

Table J-3 (continued)
Crosscheck Sample Comparisons From the DOE Mixed Analyte Performance
Evaluation Program (MAPEP)^a; November 2004

Analyte	Matrix	Units	Actual	Reported	Acceptance Range	Accept?	Analyzed by:
MAPEP - 04 - MaW12 Water Standard							
Antimony	Water	mg/L	0.936	0.939	0.66–1.22	Yes	LVLI
Arsenic	Water	mg/L	1.3775	1.400	0.96–1.79	Yes	LVLI
Barium	Water	mg/L	29.3	29.700	20.51–38.09	Yes	LVLI
Beryllium	Water	mg/L	--	0.00010	--	Yes ^b	LVLI
Cadmium	Water	mg/L	0.5524	0.549	0.39–0.72	Yes	LVLI
Chromium	Water	mg/L	0.956	0.963	0.67–1.24	Yes	LVLI
Copper	Water	mg/L	9.162	9.230	6.41–11.91	Yes	LVLI
Lead	Water	mg/L	0.503	0.506	0.35–0.65	Yes	LVLI
Nickel	Water	mg/L	3.0806	3.120	2.16–4.00	Yes	LVLI
Selenium	Water	mg/L	--	0.0039	--	Yes	LVLI
Thallium	Water	mg/L	4.202	4.330	2.94–5.46	Yes	LVLI
Vanadium	Water	mg/L	0.506	0.507	0.35–0.66	Yes	LVLI
Zinc	Water	mg/L	2.292	2.330	1.60–2.98	Yes	LVLI
Cs-137	Water	Bq/L	250	240	175.00–325.00	Yes	ELAB
Co-60	Water	Bq/L	163	159	114.10–211.90	Yes	ELAB
H-3	Water	Bq/L	82.9	85.1	58.10–107.90	Yes	ELAB
Sr-90	Water	Bq/L	7.4	0.459	4.90–9.10	No	ELAB
Am-241	Water	Bq/L	0.59	0.605	0.42–0.78	Yes	GEL
Cs-137	Water	Bq/L	250	236.874	175.00–325.00	Yes	GEL
Co-60	Water	Bq/L	163	162.837	114.10–211.90	Yes	GEL
H-3	Water	Bq/L	82.9	95.726	58.10–107.90	Yes	GEL
Pu-238	Water	Bq/L	1.24	1.277	0.84–1.56	Yes	GEL
Pu-239/240	Water	Bq/L	--	0.020	--	Yes	GEL
Sr-90	Water	Bq/L	7.4	6.685	4.90–9.10	Yes	GEL
Tc-99	Water	Bq/L	10.4	9.098	7.00–13.00	Yes	GEL
U-233/234	Water	Bq/L	0.144	0.141	0.10–0.19	Yes	GEL
U-238	Water	Bq/L	0.94	0.982	0.63–1.17	Yes	GEL

ELAB - Environmental Laboratory

GEL - General Engineering Laboratories

LVLI - Lionville Laboratories, Inc.

^a MAPEP monitors performance and requests corrective action as required.

^b Although no actual values or acceptable range was provided, the results were assessed by MAPEP as acceptable.

Note: This report has been excerpted to include only those matrix/analyte combinations performed in support of the analyses of samples collected at the WVDP and which are presented in this Annual Site Environmental Report.

Table J-3 (concluded)
Crosscheck Sample Comparisons From the DOE Mixed Analyte Performance
Evaluation Program (MAPEP)^a; November 2004

Analyte	Matrix	Units	Actual	Reported	Acceptance Range	Accept?	Analyzed by:
MAPEP - 04 - RdF12 Radiological Air Filter							
Cs-137	Air Filter	Bq/sample	1.96	1.74	1.40–2.60	Yes	ELAB
Co-60	Air Filter	Bq/sample	2.35	2.19	1.61–2.99	Yes	ELAB
Am-241	Air Filter	Bq/sample	0.1	0.12	0.07–0.13	Yes	GEL
Cs-137	Air Filter	Bq/sample	1.96	1.918	1.40–2.60	Yes	GEL
Co-60	Air Filter	Bq/sample	2.35	2.379	1.61–2.99	Yes	GEL
Pu-238	Air Filter	Bq/sample	0.13	0.124	0.09–0.17	Yes	GEL
Pu-239/240	Air Filter	Bq/sample	0.09	0.088	0.06–0.12	Yes	GEL
Sr-90	Air Filter	Bq/sample	0.83	0.783	0.56–1.04	Yes	GEL
U-233/234	Air Filter	Bq/sample	0.21	0.222	0.15–0.27	Yes	GEL
U-238	Air Filter	Bq/sample	0.22	0.227	0.15–0.29	Yes	GEL

ELAB - Environmental Laboratory

GEL - General Engineering Laboratories

^a MAPEP monitors performance and requests corrective action as required.

Note: This report has been excerpted to include only those matrix/analyte combinations performed in support of the analyses of samples collected at the WVDP and which are presented in this Annual Site Environmental Report.

Table J-4
Crosscheck Sample Comparisons of Results Analyzed for Water Quality Parameters as Part of the EPA's 2004 Discharge Monitoring Report - Quality Assurance (DMR-QA) Study 24 for the National Pollutant Discharge Elimination System (NPDES)

Analyte	Units	Actual	Reported	Acceptance Range ^a	Accept?	Analyzed by ^b :
Aluminum	µg/L	639	661	538-739	Yes	STL
Ammonia (as Nitrogen)	mg/L	12.5	12.1	9.71-15.2	Yes	STL
Arsenic	µg/L	355	342	296-417	Yes	STL
Biochemical oxygen demand	mg/L	75.3	55.2	38.0-113	Yes	STL
Cadmium	µg/L	690	648	589-783	Yes	STL
Chlorine, total residual	mg/L	1.14	1.20	0.890-1.39	Yes	WVNSCO
Chromium	µg/L	298	292	258-338	Yes	STL
Cobalt	µg/L	595	610	523-667	Yes	STL
Copper	µg/L	226	237	203-250	Yes	STL
Cyanide, total	mg/L	0.449	0.376	0.308-0.580	Yes	STL
Grease and Oil (Gravimetric)	mg/L	31.0	26.9	19.7-36.3	Yes	STL
Iron	µg/L	770	772	679-872	Yes	STL
Lead	µg/L	392	378	339-443	Yes	STL
Manganese	µg/L	817	837	734-908	Yes	STL
Mercury	µg/L	13.4	8.38	10.0-16.7	No	STL
Nickel	µg/L	285	287	252-322	Yes	STL
Nitrate (as Nitrogen)	mg/L	10.6	11.8	8.38-12.6	Yes	STL
pH	SU	8.43	8.44	8.18-8.67	Yes	WVNSCO
Phenolics, total	mg/L	0.220	0.193	0.114-0.326	Yes	STL
Selenium	µg/L	466	446	368-540	Yes	STL
Suspended solids, total	mg/L	37.9	36.0	28.0-40.4	Yes	STL
Vanadium	µg/L	603	600	542-662	Yes	STL
Zinc	µg/L	301	304	264-342	Yes	STL

Samples provided by Environmental Research Associates (ERA)

^a Acceptance limits are determined by ERA or the New York State Department of Health (NYSDOH), as applicable.

^b Analyses were conducted by Severn Trent Laboratories (STL) or the WVDP Wastewater Treatment Facility Laboratory (WVNSCO).

Appendix K
Environmental Laws, Regulations, Standards, and Orders

This page intentionally left blank

Table K-1
U.S. Department of Energy Radiation Protection Standards
and Derived Concentration Guides¹

Effective Dose Equivalent Radiation Standard for Protection of the Public

*Continuous exposure of any member of the public from routine activities:
All exposure pathways = 100 mrem/year (1 mSv/yr) effective dose equivalent*

U.S. Department of Energy Derived Concentration Guides (DCGs)
for Inhaled Air or Ingested Water ($\mu\text{Ci}/\text{mL}$)

<i>Radionuclide</i>	<i>Half-life² (years)</i>	<i>In Air</i>	<i>In Water</i>	<i>Radionuclide</i>	<i>Half-life² (years)</i>	<i>In Air</i>	<i>In Water</i>
H-3*	1.23E+01	1E-07	2E-03	Eu-152	1.35E+01	5E-11	2E-05
C-14*	5.73E+03	6E-09	7E-05	Eu-154*	8.59E+00	5E-11	2E-05
K-40	1.28E+09	9E-10	7E-06	Eu-155	4.76E+00	3E-10	1E-04
Fe-55	2.73E+00	5E-09	2E-04	Th-232	1.40E+10	7E-15	5E-08
Co-60*	5.27E+00	8E-11	5E-06	U-232*	6.89E+01	2E-14	1E-07
Ni-59	7.60E+04	4E-09	7E-04	U-233*	1.59E+05	9E-14	5E-07
Ni-63	1.00E+02	2E-09	3E-04	U-234*	2.46E+05	9E-14	5E-07
Sr-90*	2.88E+01	9E-12	1E-06	U-235*	7.04E+08	1E-13	6E-07
Y-90	7.30E-03	1E-09	1E-05	U-236*	2.34E+07	1E-13	5E-07
Zr-93	1.53E+06	4E-11	9E-05	U-238*	4.47E+09	1E-13	6E-07
Nb-93m	1.61E+01	4E-10	3E-04	Np-239	6.45E-03	5E-09	5E-05
Tc-99*	2.11E+05	2E-09	1E-04	Pu-238*	8.77E+01	3E-14	4E-08
Ru-106	1.02E+00	3E-11	6E-06	Pu-239*	2.41E+04	2E-14	3E-08
Cd-113m	1.41E+01	8E-12	9E-07	Pu-240*	6.56E+03	2E-14	3E-08
Sn-126	1.00E+05	1E-10	8E-06	Pu-241	1.43E+01	1E-12	2E-06
Sb-125	2.76E+00	1E-09	5E-05	Am-241*	4.32E+02	2E-14	3E-08
Te-125m	1.57E-01	2E-09	4E-05	Am-242m	1.41E+02	2E-14	3E-08
I-129*	1.57E+07	7E-11	5E-07	Am-243	7.37E+03	2E-14	3E-08
Cs-134	2.07E+00	2E-10	2E-06	Cm-243	2.91E+01	3E-14	5E-08
Cs-135	2.30E+06	3E-09	2E-05	Cm-244	1.81E+01	4E-14	6E-08
Cs-137*	3.01E+01	4E-10	3E-06	Gross Alpha	NA	2E-14	3E-08
Pm-147	2.62E+00	3E-10	1E-04	(as Am-241)			
Sm-151	9.00E+01	4E-10	4E-04	Gross Beta	NA	9E-12	1E-06
				(as Sr-90)			

¹ DOE Order 5400.5 (February 8, 1990). Effective May 8, 1990. (See Derived Concentration Guides [p. 1-5] in Chapter 1, Environmental Program Information.)

² Nuclear Wallet Cards. January 2000. National Nuclear Data Center. Brookhaven National Laboratory. Upton, New York.

* Radionuclides measured in WVDP effluent.

NA - Not applicable.

Table K-2
Environmental Laws, Regulations, Standards, and Orders

The following environmental standards and laws are applicable, in whole or in part, to the West Valley Demonstration Project. Although the list covers the major activities at the West Valley Demonstration Project, it does not constitute a complete enumeration.

Atomic Energy Act of 1954, 42 United States Code (USC) §2011 et seq., as amended, and federal implementing regulations.

Clean Air Act (CAA). Pub. L. No. 84-159. 42 USC §7401 et seq., as amended, and federal and state implementing regulations.

Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). Pub. L. No. 96-510. 42 USC §9601 et seq. (including Superfund Amendments and Reauthorization Act [SARA] of 1986), and federal implementing regulations.

DOE Order 231.1A. August 19, 2003. Environment, Safety, and Health Reporting, replaces DOE Orders 231.1 and 232.1A, including Change 1 (June 3, 2004).

DOE Order 414.1B. April 29, 2004. Quality Assurance.

DOE Order 435.1. July 9, 1999. Radioactive Waste Management, including Change 1 (August 28, 2001).

DOE Order 440.1A. March 27, 1998. Worker Protection Management for DOE Federal and Contractor Employees.

DOE Order 450.1. January 15, 2003. Environmental Protection Program, including Change 1 (January 15, 2005). (DOE Order 450.1 canceled DOE Order 5400.1.)

DOE Order 451.1B. October 26, 2000. National Environmental Policy Act Compliance Program, including Change 1 (September 28, 2001).

DOE Order 5400.5. February 8, 1990. Radiation Protection of the Public and the Environment, including Change 2 (January 7, 1993).

DOE Order 5480.4. May 15, 1984. Environmental Protection, Safety, and Health Protection Standards, including Change 4 (January 7, 1993).

DOE Policy 141.1. May 2, 2001. Department of Energy Management of Cultural Resources.

DOE Policy 141.2. May 2, 2003. Public Participation and Community Relations.

Table K-2 (continued)
Environmental Laws, Regulations, Standards, and Orders

DOE Regulatory Guide DOE/EH-0173T. January 1991. *Environmental Regulatory Guide for Radiological Effluent Monitoring and Environmental Surveillance.*

DOE Standard DOE-STD-1153-2002. July 2002. *A Graded Approach for Evaluating Radiation Doses to Aquatic and Terrestrial Biota.*

Emergency Planning and Community Right-to-Know Act (EPCRA) of 1986. Pub. L. No. 99-499. 42 USC §11001 *et seq.*, and federal implementing regulations.

Endangered Species Act of 1973. Pub. L. No. 93-205. 16 USC §1531 *et seq.*, and federal and state implementing regulations.

Environmental Conservation Law of the New York State Consolidated Laws and state implementing regulations (NYCRR).

Executive Order 11988. *Floodplain Management.*

Executive Order 11990. *Protection of Wetlands.*

Executive Order 13101. *Greening the Government Through Waste Prevention, Recycling, and Federal Acquisition.*

Executive Order 13148. *Greening the Government Through Leadership in Environmental Management.*

Federal Water Pollution Control Act (Clean Water Act [CWA]). Pub. L. No. 95-217. 33 USC §1251 *et seq.*, as amended, and federal and state implementing regulations.

Migratory Bird Treaty Act. 16 USC §703–712 as amended, and federal and state implementing regulations.

National Environmental Policy Act (NEPA) of 1969. Pub. L. No. 91-190. 42 USC §4321 *et seq.*, as amended, and federal implementing regulations.

National Historic Preservation Act of 1966. Pub. L. No. 102-575. 16 USC §470 *et seq.*, and federal implementing regulations.

Resource Conservation and Recovery Act (RCRA). Pub. L. No. 94-580. 42 USC §6901 *et seq.*, as amended, and federal and state implementing regulations.

Table K-2 (concluded)
Environmental Laws, Regulations, Standards, and Orders

Safe Drinking Water Act (SDWA). Pub. L. No. 93-523. 42 USC §300f *et seq.*, as amended, and federal and state implementing regulations.

Toxic Substances Control Act (TSCA). Pub. L. No. 94-469. 15 USC §2601 *et seq.*, as amended, and federal implementing regulations.

U.S. Environmental Protection Agency. 1992. *Region II Administrative Order on Consent. Docket No. II RCRA 3008(h)-92-0202. In the Matter of: Western New York Nuclear Service Center.*

U.S. Environmental Protection Agency. 1996. *West Valley Demonstration Project Federal Facilities Compliance Act Order.*

Water quality standards contained in the New York State Pollutant Discharge Elimination System (SPDES) permit issued for the facility are listed in Table C-1A. Airborne emissions are regulated by the Environmental Protection Agency under the National Emission Standards for Hazardous Air Pollutants (NESHAP), 40 CFR §61 Subpart H (December 15, 1989, including amendments effective September 9, 2002).

Table K-3
West Valley Demonstration Project Act
(Public Law 96-368 [S. 2443]; October 1, 1980)

(As presented in Exhibit G of the Cooperative Agreement between United States Department of Energy and New York State Energy Research and Development Authority on the Western New York Nuclear Service Center at West Valley, New York; Effective October 1, 1980 as amended September 18, 1981.)

EXHIBIT G

WEST VALLEY PROJECT DEMONSTRATION ACT

PUBLIC LAW 96-368 [S. 2443]; October 1, 1980

WEST VALLEY DEMONSTRATION PROJECT ACT

For Legislative History of this and other Laws, see Table 1, Public Laws and Legislative History, at end of final volume

An Act to authorize the Department of Energy to carry out a high-level liquid nuclear waste management demonstration project at the Western New York Service Center in West Valley, New York.

Be it enacted by the Senate and House of Representatives of the United States of America in Congress assembled,

SECTION 1. This Act may be cited as the "West Valley Demonstration Project Act".

SEC. 2. (a) The Secretary shall carry out, in accordance with this Act, a high level radioactive waste management demonstration project at the Western New York Service Center in West Valley, New York, for the purpose of demonstrating solidification techniques which can be used for preparing high level radioactive waste for disposal. Under the project the Secretary shall carry out the following activities:

(1) The Secretary shall solidify, in a form suitable for transportation and disposal, the high level radioactive waste at the Center by vitrification or by such other technology which the Secretary determines to be the most effective for solidification.

(2) The Secretary shall develop containers suitable for the permanent disposal of the high level radioactive waste solidified at the Center.

(3) The Secretary shall, as soon as feasible, transport, in accordance with applicable provisions of law, the waste solidified at the Center to an appropriate Federal repository for permanent disposal.

(4) The Secretary shall, in accordance with applicable licensing requirements, dispose of low level radioactive waste and transuranic waste produced by the solidification of the high level radioactive waste under the project.

(5) The Secretary shall decontaminate and decommission—
(A) the tanks and other facilities of the Center in which the high level radioactive waste solidified under the project was stored,

(B) the facilities used in the solidification of the waste, and

(C) any material and hardware used in connection with the project,

in accordance with such requirements as the Commission may prescribe.

(b) Before undertaking the project and during the fiscal year ending September 30, 1981, the Secretary shall carry out the following:

(1) The Secretary shall hold in the vicinity of the Center public hearings to inform the residents of the area in which the Center is located of the activities proposed to be undertaken under the project and to receive their comments on the project.

(2) The Secretary shall consider the various technologies available for the solidification and handling of high level radioactive waste taking into account the unique characteristics of such waste at the Center.

West Valley
Demonstration
Project Act.
42 USC 2021a
note.
42 USC 2021a
note.

Activities.

Hearings.

94 STAT. 1347

G-1

K - 7

(3) The Secretary shall—

(A) undertake detailed engineering and cost estimates for the project.

(B) prepare a plan for the safe removal of the high level radioactive waste at the Center for the purposes of solidification and include in the plan provisions respecting the safe breaching of the tanks in which the waste is stored, operating equipment to accomplish the removal, and sluicing techniques,

(C) conduct appropriate safety analyses of the project, and

(D) prepare required environmental impact analyses of the project.

(4) The Secretary shall enter into a cooperative agreement with the State in accordance with the Federal Grant and Cooperative Agreement Act of 1977 under which the State will carry out the following:

42 USC 501 note.

(A) The State will make available to the Secretary the facilities of the Center and the high level radioactive waste at the Center which are necessary for the completion of the project. The facilities and the waste shall be made available without the transfer of title and for such period as may be required for completion of the project.

(B) The Secretary shall provide technical assistance in securing required license amendments.

State costs, percentage.

(C) The State shall pay 10 per centum of the costs of the project, as determined by the Secretary. In determining the costs of the project, the Secretary shall consider the value of the use of the Center for the project. The State may not use Federal funds to pay its share of the cost of the project, but may use the perpetual care fund to pay such share.

Licensing amendment application.

(D) Submission jointly by the Department of Energy and the State of New York of an application for a licensing amendment as soon as possible with the Nuclear Regulatory Commission providing for the demonstration.

(c) Within one year from the date of the enactment of this Act, the Secretary shall enter into an agreement with the Commission to establish arrangements for review and consultation by the Commission with respect to the project: *Provided*, That review and consultation by the Commission pursuant to this subsection shall be conducted informally by the Commission and shall not include nor require formal procedures or actions by the Commission pursuant to the Atomic Energy Act of 1954, as amended, the Energy Reorganization Act of 1974, as amended, or any other law. The agreement shall provide for the following:

42 USC 2011 note.
42 USC 5801 note.

(1) The Secretary shall submit to the Commission, for its review and comment, a plan for the solidification of the high level radioactive waste at the Center, the removal of the waste for purposes of its solidification, the preparation of the waste for disposal, and the decontamination of the facilities to be used in solidifying the waste. In preparing its comments on the plan, the Commission shall specify with precision its objections to any provision of the plan. Upon submission of a plan to the Commission, the Secretary shall publish a notice in the Federal Register of the submission of the plan and of its availability for public inspection, and, upon receipt of the comments of the Commission respecting a plan, the Secretary shall publish a notice in the Federal Register of the receipt of the comments and of the availability of the comments for public inspection. If the Secre-

Publications in Federal Register.

tary does not revise the plan to meet objections specified in the comments of the Commission, the Secretary shall publish in the Federal Register a detailed statement for not so revising the plan.

(2) The Secretary shall consult with the Commission with respect to the form in which the high level radioactive waste at the Center shall be solidified and the containers to be used in the permanent disposal of such waste.

(3) The Secretary shall submit to the Commission safety analysis reports and such other information as the Commission may require to identify any danger to the public health and safety which may be presented by the project.

(4) The Secretary shall afford the Commission access to the Center to enable the Commission to monitor the activities under the project for the purpose of assuring the public health and safety.

(d) In carrying out the project, the Secretary shall consult with the Administrator of the Environmental Protection Agency, the Secretary of Transportation, the Director of the Geological Survey, and the commercial operator of the Center.

SEC. 3. (a) There are authorized to be appropriated to the Secretary for the project not more than \$5,000,000 for the fiscal year ending September 30, 1981.

(b) The total amount obligated for the project by the Secretary shall be 90 per centum of the costs of the project.

(c) The authority of the Secretary to enter into contracts under this Act shall be effective for any fiscal year only to such extent or in such amounts as are provided in advance by appropriation Acts.

SEC. 4. Not later than February 1, 1981, and on February 1 of each calendar year thereafter during the term of the project, the Secretary shall transmit to the Speaker of the House of Representatives and the President pro tempore of the Senate an up-to-date report containing a detailed description of the activities of the Secretary in carrying out the project, including agreements entered into and the costs incurred during the period reported on and the activities to be undertaken in the next fiscal year and the estimated costs thereof.

SEC. 5. (a) Other than the costs and responsibilities established by this Act for the project, nothing in this Act shall be construed as affecting any rights, obligations, or liabilities of the commercial operator of the Center, the State, or any person, as is appropriate, arising under the Atomic Energy Act of 1954 or under any other law, contract, or agreement for the operation, maintenance, or decontamination of any facility or property at the Center or for any wastes at the Center. Nothing in this Act shall be construed as affecting any applicable licensing requirement of the Atomic Energy Act of 1954 or the Energy Reorganization Act of 1974. This Act shall not apply or be extended to any facility or property at the Center which is not used in conducting the project. This Act may not be construed to expand or diminish the rights of the Federal Government.

(b) This Act does not authorize the Federal Government to acquire title to any high level radioactive waste at the Center or to the Center or any portion thereof.

SEC. 6. For the purposes of this Act:

(1) The term "Secretary" means the Secretary of Energy.

(2) The term "Commission" means the Nuclear Regulatory Commission.

(3) The term "State" means the State of New York.

Reports and other information to Commission.

Consultation with EPA and others.

Appropriation authorization. 42 USC 2021a note.

Report to Speaker of the House and President pro tempore of the Senate. 42 USC 2021a note.

42 USC 2021a note.

42 USC 2011 note.

42 USC 5801 note.

Definitions. 42 USC 2021a note.

(4) The term "high level radioactive waste" means the high level radioactive waste which was produced by the reprocessing at the Center of spent nuclear fuel. Such term includes both liquid wastes which are produced directly in reprocessing, dry solid material derived from such liquid waste, and such other material as the Commission designates as high level radioactive waste for purposes of protecting the public health and safety.

(5) The term "transuranic waste" means material contaminated with elements which have an atomic number greater than 92, including neptunium, plutonium, americium, and curium, and which are in concentrations greater than 10 nanocuries per gram, or in such other concentrations as the Commission may prescribe to protect the public health and safety.

(6) The term "low level radioactive waste" means radioactive waste not classified as high level radioactive waste, transuranic waste, or byproduct material as defined in section 11 e. (2) of the Atomic Energy Act of 1954.

42 USC 2014.

(7) The term "project" means the project prescribed by section 2(a).

(8) The term "Center" means the Western New York Service Center in West Valley, New York.

Approved October 1, 1980.

Appendix L

***Summary of New York State Energy Research
and Development Authority (NYSERDA)
Groundwater Monitoring Data for the
New York State-Licensed Disposal Area (SDA)***

This page intentionally left blank

Table L-1
2004 Contamination Indicator Results From SDA Monitoring Wells

Sample Location	Date	Conductivity (µmhos/cm@25°C)	pH (SU)	Temperature (°C)	Turbidity (NTU)
WNW1101A	<i>June</i>	649	7.40	9.4	1.37
WNW1101A	<i>December</i>	632	6.99	9.3	1.52
WNW1101B	<i>June</i>	614	7.44	10.1	6.88
WNW1101B	<i>December</i>	611	7.38	8.2	3.65
WNW1101C	<i>June</i>	409	7.32	10.1	27.8
WNW1101C	<i>December</i>	350	7.53	8.1	256
WNW1102A	<i>June</i>	714	7.49	9.9	5.23
WNW1102A	<i>December</i>	646	7.36	9.2	13.5
WNW1102B	<i>June</i>	531	7.42	10.5	13.3
WNW1102B	<i>December</i>	516	7.32	8.6	13.7
WNW1103A	<i>June</i>	861	7.03	11.3	89.8
WNW1103A	<i>December</i>	866	7.31	9.4	196
WNW1103B	<i>June</i>	601	7.36	10.2	5.62
WNW1103B	<i>December</i>	624	7.39	8.2	23.0
WNW1104A	<i>June</i>	698	7.42	12.4	2.50
WNW1104A	<i>December</i>	700	7.50	10.2	4.32
WNW1104B	<i>June</i>	556	7.49	13.0	1.82
WNW1104B	<i>December</i>	551	7.53	8.0	0.86
WNW1105A	<i>June</i>	628	7.51	8.5	223
WNW1105A	<i>December</i>	619	7.57	8.5	340
WNW1105B	<i>June</i>	622	7.57	8.6	>1,000
WNW1105B	<i>December</i>	626	7.66	7.8	149
WNW1106A	<i>June</i>	703	7.34	9.4	2.46
WNW1106A	<i>December</i>	711	7.39	9.9	8.99
WNW1106B	<i>June</i>	700	7.27	10.8	116
WNW1106B	<i>December</i>	699	7.17	9.4	66.6
WNW1107A	<i>June</i>	1,854	6.69	9.4	1.28
WNW1107A	<i>June</i>	1,854	6.69	9.4	1.28
WNW1107A	<i>December</i>	1,818	6.68	9.9	1.44

All data in Tables L-1 through L-3 have been provided by NYSERDA.

Table L-1 (concluded)
2004 Contamination Indicator Results From SDA Monitoring Wells

Sample Location	Date	Conductivity (µmhos/cm@25°C)	pH (SU)	Temperature (°C)	Turbidity (NTU)
WNW1108A	<i>June</i>	821	7.13	8.8	>1,000
WNW1108A	<i>December</i>	860	7.28	10.3	484
WNW1109A	<i>June</i>	552	7.50	8.1	4.92
WNW1109A	<i>December</i>	575	7.37	9.0	4.64
WNW1109B	<i>June</i>	442	7.58	9.0	50.8
WNW1109B	<i>December</i>	428	7.49	8.7	49.0
WNW1109B	<i>December</i>	428	7.49	8.7	49.0
WNW1111A	<i>June</i>	966	7.13	9.4	5.63
WNW1111A	<i>December</i>	968	7.07	8.9	1.66

All data in Tables L-1 through L-3 have been provided by NYSERDA.

Table L-2
2004 Radiological Indicator Results From SDA Monitoring Wells ($\mu\text{Ci}/\text{mL}$)

Sample Location	Date	Gross Alpha	Gross Beta	H-3
WNW1101A	<i>June</i>	4.17±2.10E-09	2.80±1.40E-09	2.13±4.90E-08
WNW1101A	<i>December</i>	4.12±2.00E-09	3.44±1.80E-09	8.46±5.80E-08
WNW1101B	<i>June</i>	5.68±2.70E-09	1.73±1.40E-09	-2.50±4.70E-08
WNW1101B	<i>December</i>	3.82±1.90E-09	1.72±1.70E-09	1.65±5.30E-08
WNW1101C	<i>June</i>	1.10±1.10E-09	2.88±1.80E-09	-4.81±5.20E-08
WNW1101C	<i>December</i>	1.00±0.87E-09	2.00±1.70E-09	0.16±5.20E-08
WNW1102A	<i>June</i>	4.06±2.00E-09	6.91±2.70E-09	2.10±0.54E-07
WNW1102A	<i>December</i>	2.05±1.40E-09	3.16±1.80E-09	2.74±0.68E-07
WNW1102B	<i>June</i>	1.24±1.00E-09	4.00±1.70E-09	-0.90±5.40E-08
WNW1102B	<i>December</i>	0.18±1.10E-09	0.55±1.70E-09	3.64±5.00E-08
WNW1103A	<i>June</i>	8.25±3.40E-09	2.36±1.70E-09	4.55±0.85E-07
WNW1103A	<i>December</i>	4.39±1.90E-09	3.68±2.10E-09	4.35±0.81E-07
WNW1103B	<i>June</i>	0.86±1.20E-09	1.96±1.50E-09	-4.56±5.00E-08
WNW1103B	<i>December</i>	1.85±1.10E-09	2.28±1.70E-09	2.47±5.00E-08
WNW1103C	<i>June</i>	0.97±1.10E-09	7.01±2.10E-09	-3.01±4.70E-08
WNW1103C	<i>December</i>	1.76±1.40E-09	6.27±2.40E-09	-0.04±5.20E-08
WNW1104A	<i>June</i>	4.56±2.30E-09	4.80±2.10E-09	1.69±0.66E-07
WNW1104A	<i>December</i>	1.61±1.20E-09	3.42±2.10E-09	1.81±0.62E-07
WNW1104B	<i>June</i>	1.23±1.10E-09	2.27±1.80E-09	-4.03±5.20E-08
WNW1104B	<i>December</i>	4.70±8.20E-10	2.71±1.80E-09	-1.83±4.70E-08
WNW1104C	<i>June</i>	5.46±5.20E-09	1.12±0.48E-08	-1.60±4.80E-08
WNW1104C	<i>December</i>	4.42±2.00E-09	3.27±2.00E-09	-6.97±4.60E-08
WNW1105A	<i>June</i>	4.03±2.30E-09	3.68±1.90E-09	1.02±0.51E-07
WNW1105A	<i>December</i>	3.04±1.70E-09	4.49±1.80E-09	1.20±0.56E-07
WNW1105B	<i>June</i>	3.25±2.10E-09	3.10±1.60E-09	-4.26±4.70E-08
WNW1105B	<i>December</i>	1.90±1.40E-09	1.45±1.70E-09	2.14±4.80E-08
WNW1106A	<i>June</i>	4.89±2.70E-09	3.59±1.70E-09	4.61±0.61E-07
WNW1106A	<i>December</i>	2.51±1.40E-09	3.55±1.90E-09	5.38±0.89E-07

All data in Tables L-1 through L-3 have been provided by NYSERDA.

Table L-2 (concluded)
2004 Radiological Indicator Results From SDA Monitoring Wells ($\mu\text{Ci}/\text{mL}$)

Sample Location	Date	Gross Alpha	Gross Beta	H-3
WNW1106B	<i>June</i>	2.14±1.20E-09	2.70±1.70E-09	-6.51±4.60E-08
WNW1106B	<i>December</i>	1.67±1.10E-09	2.32±1.70E-09	-0.44±4.70E-08
WNW1107A	<i>June</i>	4.13±3.20E-09	1.70±0.49E-08	1.09±0.04E-05
WNW1107A	<i>June</i>	3.51±2.70E-09	1.30±0.46E-08	1.02±0.04E-05
WNW1107A	<i>December</i>	3.83±1.80E-09	1.70±0.42E-08	1.10±0.08E-05
WNW1108A	<i>June</i>	5.08±2.40E-09	5.58±2.50E-09	9.81±6.10E-08
WNW1108A	<i>December</i>	3.60±1.70E-09	4.06±2.20E-09	1.38±0.58E-07
WNW1109A	<i>June</i>	4.62±2.40E-09	2.74±1.50E-09	2.33±0.55E-07
WNW1109A	<i>December</i>	2.65±1.60E-09	1.06±1.80E-09	2.17±0.69E-07
WNW1109B	<i>June</i>	2.17±1.60E-09	1.34±1.30E-09	6.50±1.10E-07
WNW1109B	<i>December</i>	4.05±7.20E-10	0.35±1.70E-09	3.99±0.80E-07
WNW1109B	<i>December</i>	1.01±0.88E-09	1.62±1.20E-09	3.98±0.80E-07
WNW1110A	<i>June</i>	NA	NA	2.75±0.79E-07
WNW1110A	<i>December</i>	1.14±0.36E-08	5.02±2.30E-09	1.36±0.62E-07
WNW1111A	<i>June</i>	7.35±3.30E-09	4.00±1.70E-09	1.53±0.52E-07
WNW1111A	<i>December</i>	5.18±2.70E-09	2.82±1.90E-09	1.61±0.63E-07

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3
2004 Radioisotopic Results From SDA Monitoring Wells ($\mu\text{Ci/mL}$)

Sample Location	Date	Actinium-228	Bismuth-214	Carbon-14	Cesium-134
WNW1101A	June	1.35±1.40E-08	3.23±8.20E-09	0.96±3.80E-09	6.99±3.80E-09
WNW1101B	June	1.09±1.30E-08	8.91±9.20E-09	2.05±3.80E-09	1.35±4.10E-09
WNW1101C	June	0.66±1.60E-08	-0.21±1.20E-08	1.66±3.90E-09	-1.75±5.90E-09
WNW1102A	June	0.27±1.70E-08	0.38±1.00E-08	-1.34±3.70E-09	-5.67±5.60E-09
WNW1102B	June	-4.80±9.90E-09	7.54±6.50E-09	1.56±3.90E-09	0.60±3.20E-09
WNW1103A	June	0.46±1.40E-08	0.25±8.30E-09	2.67±3.90E-09	-0.59±3.40E-09
WNW1103B	June	0.51±1.00E-08	5.24±8.00E-09	1.24±3.90E-09	0.03±3.70E-09
WNW1104A	June	-3.32±2.50E-08	0.16±1.30E-08	2.30±3.90E-09	-4.76±6.10E-09
WNW1104B	June	-1.92±2.70E-08	-0.75±1.50E-08	-0.22±3.80E-09	-6.43±6.10E-09
WNW1105A	June	1.14±1.90E-08	1.05±1.20E-08	-0.04±3.80E-09	1.44±6.20E-09
WNW1105B	June	0.10±1.90E-08	-5.63±9.80E-09	0.81±3.80E-09	-2.22±5.80E-09
WNW1106A	June	0.71±1.10E-08	1.17±6.30E-09	-2.37±3.70E-09	0.36±3.60E-09
WNW1106B	June	1.11±1.20E-08	3.52±7.90E-09	1.56±3.80E-09	-0.33±4.00E-09
WNW1107A	June	2.67±2.30E-08	0.24±1.20E-08	3.29±3.90E-09	-3.91±4.90E-09
WNW1107A	June	0.52±2.10E-08	-0.49±1.30E-08	2.11±3.80E-09	0.29±6.00E-09
WNW1108A	June	1.82±3.00E-08	0.80±1.60E-08	2.33±3.90E-09	-1.75±6.90E-09
WNW1109A	June	-0.75±2.30E-08	-1.47±1.30E-08	1.22±3.80E-09	4.89±5.60E-09
WNW1109B	June	-0.10±2.40E-08	0.56±1.10E-08	-1.31±3.80E-09	1.40±5.50E-09
WNW1111A	June	1.16±2.00E-08	-0.26±1.20E-08	3.81±3.90E-09	-0.50±5.20E-09

All data in Tables L-1 through L-3 have been provided by NYSERDA.

Table L-3 (continued)
2004 Radioisotopic Results From SDA Monitoring Wells ($\mu\text{Ci}/\text{mL}$)

Sample Location	Date	Cesium-137	Cobalt-57	Cobalt-60	Iodine-129
WNW1101A	June	4.76±6.30E-09	0.20±1.70E-08	2.47±4.50E-09	-2.64±2.50E-10
WNW1101B	June	1.42±3.80E-09	-0.81±1.90E-08	-2.56±3.80E-09	0.38±2.30E-10
WNW1101C	June	0.73±5.20E-09	-1.31±2.60E-08	1.68±4.90E-09	0.31±2.10E-10
WNW1102A	June	-1.28±5.70E-09	-1.31±2.60E-08	-2.18±6.20E-09	1.38±3.10E-10
WNW1102B	June	-9.45±4.90E-09	0.58±1.70E-08	-1.77±3.40E-09	-2.28±2.70E-10
WNW1103A	June	0.10±3.50E-09	0.37±2.00E-08	1.55±3.20E-09	0.03±2.80E-10
WNW1103B	June	0.54±3.30E-09	-1.85±1.90E-08	-0.29±3.40E-09	0.88±2.10E-10
WNW1104A	June	4.77±5.80E-09	-0.23±3.10E-08	-2.99±5.70E-09	1.17±2.40E-10
WNW1104B	June	-2.80±6.20E-09	-2.43±3.40E-08	3.21±6.60E-09	-0.03±1.80E-10
WNW1104C	June	NA	NA	NA	2.79±3.50E-10
WNW1105A	June	-3.61±4.90E-09	-1.51±2.30E-08	-3.12±5.50E-09	-0.20±2.60E-10
WNW1105B	June	-0.57±4.50E-09	-0.37±2.00E-08	-0.52±4.30E-09	-1.25±2.00E-10
WNW1106A	June	-0.48±4.90E-09	-0.64±1.20E-08	0.46±3.00E-09	2.44±2.40E-10
WNW1106B	June	-2.96±3.60E-09	-0.32±1.50E-08	2.91±3.40E-09	0.01±2.50E-10
WNW1107A	June	-2.94±4.60E-09	1.41±2.40E-08	-2.07±5.40E-09	2.20±2.60E-10
WNW1107A	June	-0.70±5.30E-09	-0.92±2.20E-08	1.99±4.10E-09	0.20±2.00E-10
WNW1108A	June	-2.51±6.20E-09	2.77±3.00E-08	0.74±7.30E-09	-1.71±2.50E-10
WNW1109A	June	-2.19±4.90E-09	-1.46±2.20E-08	-1.64±4.70E-09	0.70±2.60E-10
WNW1109B	June	-3.37±4.60E-09	-0.27±2.20E-08	4.58±5.10E-09	0.00±2.20E-10
WNW1111A	June	1.12±4.90E-09	-1.19±2.20E-08	3.52±4.30E-09	0.07±2.30E-10

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3 (continued)
2004 Radioisotopic Results From SDA Monitoring Wells ($\mu\text{Ci/mL}$)

Sample Location	Date	Lead-212	Lead-214	Potassium-40	Radium-224
WNW1101A	June	-0.99 \pm 5.00E-09	7.08 \pm 7.60E-09	2.44 \pm 9.80E-08	-1.02 \pm 5.20E-09
WNW1101B	June	3.26 \pm 5.50E-09	-0.20 \pm 8.30E-09	3.00 \pm 6.80E-08	3.36 \pm 5.60E-09
WNW1101C	June	4.39 \pm 6.40E-09	-0.06 \pm 1.10E-08	2.45 \pm 9.50E-08	4.79 \pm 7.00E-09
WNW1102A	June	0.87 \pm 7.60E-09	4.43 \pm 9.90E-09	-0.37 \pm 1.20E-07	0.90 \pm 7.80E-09
WNW1102B	June	1.23 \pm 3.80E-09	-0.95 \pm 6.50E-09	-1.22 \pm 6.80E-08	1.35 \pm 4.10E-09
WNW1103A	June	4.17 \pm 5.20E-09	-4.69 \pm 7.70E-09	-6.47 \pm 8.20E-08	4.55 \pm 5.70E-09
WNW1103B	June	-0.50 \pm 4.00E-09	6.67 \pm 7.10E-09	-5.52 \pm 5.10E-08	-0.54 \pm 4.30E-09
WNW1104A	June	-2.37 \pm 9.00E-09	1.41 \pm 1.00E-08	-0.62 \pm 1.40E-07	-2.60 \pm 9.80E-09
WNW1104B	June	-1.01 \pm 0.98E-08	-0.25 \pm 1.50E-08	-1.08 \pm 1.50E-07	-1.10 \pm 1.10E-08
WNW1105A	June	-1.97 \pm 7.10E-09	-0.25 \pm 1.00E-08	0.20 \pm 1.00E-07	-2.03 \pm 7.30E-09
WNW1105B	June	-3.89 \pm 7.50E-09	-3.07 \pm 9.00E-09	-0.43 \pm 1.10E-07	-4.00 \pm 7.70E-09
WNW1106A	June	3.35 \pm 4.10E-09	-2.43 \pm 5.70E-09	-3.67 \pm 6.60E-08	3.44 \pm 4.20E-09
WNW1106B	June	-1.20 \pm 4.40E-09	5.61 \pm 7.70E-09	2.17 \pm 6.40E-08	-1.24 \pm 4.50E-09
WNW1107A	June	-4.25 \pm 8.00E-09	1.52 \pm 0.89E-08	-0.36 \pm 1.30E-07	-4.37 \pm 8.20E-09
WNW1107A	June	-0.03 \pm 8.10E-09	0.21 \pm 1.00E-08	1.03 \pm 1.10E-07	-0.03 \pm 8.30E-09
WNW1108A	June	0.29 \pm 1.20E-08	1.78 \pm 1.80E-08	-1.54 \pm 1.60E-07	0.31 \pm 1.30E-08
WNW1109A	June	-4.89 \pm 8.60E-09	0.68 \pm 1.00E-08	-0.54 \pm 1.30E-07	-5.03 \pm 8.80E-09
WNW1109B	June	-4.33 \pm 7.20E-09	-2.58 \pm 9.10E-09	1.10 \pm 0.98E-07	-4.72 \pm 7.80E-09
WNW1111A	June	-1.80 \pm 7.00E-09	5.68 \pm 8.70E-09	-2.28 \pm 1.20E-07	-1.85 \pm 7.20E-09

All data in Tables L-1 through L-3 have been provided by NYSERDA.

Table L-3 (continued)
2004 Radioisotopic Results From SDA Monitoring Wells ($\mu\text{Ci}/\text{mL}$)

Sample Location	Date	Radium-226	Strontium-90	Technetium-99	Thallium-208
WNW1101A	June	4.23±8.10E-09	3.19±4.70E-10	0.71±6.80E-10	-0.32±3.80E-09
WNW1101B	June	8.91±9.20E-09	4.28±4.40E-10	4.22±5.30E-10	2.42±4.10E-09
WNW1101C	June	-0.20±1.20E-08	0.13±1.60E-10	1.83±0.70E-09	3.73±5.40E-09
WNW1102A	June	0.38±1.00E-08	1.32±0.85E-09	0.70±1.80E-09	4.53±5.10E-09
WNW1102B	June	7.55±6.50E-09	-2.51±2.60E-10	4.39±5.70E-10	0.83±2.70E-09
WNW1103A	June	0.22±8.30E-09	3.24±3.60E-10	4.80±6.50E-10	1.21±3.30E-09
WNW1103B	June	5.22±8.00E-09	1.07±3.00E-10	2.48±5.40E-10	-1.76±3.30E-09
WNW1104A	June	0.08±1.30E-08	1.31±2.50E-10	8.63±6.20E-10	8.56±6.70E-09
WNW1104B	June	-0.74±1.50E-08	-0.29±1.90E-10	0.48±6.40E-10	-9.36±6.60E-09
WNW1104C	December	NA	NA	1.62±2.00E-09	NA
WNW1105A	June	1.13±1.20E-08	0.84±3.20E-10	4.27±6.20E-10	1.66±5.40E-09
WNW1105B	June	-5.60±9.80E-09	-0.28±2.90E-10	2.21±5.30E-10	-1.16±5.60E-09
WNW1106A	June	2.39±6.10E-09	0.50±3.30E-10	3.75±5.70E-10	2.04±2.90E-09
WNW1106B	June	3.54±7.90E-09	5.83±3.90E-10	1.25±5.20E-10	0.25±3.10E-09
WNW1107A	June	0.24±1.20E-08	6.56±1.30E-09	9.89±6.00E-10	-0.18±6.20E-09
WNW1107A	June	-0.48±1.30E-08	1.01±0.19E-08	1.29±0.64E-09	6.71±5.40E-09
WNW1108A	June	0.80±1.60E-08	0.51±2.00E-10	1.45±1.10E-09	-1.47±7.20E-09
WNW1109A	June	-1.47±1.30E-08	3.12±3.00E-10	2.33±5.50E-10	-1.63±5.50E-09
WNW1109B	June	0.56±1.10E-08	1.16±1.60E-10	7.69±5.90E-10	3.35±6.00E-09
WNW1110A	December	NA	-0.42±6.80E-10	2.79±2.20E-09	NA
WNW1111A	June	-0.26±1.20E-08	-0.38±2.90E-10	4.52±6.10E-10	-1.28±5.60E-09

All data in Tables L-1 through L-3 have been provided by NYSERDA.

NA - Not available. Some scheduled analyses could not be performed due to insufficient sample.

Table L-3 (concluded)
2004 Radioisotopic Results From SDA Monitoring Wells ($\mu\text{Ci/mL}$)

Sample Location	Date	Thorium-234	Uranium-235
WNW1101A	June	-2.07 \pm 5.00E-07	-1.36 \pm 1.70E-08
WNW1101B	June	-2.42 \pm 6.10E-07	-0.98 \pm 1.80E-08
WNW1101C	June	1.20 \pm 8.50E-07	-0.83 \pm 2.10E-08
WNW1102A	June	1.55 \pm 8.60E-07	1.25 \pm 2.50E-08
WNW1102B	June	-2.19 \pm 4.10E-07	-0.69 \pm 1.20E-08
WNW1103A	June	-6.89 \pm 5.70E-07	0.50 \pm 1.90E-08
WNW1103B	June	3.82 \pm 4.70E-07	1.15 \pm 1.50E-08
WNW1104A	June	1.56 \pm 7.40E-07	0.76 \pm 2.40E-08
WNW1104B	June	-5.59 \pm 9.80E-07	0.06 \pm 2.90E-08
WNW1105A	June	-2.88 \pm 8.00E-07	-1.45 \pm 2.30E-08
WNW1105B	June	4.81 \pm 7.20E-07	1.65 \pm 2.00E-08
WNW1106A	June	-2.96 \pm 4.10E-07	-0.01 \pm 1.30E-08
WNW1106B	June	-2.18 \pm 4.90E-07	0.37 \pm 1.70E-08
WNW1107A	June	-3.80 \pm 8.20E-07	1.08 \pm 2.20E-08
WNW1107A	June	0.00 \pm 8.10E-07	-0.10 \pm 2.10E-08
WNW1108A	June	-3.59 \pm 8.50E-07	-1.49 \pm 2.60E-08
WNW1109A	June	3.54 \pm 8.00E-07	-0.56 \pm 2.20E-08
WNW1109B	June	6.13 \pm 6.60E-07	0.09 \pm 2.00E-08
WNW1111A	June	-3.66 \pm 8.00E-07	1.33 \pm 2.00E-08

All data in Tables L-1 through L-3 have been provided by NYSERDA.

This page intentionally left blank