

**U.S. Department of Energy  
Naval Reactors Representative's Office  
Kesselring Site**

National Environmental Policy Act (NEPA) Categorical Exclusion (CX)  
Determination Summary Form  
Kesselring Site Perimeter Roads Maintenance Project

**REFERENCE**

10 CFR Part 1021, Department of Energy National Environmental Policy Act Implementing Procedures, Subpart D, Typical Classes of Actions

**PROJECT SCOPE DISCUSSION**

The Kesselring Site Perimeter Roads Maintenance Project will rehabilitate approximately 11 miles of the Kesselring Site Perimeter Roadway System to include 6 miles of the perimeter loop road and 5 miles of spur roads. This project will also include the replacement of four major culverts, replacement of seven minor culverts, replacement of the Parkis Mills bridge, demolition of the Lee Road bridge, tree clearing to establish 50-foot-wide roadway cross sections including swales, re-establishment of storm water management swales, and the replacement of roadway sub-base materials at select locations. Legacy structures planned for demolition have the potential to contain asbestos, lead and PCB constituents. Characterization will be completed prior to the start of the project.

The project does not violate applicable regulatory requirements, require construction or major expansion of waste handling facilities, result in unpermitted releases of hazardous substances, or adversely affect environmentally sensitive resources, including wetlands. The project does not involve genetically engineered organisms or species. There are no extraordinary circumstances related to the proposed action. The project has not been segmented to meet the definition of a categorical exclusion and is not connected to other actions with potentially significant and/or cumulative impacts.

**CONCLUSION**

The Kesselring Site Perimeter Roads Maintenance Project is categorically excluded from additional NEPA documentation under 10 CFR 1021 Subpart D, Appendix B1.3, B1.16, B1.17, B1.23, B1.32, B1.33 and B1.34).

**B1.3 Routine Maintenance**

Routine maintenance activities and custodial services for buildings, structures, rights-of-way, infrastructures (including, but not limited to, pathways, roads, and railroads), vehicles and equipment, and localized vegetation and pest control, during which operations may be suspended and resumed, provided that the activities would be conducted in a manner in accordance with applicable requirements. Custodial services are activities to preserve facility appearance, working conditions, and sanitation (such as cleaning, window washing, lawn mowing, trash collection, painting, and snow removal). Routine maintenance activities, corrective (that is, repair), preventive, and predictive, are required to maintain and preserve buildings, structures, infrastructures, and equipment in a condition suitable for a facility to be used for its designated purpose. Such maintenance may occur as a result of severe weather (such as hurricanes, floods, and tornados), wildfires, and other such events. Routine maintenance may result in replacement to the extent that replacement is in-kind and is not a substantial upgrade or improvement. In-kind replacement includes installation of new components to

replace outmoded components, provided that the replacement does not result in a significant change in the expected useful life, design capacity, or function of the facility. Routine maintenance does not include replacement of a major component that significantly extends the originally intended useful life of a facility (for example, it does not include the replacement of a reactor vessel near the end of its useful life). Routine maintenance activities include, but are not limited to:

- (a) Repair or replacement of facility equipment, such as lathes, mills, pumps, and presses;
- (b) Door and window repair or replacement;
- (c) Wall, ceiling, or floor repair or replacement;
- (d) Reroofing;
- (e) Plumbing, electrical utility, lighting, and telephone service repair or replacement;
- (f) Routine replacement of high-efficiency particulate air filters;
- (g) Inspection and/or treatment of currently installed utility poles;
- (h) Repair of road embankments;
- (i) Repair or replacement of fire protection sprinkler systems;
- (j) Road and parking area resurfacing, including construction of temporary access to facilitate resurfacing, and scraping and grading of unpaved surfaces;
- (k) Erosion control and soil stabilization measures (such as reseeding, gabions, grading, and revegetation);
- (l) Surveillance and maintenance of surplus facilities in accordance with DOE Order 435.1, "Radioactive Waste Management," or its successor;
- (m) Repair and maintenance of transmission facilities, such as replacement of conductors of the same nominal voltage, poles, circuit breakers, transformers, capacitors, crossarms, insulators, and downed powerlines, in accordance, where appropriate, with 40 CFR part 761 (Polychlorinated Biphenyls Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions) or its successor;
- (n) Routine testing and calibration of facility components, subsystems, or portable equipment (such as control valves, in-core monitoring devices, transformers, capacitors, monitoring wells, lysimeters, weather stations, and flumes);
- (o) Routine decontamination of the surfaces of equipment, rooms, hot cells, or other interior surfaces of buildings (by such activities as wiping with rags, using strippable latex, and minor vacuuming), and removal of contaminated intact equipment and other material (not including spent nuclear fuel or special nuclear material in nuclear reactors); and
- (p) Removal of debris.

#### B1.16 Asbestos removal

Removal of asbestos-containing materials from buildings in accordance with applicable requirements (such as 40 CFR part 61, "National Emission Standards for Hazardous Air Pollutants"; 40 CFR part 763, "Asbestos"; 29 CFR part 1910, subpart I, "Personal Protective Equipment"; and 29 CFR part 1926, "Safety and Health Regulations for Construction"; and appropriate state and local requirements, including certification of removal contractors and technicians).

#### B1.17 Polychlorinated biphenyl removal

Removal of polychlorinated biphenyl (PCB)-containing items (including, but not limited to, transformers and capacitors), PCB-containing oils flushed from transformers, PCB-flushing solutions, and PCB-containing spill materials from buildings or other aboveground locations in accordance with applicable requirements (such as 40 CFR part 761).

### B1.23 Demolition and disposal of buildings

Demolition and subsequent disposal of buildings, equipment, and support structures (including, but not limited to, smoke stacks and parking lot surfaces), provided that there would be no potential for release of substances at a level, or in a form, that could pose a threat to public health or the Environment.

### B1.32 Traffic flow adjustments

Traffic flow adjustments to existing roads (including, but not limited to, stop sign or traffic light installation, adjusting direction of traffic flow, and adding turning lanes), and road adjustments (including, but not limited to, widening and realignment) that are within an existing right-of-way and consistent with approved land use or transportation improvement plans.

### B1.33 Storm water runoff control

Design, construction, and operation of control practices to reduce stormwater runoff and maintain natural hydrology. Activities include, but are not limited to, those that reduce impervious surfaces (such as vegetative practices and use of porous pavements), best management practices (such as silt fences, straw wattles, and fiber rolls), and use of green infrastructure or other low impact development practices (such as cisterns and green roofs).

### B1.34 Lead-based paint containment, removal, and disposal

Containment, removal, and disposal of lead-based paint in accordance with applicable requirements (such as provisions relating to the certification of removal contractors and technicians at 40 CFR part 745, "Lead-Based Paint Poisoning Prevention In Certain Residential Structures").

HARRY S.  
MILLER

Digitally signed by  
milleha@nnpp.gov  
(100000472)  
Date: 2024.12.05  
14:48:25 -05'00'

H. S. Miller  
Project Officer, Facilities and Construction